

C++ Annotations Version 8.2.0

Frank B. Brokken
Center of Information Technology,
University of Groningen
Nettelbosje 1,
P.O. Box 11044,
9700 CA Groningen
The Netherlands
Published at the University of Groningen
ISBN 90 367 0470 7

1994 - 2010

Abstract

This document is intended for knowledgeable users of **C** (or any other language using a **C**-like grammar, like **Perl** or **Java**) who would like to know more about, or make the transition to, **C++**. This document is the main textbook for Frank's **C++** programming courses, which are yearly organized at the University of Groningen. The **C++** Annotations do not cover all aspects of **C++**, though. In particular, **C++**'s basic grammar is not covered when equal to **C**'s grammar. Any basic book on **C** may be consulted to refresh that part of **C++**'s grammar.

If you want a **hard-copy version of the C++ Annotations**: printable versions are available in postscript, pdf and other formats in

`http://sourceforge.net/projects/cppannotations/,`

in files having names starting with `cplusplus` (A4 paper size). Files having names starting with `'cplusplusus'` are intended for the US *legal* paper size.

The latest version of the **C++** Annotations in html-format can be browsed at:

`http://cppannotations.sourceforge.net/`
and/or at
`http://www.icce.rug.nl/documents/`

Contents

1	Overview Of The Chapters	1
2	Introduction	3
2.1	What's new in the C++ Annotations	4
2.2	C++'s history	7
2.2.1	History of the C++ Annotations	8
2.2.2	Compiling a C program using a C++ compiler	8
2.2.3	Compiling a C++ program	9
2.3	C++: advantages and claims	10
2.4	What is Object-Oriented Programming?	12
2.5	Differences between C and C++	13
2.5.1	The function 'main'	13
2.5.2	End-of-line comment	13
2.5.3	Strict type checking	14
2.5.4	Function Overloading	14
2.5.5	Default function arguments	15
2.5.6	NULL-pointers vs. 0-pointers and nullptr (C++0x, ?)	16
2.5.7	The 'void' parameter list	17
2.5.8	The '#define __cplusplus'	17
2.5.9	Using standard C functions	17
2.5.10	Header files for both C and C++	18
2.5.11	Defining local variables	19
2.5.12	The keyword 'typedef'	21
2.5.13	Functions as part of a struct	21
3	A First Impression Of C++	23
3.1	Extensions to C	23
3.1.1	Namespaces	23

3.1.2	The scope resolution operator <code>::</code>	23
3.1.3	Using the keyword <code>'const'</code>	24
3.1.4	<code>'cout'</code> , <code>'cin'</code> , and <code>'cerr'</code>	26
3.2	Functions as part of structs	28
3.2.1	Data hiding: public, private and class	29
3.2.2	Structs in C vs. structs in C++	30
3.3	More extensions to C	31
3.3.1	References	31
3.3.2	Rvalue References (C++0x)	35
3.3.3	Raw String Literals (C++0x, 4.5)	38
3.3.4	Strongly typed enumerations (C++0x, 4.4)	38
3.3.5	Initializer lists (C++0x, 4.4)	39
3.3.6	Type inference using <code>'auto'</code> (C++0x, 4.4)	40
3.3.7	Range-based for-loops (C++0x, ?)	41
3.4	New language-defined data types	41
3.4.1	The data type <code>'bool'</code>	42
3.4.2	The data type <code>'wchar_t'</code>	43
3.4.3	Unicode encoding (C++0x, 4.4)	43
3.4.4	The data type <code>'long long int'</code> (C++0x)	44
3.4.5	The data type <code>'size_t'</code>	44
3.5	A new syntax for casts	44
3.5.1	The <code>'static_cast'</code> -operator	45
3.5.2	The <code>'const_cast'</code> -operator	46
3.5.3	The <code>'reinterpret_cast'</code> -operator	46
3.5.4	The <code>'dynamic_cast'</code> -operator	47
3.6	Keywords and reserved names in C++	47
4	Name Spaces	49
4.1	Namespaces	49
4.1.1	Defining namespaces	49
4.1.2	Referring to entities	50
4.1.3	The standard namespace	54
4.1.4	Nesting namespaces and namespace aliasing	55
5	The <code>'string'</code> Data Type	59
5.1	Operations on strings	60

5.2	A <code>std::string</code> reference	61
5.2.1	Initializers	62
5.2.2	Iterators	62
5.2.3	Operators	63
5.2.4	Member functions	64
6	The IO-stream Library	71
6.1	Special header files	74
6.2	The foundation: the class ‘ <code>ios_base</code> ’	74
6.3	Interfacing ‘ <code>streambuf</code> ’ objects: the class ‘ <code>ios</code> ’	75
6.3.1	Condition states	76
6.3.2	Formatting output and input	79
6.4	Output	84
6.4.1	Basic output: the class ‘ <code>ostream</code> ’	85
6.4.2	Output to files: the class ‘ <code>ofstream</code> ’	87
6.4.3	Output to memory: the class ‘ <code>ostreamstream</code> ’	89
6.5	Input	90
6.5.1	Basic input: the class ‘ <code>istream</code> ’	91
6.5.2	Input from files: the class ‘ <code>ifstream</code> ’	93
6.5.3	Input from memory: the class ‘ <code>istreamstream</code> ’	95
6.5.4	Copying streams	95
6.5.5	Coupling streams	97
6.6	Advanced topics	97
6.6.1	Redirecting streams	97
6.6.2	Reading AND Writing streams	99
7	Classes	107
7.1	The constructor	108
7.1.1	A first application	109
7.1.2	Constructors: with and without arguments	112
7.2	Objects inside objects: composition	114
7.2.1	Composition and const objects: const member initializers	115
7.2.2	Composition and reference objects: reference member initializers	116
7.2.3	Constructors calling constructors (C++0x, ?)	117
7.3	Uniform initialization (C++0x, 4.4)	118
7.4	Defaulted and deleted class members (C++0x, 4.4)	120

7.5	Const member functions and const objects	120
7.5.1	Anonymous objects	122
7.6	The keyword ‘inline’	125
7.6.1	Defining members inline	126
7.6.2	When to use inline functions	127
7.7	Local classes: classes inside functions	128
7.8	The keyword ‘mutable’	129
7.9	Header file organization	130
7.9.1	Using namespaces in header files	133
7.10	Sizeof applied to class data members (C++0x, 4.4)	134
7.11	Unrestricted Unions (C++0x, ?)	135
8	Classes And Memory Allocation	137
8.1	Operators ‘new’ and ‘delete’	138
8.1.1	Allocating arrays	139
8.1.2	Deleting arrays	140
8.1.3	Enlarging arrays	140
8.1.4	Managing ‘raw’ memory	141
8.1.5	The ‘placement new’ operator	142
8.2	The destructor	144
8.2.1	Object pointers revisited	146
8.2.2	The function set_new_handler()	148
8.3	The assignment operator	149
8.3.1	Overloading the assignment operator	151
8.4	The ‘this’ pointer	154
8.4.1	Sequential assignments and this	154
8.5	The copy constructor: initialization vs. assignment	155
8.5.1	Revising ‘operator=()’	157
8.6	The move constructor (C++0x)	158
8.6.1	Move-only classes (C++0x)	161
8.7	Copy Elision and Return Value Optimization	161
8.8	Plain Old Data (C++0x)	163
8.9	Conclusion	164
9	Exceptions	165
9.1	Exception syntax	165

9.2	An example using exceptions	166
9.2.1	Anachronisms: ‘setjmp’ and ‘longjmp’	168
9.2.2	Exceptions: the preferred alternative	169
9.3	Throwing exceptions	171
9.3.1	The empty ‘throw’ statement	174
9.4	The try block	175
9.5	Catching exceptions	175
9.5.1	The default catcher	178
9.6	Declaring exception throwers	179
9.7	Iostreams and exceptions	181
9.8	Standard Exceptions	182
9.9	Exception guarantees	183
9.9.1	The basic guarantee	184
9.9.2	The strong guarantee	185
9.9.3	The nothrow guarantee	187
9.10	Function try blocks	187
9.11	Exceptions in constructors and destructors	190
10	More Operator Overloading	197
10.1	Overloading ‘operator[]()’	197
10.2	Overloading the insertion and extraction operators	200
10.3	Conversion operators	201
10.4	The keyword ‘explicit’	205
10.4.1	Explicit conversion operators (C++0x, 4.5)	206
10.5	Overloading the increment and decrement operators	206
10.6	Overloading binary operators	208
10.7	Overloading ‘operator new(size_t)’	212
10.8	Overloading ‘operator delete(void *)’	214
10.9	Operators ‘new[]’ and ‘delete[]’	215
10.9.1	Overloading ‘new[]’	215
10.9.2	Overloading ‘delete[]’	216
10.9.3	‘new[]’, ‘delete[]’ and exceptions	218
10.10	Function Objects	219
10.10.1	Constructing manipulators	221
10.11	The case of [io]fstream::open()	224

10.12	Overloadable operators	225
11	Static Data And Functions	227
11.1	Static data	227
11.1.1	Private static data	228
11.1.2	Public static data	229
11.1.3	Initializing static const data	230
11.2	Static member functions	230
11.2.1	Calling conventions	232
12	Abstract Containers	235
12.1	Notations used in this chapter	237
12.2	The ‘pair’ container	237
12.3	Sequential Containers	238
12.3.1	The ‘vector’ container	238
12.3.2	The ‘list’ container	240
12.3.3	The ‘queue’ container	247
12.3.4	The ‘priority_queue’ container	248
12.3.5	The ‘deque’ container	251
12.3.6	The ‘map’ container	252
12.3.7	The ‘multimap’ container	260
12.3.8	The ‘set’ container	262
12.3.9	The ‘multiset’ container	264
12.3.10	The ‘stack’ container	266
12.3.11	Hash Tables (C++0x)	268
12.3.12	Regular Expressions (C++0x, ?)	270
12.4	The ‘complex’ container	271
13	Inheritance	273
13.1	Related types	274
13.1.1	Inheritance depth: desirable?	276
13.2	The constructor of a derived class	277
13.2.1	Merely using base class constructors (C++0x, ?)	278
13.3	The destructor of a derived class	279
13.4	Redefining member functions	280
13.5	Multiple inheritance	283

13.6 Public, protected and private derivation	285
13.6.1 Promoting access rights	286
13.7 Conversions between base classes and derived classes	287
13.7.1 Conversions with object assignments	287
13.7.2 Conversions with pointer assignments	288
13.8 Using non-default constructors with new[]	289
14 Polymorphism	293
14.1 Virtual functions	295
14.2 Virtual destructors	296
14.3 Pure virtual functions	297
14.3.1 Implementing pure virtual functions	298
14.4 Virtual functions and multiple inheritance	299
14.4.1 Ambiguity in multiple inheritance	300
14.4.2 Virtual base classes	301
14.4.3 When virtual derivation is not appropriate	305
14.5 Run-time type identification	306
14.5.1 The dynamic_cast operator	306
14.5.2 The ‘typeid’ operator	309
14.6 Inheritance: when to use to achieve what?	311
14.7 The ‘streambuf’ class	313
14.7.1 Protected ‘streambuf’ members	315
14.7.2 The class ‘filebuf’	319
14.8 A polymorphic exception class	320
14.9 How polymorphism is implemented	322
14.10 Undefined reference to vtable	326
14.11 Virtual constructors	327
15 Friends	331
15.1 Friend functions	331
16 Classes Having Pointers To Members	335
16.1 Pointers to members: an example	335
16.2 Defining pointers to members	336
16.3 Using pointers to members	338
16.4 Pointers to static members	340

16.5 Pointer sizes	341
17 Nested Classes	343
17.1 Defining nested class members	345
17.2 Declaring nested classes	345
17.3 Accessing private members in nested classes	346
17.4 Nesting enumerations	349
17.4.1 Empty enumerations	350
17.5 Revisiting virtual constructors	351
18 The Standard Template Library	353
18.1 Predefined function objects	353
18.1.1 Arithmetic function objects	355
18.1.2 Relational function objects	358
18.1.3 Logical function objects	359
18.1.4 Function adaptors	360
18.2 Iterators	362
18.2.1 Insert iterators	365
18.2.2 Iterators for ‘istream’ objects	366
18.2.3 Iterators for ‘istreambuf’ objects	367
18.2.4 Iterators for ‘ostream’ objects	368
18.3 The class ‘unique_ptr’ (C++0x, 4.4)	369
18.3.1 Defining ‘unique_ptr’ objects (C++0x, 4.4)	370
18.3.2 Creating a plain ‘unique_ptr’ (C++0x, 4.4)	370
18.3.3 Moving another ‘unique_ptr’ (C++0x, 4.4)	371
18.3.4 Pointing to a newly allocated object (C++0x, 4.4)	371
18.3.5 Operators and members (C++0x, 4.4)	373
18.3.6 Using ‘unique_ptr’ objects for arrays (C++0x, 4.4)	374
18.3.7 The legacy class ‘auto_ptr’ (deprecated)	374
18.4 The class ‘shared_ptr’ (C++0x)	375
18.4.1 Defining ‘shared_ptr’ objects (C++0x)	375
18.4.2 Creating a plain ‘shared_ptr’ (C++0x)	375
18.4.3 Pointing to a newly allocated object (C++0x)	376
18.4.4 Operators and members (C++0x)	377
18.4.5 Casting shared pointers (C++0x)	378
18.4.6 Using ‘shared_ptr’ objects for arrays (C++0x)	379

18.5 Classes having pointer data members (C++0x)	380
18.6 Multi Threading (C++0x, 4.4)	382
18.6.1 The class 'std::thread' (C++0x, 4.4)	382
18.6.2 Synchronization (mutexes) (C++0x, 4.4)	384
18.6.3 Event handling (condition variables) (C++0x)	386
18.7 Lambda functions (C++0x, 4.5)	388
18.8 Polymorphous wrappers for function objects (C++0x, ?)	391
18.9 Randomization and Mathematical Distributions (C++0x)	391
18.9.1 Random Number Generators (C++0x)	391
18.9.2 Mathematical distributions (C++0x)	392
19 The STL Generic Algorithms	395
19.1 The Generic Algorithms	395
19.1.1 accumulate	396
19.1.2 adjacent_difference	397
19.1.3 adjacent_find	398
19.1.4 binary_search	399
19.1.5 copy	400
19.1.6 copy_backward	401
19.1.7 count	402
19.1.8 count_if	402
19.1.9 equal	403
19.1.10 equal_range	404
19.1.11 fill	406
19.1.12 fill_n	406
19.1.13 find	407
19.1.14 find_end	407
19.1.15 find_first_of	409
19.1.16 find_if	410
19.1.17 for_each	411
19.1.18 generate	413
19.1.19 generate_n	414
19.1.20 includes	415
19.1.21 inner_product	416
19.1.22 inplace_merge	418

19.1.23	<code>iter_swap</code>	419
19.1.24	<code>lexicographical_compare</code>	420
19.1.25	<code>lower_bound</code>	422
19.1.26	<code>max</code>	423
19.1.27	<code>max_element</code>	424
19.1.28	<code>merge</code>	424
19.1.29	<code>min</code>	426
19.1.30	<code>min_element</code>	427
19.1.31	<code>mismatch</code>	427
19.1.32	<code>next_permutation</code>	429
19.1.33	<code>nth_element</code>	430
19.1.34	<code>partial_sort</code>	431
19.1.35	<code>partial_sort_copy</code>	432
19.1.36	<code>partial_sum</code>	433
19.1.37	<code>partition</code>	434
19.1.38	<code>prev_permutation</code>	435
19.1.39	<code>random_shuffle</code>	436
19.1.40	<code>remove</code>	438
19.1.41	<code>remove_copy</code>	438
19.1.42	<code>remove_copy_if</code>	439
19.1.43	<code>remove_if</code>	440
19.1.44	<code>replace</code>	441
19.1.45	<code>replace_copy</code>	442
19.1.46	<code>replace_copy_if</code>	443
19.1.47	<code>replace_if</code>	443
19.1.48	<code>reverse</code>	444
19.1.49	<code>reverse_copy</code>	444
19.1.50	<code>rotate</code>	445
19.1.51	<code>rotate_copy</code>	446
19.1.52	<code>search</code>	447
19.1.53	<code>search_n</code>	448
19.1.54	<code>set_difference</code>	449
19.1.55	<code>set_intersection</code>	450
19.1.56	<code>set_symmetric_difference</code>	451
19.1.57	<code>set_union</code>	452

19.1.58	sort	453
19.1.59	stable_partition	454
19.1.60	stable_sort	455
19.1.61	swap	457
19.1.62	swap_ranges	458
19.1.63	transform	459
19.1.64	unique	460
19.1.65	unique_copy	461
19.1.66	upper_bound	462
19.1.67	Heap algorithms	463
20	Function Templates	469
20.1	Defining function templates	469
20.1.1	Late-specified return type (C++0x, 4.4)	474
20.2	Passing arguments by reference (reference wrappers) (C++0x)	475
20.3	Template parameter deduction	476
20.3.1	Lvalue transformations	478
20.3.2	Qualification transformations	479
20.3.3	Transformation to a base class	479
20.3.4	The template parameter deduction algorithm	480
20.3.5	Template type contractions	481
20.4	Declaring function templates	482
20.4.1	Instantiation declarations	483
20.5	Instantiating function templates	484
20.6	Using explicit template types	486
20.7	Overloading function templates	487
20.8	Specializing templates for deviating types	490
20.9	The function selection mechanism	493
20.10	SFINAE: Substitution Failure Is Not An Error	497
20.11	Compiling template definitions and instantiations	498
20.12	Static assertions (C++0x)	498
20.13	Summary of the template declaration syntax	499
21	Class Templates	501
21.1	Defining class templates	502
21.1.1	Default class template parameters	508

21.1.2	Declaring class templates	509
21.1.3	Preventing template instantiations (C++0x)	509
21.1.4	Non-type parameters	511
21.1.5	Member templates	513
21.2	Static data members	515
21.2.1	Extended use of the keyword ‘typename’	516
21.3	Specializing class templates for deviating types	518
21.4	Partial specializations	522
21.5	Variadic templates (C++0x)	528
21.5.1	Defining and using variadic templates (C++0x)	529
21.5.2	Perfect forwarding (C++0x)	531
21.5.3	The unpack operator (C++0x)	533
21.5.4	Computing the return type of function objects (C++0x)	535
21.5.5	Tuples (C++0x)	537
21.5.6	User-defined literals (C++0x, ?)	538
21.6	Template typedefs and ‘using’ declarations (C++0x, ?)	539
21.7	Instantiating class templates	540
21.8	Processing class templates and instantiations	541
21.9	Declaring friends	542
21.9.1	Non-function templates or classes as friends	543
21.9.2	Templates instantiated for specific types as friends	545
21.9.3	Unbound templates as friends	548
21.10	Class template derivation	550
21.10.1	Deriving ordinary classes from class templates	551
21.10.2	Deriving class templates from class templates	552
21.10.3	Deriving class templates from ordinary classes	555
21.11	Class templates and nesting	560
21.12	Constructing iterators	562
21.12.1	Implementing a ‘RandomAccessIterator’	563
21.12.2	Implementing a ‘reverse_iterator’	567

22 Advanced Template Use **571**

22.1	Subtleties	571
22.1.1	Returning types nested under class templates	572
22.1.2	Type resolution for base class members	573

22.1.3	<code>::template</code> , <code>.template</code> and <code>->template</code>	575
22.2	Template Meta Programming	577
22.2.1	Values according to templates	577
22.2.2	Selecting alternatives using templates	579
22.2.3	Templates: Iterations by Recursion	583
22.3	Template template parameters	584
22.3.1	Policy classes - I	585
22.3.2	Policy classes - II: template template parameters	587
22.3.3	Structure by Policy	590
22.4	Trait classes	591
22.4.1	Distinguishing class from non-class types	593
22.4.2	Available type traits (C++0x)	595
22.5	More conversions to class types	597
22.5.1	Types to types	597
22.5.2	An empty type	598
22.5.3	Type convertability	599
22.6	Template TypeList processing	601
22.6.1	The length of a TypeList	602
22.6.2	Searching a TypeList	603
22.6.3	Selecting from a TypeList	604
22.6.4	Prefixing/Appending to a TypeList	605
22.6.5	Erasing from a TypeList	606
22.7	Using a TypeList	610
22.7.1	The Wrap and Multi class templates	610
22.7.2	The MultiBase class template	612
22.7.3	Support templates	613
22.7.4	Using Multi	615
23	Concrete Examples	617
23.1	Using file descriptors with ‘streambuf’ classes	617
23.1.1	Classes for output operations	617
23.1.2	Classes for input operations	620
23.2	Fixed-sized field extraction from istream objects	630
23.3	The ‘fork’ system call	634
23.3.1	Redirection revisited	637

23.3.2	The ‘Daemon’ program	638
23.3.3	The class ‘Pipe’	639
23.3.4	The class ‘ParentSlurp’	641
23.3.5	Communicating with multiple children	642
23.4	Function objects performing bitwise operations	655
23.5	A text to anything converter	656
23.6	Distinguishing lvalues from rvalues with operator[]()	658
23.7	Implementing a ‘reverse_iterator’	661
23.8	Using ‘bisonc++’ and ‘flex’	664
23.8.1	Using ‘flex’ to create a scanner	665
23.8.2	Using ‘bisonc++’ and ‘flex’	673
23.8.3	Using polymorphic semantic values with Bisonc++	683

Chapter 1

Overview Of The Chapters

The chapters of the C++ Annotations cover the following topics:

- Chapter 1: This overview of the chapters.
- Chapter 2: A general introduction to C++.
- Chapter 3: A first impression: differences between C and C++.
- Chapter 4: Name Spaces: how to avoid name collisions.
- Chapter 5: The 'string' data type.
- Chapter 6: The C++ I/O library.
- Chapter 7: The 'class' concept: structs having functions. The 'object' concept: variables of a class.
- Chapter 8: Allocation and returning unused memory: `new`, `delete`, and the function `set_new_handler()`.
- Chapter 9: Exceptions: handle errors where appropriate, rather than where they occur.
- Chapter 10: Give your own meaning to operators.
- Chapter 11: Static data and functions: members of a class not bound to objects.
- Chapter 12: Abstract Containers to put stuff into.
- Chapter 13: Building classes upon classes: setting up class hierarcies.
- Chapter 14: Changing the behavior of member functions accessed through base class pointers.
- Chapter 15: Gaining access to private parts: friend functions and classes.
- Chapter 16: Classes having pointers to members: pointing to locations inside objects.
- Chapter 17: Constructing classes and enums within classes.
- Chapter 18: The Standard Template Library.
- Chapter 19: The STL generic algorithms.
- Chapter 20: Function templates: using *molds* for type independent functions.
- Chapter 21: Class templates: using *molds* for type independent classes.
- Chapter 22: Advanced Template Use: programming the compiler.
- Chapter 23: Several examples of programs written in C++.

Chapter 2

Introduction

This document offers an introduction to the **C++** programming language. It is a guide for **C/C++** programming courses, yearly presented by Frank at the University of Groningen. This document is not a complete **C/C++** handbook, as much of the **C**-background of **C++** is not covered. Other sources should be referred to for that (e.g., the Dutch book *De programmeertaal C*, Brokken and Kubat, University of Groningen, 1996) or the on-line book¹ suggested to me by George Danchev (danchev at spnet dot net).

The reader should be forewarned that extensive knowledge of the **C** programming language is actually assumed. The **C++** Annotations continue where topics of the **C** programming language end, such as pointers, basic flow control and the construction of functions.

The version number of the **C++** Annotations (currently 8.2.0) is updated when the contents of the document change. The first number is the major number, and will probably not be changed for some time: it indicates a major rewriting. The middle number is increased when new information is added to the document. The last number only indicates small changes; it is increased when, e.g., series of typos are corrected.

This document is published by the Computing Center, University of Groningen, the Netherlands under the GNU General Public License².

The **C++ Annotations** were typeset using the `yodl`³ formatting system.

All correspondence concerning suggestions, additions, improvements or changes to this document should be directed to the author:

Frank B. Brokken
Center of Information Technology,
University of Groningen
Nettelbosje 1,
P.O. Box 11044,
9700 CA Groningen
The Netherlands
(email: f.b.brokken@rug.nl)

In this chapter an overview of **C++**'s defining features is presented. A few extensions to **C** are reviewed and the concepts of object based and object oriented programming (OOP) are briefly introduced.

¹http://publications.gbdirect.co.uk/c_book/

²<http://www.gnu.org/licenses/>

³<http://yodl.sourceforge.net>

2.1 What's new in the C++ Annotations

This section is modified when the first or second part of the version number changes (and sometimes for the third part as well).

- Version 8.2.0 adds a section about casting `shared_ptrs` (section 18.4.5) and about sharing arrays of objects (18.4.6).
- Version 8.1.0 was released following a complete overhaul of the C++ Annotations, with two pre-releases in between. Many inconsistencies that had crept into the text and examples were removed, streamlining the text and synchronizing examples with the text. All of the code examples have received a work-over, replacing `endl` by `'\n'`, making virtual functions private, etc., etc. The sections labeled C++0x were improved and sections showing C++0x now also mention the g++ version in which the new feature will be made available, using `?` if this is as yet unknown. No version is shown if the feature is already available in g++ 4.3 (or in one of its subreleases, like 4.3.3). I received a host of suggestions from Francesco Poli (thanks, Francesco (and several others), for all the effort you've put into sending me those corrections).
- Version 8.0.0 was released as a result of the upcoming new C++ standard⁴ becoming (partially) available in the Gnu g++ compiler⁵. Not all new elements of the new standard (informally called the C++0x standard) are available right now, and new subreleases of the C++ Annotations will appear once more elements become implemented in the g++ compiler. In section 2.2.3 the way to activate the new standard is shown, and new sections covering elements of the new standard show C++0x in their section-titles.

Furthermore, two new chapters were added: the STL chapter is now split in two. The STL chapter now covers the STL except for the *Generic Algorithms* which are now discussed in a separate chapter. Name spaces, originally covered by the introductory chapter are now also covered in a separate chapter.

- Version 7.3.0 adds a section about overloading operators outside of the common context of classes (section 10.11).
- Version 7.2.0 describes the implementation of polymorphism for classes inheriting from multiple base classes defining virtual member functions (section 14.9) and adds two new sections in the concrete examples chapter: Section 23.6 discusses the problem how to distinguish *lvalues* from *rvalues* with `operator[]()`, section 23.8.3 discusses in the context of the BisonC++ parser generator how to use polymorphism instead of a union to define different types of semantic values. As usual, several typos were repaired and various other improvements were made.
- Version 7.1.0 adds a description of the `type_info::before()` member (cf. section 14.5.2). Furthermore, several typographical corrections were made.
- Version 7.0.1. was released shortly after releasing version 7.0.0, as the result of very extensive feedback received by Eric S. Raymond (esr at thyrsus dot com) and Edward Welbourne (eddy at chaos dot org dot uk). Considering the extent of the received feedback, it's appropriate to mention explicitly the sub-sub-release here. Many textual changes were made and section 5.2.4 was completely reorganized.
- Version 7.0.0 comes with a new chapter discussing advanced template applications. Moreover, the general terminology used with templates has evolved. 'Templates' are now considered a core concept, which is reflected by the use of 'templates' as a noun, rather than an adjective. So, from now on it is 'class template' rather than 'template class'. The addition of another chapter, together with the addition of several new sections to existing chapters as well as various rewrites of existing sections made it appropriate to upgrade to the next major release. The newly added chapter does not aim at concrete examples of templates. Instead it discusses possibilities of templates beyond the basic function and class templates. In addition to this new chapter, several new sections were added: section 7.7 introduces *local classes*; section 8.1.5 discusses the *placement new operator*; section 13.6.1 discusses how to make available some members of privately inherited classes

⁴<http://en.wikipedia.org/wiki/C++0x>

⁵<http://gcc.gnu.org/projects/cxx0x.html>

and section 13.8 discusses how objects created by `new[]` can be initialized by non-default constructors. In addition to all this, Elwin Dijk (e dot dijk at gmail dot com), one of the students of the 2006-2007 edition of the C++ course, did a *magnificent* job by converting *all* images to vector graphics (in the process prompting me to start using vector graphics as well :-). Thanks, Elwin for a job well done!

- Version 6.5.0 changed `unsigned` into `size_t` where appropriate, and explicitly mentioned `int`-derived types like `int16_t`. In-class member function definitions were moved out of (below) their class definitions as `inline` defined members. A paragraph about implementing pure virtual member functions was added. Various bugs and compilation errors were fixed.
- Version 6.4.0 added a new section (22.1.1) further discussing the use of the `template` keyword to distinguish types nested under class templates from template members. Furthermore, Sergio Bacchi s dot bacchi at gmail dot com did an impressive job when translating the Annotations into Portuguese. His translation (which may lag a distribution or two behind the latest version of the Annotations) may also be retrieved from the `contributions/` subdirectory in the `c++-annotations_X.Y.Z.tar.gz` archive at <http://sourceforge.net/projects/cppannotations/>
- Version 6.3.0 added new sections about anonymous objects (section 7.5.1) and type resolution with class templates (section 22.1.2). Also the description of the template parameter deduction algorithm was rewritten (cf. section 20.3.4) and numerous modifications required because of the compiler's closer adherence to the C++ standard were realized, among which exception rethrowing from constructor and destructor function try blocks. Also, all textual corrections received from readers since version 6.2.4 were processed.
- In version 6.2.4 many textual improvements were realized. I received extensive lists of typos and suggestions for clarifications of the text, in particular from Nathan Johnson and from Jakob van Bethlehem. Equally valuable were suggestions I received from various other readers of the C++ annotations: all were processed in this release. The C++ content matter of this release was not substantially modified, compared to version 6.2.2.
- Version 6.2.2 offers improved implementations of the configurable class templates (removed in 8.1.0, superseded by lambda functions).
- Version 6.2.0 was released as an Annual Update, by the end of May, 2005. Apart from the usual typo corrections several new sections were added and some were removed: in the Exception chapter (9) a section was added covering the standard exceptions and their meanings; in the chapter covering static members (11) a section was added discussing `static const` data members; and the final chapter (23) covers configurable class templates using *local context structs* (replacing the previous `ForEach`, `UnaryPredicate` and `BinaryPredicate` classes). Furthermore, the final section (covering a C++ parser generator) now uses **bison++**, rather than the old (and somewhat outdated) **bison++** program.
- Version 6.1.0 was released shortly after releasing 6.0.0. Following suggestions received from Leo Razoumov <LEOR@winmain.rutgers.edu> and Paulo Tribolet, and after receiving many, many useful suggestions and extensive help from Leo, navigatable .pdf files are from now on distributed with the C++ Annotations. Also, some sections were slightly adapted.
- Version 6.0.0 was released after a full update of the text, removing many inconsistencies and typos. Since the update effected the Annotation's full text an upgrade to a new major version seemed appropriate. Several new sections were added: overloading binary operators (section 10.6); throwing exceptions in constructors and destructors (section 9.11); function try-blocks (section 9.10); calling conventions of static and global functions (section 11.2.1) and virtual constructors (section 14.11). The chapter on templates was completely rewritten and split into two separate chapters: chapter 20 discusses the syntax and use of template *functions*; chapter 21 discusses template *classes*. Various concrete examples were modified; new examples were included as well (chapter 23).
- In version 5.2.4 the description of the *random_shuffle* generic algorithm (section 19.1.39) was modified.

- In version 5.2.3 section 2.5.11 on local variables was extended and section 2.5.4 on function overloading was modified by explicitly discussing the effects of the **const** modifier with overloaded functions. Also, the description of the `compare()` function in chapter 5 contained an error, which was repaired.
- In version 5.2.2 a leftover in section 10.4 from a former version was removed and the corresponding text was updated. Also, some minor typos were corrected.
- In version 5.2.1 various typos were repaired, and some paragraphs were further clarified. Furthermore, a section was added to the *template* chapter (chapter 20), about creating several `iterator` types. This topic was further elaborated in chapter 23, where the section about the construction of a reverse iterator (section 23.7) was completely rewritten. In the same chapter, a *universal text to anything convertor* is discussed (section 23.5). Also, LaTeX, PostScript and PDF versions fitting the *US-letter* paper size are now available as `cplusplusus` versions: `cplusplusus.latex`, `cplusplusus.ps` and `cplusplus.pdf`. The *A4-paper* size is of course kept, and remains to be available in the `cplusplus.latex`, `cplusplus.ps` and `cplusplus.pdf` files.
- Version 5.2.0 was released after adding a section about the `mutable` keyword (section 7.8), and after thoroughly changing the discussion of the `Fork()` abstract base class (section 23.3). All examples should now be up-to-date with respect to the use of the `std` namespace.
- However, in the meantime the Gnu g++ compiler version 3.2 was released⁶. In this version extensions to the abstract containers (see chapter 12) like the `hash_map` were placed in a separate namespace, `__gnu_cxx`. This namespace should be used when using these containers. However, this may break compilations of sources with g++, version 3.0. In that case, a compilation can be performed conditionally to the 3.2 and the 3.0 compiler version, defining `__gnu_cxx` for the 3.2 version. Alternatively, the *dirty trick*

```
#define __gnu_cxx std
```

can be placed just before header files in which the `__gnu_cxx` namespace is used. This might eventually result in name-collisions, and it's a dirty trick by any standards, so please don't tell anybody I wrote this down.

- Version 5.1.1 was released after modifying the sections related to the `fork()` system call in chapter 23. Under the ANSI/ISO standard many of the previously available extensions (like `procbuf`, and `vform`) applied to streams were discontinued. Starting with version 5.1.1. ways of constructing these facilities under the ANSI/ISO standard are discussed in the C++ Annotations. I consider the involved subject sufficiently complex to warrant the upgrade to a new subversion.
- With the advent of the Gnu g++ compiler version 3.00, a more strict implementation of the ANSI/ISO C++ standard became available. This resulted in version 5.1.0 of the Annotations, appearing shortly after version 5.0.0. In version 5.1.0 chapter 6 was modified and several cosmetic changes took place (e.g., removing `class` from template type parameter lists, see chapter 20). Intermediate versions (like 5.0.0a, 5.0.0b) were not further documented, but were mere intermediate releases while approaching version 5.1.0. Code examples will gradually be adapted to the new release of the compiler.

In the meantime the reader should be prepared to insert `using namespace std;` in many code examples, just beyond the `#include` preprocessor directives as a temporary measure to make the example accepted by the compiler.

- New insights develop all the time, resulting in version 5.0.0 of the Annotations. In this version a lot of old code was cleaned up and typos were repaired. According to current standard, *namespaces* are required in C++ programs, so they are introduced now very early (in section 3.1.1) in the Annotations. A new section about using external programs was added to the Annotations (and removed again in version 5.1.0), and the new `stringstream` class, replacing the `strstream` class is now covered too (sections 6.4.3 and 6.5.3). Actually, the chapter on input and output was completely rewritten. Furthermore, the operators `new` and `delete` are now discussed in chapter 8, where they fit better than in a chapter on classes, where they previously were discussed.

⁶<http://www.gnu.org>

Chapters were moved, split and reordered, so that subjects could generally be introduced without forward references. Finally, the `html`, `PostScript` and `pdf` versions of the **C++** Annotations now contain an index (sigh of relief?) All in, considering the volume and nature of the modifications, it seemed right to upgrade to a full major version. So here it is.

Considering the volume of the Annotations, I'm sure there will be typos found every now and then. Please do not hesitate to send me mail containing any mistakes you find or corrections you would like to suggest.

- In release 4.4.1b the pagesize in the LaTeX file was defined to be `\din A4`. In countries where other pagesizes are standard the default pagesize might be a better choice. In that case, remove the `a4paper`, `twoside` option from `cplusplus.tex` (or `cplusplus.yo` if you have `yodl` installed), and reconstruct the Annotations from the *TeX*-file or *Yodl*-files.

The Annotations mailing lists was stopped at release 4.4.1d. From this point on only minor modifications were expected, which are not anymore generally announced.

At some point, I considered version 4.4.1 to be the final version of the **C++** Annotations. However, a section on special I/O functions was added to cover unformatted I/O, and the section about the `string` datatype had its layout improved and was, due to its volume, given a chapter of its own (chapter 5). All this eventually resulted in version 4.4.2.

Version 4.4.1 again contains new material, and reflects the ANSI/ISO⁷ standard (well, I try to have it reflect the ANSI/ISO standard). In version 4.4.1. several new sections and chapters were added, among which a chapter about the *Standard Template Library* (STL) and *generic algorithms*.

Version 4.4.0 (and subletters) was a mere construction version and was never made available.

The version 4.3.1a is a precursor of 4.3.2. In 4.3.1a most of the typos I've received since the last update have been processed. In version 4.3.2 extra attention was paid to the syntax for function addresses and pointers to member functions.

The decision to upgrade from version 4.2.* to 4.3.* was made after realizing that the lexical scanner function `yylex()` can be defined in the scanner class that is derived from `yyFlexLexer`. Under this approach the `yylex()` function can access the members of the class derived from `yyFlexLexer` as well as the public and protected members of `yyFlexLexer`. The result of all this is a clean implementation of the rules defined in the `flex++` specification file.

The upgrade from version 4.1.* to 4.2.* was the result of the inclusion of section 3.4.1 about the **bool** data type in chapter 3. The distinction between differences between **C** and **C++** and extensions of the **C** programming languages is (albeit a bit fuzzy) reflected in the introduction chapter and the chapter on first impressions of **C++**: The introduction chapter covers some differences between **C** and **C++**, whereas the chapter about first impressions of **C++** covers some extensions of the **C** programming language as found in **C++**.

Major version 4 is a major rewrite of the previous version 3.4.14. The document was rewritten from SGML to Yodl and many new sections were added. All sections got a tune-up. The distribution basis, however, hasn't changed: see the introduction.

Modifications in versions 1.*, 2.*, and 3.* (replace the stars by any applicable number) were not logged.

Subreleases like 4.4.2a etc. contain bugfixes and typographical corrections.

2.2 C++'s history

The first implementation of **C++** was developed in the 1980s at the AT&T Bell Labs, where the Unix operating system was created.

C++ was originally a 'pre-compiler', similar to the preprocessor of **C**, converting special constructions in its source code to plain **C**. Back then this code was compiled by a standard **C** compiler. The 'pre-code', which was read by the **C++** pre-compiler, was usually located in a file with the extension `.cc`, `.C` or

⁷<ftp://research.att.com/dist/c++std/WP/>

.cpp. This file would then be converted to a C source file with the extension .c, which was thereupon compiled and linked.

The nomenclature of C++ source files remains: the extensions .cc and .cpp are still used. However, the preliminary work of a C++ pre-compiler is nowadays usually performed during the actual compilation process. Often compilers determine the language used in a source file from its extension. This holds true for Borland's and Microsoft's C++ compilers, which assume a C++ source for an extension .cpp. The Gnu compiler g++, which is available on many Unix platforms, assumes for C++ the extension .cc.

The fact that C++ used to be compiled into C code is also visible from the fact that C++ is a superset of C: C++ offers the full C grammar and supports all C-library functions, and adds to this features of its own. This makes the transition from C to C++ quite easy. Programmers familiar with C may start 'programming in C++' by using source files having extensions .cc or .cpp instead of .c, and may then comfortably slip into all the possibilities offered by C++. No abrupt change of habits is required.

2.2.1 History of the C++ Annotations

The original version of the C++ Annotations was written by Frank Brokken and Karel Kubat in Dutch using LaTeX. After some time, Karel rewrote the text and converted the guide to a more suitable format and (of course) to English in september 1994.

The first version of the guide appeared on the net in october 1994. By then it was converted to SGML.

Gradually new chapters were added, and the contents were modified and further improved (thanks to countless readers who sent us their comment).

In major version four Frank added new chapters and converted the document from SGML to yodl⁸.

The C++ Annotations are freely distributable. Be sure to read the legal notes⁹.

Reading the annotations beyond this point implies that you are aware of these notes and that you agree with them.

If you like this document, tell your friends about it. Even better, let us know by sending email to Frank¹⁰.

In the Internet, many useful hyperlinks exist to C++. Without even suggesting completeness (and without being checked regularly for existence: they might have died by the time you read this), the following might be worthwhile visiting:

- <http://www.cplusplus.com/ref/>: a reference site for C++.
- <http://www.csci.csusb.edu/dick/c++std/cd2/index.html>: offers a version of the 1996 working paper of the C++ ANSI/ISO standard.

2.2.2 Compiling a C program using a C++ compiler

Prospective C++ programmers should realize that C++ is not a perfect superset of C. There are some differences you might encounter when you simply rename a file to a file having the extension .cc and run it through a C++ compiler:

- In C, `sizeof('c')` equals `sizeof(int)`, 'c' being any ASCII character. The underlying philosophy is probably that chars, when passed as arguments to functions, are passed as integers

⁸<http://yodl.sourceforge.net>

⁹[legal.shtml](#)

¹⁰<mailto:f.b.brokken@rug.nl>

anyway. Furthermore, the **C** compiler handles a character constant like `'c'` as an integer constant. Hence, in **C**, the function calls

```
putchar(10);
```

and

```
putchar('\n');
```

are synonymous.

By contrast, in **C++**, `sizeof('c')` is always 1 (but see also section 3.4.2). An `int` is still an `int`, though. As we shall see later (section 2.5.4), the two function calls

```
somefunc(10);
```

and

```
somefunc('\n');
```

may be handled by different functions: **C++** distinguishes functions not only by their names, but also by their argument types, which are different in these two calls. The former using an `int` argument, the latter a `char`.

- **C++** requires very strict prototyping of external functions. E.g., in **C** a prototype like

```
void func();
```

means that a function `func()` exists, returning no value. The declaration doesn't specify which arguments (if any) are accepted by the function.

However, in **C++** the above declaration means that the function `func()` does *not* accept any arguments at all. Any arguments passed to it will result in a compile-time error.

Note that the keyword `extern` is not required when declaring functions. A function definition becomes a function declaration simply by replacing a function's body by a semicolon. The keyword `extern` is required, though, when declaring variables.

2.2.3 Compiling a C++ program

To compile a **C++** program, a **C++** compiler is required. Considering the free nature of this document, it won't come as a surprise that a *free compiler* is suggested here. The Free Software Foundation (FSF) provides at <http://www.gnu.org> a free **C++** compiler which is, among other places, also part of the Debian (<http://www.debian.org>) distribution of Linux (<http://www.linux.org>).

The upcoming C++0x standard has not yet fully been implemented in the `g++` compiler. Unless indicated otherwise, all features of the C++0x standard covered by the **C++** Annotations are available in `g++` 4.4, unless indicated otherwise. To use these features the compiler flag `-std=c++0x` must currently be provided. It is assumed that this flag is used when compiling the examples given by the Annotations. The features of the C++0x standard may or may not be available in `g++` versions older than 4.4.

2.2.3.1 C++ under MS-Windows

For MS-Windows Cygnus (<http://sources.redhat.com/cygwin>) provides the foundation for installing the *Windows port* of the Gnu `g++` compiler.

When visiting the above URL to obtain a free `g++` compiler, click on `install now`. This will download the file `setup.exe`, which can be run to install `cygwin`. The software to be installed can be downloaded by `setup.exe` from the internet. There are alternatives (e.g., using a CD-ROM), which are described

on the Cygwin page. Installation proceeds interactively. The offered defaults are sensible and should be accepted unless you have reasons to divert.

The most recent Gnu `g++` compiler can be obtained from <http://gcc.gnu.org>. If the compiler that is made available in the Cygnus distribution lags behind the latest version, the sources of the latest version can be downloaded after which the compiler can be built using an already available compiler. The compiler's webpage (mentioned above) contains detailed instructions on how to proceed. In our experience building a new compiler within the Cygnus environment works flawlessly.

2.2.3.2 Compiling a C++ source text

Generally the following command can be used to compile a **C++** source file `'source.cc'`:

```
g++ source.cc
```

This produces a binary program (`a.out` or `a.exe`). If the default name is inappropriate, the name of the executable can be specified using the `-o` flag (here producing the program `source`):

```
g++ -o source source.cc
```

If a mere compilation is required, the compiled module can be produced using the `-c` flag:

```
g++ -c source.cc
```

This generates the file `source.o`, which can later on be linked to other modules. As pointed out, provide the compiler option `-std=c++0x` (note: two dashes). to activate the features of the C++0x standard.

C++ programs quickly become too complex to maintain 'by hand'. With all serious programming projects program maintenance tools are used. Usually the standard `make` program is be used to maintain **C++** programs, but good alternatives exist, like the `icmake`¹¹ program maintenance utility, `ccbuild`¹² or `lake`¹³

It is strongly advised to start using maintenance utilities early in the study of **C++**.

2.3 C++: advantages and claims

Often it is said that programming in **C++** leads to 'better' programs. Some of the claimed advantages of **C++** are:

- New programs would be developed in less time because old code can be reused.
- Creating and using new data types would be easier than in **C**.
- The memory management under **C++** would be easier and more transparent.
- Programs would be less bug-prone, as **C++** uses a stricter syntax and type checking.
- 'Data hiding', the usage of data by one program part while other program parts cannot access the data, would be easier to implement with **C++**.

¹¹<http://icmake.sourceforge.net/>

¹²<http://ccbuild.sourceforge.net/>

¹³<http://nl.logilogi.org/MetaLogi/LaKe>

Which of these allegations are true? Originally, our impression was that the C++ language was somewhat overrated; the same holding true for the entire object-oriented programming (OOP) approach. The enthusiasm for the C++ language resembles the once uttered allegations about Artificial-Intelligence (AI) languages like Lisp and Prolog: these languages were supposed to solve the most difficult AI-problems ‘almost without effort’. New languages are often oversold: in the end, each problem can be coded in any programming language (say BASIC or assembly language). The advantages and disadvantages of a given programming language aren’t in ‘what you can do with them’, but rather in ‘which tools the language offers to implement an efficient and understandable solution to a programming problem’. Often these tools take the form of syntactic *restrictions*, enforcing or promoting certain constructions or which simply suggest intentions by applying or ‘embracing’ such syntactic forms. Rather than a long list of plain assembly instructions we now use flow control statements, functions, objects or even (with C++) so-called *templates* to structure and organize code and to express oneself ‘eloquently’ in the language of one’s choice.

Concerning the above allegations of C++, we support the following, however.

- The development of new programs while existing code is reused can also be implemented in C by, e.g., using function libraries. Functions can be collected in a library and need not be re-invented with each new program. C++, however, offers specific syntax possibilities for code reuse, apart from function libraries (see chapters 13 and 20).
- Creating and using new data types is certainly possible in C; e.g., by using `structs`, `typedefs` etc.. From these types other types can be derived, thus leading to `structs` containing `structs` and so on. In C++ these facilities are augmented by defining data types which are completely ‘self supporting’, taking care of, e.g., their memory management automatically (without having to resort to an independently operating memory management system as used in, e.g., **Java**).
- In C++ memory management can in principle be either as easy or as difficult as it is in C. Especially when dedicated C functions such as `xmalloc` and `xrealloc` are used (allocating the memory or aborting the program when the memory pool is exhausted). However, with functions like `malloc` it is easy to err. Frequently errors in C programs can be traced back to miscalculations when using `malloc`. Instead, C++ offers facilities to allocate memory in a somewhat safer way, using its operator `new`.
- Concerning ‘bug proneness’ we can say that C++ indeed uses stricter type checking than C. However, most modern C compilers implement ‘warning levels’; it is then the programmer’s choice to disregard or get rid of the warnings. In C++ many of such warnings become fatal errors (the compilation stops).
- As far as ‘data hiding’ is concerned, C does offer some tools. E.g., where possible, local or `static` variables can be used and special data types such as `structs` can be manipulated by dedicated functions. Using such techniques, data hiding can be implemented even in C; though it must be admitted that C++ offers special syntactic constructions, making it far easier to implement ‘data hiding’ (and more in general: ‘encapsulation’) in C++ than in C.

C++ in particular (and OOP in general) is of course not *the* solution to all programming problems. However, the language *does* offer various new and elegant facilities which are worth investigating. At the downside, the level of grammatical complexity of C++ has increased significantly as compared to C. This may be considered a serious drawback of the language. Although we got used to this increased level of complexity over time, the transition was neither fast nor painless.

With the C++ Annotations we hope to help the reader when transiting from C to C++ by focusing on the additions of C++ as compared to C and by leaving out plain C. It is our hope that you like this document and may benefit from it.

Enjoy and good luck on your journey into C++!




Figure 2.1: Hierarchy of objects in the salary administration.

2.4 What is Object-Oriented Programming?

Object-oriented (and object-based) programming propagates a slightly different approach to programming problems than the strategy usually used in **C** programs. In **C** programming problems are usually solved using a ‘procedural approach’: a problem is decomposed into subproblems and this process is repeated until the subtasks can be coded. Thus a conglomerate of functions is created, communicating through arguments and variables, global or local (or *static*).

In contrast (or maybe better: in addition) to this, an object-based approach identifies the **keywords** used in a problem statement. These keywords are then depicted in a diagram where arrows are drawn between those keywords to depict an internal hierarchy. The keywords become the objects in the implementation and the hierarchy defines the relationship between these objects. The term object is used here to describe a limited, well-defined structure, containing all information about an entity: data types and functions to manipulate the data. As an example of an object oriented approach, an illustration follows:

The employees and owner of a car dealer and auto garage company are paid as follows. First, mechanics who work in the garage are paid a certain sum each month. Second, the owner of the company receives a fixed amount each month. Third, there are car salesmen who work in the showroom and receive their salary each month plus a bonus per sold car. Finally, the company employs second-hand car purchasers who travel around; these employees receive their monthly salary, a bonus per bought car, and a restitution of their travel expenses.

When representing the above salary administration, the keywords could be mechanics, owner, salesmen and purchasers. The properties of such units are: a monthly salary, sometimes a bonus per purchase or sale, and sometimes restitution of travel expenses. When analyzing the problem in this manner we arrive at the following representation:

- The owner and the mechanics can be represented by identical types, receiving a given salary per month. The relevant information for such a type would be the monthly amount. In addition this object could contain data as the name, address and social security number.
- Car salesmen who work in the showroom can be represented as the same type as above but with some *extra* functionality: the number of transactions (sales) and the bonus per transaction.

In the hierarchy of objects we would define the dependency between the first two objects by letting the car salesmen be ‘derived’ from the owner and mechanics.

- Finally, there are the second-hand car purchasers. These share the functionality of the salesmen except for travel expenses. The additional functionality would therefore consist of the expenses made and this type would be derived from the salesmen.

The hierarchy of the identified objects are further illustrated in Figure 2.1.

The overall process in the definition of a hierarchy such as the above starts with the description of the most simple type. Traditionally (and still in vogue with some popular object oriented languages) more complex types are then derived from the basic set, with each derivation adding a little extra functionality. From these derived types, more complex types can be derived *ad infinitum*, until a representation of the entire problem can be made. Over the years, however, this approach has become less popular in **C++** as it typically results in overly tight *coupling*, which in turns *reduces* rather than enhances the understanding, maintainability and testability of complex programs. In **C++** object oriented program more and more favors small, easy to understand hierarchies, limited coupling and a developmental process where *design patterns* (cf. *Gamma et al.* (1995)) play a central role.

Nonetheless, in **C++** *classes* are frequently used to define the characteristics of *objects*. Classes contain the necessary functionality to do useful things. Classes generally do not offer all their functionality (and typically *none* of their data) to objects of other classes. As we will see, classes tend to *hide* their properties in such a way that they are not directly modifiable by the outside world. Instead, dedicated functions are used to reach or modify the properties of objects. Thus class-type objects are able to uphold their own integrity. The core concept here is *encapsulation* of which *data hiding* is just an example. These concepts will be further explained in chapter 7.

2.5 Differences between C and C++

In this section some examples of **C++** code are shown. Some differences between **C** and **C++** are highlighted.

2.5.1 The function ‘main’

In **C++** there are but two variants of the function `main`: `int main()` and `int main(int argc, char **argv)`. Notes:

- The return type of `main` is `int`, and *not* `void`.
- It is *not* required to use an explicit `return` statement at the end of `main`. If omitted `main` returns 0.
- The ‘third `char **envp` parameter’ is not defined by the **C++** standard and should be avoided. Instead, the global variable `extern char **environ` should be declared providing access to the program’s environment variables. Its final element has the value 0.

2.5.2 End-of-line comment

According to the ANSI/ISO definition, ‘end of line comment’ is implemented in the syntax of **C++**. This comment starts with `//` and ends at the end-of-line marker. The standard **C** comment, delimited by `/*` and `*/` can still be used in **C++**:

```
int main()
{
    // this is end-of-line comment
    // one comment per line

    /*
        this is standard-C comment, covering
        multiple lines
    */
}
```

Despite the example, it is advised *not* to use **C** type comment inside the body of **C++** functions. Sometimes existing code must temporarily be suppressed, e.g., for testing purposes. In those cases it's very practical to be able to use standard **C** comment. If such suppressed code itself contains such comment, it would result in nested comment-lines, resulting in compiler errors. Therefore, the rule of thumb is not to use **C** type comment inside the body of **C++** functions (alternatively, `#if 0` until `#endif` pair of preprocessor directives could of course also be used).

2.5.3 Strict type checking

C++ uses very strict type checking. A prototype must be known for each function before it is called, and the call must match the prototype. The program

```
int main()
{
    printf("Hello World\n");
}
```

often compiles under **C**, albeit with a warning that `printf()` is an unknown function. But **C++** compilers (should) fail to produce code in such cases. The error is of course caused by the missing `#include <stdio.h>` (which in **C++** is more commonly included as `#include <cstdio>` directive).

And while we're at it: as we've seen in **C++** `main` *always* uses the `int` return value. Although it is possible to define `int main()` without explicitly defining a return statement, within `main` it is not possible to use a return statement without an explicit `int`-expression. For example:

```
int main()
{
    return;           // won't compile: expects int expression, e.g.
                     // return 1;
}
```

2.5.4 Function Overloading

In **C++** it is possible to define functions having identical names but performing different actions. The functions must differ in their parameter lists (and/or in their `const` attribute). An example is given below:

```
#include <stdio.h>

void show(int val)
{
    printf("Integer: %d\n", val);
}

void show(double val)
{
    printf("Double: %lf\n", val);
}

void show(char const *val)
{
    printf("String: %s\n", val);
}

int main()
```



```

{
    show(12);
    show(3.1415);
    show("Hello World\n!");
}

```

In the above program three functions `show` are defined, only differing in their parameter lists, expecting an `int`, `double` and `char *`, respectively. The functions have identical names. Functions having identical names but different parameter lists are called *overloaded*. The act of defining such functions is called ‘function overloading’.

The C++ compiler implements function overloading in a rather simple way. Although the functions share their names (in this example `show`), the compiler (and hence the linker) use quite different names. The conversion of a name in the source file to an internally used name is called ‘name mangling’. E.g., the C++ compiler might convert the prototype `void show (int)` to the internal name `VshowI`, while an analogous function having a `char *` argument might be called `VshowCP`. The actual names that are used internally depend on the compiler and are not relevant for the programmer, except where these names show up in e.g., a listing of the contents of a library.

Some additional remarks with respect to function overloading:

- Do not use function overloading for functions doing conceptually different tasks. In the example above, the functions `show` are still somewhat related (they print information to the screen).

However, it is also quite possible to define two functions `lookup`, one of which would find a name in a list while the other would determine the video mode. In this case the behavior of those two functions have nothing in common. It would therefore be more practical to use names which suggest their actions; say, `findname` and `videoMode`.

- C++ does not allow identically named functions to differ only in their return values, as it is always the programmer’s choice to either use or ignore a function’s return value. E.g., the fragment

```
printf("Hello World!\n");
```

provides no information about the return value of the function `printf`. Two functions `printf` which only differ in their return types would therefore not be distinguishable to the compiler.

- In chapter 7 the notion of `const` member functions is introduced (cf. section 7.5). Here it is merely mentioned that classes normally have so-called member functions associated with them (see, e.g., chapter 5 for an informal introduction to the concept). Apart from overloading member functions using different parameter lists, it is then also possible to overload member functions by their `const` attributes. In those cases, classes may have pairs of identically named member functions, having identical parameter lists. Then, these functions are overloaded by their `const` attribute. In such cases only one of these function must have the `const` attribute.

2.5.5 Default function arguments

In C++ it is possible to provide ‘default arguments’ when defining a function. These arguments are supplied by the compiler when they are not specified by the programmer. For example:

```

#include <stdio.h>

void showstring(char *str = "Hello World!\n");

int main()
{
    showstring("Here's an explicit argument.\n");

    showstring();           // in fact this says:

```

```

        // showstring("Hello World!\n");
    }

```

The possibility to omit arguments in situations where default arguments are defined is just a nice touch: it is the compiler who supplies the lacking argument unless it is explicitly specified at the call. The code of the program will neither be shorter nor more efficient when default arguments are used.

Functions may be defined with more than one default argument:

```

void two_ints(int a = 1, int b = 4);

int main()
{
    two_ints();           // arguments:  1, 4
    two_ints(20);        // arguments: 20, 4
    two_ints(20, 5);     // arguments: 20, 5
}

```

When the function `two_ints` is called, the compiler supplies one or two arguments whenever necessary. A statement like `two_ints(,6)` is, however, not allowed: when arguments are omitted they must be on the right-hand side.

Default arguments must be known at compile-time since at that moment arguments are supplied to functions. Therefore, the default arguments must be mentioned at the function's *declaration*, rather than at its *implementation*:

```

// sample header file
extern void two_ints(int a = 1, int b = 4);

// code of function in, say, two.cc
void two_ints(int a, int b)
{
    ...
}

```

It is an error to supply default arguments in function definitions. When the function is used by other sources the compiler reads the header file rather than the function definition. Consequently the compiler has no way to determine the values of default function arguments. Current compilers generate compile-time errors when detecting default arguments in function definitions.

2.5.6 NULL-pointers vs. 0-pointers and nullptr (C++0x, ?)

In **C++** all zero values are coded as 0. In **C** `NULL` is often used in the context of pointers. This difference is purely stylistic, though one that is widely adopted. In **C++** `NULL` should be avoided (as it is a macro, and macros can –and therefore should– easily be avoided in **C++**). Instead 0 can almost always be used.

Almost always, but not always. As **C++** allows function overloading (cf. section 2.5.4) the programmer might be confronted with an unexpected function selection in the situation shown in section 2.5.4:

```

#include <stdio.h>

void show(int val)
{
    printf("Integer: %d\n", val);
}

void show(double val)

```

```

{
    printf("Double: %lf\n", val);
}

void show(char const *val)
{
    printf("String: %s\n", val);
}

int main()
{
    show(12);
    show(3.1415);
    show("Hello World\n!");
}

```

In this situation a programmer intending to call `show(char const *)` might call `show(0)`. But this doesn't work, as 0 is interpreted as `int` and so `show(int)` is called. But calling `show(NULL)` doesn't work either, as **C++** usually defines `NULL` as 0, rather than `((void *)0)`. So, `show(int)` is called once again. To solve these kinds of problems the new **C++** standard introduces the keyword `nullptr` representing the 0 pointer. In the current example the programmer should call `show(nullptr)` to avoid the selection of the wrong function. The `nullptr` value can also be used to initialize pointer variables. E.g.,

```

int *ip = nullptr;      // OK
int value = nullptr;    // error: value is no pointer

```

2.5.7 The 'void' parameter list

In **C**, a function prototype with an empty parameter list, such as

```
void func();
```

means that the argument list of the declared function is not prototyped: the compiler will not warn against calling `func` with any set of arguments. In **C** the keyword `void` is used when it is the explicit intent to declare a function with no arguments at all, as in:

```
void func(void);
```

As **C++** enforces strict type checking, in **C++** an empty parameter list indicates the *total absence* of parameters. The keyword `void` is thus omitted.

2.5.8 The '#define __cplusplus'

Each **C++** compiler which conforms to the ANSI/ISO standard defines the symbol `__cplusplus`: it is as if each source file were prefixed with the preprocessor directive `#define __cplusplus`.

We shall see examples of the usage of this symbol in the following sections.

2.5.9 Using standard C functions

Normal **C** functions, e.g., which are compiled and collected in a run-time library, can also be used in **C++** programs. Such functions, however, must be declared as **C** functions.

As an example, the following code fragment declares a function `xmalloc` as a **C** function:

```
extern "C" void *xmalloc(int size);
```

This declaration is analogous to a declaration in **C**, except that the prototype is prefixed with `extern "C"`.

A slightly different way to declare **C** functions is the following:

```
extern "C"
{
    // C-declarations go in here
}
```

It is also possible to place preprocessor directives at the location of the declarations. E.g., a **C** header file `myheader.h` which declares **C** functions can be included in a **C++** source file as follows:

```
extern "C"
{
    #include <myheader.h>
}
```

Although these two approaches may be used, they are actually seldom encountered in **C++** sources. We will encounter a more frequently used method to declare external **C** functions in the next section.

2.5.10 Header files for both **C** and **C++**

The combination of the predefined symbol `__cplusplus` and the possibility to define `extern "C"` functions offers the ability to create header files for both **C** and **C++**. Such a header file might, e.g., declare a group of functions which are to be used in both **C** and **C++** programs.

The setup of such a header file is as follows:

```
#ifdef __cplusplus
extern "C"
{
    #endif

    /* declaration of C-data and functions are inserted here. E.g., */
    void *xmalloc(int size);

#ifdef __cplusplus
}
#endif
```

Using this setup, a normal **C** header file is enclosed by `extern "C" {` which occurs near the top of the file and by `}`, which occurs near the bottom of the file. The `#ifdef` directives test for the type of the compilation: **C** or **C++**. The ‘standard’ **C** header files, such as `stdio.h`, are built in this manner and are therefore usable for both **C** and **C++**.

In addition **C++** headers should support *include guards*. In **C++** it is usually undesirable to include the same header file twice in the same source file. Such multiple inclusions can easily be avoided by including an `#ifndef` directive in the header file. For example:

```
#ifndef MYHEADER_H_
#define MYHEADER_H_
```

```
// declarations of the header file is inserted here,
// using #ifndef __cplusplus etc. directives
#endif
```

When this file is initially scanned by the preprocessor, the symbol `MYHEADER_H_` is not yet defined. The `#ifndef` condition succeeds and all declarations are scanned. In addition, the symbol `MYHEADER_H_` is defined.

When this file is scanned next while compiling the same source file, the symbol `MYHEADER_H_` has been defined and consequently all information between the `#ifndef` and `#endif` directives is skipped by the compiler.

In this context the symbol name `MYHEADER_H_` serves only for recognition purposes. E.g., the name of the header file can be used for this purpose, in capitals, with an underscore character instead of a dot.

Apart from all this, the custom has evolved to give C header files the extension `.h`, and to give C++ header files *no* extension. For example, the standard *iostreams* `cin`, `cout` and `cerr` are available after including the header file `iostream`, rather than `iostream.h`. In the Annotations this convention is used with the standard C++ header files, but not necessarily everywhere else.

There is more to be said about header files. Section 7.9 provides an in-depth discussion of the preferred organization of C++ header files.

2.5.11 Defining local variables

In C local variables can only be defined at the top of a function or at the beginning of a nested block. In C++ local variables can be created at any position in the code, even between statements.

Furthermore, local variables can be defined within some statements, just prior to their usage. A typical example is the `for` statement:

```
#include <stdio.h>

int main()
{
    for (int i = 0; i < 20; ++i)
        printf("%d\n", i);
}
```

In this program the variable `i` is created in the initialization section of the `for` statement. According to the ANSI-standard, the variable does not exist prior to the `for`-statement and not beyond the `for`-statement. With some older compilers, the variable continues to exist after the execution of the `for`-statement, but nowadays a warning like

warning: name lookup of ‘i’ changed for new ANSI ‘for’ scoping using obsolete binding at ‘i’

is issued when the variable is used outside of the `for`-loop.

The implication seems clear: define a variable just before the `for`-statement if it is to be used beyond that statement. Otherwise the variable should be defined inside the `for`-statement itself. This reduces its scope as much as possible, which is a very desirable characteristic.

Defining local variables when they’re needed requires a little getting used to. However, eventually it tends to produce more readable, maintainable and often more efficient code than defining variables at the beginning of compound statements. We suggest the following rules of thumb for defining local variables:

- Local variables should be created at ‘intuitively right’ places, such as in the example above. This

does not only entail the `for`-statement, but also all situations where a variable is only needed, say, half-way through the function.

- More in general, variables should be defined in such a way that their scope is as *limited* and *localized* as possible. When avoidable local variables are not defined at the beginning of functions but rather where they're first used.
- It is considered good practice to *avoid global variables*. It is fairly easy to lose track of which global variable is used for what purpose. In **C++** global variables are seldom required, and by localizing variables the well known phenomenon of using the same variable for multiple purposes, thereby invalidating each individual purpose of the variable, can easily be prevented.

If considered appropriate, *nested blocks* can be used to localize auxiliary variables. However, situations exist where local variables are considered appropriate inside nested statements. The just mentioned `for` statement is of course a case in point, but local variables can also be defined within the condition clauses of `if-else` statements, within selection clauses of `switch` statements and condition clauses of `while` statements. Variables thus defined will be available to the full statement, including its nested statements. For example, consider the following `switch` statement:

```
#include <stdio.h>

int main()
{
    switch (int c = getchar())
    {
        case 'a':
        case 'e':
        case 'i':
        case 'o':
        case 'u':
            printf("Saw vowel %c\n", c);
            break;

        case EOF:
            printf("Saw EOF\n");
            break;

        default:
            printf("Saw other character, hex value 0x%2x\n", c);
    }
}
```

Note the location of the definition of the character 'c': it is defined in the expression part of the `switch` statement. This implies that 'c' is available *only* to the `switch` statement itself, including its nested (sub)statements, but not outside the scope of the `switch`.

The same approach can be used with `if` and `while` statements: a variable that is defined in the condition part of an `if` and `while` statement is available in their nested statements. There are some caveats, though:

- The variable definition must result in a variable which is initialized to a numeric or logical value;
- The variable definition cannot be nested (e.g., using parentheses) within a more complex expression.

The latter point of attention should come as no big surprise: in order to be able to evaluate the logical condition of an `if` or `while` statement, the value of the variable must be interpretable as either zero (false) or non-zero (true). Usually this is no problem, but in **C++** *objects* (like objects of the type

`std::string` (cf. chapter 5)) are often returned by functions. Such objects may or may not be interpretable as numeric values. If not (as is the case with `std::string` objects), then such variables can *not* be defined at the condition or expression clauses of condition- or repetition statements. The following example will therefore *not* compile:

```
if (std::string myString = getString())    // assume getString returns
{                                           // a std::string value
    // process myString
}
```

The above example requires additional clarification. Often a variable can profitably be given local scope, but an extra check is required immediately following its initialization. The initialization *and* the test cannot *both* be combined in one expression. Instead *two* nested statements are required. Consequently, the following example won't compile either:

```
if ((int c = getchar()) && strchr("aeiou", c))
    printf("Saw a vowel\n");
```

If such a situation occurs, either use two nested `if` statements, or localize the definition of `int c` using a nested compound statement:

```
if (int c = getchar())                    // nested if-statements
    if (strchr("aeiou", c))
        printf("Saw a vowel\n");

{                                         // nested compound statement
    int c = getchar();
    if (c && strchr("aeiou", c))
        printf("Saw a vowel\n");
}
```

2.5.12 The keyword ‘typedef’

The keyword `typedef` is still allowed in **C++**, but is not required anymore when defining union, struct or enum definitions. This is illustrated in the following example:

```
struct somestruct
{
    int    a;
    double d;
    char   string[80];
};
```

When a struct, union or other compound type is defined, the tag of this type can be used as type name (this is `somestruct` in the above example):

```
somestruct what;

what.d = 3.1415;
```

2.5.13 Functions as part of a struct

In **C++** we may define functions as members of structs. Here we encounter the first concrete example of an object: as previously described (see section 2.4), an object is a structure containing data while specialized functions exist to manipulate those data.

A definition of a struct `Point` is provided by the code fragment below. In this structure, two `int` data fields and one function `draw` are declared.

```
struct Point          // definition of a screen-dot
{
    int x;             // coordinates
    int y;             // x/y
    void draw();       // drawing function
};
```

A similar structure could be part of a painting program and could, e.g., represent a pixel. With respect to this struct it should be noted that:

- The function `draw` mentioned in the struct definition is a mere *declaration*. The actual code of the function defining the actions performed by the function is found elsewhere (the concept of functions inside structs is further discussed in section 3.2).
- The size of the struct `Point` is equal to the size of its two ints. A function declared inside the structure does not affect its size. The compiler implements this behavior by allowing the function `draw` to be available only in the context of a `Point`.

The `Point` structure could be used as follows:

```
Point a;              // two points on
Point b;              // the screen

a.x = 0;              // define first dot
a.y = 10;             // and draw it
a.draw();

b = a;                // copy a to b
b.y = 20;             // redefine y-coord
b.draw();             // and draw it
```

As shown in the above example a function that is part of the structure may be selected using the dot (`.`) (the arrow (`->`) operator is used when pointers to objects are available). This is therefore identical to the way data fields of structures are selected.

The idea behind this syntactic construction is that several types may contain functions having identical names. E.g., a structure representing a circle might contain three `int` values: two values for the coordinates of the center of the circle and one value for the radius. Analogously to the `Point` structure, a `Circle` may now have a function `draw` to draw the circle.

Chapter 3

A First Impression Of C++

In this chapter **C++** is further explored. The possibility to declare functions in `structs` is illustrated in various examples; the concept of a `class` is introduced; casting is covered in detail; many new types are introduced and several important notational extensions to **C** are discussed.

3.1 Extensions to C

Before we continue with the ‘real’ object-approach to programming, we first introduce some extensions to the **C** programming language: not mere differences between **C** and **C++**, but syntactic constructs and keywords not found in **C**.

3.1.1 Namespaces

C++ introduces the notion of a *namespace*: all symbols are defined in a larger context, called a *namespace*. Namespaces are used to avoid name conflicts that could arise when a programmer would like to define a function like `sin` operating on *degrees*, but does not want to lose the capability of using the standard `sin` function, operating on *radians*.

Namespaces are covered extensively in chapter 4. For now it should be noted that most compilers require the explicit declaration of a *standard namespace*: `std`. So, unless otherwise indicated, it is stressed that all examples in the Annotations now implicitly use the

```
using namespace std;
```

declaration. So, if you actually intend to compile examples given in the **C++** Annotations, make sure that the sources start with the above `using` declaration.

3.1.2 The scope resolution operator ::

C++ introduces several new operators, among which the scope resolution operator (`::`). This operator can be used in situations where a global variable exists having the same name as a local variable:

```
#include <stdio.h>

int counter = 50;                // global variable

int main()
```

```

{
    for (int counter = 1;           // this refers to the
        counter < 10;              // local variable
        counter++)
    {
        printf("%d\n",
            ::counter               // global variable
            /                      // divided by
            counter);              // local variable
    }
}

```

In the above program the scope operator is used to address a global variable instead of the local variable having the same name. In **C++** the scope operator is used extensively, but it is seldom used to reach a global variable shadowed by an identically named local variable. Its main purpose is described in chapter 7.

3.1.3 Using the keyword ‘const’

Even though the keyword `const` is part of the **C** grammar, its use is more important and much more common in **C++** than it is in **C**.

The `const` keyword is a modifier stating that the value of a variable or of an argument may not be modified. In the following example the intent is to change the value of a variable `ival`, which fails:

```

int main()
{
    int const ival = 3;           // a constant int
                                // initialized to 3

    ival = 4;                    // assignment produces
                                // an error message
}

```

This example shows how `ival` may be initialized to a given value in its definition; attempts to change the value later (in an assignment) are not permitted.

Variables that are declared `const` can, in contrast to **C**, be used to specify the size of an array, as in the following example:

```

int const size = 20;
char buf[size];           // 20 chars big

```

Another use of the keyword `const` is seen in the declaration of pointers, e.g., in pointer-arguments. In the declaration

```
char const *buf;
```

`buf` is a pointer variable pointing to chars. Whatever is pointed to by `buf` may not be changed through `buf`: the chars are declared as `const`. The pointer `buf` itself however may be changed. A statement like `*buf = 'a';` is therefore not allowed, while `++buf` is.

In the declaration

```
char *const buf;
```

`buf` itself is a `const` pointer which may not be changed. Whatever chars are pointed to by `buf` may be changed at will.

Finally, the declaration

```
char const *const buf;
```

is also possible; here, neither the pointer nor what it points to may be changed.

The rule of thumb for the placement of the keyword `const` is the following: whatever occurs to the *left* of the keyword may not be changed.

Although simple, this rule of thumb is often used. For example, Bjarne Stroustrup states (in <http://www.research.att.c>

Should I put "const" before or after the type?

I put it before, but that's a matter of taste. "const T" and "T const" were always (both) allowed and equivalent. For example:

```
const int a = 1;          // OK
int const b = 2;          // also OK
```

My guess is that using the first version will confuse fewer programmers ("is more idiomatic").

But we've already seen an example where applying this simple 'before' placement rule for the keyword `const` produces unexpected (i.e., unwanted) results as we will shortly see below. Furthermore, the 'idiomatic' before-placement also conflicts with the notion of *const functions*, which we will encounter in section 7.5. With `const` functions the keyword `const` is also placed behind rather than before the name of the function.

The definition or declaration (either or not containing `const`) should always be read from the variable or function identifier back to the type identifier:

"Buf is a `const` pointer to `const` characters"

This rule of thumb is especially useful in cases where confusion may occur. In examples of **C++** code published in other places one often encounters the reverse: `const` *preceding* what should not be altered. That this may result in sloppy code is indicated by our second example above:

```
char const *buf;
```

What must remain constant here? According to the sloppy interpretation, the pointer cannot be altered (as `const` precedes the pointer). In fact, the `char` values are the constant entities here, as becomes clear when we try to compile the following program:

```
int main()
{
    char const *buf = "hello";

    ++buf;                // accepted by the compiler
    *buf = 'u';            // rejected by the compiler
}
```

Compilation fails on the statement `*buf = 'u';` and *not* on the statement `++buf`.

Marshall Cline's C++ FAQ¹ gives the same rule (paragraph 18.5), in a similar context:

[18.5] What's the difference between "const Fred p", "Fred* const p" and "const Fred* const p"?*

You have to read pointer declarations right-to-left.

¹<http://www.parashift.com/c++-faq-lite/const-correctness.html>

Marshal Cline's advice might be improved, though: you should start to read pointer definitions (and declarations) at the variable name, reading as far as possible to the definition's end. Once you see a closing parenthesis, read backwards (right to left) from the initial point, until you find matching open-parenthesis or the very beginning of the definition. For example, consider the following complex declaration:

```
char const *(* const (*ip)[])[ ]
```

Here, we see:

- the variable `ip`, being a
- (reading backwards) modifiable pointer to an
- (reading forward) array of
- (reading backward) constant pointers to an
- (reading forward) array of
- (reading backward) modifiable pointers to constant characters

3.1.4 'cout', 'cin', and 'cerr'

Analogous to **C**, **C++** defines standard input- and output streams which are available when a program is executed. The streams are:

- `cout`, analogous to `stdout`,
- `cin`, analogous to `stdin`,
- `cerr`, analogous to `stderr`.

Syntactically these streams are not used as functions: instead, data are written to streams or read from them using the operators `<<`, called the *insertion operator* and `>>`, called the *extraction operator*. This is illustrated in the next example:

```
#include <iostream>

using namespace std;

int main()
{
    int    ival;
    char   sval[30];

    cout << "Enter a number:\n";
    cin >> ival;
    cout << "And now a string:\n";
    cin >> sval;

    cout << "The number is: " << ival << "\n"
         << "And the string is: " << sval << '\n';
}
```

This program reads a number and a string from the `cin` stream (usually the keyboard) and prints these data to `cout`. With respect to streams, please note:

- The standard streams are declared in the header file `iostream`. In the examples in the **C++ Annotations** this header file is often not mentioned explicitly. Nonetheless, it *must* be included

(either directly or indirectly) when these streams are used. Comparable to the use of the `using namespace std;` clause, the reader is expected to `#include <iostream>` with all the examples in which the standard streams are used.

- The streams `cout`, `cin` and `cerr` are variables of so-called *class*-types. Such variables are commonly called *objects*. Classes are discussed in detail in chapter 7 and are used extensively in C++.
- The stream `cin` extracts data from a stream and copies the extracted information to variables (e.g., `ival` in the above example) using the extraction operator (two consecutive `>` characters: `>>`). We will describe later how operators in C++ can perform quite different actions than what they are defined to do by the language, as is the case here. Function overloading has already been mentioned. In C++ operators can also have multiple definitions, which is called *operator overloading*.
- The operators which manipulate `cin`, `cout` and `cerr` (i.e., `>>` and `<<`) also manipulate variables of different types. In the above example `cout << ival` results in the printing of an integer value, whereas `cout << "Enter a number"` results in the printing of a string. The actions of the operators therefore depend on the types of supplied variables.
- The *extraction operator* (`>>`) performs a so called *type safe* assignment to a variable by ‘extracting’ its value from a text stream. Normally, the extraction operator skips all *white space* characters preceding the values to be extracted.
- Special symbolic constants are used for special situations. Normally a line is terminated by inserting `"\n"` or `'\n'`. But when inserting the `endl` symbol the line is terminated followed by the flushing of the stream’s internal buffer. Thus, `endl` can usually be avoided in favor of `'\n'` resulting in somewhat more efficient code.

The stream objects `cin`, `cout` and `cerr` are not part of the C++ grammar proper. The streams are part of the definitions in the header file `iostream`. This is comparable to functions like `printf` that are not part of the C grammar, but were originally written by people who considered such functions important and collected them in a run-time library.

A program may still use the old-style functions like `printf` and `scanf` rather than the new-style streams. The two styles can even be mixed. But streams offer several clear advantages and in many C++ programs have completely replaced the old-style C functions. Some advantages of using streams are:

- Using insertion and extraction operators is *type-safe*. The format strings which are used with `printf` and `scanf` can define wrong format specifiers for their arguments, for which the compiler sometimes can’t warn. In contrast, argument checking with `cin`, `cout` and `cerr` is performed by the compiler. Consequently it isn’t possible to err by providing an `int` argument in places where, according to the format string, a string argument should appear. With streams there are no format strings.
- The functions `printf` and `scanf` (and other functions using format strings) in fact implement a *mini-language* which is interpreted run-time. In contrast, with streams the C++ compiler knows exactly which in- or output action to perform given the arguments used. No mini-language here.
- In addition the possibilities of the insertion and extraction operators may be *extended* allowing objects of classes that didn’t exist when the streams were originally designed to be inserted into or extracted from streams. Mini languages as used with `printf` cannot be extended.
- The usage of the left-shift and right-shift operators in the context of the streams illustrates yet another capability of C++: operator overloading allowing us to redefine the actions an operator performs in certain contexts. Ascending from C operator overloading requires some getting used, but after a short little while these overloaded operators feel rather comfortable.
- Streams are independent of the media they operate upon. This (at this point somewhat abstract) notion means that the same code can be used without *any* modification at all to interface your code to *any* kind of device. The code using streams can be used when the device is a file on disk; an

Internet connection; a digital camera; a DVD device; a satellite link; and much more: you name it. Streams allow your code to be decoupled (independent) of the devices your code is supposed to operate on, which eases maintenance and allows reuse of the same code in new situations.

The *iostream library* has a lot more to offer than just `cin`, `cout` and `cerr`. In chapter 6 *istreams* will be covered in greater detail. Even though `printf` and friends can still be used in C++ programs, streams have practically replaced the old-style C I/O functions like `printf`. If you *think* you still need to use `printf` and related functions, think again: in that case you've probably not yet completely grasped the possibilities of stream objects.

3.2 Functions as part of structs

Earlier it was mentioned that functions can be part of structs (see section 2.5.13). Such functions are called *member functions*. This section briefly discusses how to define such functions.

The code fragment below shows a struct having data fields for a person's name and address. A function `print` is included in the struct's definition:

```
struct Person
{
    char name[80];
    char address[80];

    void print();
};
```

When defining the member function `print` the structure's name (`Person`) and the scope resolution operator (`::`) are used:

```
void Person::print()
{
    cout << "Name:      " << name << "\n"
         << "Address:   " << address << '\n';
}
```

The implementation of `Person::print` shows how the fields of the struct can be accessed without using the structure's type name. Here the function `Person::print` prints a variable name. Since `Person::print` is itself a part of struct `person`, the variable name implicitly refers to the same type.

This struct `Person` could be used as follows:

```
Person person;

strcpy(person.name, "Karel");
strcpy(p.address, "Marskramerstraat 33");
p.print();
```

The advantage of member functions is that the called function automatically accesses the data fields of the structure for which it was invoked. In the statement `person.print()` the object `person` is the 'substrate': the variables `name` and `address` that are used in the code of `print` refer to the data stored in the `person` object.

3.2.1 Data hiding: public, private and class

As mentioned before (see section 2.3), C++ contains specialized syntactic possibilities to implement data hiding. Data hiding is the capability of sections of a program to hide its data from other sections. This results in very clean data definitions. It also allows these sections to enforce the integrity of their data.

C++ has three keywords that are related to data hiding: `private`, `protected` and `public`. These keywords can be used in the definition of `structs`. The keyword `public` allows all subsequent fields of a structure to be accessed by all code; the keyword `private` only allows code that is part of the `struct` itself to access subsequent fields. The keyword `protected` is discussed in chapter 13, and is somewhat outside of the scope of the current discussion.

In a `struct` all fields are `public`, unless explicitly stated otherwise. Using this knowledge we can expand the `struct Person`:

```
struct Person
{
    private:
        char d_name[80];
        char d_address[80];
    public:
        void setName(char const *n);
        void setAddress(char const *a);
        void print();
        char const *name();
        char const *address();
};
```

As the data fields `d_name` and `d_address` are in a `private` section they are only accessible to the member functions which are defined in the `struct`: these are the functions `setName`, `setAddress` etc.. As an illustration consider the following code:

```
Person fbb;

fbb.setName("Frank");           // OK, setName is public
strcpy(fbb.d_name, "Knarf");    // error, x.d_name is private
```

Data integrity is implemented as follows: the actual data of a `struct Person` are mentioned in the structure definition. The data are accessed by the outside world using special functions that are also part of the definition. These member functions control all traffic between the data fields and other parts of the program and are therefore also called ‘interface’ functions. The thus implemented data hiding is illustrated in Figure 3.1. The members `setName` and `setAddress` are declared with `char const *` parameters. This indicates that the functions will not alter the strings which are supplied as their arguments. Analogously, the members `name` and `address` return `char const *`s: the compiler will prevent callers of those members from modifying the information made accessible through the return values of those members.

Two examples of member functions of the `struct Person` are shown below:

```
void Person::setName(char const *n)
{
    strncpy(d_name, n, 79);
    d_name[79] = 0;
}

char const *Person::name()
{

```




Figure 3.1: Private data and public interface functions of the class `Person`.

```
    return d_name;
}
```

The power of member functions and of the concept of data hiding results from the abilities of member functions to perform special tasks, e.g., checking the validity of the data. In the above example `setName` copies only up to 79 characters from its argument to the data member `name`, thereby avoiding a buffer overflow.

Another illustration of the concept of data hiding is the following. As an alternative to member functions that keep their data in memory a library could be developed featuring member functions storing data on file. To convert a program which stores `Person` structures in memory to one that stores the data on disk no special modifications would be required. After recompilation and linking the program to a new library it will have converted from storage in memory to storage on disk. This example illustrates a broader concept than data hiding; it illustrates *encapsulation*. Data hiding is a kind of encapsulation. Encapsulation in general results in reduced coupling of different sections of a program. This in turn greatly enhances reusability and maintainability of the resulting software. By having the structure encapsulate the actual storage medium the program using the structure becomes independent of the actual storage medium that is used.

Though data hiding can be implemented using `structs`, more often (almost always) *classes* are used instead. A class is a kind of struct, except that a class uses private access by default, whereas structs use public access by default. The definition of a class `Person` is therefore identical to the one shown above, except for the fact that the keyword `class` has replaced `struct` while the initial `private:` clause can be omitted. Our typographic suggestion for class names (and other type names defined by the programmer) is to start with a capital character to be followed by the remainder of the type name using lower case letters (e.g., `Person`).

3.2.2 Structs in C vs. structs in C++

In this section we'll discuss an important difference between `C` and `C++` structs and (member) functions. In `C` it is common to define several functions to process a `struct`, which then require a pointer to the `struct` as one of their arguments. An imaginary `C` header file showing this concept is:

```
/* definition of a struct PERSON      This is C      */
typedef struct
{
    char name[80];
    char address[80];
} PERSON;
```



```

/* some functions to manipulate PERSON structs */

/* initialize fields with a name and address */
void initialize(PERSON *p, char const *nm,
               char const *adr);

/* print information */
void print(PERSON const *p);

/* etc.. */

```

In **C++**, the declarations of the involved functions are put inside the definition of the `struct` or `class`. The argument denoting which `struct` is involved is no longer needed.

```

class Person
{
    char d_name[80];
    char d_address[80];

    public:
        void initialize(char const *nm, char const *adr);
        void print();
        // etc..
};

```

In **C++** the `struct` parameter is not used. A **C** function call such as:

```

PERSON x;

initialize(&x, "some name", "some address");

```

becomes in **C++**:

```

Person x;

x.initialize("some name", "some address");

```

3.3 More extensions to C

3.3.1 References

In addition to the common ways to define variables (plain variables or pointers) **C++** introduces *references* defining synonyms for variables. A reference to a variable is like an *alias*; the variable and the reference can both be used in statements involving the variable:

```

int int_value;
int &ref = int_value;

```

In the above example a variable `int_value` is defined. Subsequently a reference `ref` is defined, which (due to its initialization) refers to the same memory location as `int_value`. In the definition of `ref`, the reference operator `&` indicates that `ref` is not itself an `int` but a reference to one. The two statements

```

++int_value;
++ref;

```

have the same effect: they increment `int_value`'s value. Whether that location is called `int_value` or `ref` does not matter.

References serve an important function in **C++** as a means to pass modifiable arguments to functions. E.g., in standard **C**, a function that increases the value of its argument by five and returning nothing needs a pointer parameter:

```
void increase(int *valp)    // expects a pointer
{                          // to an int
    *valp += 5;
}

int main()
{
    int x;

    increase(&x);          // pass x's address
}
```

This construction can *also* be used in **C++** but the same effect is also achieved using a reference:

```
void increase(int &valr)    // expects a reference
{                          // to an int
    valr += 5;
}

int main()
{
    int x;

    increase(x);           // passed as reference
}
```

It is arguable whether code such as the above should be preferred over **C**'s method, though. The statement `increase(x)` suggests that not `x` itself but a *copy* is passed. Yet the value of `x` changes because of the way `increase()` is defined. However, references can also be used to pass objects that are only inspected (without the need for a copy or a `const *`) or to pass objects whose modification is an accepted side-effect of their use. In those cases using references are strongly preferred over existing alternatives like copy by value or passing pointers.

Behind the scenes references are implemented using pointers. So, as far as the compiler is concerned references in **C++** are just `const` pointers. With references, however, the programmer does not need to know or to bother about levels of indirection. An important distinction between plain pointers and references is of course that with references no indirection takes place. For example:

```
extern int *ip;
extern int &ir;

ip = 0;    // reassigns ip, now a 0-pointer
ir = 0;    // ir unchanged, the int variable it refers to
           // is now 0.
```

In order to prevent confusion, we suggest to adhere to the following:

- In those situations where a function does not alter its parameters of a built-in or pointer type, value parameters can be used:

```
void some_func(int val)
```

```

{
    cout << val << '\n';
}

int main()
{
    int x;

    some_func(x);        // a copy is passed
}

```

- When a function explicitly must change the values of its arguments, a pointer parameter is preferred. These pointer parameters should preferably be the function's initial parameters. This is called *return by argument*.

```

void by_pointer(int *valp)
{
    *valp += 5;
}

```

- When a function doesn't change the value of its class- or struct-type arguments, or if the modification of the argument is a trivial side-effect (e.g., the argument is a stream) references can be used. Const-references should be used if the function does not modify the argument:

```

void by_reference(string const &str)
{
    cout << str;    // no modification of str
}

int main ()
{
    int x = 7;
    by_pointer(&x);    // a pointer is passed
                      // x might be changed

    string str("hello");
    by_reference(str);    // str is not altered
}

```

References play an important role in cases where the argument is not changed by the function but where it is undesirable to copy the argument to initialize the parameter. Such a situation occurs when a large object is passed as argument, or is returned by the function. In these cases the copying operation tends to become a significant factor, as the entire object must be copied. In these cases references are preferred.

If the argument isn't modified by the function, or if the caller shouldn't modify the returned information, the `const` keyword should be used. Consider the following example:

```

struct Person                                // some large structure
{
    char    name[80];
    char    address[90];
    double  salary;
};

Person person[50];                          // database of persons

// printperson expects a
// reference to a structure
// but won't change it
void printperson (Person const &p)

```

```

{
    cout << "Name: " << p.name << '\n' <<
        "Address: " << p.address << '\n';
}

// get a person by indexvalue
Person const &person(int index)
{
    return person[index]; // a reference is returned,
}                          // not a copy of person[index]

int main()
{
    Person boss;

    printperson (boss);    // no pointer is passed,
                           // so variable won't be
                           // altered by the function

    printperson(person(5));
                           // references, not copies
                           // are passed here
}

```

- Furthermore, note that there is yet another reason for using references when passing objects as function arguments. When passing a reference to an object, the activation of a so called *copy constructor* is avoided. Copy constructors will be covered in chapter 8.

References *could* result in extremely ‘ugly’ code. A function may return a reference to a variable, as in the following example:

```

int &func()
{
    static int value;
    return value;
}

```

This allows the use of the following constructions:

```

func() = 20;
func() += func();

```

It is probably superfluous to note that such constructions should normally not be used. Nonetheless, there are situations where it is useful to return a reference. We have actually already seen an example of this phenomenon in our previous discussion of streams. In a statement like `cout << "Hello" << '\n'`; the insertion operator returns a reference to `cout`. So, in this statement first the "Hello" is inserted into `cout`, producing a reference to `cout`. Through this reference the `'\n'` is then inserted in the `cout` object, again producing a reference to `cout`, which is then ignored.

Several differences between pointers and references are pointed out in the next list below:

- A reference cannot exist by itself, i.e., without something to refer to. A declaration of a reference like

```
int &ref;
```

is not allowed; what would `ref` refer to?

- References can be declared as `external`. These references were initialized elsewhere.

- References may exist as parameters of functions: they are initialized when the function is called.
- References may be used in the return types of functions. In those cases the function determines what the return value will refer to.
- References may be used as data members of classes. We will return to this usage later.
- Pointers are variables by themselves. They point at something concrete or just “at nothing”.
- References are aliases for other variables and cannot be re-aliased to another variable. Once a reference is defined, it refers to its particular variable.
- Pointers (except for const pointers) can be reassigned to point to different variables.
- When an address-of operator `&` is used with a reference, the expression yields the address of the variable to which the reference applies. In contrast, ordinary pointers are variables themselves, so the address of a pointer variable has nothing to do with the address of the variable pointed to.

3.3.2 Rvalue References (C++0x)

In **C++**, temporary (rvalue) values are indistinguishable from `const` & types. the C++0x standard adds a new reference type called an *rvalue reference*, defined as `typename &&`.

The name *rvalue* reference is derived from assignment statements, where the variable to the left of the assignment operator is called an *lvalue* and the expression to the right of the assignment operator is called an *rvalue*. Rvalues are often temporary (or anonymous) values, like values returned by functions.

In this parlance the **C++** reference should be considered an *lvalue reference* (using the notation `typename &`). They can be contrasted to *rvalue references* (using the notation `typename &&`).

The key to understanding rvalue references is *anonymous variable*. An anonymous variable has no name and this is the distinguishing feature for the compiler to associate it automatically with an lvalue reference if it has a choice. Before introducing some interesting and new constructions that weren't available before C++0x let's first have a look at some distinguishing applications of lvalue references. The following function returns a temporary (anonymous) value:

```
int intVal()
{
    return 5;
}
```

Although the return value of `intVal` can be assigned to an `int` variable it requires a copying operation, which might become prohibitive when a function does not return an `int` but instead some large object. A *reference* or *pointer* cannot be used either to collect the anonymous return value as the return value won't survive beyond that. So the following is illegal (as noted by the compiler):

```
int &ir = intVal();           // fails: refers to a temporary
int const &ic = intVal();     // OK: immutable temporary
int *ip = &intVal();         // fails: no lvalue available
```

Apparently it is not possible to modify the temporary returned by `intVal`. But now consider the next function:

```
void receive(int &value)
{
    cout << "int value parameter\n";
}
void receive(int &&value)
{
    cout << "int R-value parameter\n";
}
```

and let's call this function from main:

```
int main()
{
    receive(18);
    int value = 5;
    receive(value);
    receive(intVal());
}
```

This program produces the following output:

```
int R-value parameter
int value parameter
int R-value parameter
```

It shows the compiler selecting `receive(int &&value)` in all cases where it receives an anonymous `int` as its argument. Note that this includes `receive(18)`: a value 18 has no name and thus `receive(int &&value)` is called. Internally, it actually uses a temporary variable to store the 18, as is shown by the following example which modifies `receive`:

```
void receive(int &&value)
{
    ++value;
    cout << "int R-value parameter, now: " << value << '\n';
    // displays 19 and 6, respectively.
}
```

Contrasting `receive(int &value)` with `receive(int &&value)` has nothing to do with `int &value` not being a `const` reference. If `receive(int const &value)` is used the same results are obtained. Bottom line: the compiler selects the overloaded function using the `rvalue` reference if the function is passed an anonymous value.

The compiler runs into problems if `void receive(int &value)` is replaced by `void receive(int value)`, though. When confronted with the choice between a value parameter and a reference parameter (either `lvalue` or `rvalue`) it cannot make a decision and reports an ambiguity. In practical contexts this is not a problem. `Rvalue` references were added to the language in order to be able to distinguish the two forms of references: named values (for which `lvalue` references are used) and anonymous values (for which `rvalue` references are used).

It is this distinction that allows the implementation of *move semantics* and *perfect forwarding*. At this point the concept of *move semantics* cannot yet fully be discussed (but see section 8.6 for a more thorough discussion) but it is very well possible to illustrate the underlying ideas.

Consider the situation where a function returns a `struct Data` containing a pointer to dynamically allocated characters. Moreover, the `struct` defines a member function `copy(Data const &other)` that takes another `Data` object and copies the other's data into the current object. The (partial) definition of the `struct Data` might look like this²:

```
struct Data
{
    char *text;
    size_t size;
    void copy(Data const &other)
    {
        text = strdup(other.text);
    }
}
```

²To the observant reader: in this example the memory leak that results from using `Data::copy()` should be ignored

```

        size = strlen(text);
    }
};

```

Next, functions `dataFactory` and `main` are defined as follows:

```

Data dataFactory(char const *txt)
{
    Data ret = {strdup(txt), strlen(txt)};
    return ret;
}

int main()
{
    Data d1 = {strdup("hello"), strlen("hello")};

    Data d2;
    d2.copy(d1);                                // 1 (see text)

    Data d3;
    d3.copy(dataFactory("hello"));              // 2
}

```

At (1) `d2` appropriately receives a copy of `d1`'s text. But at (2) `d3` receives a copy of the text stored in the temporary returned by the `dataFactory` function. As the temporary ceases to exist after the call to `copy()` two related and unpleasant consequences are observed:

- The return value is a temporary object: its only reason for existence is to pass its data on to `d3`. Now `d3` copies the temporary's data which clearly is somewhat overdone.
- The temporary `Data` object is lost following the call to `copy()`. Unfortunately its dynamically allocated data is lost as well resulting in a memory leak.

In cases like these *rvalue reference* should be used. By overloading the `copy` member with a member `copy(Data &&other)` the compiler is able to distinguish situations (1) and (2). It now calls the initial `copy()` member in situation (1) and the newly defined overloaded `copy()` member in situation (2):

```

struct Data
{
    char *text;
    size_t size;
    void copy(Data const &other)
    {
        text = strdup(other.text);
    }
    void copy(Data &&other)
    {
        text = other.text;
        other.text = 0;
    }
};

```

Note that the overloaded `copy()` function merely moves the `other.text` pointer to the current object's text pointer followed by reassigning 0 to `other.text`. Struct `Data` suddenly has become *move-aware* and implements *move semantics*, removing the drawbacks of the previously shown approach:

- Instead of making a deep copy (which is required in situation (1)), the pointer value is simply moved to its new owner;

- Since the `other.text` doesn't point to dynamically allocated memory anymore the memory leak is prevented.

Rvalue references for `*this` and initialization of class objects by rvalues are not yet supported by the g++ compiler.

3.3.3 Raw String Literals (C++0x, 4.5)

Standard ASCII-C strings are delimited by double quotes, supporting escape sequences like `\n`, `\\` and `\"`. In some cases it is useful to avoid escaping strings (e.g., in the context of XML). To this end, the C++0x standard offers *raw string literals*.

Raw string literals start with an `R`, followed by a double quote, followed by a label (which is an arbitrary sequence of characters not equal to `]`), followed by `]`. The raw string ends at the closing bracket `]`, followed by the label which is in turn followed by a double quote. Example:

```
R"[A Raw \ "String]"
R"delimiter[Another \ Raw "[String]]delimiter"
```

In the first case, everything between `"[` and `]"` is part of the string. Escape sequences aren't supported so `\"` defines three characters: a backslash, a blank character and a double quote. The second example shows a raw string defined between the markers `"delimiter[` and `]delimiter"`.

3.3.4 Strongly typed enumerations (C++0x, 4.4)

Enumeration values in **C++** are in fact `int` values, thereby bypassing type safety. E.g., values of different enumeration types may be compared for (in)equality, albeit through a (static) type cast.

Another problem with the current `enum` type is that their values are not restricted to the `enum` type name itself, but to the scope where the enumeration is defined. As a consequence, two enumerations having the same scope cannot have identical values.

In the C++0x standard these problems are solved by defining *enum classes*. An *enum class* can be defined as in the following example:

```
enum class SafeEnum
{
    NOT_OK,          // 0, by implication
    OK               = 10,
    MAYBE_OK         // 11, by implication
};
```

Enum classes use `int` values by default, but the used value type can easily be changed using the `:` type notation, as in:

```
enum class CharEnum: unsigned char
{
    NOT_OK,
    OK
};
```

To use a value defined in an enum class its enumeration name must be provided as well. E.g., `OK` is not defined, `CharEnum::OK` is.

Using the data type specification (noting that it defaults to `int`) it is possible to use enum class forward declarations. E.g.,


```
enum Enum1;           // Illegal: no size available
enum Enum2: unsigned int; // Legal in C++0x: explicitly declared type

enum class Enum3;     // Legal in C++0x: default int type is used
enum class Enum4: char; // Legal in C++0x: explicitly declared type
```

3.3.5 Initializer lists (C++0x, 4.4)

The **C** language defines the initializer list as a list of values enclosed by curly braces, possibly themselves containing initializer lists. In **C** these initializer lists are commonly used to initialize arrays and structs.

C++ extends this concept in the C++0x standard by introducing the *type* `initializer_list<Type>` where `Type` is replaced by the type name of the values used in the initializer list. Initializer lists in **C++** are, like their counterparts in **C**, recursive, so they can also be used with multi-dimensional arrays, structs and classes.

Like in **C**, initializer lists consist of a list of values surrounded by curly braces. But unlike **C**, *functions* can define initializer list parameters. E.g.,

```
void values(std::initializer_list<int> iniValues)
{
}
```

A function like `arrayValues` could be called as follows:

```
values({2, 3, 5, 7, 11, 13});
```

The initializer list appears as an argument which is a list of values surrounded by curly braces. Due to the recursive nature of initializer lists a two-dimensional series of values can also be passed, as shown in the next example:

```
void values2(std::initializer_list<int> iniValues)
{
}

values2({{1, 2}, {2, 3}, {3, 5}, {4, 7}, {5, 11}, {6, 13}});
```

Initializer lists are constant expressions and cannot be modified. However, their *size* and values may be retrieved using their `size`, `begin`, and `end` members as follows:

```
void values(initializer_list<int> iniValues)
{
    cout << "Initializer list having " << iniValues.size() << "values\n";
    for
    (
        initializer_list<int>::const_iterator begin = iniValues.begin();
        begin != iniValues.end();
        ++begin
    )
        cout << "Value: " << *begin << '\n';
}
```

Initializer lists can also be used to initialize objects of classes (cf. section 7.3).

3.3.6 Type inference using ‘auto’ (C++0x, 4.4)

A special use of the keyword `auto` is defined by the C++0x standard allowing the compiler to determine the type of a variable automatically rather than requiring the software engineer to define a variable’s type explicitly.

In parallel, the use of `auto` as a storage class specifier is no longer supported in the C++0x standard. According to that standard a variable definition like `auto int var` results in a compilation error.

This can be very useful in situations where it is very hard to determine the variable’s type in advance. These situations occur, e.g., in the context of *templates*, topics covered in chapters 18 until 22.

At this point in the Annotations only simple examples can be given, and some hints will be provided about more general uses of the `auto` keyword.

When defining and initializing a variable `int variable = 5` the type of the initializing expression is well known: it’s an `int`, and unless the programmer’s intentions are different this could be used to define variable’s type (although it shouldn’t in normal circumstances as it reduces rather than improves the clarity of the code):

```
auto variable = 5;
```

Here are some examples where using `auto` is useful. In chapter 5 the *iterator* concept is introduced (see also chapters 12 and 18). Iterators sometimes have long type definitions, like

```
std::vector<std::string>::const_reverse_iterator
```

Functions may return types like this. Since the compiler knows the types returned by functions we may exploit this knowledge using `auto`. Assuming that a function `begin()` is declared as follows:

```
std::vector<std::string>::const_reverse_iterator begin();
```

Rather than writing the verbose variable definition (at // 1) a much shorter definition (at // 2) may be used:

```
std::vector<std::string>::const_reverse_iterator iter = begin();    // 1
auto iter = begin();                                              // 2
```

It’s easy to define additional variables of this type. When initializing those variables using `iter` the `auto` keyword can be used again:

```
auto start = iter;
```

If `start` can’t be initialized immediately using an existing variable the type of a well known variable of function can be used in combination with the `decltype` keyword, as in:

```
decltype(iter) start;
decltype(begin()) spare;
```

The keyword `decltype` may also receive an expression as its argument. This feature is already available in the C++0x standard implementation in g++ 4.3. E.g., `decltype(3 + 5)` represents an `int`, `decltype(3 / double(3))` represents `double`.

The `auto` keyword can also be used to postpone the definition of a function’s return type. The declaration of a function `intArrPtr` returning a pointer to an array of 10 `ints` looks like this:

```
int (*intArrPtr())[10];
```

Such a declaration is fairly complex. E.g., among other complexities it requires ‘protection of the pointer’ using parentheses in combination with the function’s parameter list. In situations like these the specification of the return type can be postponed using the `auto` return type, followed by the specification of the function’s return type after any other specification the function might receive (e.g., as a `const` member (cf. section 7.5) or following its exception throw list (cf. section 9.6)).

Using `auto` to declare the above function, the declaration becomes:

```
auto intArrPtr() -> int (*)[10];
```

A return type specification using `auto` is called a *late-specified return type*.

The `auto` keyword can also be used to defined types that are related to the actual `auto` associated type. Here are some examples:

```
vector<int> vi;
auto iter = vi.begin();           // standard: auto is vector<int>::iterator
auto &&rref = vi.begin();          // auto is rvalue ref. to the iterator type
auto *ptr = &iter;                // auto is pointer to the iterator type
auto *ptr = &rref;                // same
```

3.3.7 Range-based for-loops (C++0x, ?)

The **C++** `for`-statement is identical to **C**’s `for`-statement:

```
for (init; cond; inc)
    statement
```

In many cases, however, the initialization, condition and increment parts are fairly obvious as in situations where all elements of an array or vector must be processed. Many languages offer the `foreach` statement for that and **C++** offers the `std::for_each` generic algorithm (cf. section 19.1.17).

The C++0x standard adds a new `for` statement syntax to this. The new syntax can be used to process each element of a range. Three types of ranges are distinguished:

- Plain arrays (e.g., `int array[10]`);
- Standard containers (or comparable) (cf. chapter 12);
- Ranges contained in a `std::pair` (cf. section 12.2, e.g., `std::pair subRange(array + 1, array + 8)`).

In these cases the C++0x standard offers the following additional `for`-statement syntax:

```
// assume int array[30]
for (int &element: array)
    statement
```

here an `int &element` is defined whose lifetime and scope is restricted to the lifetime of the `for`-statement. It refers to each of the subsequent elements of `array` at each new iteration of the `for`-statement, starting with the first element of the range.

3.4 New language-defined data types

In **C** the following built-in data types are available: `void`, `char`, `short`, `int`, `long`, `float` and `double`. **C++** extends these built-in types with several additional built-in types: the types `bool`,

`wchar_t`, `long long` and `long double` (Cf. ANSI/ISO draft (1995), par. 27.6.2.4.1 for examples of these very long types). The type `long long` is merely a double-long `long` datatype. The type `long double` is merely a double-long `double` datatype. These built-in types as well as pointer variables are called *primitive types* in the C++ Annotations.

Except for these built-in types the class-type `string` is available for handling character strings. The datatypes `bool`, and `wchar_t` are covered in the following sections, the datatype `string` is covered in chapter 5. Note that recent versions of C may also have adopted some of these newer data types (notably `bool` and `wchar_t`). Traditionally, however, C doesn't support them, hence they are mentioned here.

Now that these new types are introduced, let's refresh your memory about *letters* that can be used in *literal constants* of various types. They are:

- E or e: the *exponentiation* character in floating point literal values. For example: `1.23E+3`. Here, E should be pronounced (and interpreted) as: *times 10 to the power*. Therefore, `1.23E+3` represents the value 1230.
- F can be used as *postfix* to a non-integral numeric constant to indicate a value of type `float`, rather than `double`, which is the default. For example: `12.F` (the dot transforms 12 into a floating point value); `1.23E+3F` (see the previous example. `1.23E+3` is a double value, whereas `1.23E+3F` is a float value).
- L can be used as *prefix* to indicate a character string whose elements are `wchar_t`-type characters. For example: `L"hello world"`.
- L can be used as *postfix* to an integral value to indicate a value of type `long`, rather than `int`, which is the default. Note that there is no letter indicating a short type. For that a `static_cast<short>()` must be used.
- p, to specify the power in hexadecimal floating point numbers. E.g. `0x10p4`. The exponent itself is read as a decimal constant and can therefore not start with 0x. The exponent part is interpreted as a power of 2. So `0x10p2` is (decimal) equal to 64: $16 * 2^2$.
- U can be used as *postfix* to an integral value to indicate an unsigned value, rather than an `int`. It may also be combined with the postfix L to produce an unsigned `long int` value.

And, of course: the x and a until f characters can be used to specify hexadecimal constants (optionally using capital letters).

3.4.1 The data type 'bool'

The type `bool` represents boolean (logical) values, for which the (now reserved) constants `true` and `false` may be used. Except for these reserved values, integral values may also be assigned to variables of type `bool`, which are then implicitly converted to `true` and `false` according to the following conversion rules (assume `intValue` is an `int`-variable, and `boolValue` is a `bool`-variable):

```
// from int to bool:
boolValue = intValue ? true : false;

// from bool to int:
intValue = boolValue ? 1 : 0;
```

Furthermore, when `bool` values are inserted into streams then `true` is represented by 1, and `false` is represented by 0. Consider the following example:

```
cout << "A true value: " << true << "\n"
      "A false value: " << false << '\n';
```

The `bool` data type is found in other programming languages as well. **Pascal** has its type `Boolean`; **Java** has a `boolean` type. Different from these languages, **C++**'s type `bool` acts like a kind of `int` type. It is primarily a documentation-improving type, having just two values `true` and `false`. Actually, these values can be interpreted as `enum` values for 1 and 0. Doing so would ignore the philosophy behind the `bool` data type, but nevertheless: assigning `true` to an `int` variable neither produces warnings nor errors.

Using the `bool`-type is usually clearer than using `int`. Consider the following prototypes:

```
bool exists(char const *fileName); // (1)
int  exists(char const *fileName); // (2)
```

For the first prototype, readers will expect the function to return `true` if the given filename is the name of an existing file. However, using the second prototype some ambiguity arises: intuitively the return value 1 is appealing, as it allows constructions like

```
if (exists("myfile"))
    cout << "myfile exists";
```

On the other hand, many system functions (like `access`, `stat`, and many other) return 0 to indicate a successful operation, reserving other values to indicate various types of errors.

As a rule of thumb I suggest the following: if a function should inform its caller about the success or failure of its task, let the function return a `bool` value. If the function should return success or various types of errors, let the function return `enum` values, documenting the situation by its various symbolic constants. Only when the function returns a conceptually meaningful integral value (like the sum of two `int` values), let the function return an `int` value.

3.4.2 The data type ‘`wchar_t`’

The `wchar_t` type is an extension of the `char` built-in type, to accomodate *wide* character values (but see also the next section). The `g++` compiler reports `sizeof(wchar_t)` as 4, which easily accomodates all 65,536 different *Unicode* character values.

Note that **Java**'s `char` data type is somewhat comparable to **C++**'s `wchar_t` type. **Java**'s `char` type is 2 bytes wide, though. On the other hand, **Java**'s `byte` data type is comparable to **C++**'s `char` type: one byte. Confusing?

3.4.3 Unicode encoding (C++0x, 4.4)

In **C++** string literals can be defined as ASCII-Z `C` strings. Prepending an ASCII-Z string by `L` (e.g., `L"hello"`) defines a `wchar_t` string literal.

The new C++0x standard adds to this support for 8, 16 and 32 bit Unicode encoded strings. Furthermore, two new data types are introduced: `char16_t` and `char32_t` storing, respectively, a UTF-16 and UTF-32 unicode value.

In addition, `char` will be large enough to contain any UTF-8 unicode value as well (i.e., it will remain an 8-bit value).

String literals for the various types of unicode encodings (and associated variables) can be defined as follows:

```
char      utf_8[] = u8"This is UTF-8 encoded.";
char16_t  utf16[] = u"This is UTF-16 encoded.";
char32_t  utf32[] = U"This is UTF-32 encoded.";
```

Alternatively, unicode constants may be defined using the `\u` escape sequence, followed by a hexadecimal value. Depending on the type of the unicode variable (or constant) a UTF-8, UTF-16 or UTF-32 value is used. E.g.,

```
char    utf_8[] = u8"\u2018";
char16_t utf16[] = u"\u2018";
char32_t utf32[] = U"\u2018";
```

Unicode strings can be delimited by double quotes but raw string literals can also be used.

3.4.4 The data type ‘long long int’ (C++0x)

The C++0x standard adds the type `long long int` to the set of standard types. On 32 bit systems it will have at least 64 usable bits. Some compilers already supported `long long int` as an extension, but C++0x officially adds it to C++.

3.4.5 The data type ‘size_t’

The `size_t` type is not really a built-in primitive data type, but a data type that is promoted by **POSIX** as a typename to be used for non-negative integral values answering questions like ‘how much’ and ‘how many’, in which case it should be used instead of `unsigned int`. It is not a specific C++ type, but also available in, e.g., C. Usually it is defined implicitly when a (any) system header file is included. The header file ‘officially’ defining `size_t` in the context of C++ is `cstdint`.

Using `size_t` has the advantage of being a *conceptual* type, rather than a standard type that is then modified by a modifier. Thus, it improves the self-documenting value of source code.

Sometimes functions explicitly require `unsigned int` to be used. E.g., on amd-architectures the X-windows function `XQueryPointer` explicitly requires a pointer to an `unsigned int` variable as one of its arguments. In such situations a pointer to a `size_t` variable can’t be used, but the address of an `unsigned int` must be provided. Such situations are exceptional, though.

Other useful bit-represented types also exists. E.g., `uint32_t` is guaranteed to hold 32-bits unsigned values. Analogously, `int32_t` holds 32-bits signed values. Corresponding types exist for 8, 16 and 64 bits values. These types are defined in the header file `cstdint`.

3.5 A new syntax for casts

Traditionally, C offers the following *cast* syntax:

```
(typename)expression
```

here `typename` is the name of a valid *type*, and `expression` is an expression.

C style casts are now deprecated. Although C++ offers *function call* notations using the following syntax:

```
typename(expression)
```

the function call notation does in fact not represents a cast, but a request to the compiler to construct an (anonymous) variable having type `typename` from `expression`. Although this form is very often used in C++, it should *not* be used for casting. Instead, there are now four *new-style casts* available, that are introduced in the following sections.

The C++0x standard defines the *shared_ptr* type (cf. section 18.4). To cast shared pointers specialized casts should be used. These are discussed in section 18.4.5.

3.5.1 The ‘static_cast’-operator

The cast converting conceptually comparable types to each other is:

```
static_cast<type>(expression)
```

This type of cast is used to convert, e.g., a double to an int: both are numbers, but as the int has no fractions precision is potentially reduced. But the converse also holds true. When the quotient of two int values must be assigned to a double the fraction part of the division will get lost unless a cast is used.

Here is an example of such a cast is (assuming quotient is of type double and lhs and rhs are int-typed variables):

```
quotient = static_cast<double>(lhs) / rhs;
```

If the cast is omitted, the division operator will ignore the remainder as its operands are int expressions. Note that the division should be put outside of the cast expression. If the division is put inside (as in `static_cast<double>(lhs / rhs)`) an *integer division* will have been performed *before* the cast has had a chance to convert the type of an operand to double.

Another nice example of code in which it is a good idea to use the `static_cast<>()`-operator is in situations where the arithmetic assignment operators are used in mixed-typed expressions. Consider the following expression (assume `doubleVar` is a variable of type double):

```
intVar += doubleVar;
```

This statement actually evaluates to:

```
intVar = static_cast<int>(static_cast<double>(intVar) +
doubleVar);
```

Here `intVar` is first promoted to a double, and is then added as a double value to `doubleVar`. Next, the sum is cast back to an int. These two casts are a bit overdone. The same result is obtained by explicitly casting `doubleVar` to an int, thus obtaining an int-value for the right-hand side of the expression:

```
intVar += static_cast<int>(doubleVar);
```

A `static_cast` can also be used to undo or introduce the signed-modifier of an int-typed variable. The C function `tolower` requires an int representing the value of an unsigned `char`. But `char` by default is a signed type. To call `tolower` using an available `char ch` we should use:

```
tolower(static_cast<unsigned char>(ch))
```

Casts like these provide information to the compiler about how to handle the provided data. Very often (especially with data types differing only in size but not in representation) the cast won't require any additional code. Additional code will be required, however, to convert one representation to another, e.g., when converting double to int.

3.5.2 The ‘const_cast’-operator

The `const` keyword has been given a special place in casting. Normally anything `const` is `const` for a good reason. Nonetheless situations may be encountered where the `const` can be ignored. For these special situations the `const_cast` should be used. Its syntax is:

```
const_cast<type>(expression)
```

A `const_cast<type>(expression)` expression is used to undo the `const` attribute of a (pointer) type.

The need for a `const_cast` may occur in combination with functions from the standard C library which traditionally weren’t always as `const`-aware as they should. A function `strfun(char *s)` might be available, performing some operation on its `char *s` parameter without actually modifying the characters pointed to by `s`. Passing `char const hello[] = "hello";` to `strfun` will produce the warning

```
passing ‘const char *’ as argument 1 of ‘fun(char *)’ discards const
```

A `const_cast` is the appropriate way to prevent the warning:

```
strfun(const_cast<char *>(hello));
```

3.5.3 The ‘reinterpret_cast’-operator

The third new-style cast is used to change the *interpretation* of information: the `reinterpret_cast`. It is somewhat reminiscent of the `static_cast`, but `reinterpret_cast` should be used when it is *known* that the information as defined in fact is or can be interpreted as something completely different. Its syntax is:

```
reinterpret_cast<pointer type>(pointer expression)
```

A `reinterpret_cast<type>(expression)` operator is appropriately used to reinterpret a `void *` to a pointer of a well-known type. Void pointers are encountered with functions from the C library like `qsort`. The `qsort` function expects a pointer to a (comparison) function having two `void const *` parameters. In fact, the `void const *`s point to data elements of the array to sort, and so the comparison function may cast the `void const *` parameters to pointers to the elements of the array to be sorted. E.g., if the array is an `int array[]` and the compare function’s parameters are `void const *p1`, `void const *p2` then the compare function may obtain the address of the `int` pointed to by `p1` by using:

```
reinterpret_cast<int const *>(p1)
```

Another example of a `reinterpret_cast` is found in combination with the write functions that are available for files and streams. In C++ streams are the preferred interface to, e.g., files. Output streams (like `cout`) offer write members having the prototype

```
write(char const *buffer, int length)
```

To write a `double` to a stream using `write` a `reinterpret_cast` is needed as well. E.g., to write the raw bytes of a variable `double value` to `cout` we would use:

```
cout.write(reinterpret_cast<char const *>(&value), sizeof(double));
```


All casts are potentially dangerous, but the `reinterpret_cast` is the most dangerous of all casts. Effectively we tell the compiler: back off, we know what we're doing, so stop fuzzing. All bets are off, and we'd better *do* know what we're doing in situations like these. As a case in point consider the following code:

```
int value = 0x12345678;      // assume a 32-bits int

cout << "Value's first byte has value: " << hex <<
    static_cast<int>(<
        *reinterpret_cast<unsigned char *>(&value)
    );
```

The above code will show different results on little and big endian computers. Little endian computers will show the value 78, big endian computers the value 12. Also note that the different representations used by little and big endian computers renders the previous example (`cout.write(...)`) non-portable over computers of different architectures.

As a rule of thumb: if circumstances arise in which casts *have* to be used, clearly document the reasons for their use in your code, making double sure that the cast will not eventually cause a program to misbehave.

3.5.4 The 'dynamic_cast'-operator

Finally there is a new style cast that is used in combination with polymorphism (see chapter 14). Its syntax is:

```
dynamic_cast<type>(expression)
```

It is used run-time to convert, a pointer to an object of a class to a pointer to an object of a class that is found further down its so-called *class hierarchy* (which is also called a *downcast*). At this point in the *Annotations* a `dynamic_cast` cannot yet be discussed extensively, but we will return to this topic in section 14.5.1.

3.6 Keywords and reserved names in C++

C++'s keywords are a superset of C's keywords. Here is a list of all keywords of the language:

<code>alignof</code>	<code>compl</code>	<code>explicit</code>	<code>namespace</code>	<code>return</code>	<code>typeid</code>
<code>and</code>	<code>concept</code>	<code>export</code>	<code>new</code>	<code>short</code>	<code>typename</code>
<code>and_eq</code>	<code>const</code>	<code>extern</code>	<code>not</code>	<code>signed</code>	<code>union</code>
<code>asm</code>	<code>const_cast</code>	<code>false</code>	<code>not_eq</code>	<code>sizeof</code>	<code>unsigned</code>
<code>auto</code>	<code>constexpr</code>	<code>float</code>	<code>nullptr</code>	<code>static</code>	<code>using</code>
<code>axiom</code>	<code>continue</code>	<code>for</code>	<code>operator</code>	<code>static_cast</code>	<code>virtual</code>
<code>bitand</code>	<code>decltype</code>	<code>friend</code>	<code>or</code>	<code>struct</code>	<code>void</code>
<code>bitor</code>	<code>default</code>	<code>goto</code>	<code>or_eq</code>	<code>switch</code>	<code>volatile</code>
<code>bool</code>	<code>delete</code>	<code>if</code>	<code>private</code>	<code>template</code>	<code>wchar_t</code>
<code>break</code>	<code>do</code>	<code>import</code>	<code>protected</code>	<code>this</code>	<code>while</code>
<code>case</code>	<code>double</code>	<code>inline</code>	<code>public</code>	<code>throw</code>	<code>xor</code>
<code>catch</code>	<code>dynamic_cast</code>	<code>int</code>	<code>register</code>	<code>true</code>	<code>xor_eq</code>
<code>char</code>	<code>else</code>	<code>long</code>	<code>reinterpret_cast</code>	<code>try</code>	
<code>class</code>	<code>enum</code>	<code>mutable</code>	<code>requires</code>	<code>typedef</code>	

Notes:

- The `export` keyword is removed from the language under the C++0x standard, but remains a keyword, reserved for future use.
- The `nullptr` keyword is defined in the C++0x standard (not yet supported by the g++ compiler).
- the *operator keywords*: `and`, `and_eq`, `bitand`, `bitor`, `compl`, `not`, `not_eq`, `or`, `or_eq`, `xor` and `xor_eq` are symbolic alternatives for, respectively, `&&`, `&=`, `&`, `|`, `~`, `!`, `!=`, `||`, `|=`, `^` and `^=`.

Keywords can only be used for their intended purpose and cannot be used as names for other entities (e.g., variables, functions, class-names, etc.). In addition to keywords identifiers starting with an underscore and living in the *global namespace* (i.e., not using any explicit namespace or using the mere `::` namespace specification) or living in the *std namespace* are reserved identifiers in the sense that their use is a prerogative of the implementor.

Chapter 4

Name Spaces

4.1 Namespaces

Imagine a math teacher who wants to develop an interactive math program. For this program functions like `cos`, `sin`, `tan` etc. are to be used accepting arguments in degrees rather than arguments in radians. Unfortunately, the function name `cos` is already in use, and that function accepts radians as its arguments, rather than degrees.

Problems like these are usually solved by defining another name, e.g., the function name `cosDegrees` is defined. **C++** offers an alternative solution through *namespaces*. Namespaces can be considered as areas or regions in the code in which identifiers are defined that normally won't conflict with names already defined elsewhere.

Now that the ANSI/ISO standard has been implemented to a large degree in recent compilers, the use of namespaces is more strictly enforced than in previous versions of compilers. This affects the setup of `class` header files. At this point in the Annotations this cannot be discussed in detail, but in [section 7.9.1](#) the construction of header files using entities from namespaces is discussed.

4.1.1 Defining namespaces

Namespaces are defined according to the following syntax:

```
namespace identifier
{
    // declared or defined entities
    // (declarative region)
}
```

The identifier used when defining a namespace is a standard **C++** identifier.

Within the *declarative region*, introduced in the above code example, functions, variables, structs, classes and even (nested) namespaces can be defined or declared. Namespaces cannot be defined within a function body. However, it is possible to define a namespace using multiple *namespace* declarations. Namespaces are 'open' meaning that a namespace `CppAnnotations` could be defined in a file `file1.cc` and also in a file `file2.cc`. Entities defined in the `CppAnnotations` namespace of files `file1.cc` and `file2.cc` are then united in one `CppAnnotations` namespace region. For example:

```
// in file1.cc
namespace CppAnnotations
{
    double cos(double argInDegrees)
```

```

    {
        ...
    }
}

// in file2.cc
namespace CppAnnotations
{
    double sin(double argInDegrees)
    {
        ...
    }
}

```

Both `sin` and `cos` are now defined in the same `CppAnnotations` namespace.

Namespace entities can be defined outside of their namespaces. This topic is discussed in section [4.1.4.1](#).

4.1.1.1 Declaring entities in namespaces

Instead of *defining* entities in a namespace, entities may also be *declared* in a namespace. This allows us to put all the declarations in a header file that can thereupon be included in sources using the entities defined in the namespace. Such a header file could contain, e.g.,

```

namespace CppAnnotations
{
    double cos(double degrees);
    double sin(double degrees);
}

```

4.1.1.2 A closed namespace

Namespaces can be defined without a name. Such an anonymous namespace restricts the visibility of the defined entities to the source file defining the anonymous namespace.

Entities defined in the anonymous namespace are comparable to C's `static` functions and variables. In C++ the `static` keyword can still be used, but its preferred use is in `class` definitions (see chapter 7). In situations where in C static variables or functions would have been used the anonymous namespace should be used in C++.

The anonymous namespace is a closed namespace: it is not possible to add entities to the same anonymous namespace using different source files.

4.1.2 Referring to entities

Given a namespace and its entities, the scope resolution operator can be used to refer to its entities. For example, the function `cos()` defined in the `CppAnnotations` namespace may be used as follows:

```

// assume CppAnnotations namespace is declared in the
// following header file:
#include <cppannotations>

int main()
{

```

```

    cout << "The cosine of 60 degrees is: " <<
        CppAnnotations::cos(60) << '\n';
}

```

This is a rather cumbersome way to refer to the `cos()` function in the `CppAnnotations` namespace, especially so if the function is frequently used. In cases like these an *abbreviated* form can be used after specifying a *using declaration*. Following

```

using CppAnnotations::cos; // note: no function prototype,
                           // just the name of the entity
                           // is required.

```

calling `cos` will call the `cos` function defined in the `CppAnnotations` namespace. This implies that the standard `cos` function, accepting radians, is not automatically called anymore. To call that latter `cos` function the plain scope resolution operator should be used:

```

int main()
{
    using CppAnnotations::cos;
    ...
    cout << cos(60)           // calls CppAnnotations::cos()
        << ::cos(1.5)        // call the standard cos() function
        << '\n';
}

```

A *using declaration* can have restricted scope. It can be used inside a block. The *using declaration* prevents the definition of entities having the same name as the one used in the *using declaration*. It is not possible to specify a *using declaration* for a variable value in some namespace, and to define (or declare) an identically named object in a block also containing a *using declaration*. Example:

```

int main()
{
    using CppAnnotations::value;
    ...
    cout << value << '\n'; // uses CppAnnotations::value
    int value;             // error: value already declared.
}

```

4.1.2.1 The ‘using’ directive

A generalized alternative to the *using declaration* is the *using directive*:

```

using namespace CppAnnotations;

```

Following this directive, *all* entities defined in the `CppAnnotations` namespace are used as if they were declared by *using declarations*.

While the *using directive* is a quick way to import all the names of a namespace (assuming the namespace has previously been declared or defined), it is at the same time a somewhat dirty way to do so, as it is less clear what entity will be used in a particular block of code.

If, e.g., `cos` is defined in the `CppAnnotations` namespace, `CppAnnotations::cos` will be used when `cos` is called. However, if `cos` is *not* defined in the `CppAnnotations` namespace, the standard `cos` function will be used. The *using directive* does not document as clearly as the *using declaration* what entity will be used. Therefore use caution when applying the *using directive*.

4.1.2.2 ‘Koenig lookup’

If *Koenig lookup* were called the ‘Koenig principle’, it could have been the title of a new Ludlum novel. However, it is not. Instead it refers to a **C++** technicality.

‘Koenig lookup’ refers to the fact that if a function is called without specifying its namespace, then the namespaces of its arguments are used to determine its namespace. If the namespace in which the arguments are defined contains such a function, then that function is used. This is called the ‘Koenig lookup’.

This is illustrated in the following example. The function `FBB::fun(FBB::Value v)` is defined in the `FBB` namespace. It can be called without explicitly mentioning its namespace:

```
#include <iostream>

namespace FBB
{
    enum Value          // defines FBB::Value
    {
        FIRST
    };

    void fun(Value x)
    {
        std::cout << "fun called for " << x << '\n';
    }
}

int main()
{
    fun(FBB::FIRST);    // Koenig lookup: no namespace
                        // for fun() specified
}
/*
    generated output:
    fun called for 0
*/
```

The compiler is fairly smart when handling namespaces. If `Value` in the namespace `FBB` would have been defined as `typedef int Value` then `FBB::Value` would be recognized as `int`, thus causing the Koenig lookup to fail.

As another example, consider the next program. Here two namespaces are involved, each defining their own `fun` function. There is no ambiguity, since the argument defines the namespace and `FBB::fun` is called:

```
#include <iostream>

namespace FBB
{
    enum Value          // defines FBB::Value
    {
        FIRST
    };

    void fun(Value x)
    {
        std::cout << "FBB::fun() called for " << x << '\n';
    }
}
```

```

}

namespace ES
{
    void fun(FBB::Value x)
    {
        std::cout << "ES::fun() called for " << x << '\n';
    }
}

int main()
{
    fun(FBB::FIRST);    // No ambiguity: argument determines
                        // the namespace
}
/*
    generated output:
    FBB::fun() called for 0
*/

```

Here is an example in which there *is* an ambiguity: `fun` has two arguments, one from each namespace. The ambiguity must be resolved by the programmer:

```

#include <iostream>

namespace ES
{
    enum Value          // defines ES::Value
    {
        FIRST
    };
}

namespace FBB
{
    enum Value          // defines FBB::Value
    {
        FIRST
    };

    void fun(Value x, ES::Value y)
    {
        std::cout << "FBB::fun() called\n";
    }
}

namespace ES
{
    void fun(FBB::Value x, Value y)
    {
        std::cout << "ES::fun() called\n";
    }
}

int main()
{
    // fun(FBB::FIRST, ES::FIRST); ambiguity: resolved by
    //                               explicitly mentioning
    //                               the namespace
}

```

```

    ES::fun(FBB::FIRST, ES::FIRST);
}
/*
    generated output:
    ES::fun() called
*/

```

An interesting subtlety with namespaces is that definitions in one namespace may break the code defined in another namespace. It shows that namespaces may affect each other and that may backfire if we're not aware of their peculiarities. Consider the following example:

```

namespace FBB
{
    struct Value
    {};

    void fun(int x);
    void gun(Value x);
}

namespace ES
{
    void fun(int x)
    {
        fun(x);
    }
    void gun(FBB::Value x)
    {
        gun(x);
    }
}

```

Whatever happens, the programmer'd better not use any of the `ES::fun` functions since it will doubtlessly result in infinite recursion, but that's not the point. The point is that the programmer won't even be given the opportunity to call `ES::fun` since the compilation fails.

Compilation fails for `gun` but not for `fun`. Why is that? Why is `ES::fun` flawlessly compiling while `ES::gun` isn't? In `ES::fun` `fun(x)` is called. As `x`'s type is not defined in a namespace the Koenig lookup does not apply and `fun` calls itself with infinite recursion.

With `ES::gun` the argument is defined in the `FBB` namespace. Consequently, the `FBB::gun` function is a possible candidate to be called. But `ES::gun` itself also is possible as `ES::gun`'s prototype perfectly matches the call `gun(x)`.

Now consider the situation where `FBB::gun` has not yet been declared. Then there is of course no ambiguity. The programmer responsible for the `ES` namespace is resting happily. Some time after that the programmer who's maintaining the `FBB` namespace decides it may be nice to add a function `gun(Value x)` to the `FBB` namespace. Now suddenly the code in the namespace `ES` breaks because of an addition in a completely other namespace (`FBB`). Namespaces clearly are not completely independent of each other and we should be aware of subtleties like the above. Later in the [C++ Annotations](#) (chapter [10](#)) we'll return to this issue.

4.1.3 The standard namespace

The `std` namespace is reserved by **C++**. The standard defines many entities that are part of the runtime available software (e.g., `cout`, `cin`, `cerr`); the templates defined in the *Standard Template Library* (cf. chapter [18](#)); and the *Generic Algorithms* (cf. chapter [19](#)) are defined in the `std` namespace.

Regarding the discussion in the previous section, `using` declarations may be used when referring to entities in the `std` namespace. For example, to use the `std::cout` stream, the code may declare this object as follows:

```
#include <iostream>
using std::cout;
```

Often, however, the identifiers defined in the `std` namespace can all be accepted without much thought. Because of that, one frequently encounters a `using` directive, allowing the programmer to omit a namespace prefix when referring to any of the entities defined in the namespace specified with the `using` directive. Instead of specifying `using` declarations the following `using` directive is frequently encountered: construction like

```
#include <iostream>
using namespace std;
```

Should a `using` directive, rather than `using` declarations be used? As a rule of thumb one might decide to stick to `using` declarations, up to the point where the list becomes impractically long, at which point a `using` directive could be considered.

Two restrictions apply to `using` directives and declarations:

- Programmers should not declare or define anything inside the namespace `std`. This is *not* compiler enforced but is imposed upon user code by the standard;
- `Using` declarations and directives should not be imposed upon code written by third parties. In practice this means that `using` directives and declarations should be banned from header files and should only be used in source files (cf. section 7.9.1).

4.1.4 Nesting namespaces and namespace aliasing

Namespaces can be nested. Here is an example:

```
namespace CppAnnotations
{
    namespace Virtual
    {
        void *pointer;
    }
}
```

The variable `pointer` is defined in the `Virtual` namespace, that itself is nested under the `CppAnnotations` namespace. To refer to this variable the following options are available:

- The *fully qualified name* can be used. A fully qualified name of an entity is a list of all the namespaces that are encountered until reaching the definition of the entity. The namespaces and entity are glued together by the scope resolution operator:

```
int main()
{
    CppAnnotations::Virtual::pointer = 0;
}
```

- A `using` declaration for `CppAnnotations::Virtual` can be provided. Now `Virtual` can be used without any prefix, but `pointer` must be used with the `Virtual::` prefix:

```
using CppAnnotations::Virtual;
```

```
int main()
{
    Virtual::pointer = 0;
}
```

- A using declaration for `CppAnnotations::Virtual::pointer` can be used. Now `pointer` can be used without any prefix:

```
using CppAnnotations::Virtual::pointer;

int main()
{
    pointer = 0;
}
```

- A using directive or directives can be used:

```
using namespace CppAnnotations::Virtual;

int main()
{
    pointer = 0;
}
```

Alternatively, two separate using directives could have been used:

```
using namespace CppAnnotations;
using namespace Virtual;

int main()
{
    pointer = 0;
}
```

- A combination of using declarations and using directives can be used. E.g., a using directive can be used for the `CppAnnotations` namespace, and a using declaration can be used for the `Virtual::pointer` variable:

```
using namespace CppAnnotations;
using Virtual::pointer;

int main()
{
    pointer = 0;
}
```

At every using directive all entities of that namespace can be used without any further prefix. If a namespace is nested, then that namespace can also be used without any further prefix. However, the entities defined in the nested namespace still need the nested namespace's name. Only after applying a using declaration or directive the qualified name of the nested namespace can be omitted.

When fully qualified names are preferred but a long name like

```
CppAnnotations::Virtual::pointer
```

is nevertheless considered too long, a *namespace alias* may be used:

```
namespace CV = CppAnnotations::Virtual;
```

This defines CV as an *alias* for the full name. The variable pointer may now be accessed using:

```
CV::pointer = 0;
```

A namespace alias can also be used in a using declaration or directive:

```
namespace CV = CppAnnotations::Virtual;
using namespace CV;
```

4.1.4.1 Defining entities outside of their namespaces

It is not strictly necessary to define members of namespaces inside a namespace region. But before an entity is defined *outside* of a namespace it must have been declared *inside* its namespace.

To define an entity outside of its namespace its name must be *fully qualified* by prefixing the member by its namespaces. The definition may be provided at the global level or at intermediate levels in the case of nested namespaces. This allows us to define an entity belonging to namespace A : B within the region of namespace A.

Assume the type `int INT8[8]` is defined in the `CppAnnotations::Virtual` namespace. Furthermore assume that it is our intent to define a function `squares`, inside the namespace `CppAnnotations::Virtual` returning a pointer to `CppAnnotations::Virtual::INT8`.

Having defined the prerequisites within the `CppAnnotations::Virtual` namespace, our function could be defined as follows (cf. chapter 8 for coverage of the memory allocation operator `new[]`):

```
namespace CppAnnotations
{
    namespace Virtual
    {
        void *pointer;

        typedef int INT8[8];

        INT8 *squares()
        {
            INT8 *ip = new INT8[1];

            for (size_t idx = 0; idx != sizeof(INT8) / sizeof(int); ++idx)
                (*ip)[idx] = (idx + 1) * (idx + 1);

            return ip;
        }
    }
}
```

The function `squares` defines an array of one `INT8` vector, and returns its address after initializing the vector by the squares of the first eight natural numbers.

Now the function `squares` can be defined outside of the `CppAnnotations::Virtual` namespace:

```
namespace CppAnnotations
{
    namespace Virtual
    {
        void *pointer;
```

```

        typedef int INT8[8];

        INT8 *squares();
    }
}

CppAnnotations::Virtual::INT8 *CppAnnotations::Virtual::squares()
{
    INT8 *ip = new INT8[1];

    for (size_t idx = 0; idx != sizeof(INT8) / sizeof(int); ++idx)
        (*ip)[idx] = (idx + 1) * (idx + 1);

    return ip;
}

```

In the above code fragment note the following:

- `squares` is declared inside of the `CppAnnotations::Virtual` namespace.
- The definition outside of the namespace region requires us to use the fully qualified name of the function *and* of its return type.
- *Inside* the body of the function `squares` we are within the `CppAnnotations::Virtual` namespace, so inside the function fully qualified names (e.g., for `INT8`) are not required any more.

Finally, note that the function could also have been defined in the `CppAnnotations` region. In that case the `Virtual` namespace would have been required when defining `squares()` and when specifying its return type, while the internals of the function would remain the same:

```

namespace CppAnnotations
{
    namespace Virtual
    {
        void *pointer;

        typedef int INT8[8];

        INT8 *squares();
    }

    Virtual::INT8 *Virtual::squares()
    {
        INT8 *ip = new INT8[1];

        for (size_t idx = 0; idx != sizeof(INT8) / sizeof(int); ++idx)
            (*ip)[idx] = (idx + 1) * (idx + 1);

        return ip;
    }
}

```

Chapter 5

The ‘string’ Data Type

C++ offers many solutions for common problems. Most of these facilities are part of the *Standard Template Library* or they are implemented as *generic algorithms* (see chapter 19).

Among the facilities C++ programmers have developed over and over again are those manipulating chunks of text, commonly called *strings*. The C programming language offers rudimentary string support. C’s ASCII-Z terminated series of characters form the foundation upon which an enormous amount of code has been built¹.

To process text C++ offers a `std::string` type. In C++ the traditional C library functions manipulating ASCII-Z strings are deprecated in favor of using `string` objects. Many problems in C programs are caused by buffer overruns, boundary errors and allocation problems that can be traced back to improperly using these traditional C string library functions. Many of these problems can be prevented using C++ string objects.

Actually, `string` objects are *class type* variables, and in that sense they are comparable to stream objects like `cin` and `cout`. In this section the use of `string` type objects is covered. The focus is on their definition and their use. When using `string` objects the *member function syntax* is commonly used:

```
stringVariable.operation(argumentList)
```

For example, if `string1` and `string2` are variables of type `std::string`, then

```
string1.compare(string2)
```

can be used to compare both strings.

In addition to the common member functions the `string` class also offers a wide variety of *operators*, like the assignment (`=`) and the comparison operator (`==`). Operators often result in code that is easy to understand and their use is generally preferred over the use of member functions offering comparable functionality. E.g., rather than writing

```
if (string1.compare(string2) == 0)
```

the following is generally preferred:

```
if (string1 == string2)
```

To define and use `string`-type objects, sources must include the header file `string`. To merely *declare* the `string` type the header should be included.

¹We define an ASCII-Z string as a series of ASCII-characters terminated by the ASCII-character zero (hence -Z), which has the value zero, and should not be confused with character ‘0’, which usually has the value 0x30

5.1 Operations on strings

Some of the operations that can be performed on strings return indices within the strings. Whenever such an operation fails to find an appropriate index, the *value* `string::npos` is returned. This value is a symbolic value of type `string::size_type`, which is (for all practical purposes) an (unsigned) `int`.

All `string` members accepting `string` objects as arguments also accept `char const *` (C ASCII-Z `string`) arguments. The same usually holds true for operators accepting `string` objects.

Some `string`-members use *iterators*. Iterators are formally introduced in section 18.2. Member functions using iterators are listed in the next section (5.2), but the iterator concept itself is not further covered by this chapter.

Strings support a large variety of members and operators. A short overview listing their capabilities is provided in this section, with subsequent sections offering a detailed discussion. The bottom line: C++ strings are extremely versatile and there is hardly a reason for falling back on the C library to process text. C++ strings handle all the required memory management and thus memory related problems, which is the #1 source of problems in C programs, can be prevented when C++ strings are used. Strings do come at a price, though. The class’s extensive capabilities have also turned it into a beast. It’s hard to learn and master all its features and in the end you’ll find that not all that you expected is actually there. For example, `std::string` doesn’t offer case-insensitive comparisons. But in the end it even isn’t as simple as that. It *is* there, but it is somewhat hidden and at this point in the C++ Annotations it’s too early to study into that hidden corner yet. Instead, realize that C’s standard library *does* offer useful functions that can be used as long as we’re aware of their limitations and are able to avoid their traps. So for now, to perform a classical case-insensitive comparison of the contents of two `std::string` objects `str1` and `str2` the following will do:

```
strcasecmp(str1.c_str(), str2.c_str());
```

Strings support the following functionality:

- initialization:

when `string` objects are defined they are always properly initialized. In other words, they are always in a valid state. Strings may be initialized empty or already existing text can be used to initialize strings.

- assignment:

strings may be given new values. New values may be assigned using member functions (like `assign`) but a plain assignment operator (i.e., `=`) may also be used. Furthermore, assignment to a character buffer is also supported.

- conversions:

the partial or complete contents of `string` objects may be interpreted as C strings but the `string`’s contents may also be processed as a series of raw binary bytes, not necessarily terminating in an ASCII-Z byte. Furthermore, in many situations plain characters and C strings may be used where `std::strings` are accepted as well.

- breakdown:

the individual characters stored in a `string` can be accessed using the familiar index operator (`[]`) allowing us to either access or modify information in the middle of a `string`.

- comparisons:

strings may be compared to other strings (or C ASCII-Z strings) using the familiar logical comparison operators `==`, `!=`, `<`, `<=`, `>` and `>=`. There are also member functions available offering a more fine-grained comparison.

- `modification`:

the contents of strings may be modified in many ways. Operators are available to add information to string objects, to insert information in the middle of string objects, or to replace or erase (parts of) a string's contents.

- `swapping`:

the string's swapping capability allows us in principle to exchange the contents of two string objects without a byte-by-byte copying operation of the string's contents.

- `searching`:

the locations of characters, sets of characters, or series of characters may be searched for from any position within the string object and either searching in a forward or backward direction.

- `housekeeping`:

several housekeeping facilities are offered: the string's length, or its empty-state may be interrogated. But string objects may also be resized.

- `stream I/O`:

strings may be extracted from or inserted into streams. In addition to plain string extraction a line of a text file may be read without running the risk of a buffer overrun. Since extraction and insertion operations are stream based the I/O facilities are *device independent*.

5.2 A `std::string` reference

In this section the string members and string-related operations are referenced. The subsections cover, respectively the string's initializers, iterators, operators, and member functions. The following terminology is used throughout this section:

- `object` is always a `string-object`;
- `argument` is a `string const &` or a `char const *` unless indicated otherwise. The contents of an argument never is modified by the operation processing the argument;
- `opos` refers to an offset into an object `string`;
- `apos` refers to an offset into an argument;
- `on` represents a number of characters in an object (starting at `opos`);
- `an` represents a number of characters in an argument (starting at `apos`).

Both `opos` and `apos` must refer to existing offsets, or an exception (cf. chapter 9) is generated. In contrast, `an` and `on` may exceed the number of available characters, in which case only the available characters will be considered.

Many members declare default values for `on`, `an` and `apos`. Some members declare default values for `opos`. Default offset values are 0, the default values of `on` and `an` is `string::npos`, which can be interpreted as 'the required number of characters to reach the end of the string'.

With members starting their operations at the end of the string object's contents proceeding backwards, the default value of `opos` is the index of the object's *last* character, with `on` by default equal to `opos + 1`, representing the length of the substring *ending* at `opos`.

In the overview of member functions presented below it may be assumed that all these parameters accept default values unless indicated otherwise. Of course, the default argument values cannot be used if a function requires additional arguments beyond the ones otherwise accepting default values.

Some members have overloaded versions expecting an initial argument of type `char const *`. But even if that is not the case the first argument can *always* be of type `char const *` where a parameter of `std::string` is defined.

Several member functions accept *iterators*. Section 18.2 covers the technical aspects of *iterators*, but these may be ignored at this point without loss of continuity. Like `apos` and `opos`, iterators must refer to existing positions and/or to an existing range of characters within the string object’s contents.

Finally, all string-member functions computing indices return the predefined constant `string::npos` on failure.

5.2.1 Initializers

After defining string objects they are guaranteed to be in a valid state. At *definition time* string objects may be initialized in one of the following ways: The following string constructors are available:

- `string object`:
initializes object to an empty string. When defining a string this way no argument list may be specified;
- `string object(string::size_type count, char ch)`:
initializes object with count characters `ch`;
- `string object(string const &argument)`:
initializes object with argument;
- `string object(std::string const &argument, string::size_type apos, string::size_type an)`:
initializes object with argument’s contents starting at index position `apos`, using at most `an` of argument’s characters;
- `string object(InputIterator begin, InputIterator end)`:
initializes object with the characters in the range of characters defined by the two InputIterators.

5.2.2 Iterators

See section 18.2 for details about *iterators*. As a quick introduction to iterators: an iterator acts like a pointer, and pointers can often be used in situations where iterators are requested. Iterators usually come in pairs, defining a range of entities. The begin-iterator points to the first entity of the range, the end-iterator points just beyond the last entity that will be considered. Their difference is equal to the number of entities in the iterator-range.

Iterators play an important role in the context of *generic algorithms* (cf. chapter 19). The class `std::string` defines the following *iterator types*:

- `string::iterator` and `string::const_iterator`:
these iterators are *forward iterators*. The `const_iterator` is returned by `string const` objects, the plain iterator is returned by non-const string objects. Characters referred to by iterators may be modified;
- `string::reverse_iterator` and `string::reverse_const_iterator`:
these iterators are also *forward iterators* but when *incrementing* the iterator the *previous* character in the string object is reached. Other than that they are comparable to, respectively, `string::iterator` and `string::const_iterator`.

5.2.3 Operators

String objects may be manipulated by member functions but also by operators. Using operators often results in more natural-looking code. In cases where operators are available having equivalent functionality as member function the operator is practically always preferred.

The following operators are available for `string` objects (in the examples ‘object’ and ‘argument’ refer to existing `std::string` objects).

- plain assignment:

a character, **C** or **C++** string may be assigned to a `string` object. The assignment operator returns its left-hand side operand. Example:

```
object = argument;
object = "C string";
object = 'x';
object = 120;           // same as object = 'x'
```

- addition:

the arithmetic additive assignment operator and the addition operator add text to a `string` object. The arithmetic assignment operator returns its left-hand side operand, the addition operator returns its result in a temporary `string` object. When using the addition operator either the left-hand side operand or the right-hand side operand must be a `std::string` object. The other operand may be a `char`, a **C** string or a **C++** string. Example:

```
object += argument;
object += "hello";
object += 'x';           // integral expressions are OK

argument + otherArgument; // two std::string objects
argument + "hello";       // using + at least one
"hello" + argument;       // std::string is required
argument + 'a'            // integral expressions are OK
'a' + argument;
```

- index operator:

The index operator may be used to retrieve object’s individual characters, or to assign new values to individual characters of a non-const `string` object. There is no range-checking (use the `at()` member function for that). This operator returns a `char &` or `char const &`. Example:

```
object[3] = argument[5];
```

- logical operators:

the logical comparison operators may be applied to two `string` objects or to a `string` object and a **C** string to compare their contents. These operators return a `bool` value. The `==`, `!=`, `>`, `>=`, `<` and `<=` operators are available. The ordering operators perform a lexicographical comparison of their contents using the ASCII character collating sequence. Example:

```
object == object;        // true
object != (object + 'x'); // true
object <= (object + 'x'); // true
```

- stream related operators:

the insertion-operator (cf. section 3.1.4) may be used to insert a `string` object into an `ostream`, the extraction-operator may be used to extract a `string` object from an `istream`. The extraction operator by default first ignores all white space characters

and then extracts all consecutively non-blank characters from an `istream`. Instead of a string a character array may be extracted as well, but the advantage of using a string object should be clear: the destination string object is automatically resized to the required number of characters. Example:

```
cin >> object;
cout << object;
```

5.2.4 Member functions

The `std::string` class offers many member function as well as additional non-member functions that should be considered part of the string class. All these functions are listed below in alphabetic order.

The symbolic value `string::npos` is defined by the string class. It represents 'index-not-found' when returned by member functions returning string offset positions. Example: when calling `object.find('x')` (see below) on a string object not containing the character 'x', `npos` is returned, as the requested position does not exist.

The final 0-byte used in C strings to indicate the end of an ASCII-Z string is *not* considered part of a C++ string, and so the member function will return `npos`, rather than `length()` when looking for 0 in a string object containing the characters of a C string.

Here are the standard functions that operate on objects of the class `string`. When a parameter of `size_t` is mentioned it may be interpreted as a parameter of type `string::size_type`, but without defining a default argument value. The type `size_type` should be read as `string::size_type`. With `size_type` the default argument values mentioned in section 5.2 apply. All quoted functions are member functions of the class `std::string`, except where indicated otherwise.

- `char &at(size_t opos):`

a reference to the character at the indicated position is returned. When called with `string` const objects a `char const &` is returned. The member function performs range-checking, raising an exception (that by default aborts the program) if an invalid index is passed.

- `string &append(InputIterator begin, InputIterator end):`

the characters in the range defined by `begin` and `end` are appended to the current string object.

- `string &append(string const &argument, size_type apos, size_type an):`

`argument` (or a substring) is appended to the current string object.

- `string &append(char const *argument, size_type an):`

the first `an` characters of `argument` are appended to the string object.

- `string &append(size_type n, char ch):`

`n` characters `ch` are appended to the current string object.

- `string &assign(string const &argument, size_type apos, size_type an):`

`argument` (or a substring) is assigned to the string object. If `argument` is of type `char const *` and one additional argument is provided the second argument is interpreted as a value initializing `an`, using 0 to initialize `apos`.

- `string &assign(size_type n, char ch):`

`n` characters `ch` are assigned to the current string object.

- `size_type capacity() const:`

the number of characters that can currently be stored in the string object without needing to resize it is returned.

- `int compare(string const &argument) const:`

the text stored in the current string object and the text stored in `argument` is compared using a lexicographical comparison using the ASCII character collating sequence. zero is returned if the two strings have identical contents, a negative value is returned if the text in the current object should be ordered *before* the text in `argument`; a positive value is returned if the text in the current object should be ordered *beyond* the text in `argument`.

- `int compare(size_t opos, size_t on, string const &argument) const:`

a substring of the text stored in the current string object is compared to the text stored in `argument`. At most `on` characters starting at offset `opos` are compared to the text in `argument`.

- `int compare(size_t opos, size_t on, string const &argument, size_type apos, size_type an):`

a substring of the text stored in the current string object is compared to a substring of the text stored in `argument`. At most `on` characters of the current string object, starting at offset `opos`, are compared to at most `an` characters of `argument`, starting at offset `apos`. In this case `argument` *must* be a string object.

- `int compare(size_t opos, size_t on, char const *argument, size_t an):`

a substring of the text stored in the current string object is compared to a substring of the text stored in `argument`. At most `on` characters of the current string object starting at offset `opos` are compared to at most `an` characters of `argument`. `Argument` must have at least `an` characters. The characters may have arbitrary values: the ASCII-Z value has no special meaning.

- `size_t copy(char *argument, size_t on, size_type opos) const:`

the contents of the current string object are (partially) copied into `argument`. The actual number of characters copied is returned. The second argument, specifying the number of characters to copy, from the current string object is required. No ASCII-Z is appended to the copied string but can be appended to the copied text using an idiom like the following:

```
argument[object.copy(argument, string::npos)] = 0;
```

Of course, the programmer should make sure that `argument`'s size is large enough to accomodate the additional 0-byte.

- `char const *c_str() const:`

the contents of the current string object as an ASCII-Z terminated C-string.

- `char const *data() const:`

the raw contents of the current string object are returned. Since this member does not return an ASCII-Z terminated C string (as `c_str` does), it can be used to retrieve any kind of information stored inside the current string object including, e.g., series of 0-bytes:

```
string s(2, 0);
cout << static_cast<int>(s.data()[1]) << '\n';
```

- `bool empty() const:`

true is returned if the current string object contains no data.

- `string &erase(size_type opos, size_type on):`

a (sub)string of the information stored in the current string object is erased.

- `string::iterator erase(string::iterator begin, string::iterator end):`

the parameter `end` is optional. If omitted the value returned by the current object's `end` member is used. The characters defined by the `begin` and `end` iterators are erased. The iterator `begin` is returned, which is then referring to the position immediately following the last erased character.

- `size_t find(string const &argument, size_type opos) const:`

the first index in the current string object where `argument` is found is returned.

- `size_t find(char const *argument, size_type opos, size_type an) const:`

the first index in the current string object where `argument` is found is returned. When all three arguments are specified the first argument *must* be a `char const *`.

- `size_t find(char ch, size_type opos) const:`

the first index in the current string object where `ch` is found is returned.

- `size_t find_first_of(string const &argument, size_type opos) const:`

the first index in the current string object where any character in `argument` is found is returned.

- `size_type find_first_of(char const *argument, size_type opos, size_type an) const:`

the first index in the current string object where any character in `argument` is found is returned. If `opos` is provided it refers to the first index in the current string object where the search for `argument` should start. If omitted, the string object is scanned completely. If `an` is provided it indicates the number of characters of the `char const * argument` that should be used in the search. It defines a substring starting at the beginning of `argument`. If omitted, all of `argument`'s characters are used.

- `size_type find_first_of(char ch, size_type opos):`

the first index in the current string object where character `ch` is found is returned.

- `size_t find_first_not_of(char ch, size_type opos) const:`

the first index in the current string object where another character than `ch` is found is returned.

- `size_t find_last_of(string const &argument, size_type opos) const:`

the last index in the current string object where any character in `argument` is found is returned.

- `size_type find_last_of(char const *argument, size_type opos, size_type an) const:`

the last index in the current string object where any character in `argument` is found is returned. If `opos` is provided it refers to the last index in the current string object where the search for `argument` should start. If omitted, the string object is scanned completely. If `an` is provided it indicates the number of characters of the `char const * argument` that should be used in the search. It defines a substring starting at the beginning of `argument`. If omitted, all of `argument`'s characters are used.

- `size_type find_last_of(char ch, size_type opos):`

the last index in the current string object where character `ch` is found is returned.

- `size_t find_last_not_of(string const &argument, size_type opos) const:`
the last index in the current string object where any character *not* appearing in argument is found is returned.
- `istream &std::getline(istream &istr, string &object, char delimiter = '\\n'):`

Note: this is *not* a member function of the class `string`.

A line of text is read from `istr`. All characters until `delimiter` (or the end of the stream, whichever comes first) are read from `istr` and are stored in `object`. If the `delimiter` is encountered it is removed from the stream, but is not stored in `line`.

If the `delimiter` is not found, `istr.eof` returns `true` (see section 6.3.1). Since streams may be interpreted as `bool` values (cf. section 6.3.1) a commonly encountered idiom to read all lines from a stream successively into a string object `line` looks like this:

```
while (getline(istr, line))
    process(line);
```

The contents of the last line, whether or not it was terminated by a `delimiter`, is eventually also assigned to `object`.

- `string &insert(size_t opos, string const &argument, size_type apos, size_type an)`
a (sub)string of `argument` is inserted into the current string object at the current string object's index position `opos`. Arguments for `apos` and `an` must either both be provided or they must both be omitted.
- `string &insert(size_t opos, char const *argument, size_type an):`
`argument` (of type `char const *`) is inserted at index `opos` into the current string object.
- `string &insert(size_t opos, size_t count, char ch):`
Count characters `ch` are inserted at index `opos` into the current string object.
- `string::iterator insert(string::iterator begin, char ch):`
the character `ch` is inserted at the current object's position referred to by `begin`. `Begin` is returned.
- `string::iterator insert(string::iterator begin, size_t count, char ch):`
Count characters `ch` are inserted at the current object's position referred to by `begin`. `Begin` is returned.
- `string::iterator insert(string::iterator begin, InputIterator abegin, InputIterator aend):`
the characters in the range defined by the `InputIterators` `abegin` and `aend` are inserted at the current object's position referred to by `begin`. `Begin` is returned.
- `size_t length() const:`
the number of characters stored in the current string object is returned.
- `size_t max_size() const:`
the maximum number of characters that can be stored in the current string object is returned.
- `string &replace(size_t opos, size_t on, string const &argument, size_type apos, size_type an):`
a (sub)string of characters in `object` are replaced by the (subset of) characters of `argument`. If `on` is specified as 0 `argument` is inserted into `object` at offset `opos`.

- `string &replace(size_t opos, size_t on, char const *argument, size_type an):`

a series of characters in object are be replaced by the first an characters of char const * argument.

- `string &replace(size_t opos, size_t on, size_type count, char ch):`

on characters of the current string object, starting at index position opos, are replaced by count characters ch.

- `string &replace(string::iterator begin, string::iterator end, string const &argument):`

the series of characters in the current string object defined by the iterators begin and end are replaced by argument. If argument is a char const *, an additional argument an may be used, specifying the number of characters of argument that are used in the replacement.

- `string &replace(string::iterator begin, string::iterator end, size_type count, char ch):`

the series of characters in the current string object defined by the iterators begin and end are replaced by count characters having values ch.

- `string &replace(string::iterator begin, string::iterator end, InputIterator abegin, InputIterator aend):`

the series of characters in the current string object defined by the iterators begin and end are replaced by the characters in the range defined by the InputIterators abegin and aend.

- `void reserve(size_t request):`

the current string object's capacity is changed to at least request. After calling this member, capacity's return value will be at least request. A request for a smaller size than the value returned by capacity is ignored. A `std::length_error` exception is thrown if request exceeds the value returned by `max_size` (`std::length_error` is defined in the `stdexcept` header). Calling `reserve()` has the effect of redefining a string's capacity, not of actually making available the memory to the program. This is illustrated by the exception thrown by the string's `at()` member when trying to access an element exceeding the string's size but not the string's capacity.

- `void resize(size_t size, char ch = 0):`

the current string object is resized to size characters. If the string object is resized to a size larger than its current size the additional characters will be initialized to ch. If it is reduced in size the characters having the highest indices are chopped off.

- `size_t rfind(string const &argument, size_type opos) const:`

the last index in the current string object where argument is found is returned. Searching proceeds from the current object's offset opos back to its beginning.

- `size_t rfind(char const *argument, size_type opos, size_type an) const:`

the last index in the current string object where argument is found is returned. Searching proceeds from the current object's offset opos back to its beginning. The parameter an specifies the length of the substring of argument to look for, starting at argument's beginning.

- `size_t rfind(char ch, size_type opos) const:`

the last index in the current string object where ch is found is returned. Searching proceeds from the current object's offset opos back to its beginning.

- `size_t size() const`:

the number of characters stored in the current string object is returned. This member is a synonym of `length()`.

- `string substr(size_type opos, size_type on) const`:

a substring of the current string object of at most `on` characters starting at index `opos` is returned.

- `void swap(string &argument)`:

the contents of the current string object are swapped with the contents of `argument`. For this member `argument` must be a string object and cannot be a `char const *`.

Chapter 6

The IO-stream Library

Extending the standard stream (FILE) approach, well known from the C programming language, C++ offers an *input/output* (I/O) library based on class concepts.

All C++ I/O facilities are defined in the namespace `std`. The `std::` prefix is omitted below, except for situations where this would result in ambiguities.

Earlier (in chapter 3) we've seen several examples of the use of the C++ I/O library, in particular showing insertion operator (`<<`) and the extraction operator (`>>`). In this chapter we'll cover I/O in more detail.

The discussion of input and output facilities provided by the C++ programming language heavily uses the class concept and the notion of member functions. Although class construction has not yet been covered (for that see chapter 7) and although *inheritance* will not be covered formally before chapter 13, we think it is quite possible to introduce I/O facilities long before the technical background of their construction has been covered.

Most C++ I/O classes have names starting with `basic_` (like `basic_ios`). However, these `basic_` names are not regularly found in C++ programs, as most classes are also defined using `typedef` definitions like:

```
typedef basic_ios<char>      ios;
```

Since C++ supports various kinds of character types (e.g., `char`, `wchar_t`), I/O facilities were developed using the *template* mechanism allowing for easy conversions to character types other than the traditional `char` type. As elaborated in chapter 20, this also allows the construction of generic software, that could thereupon be used for any particular type representing characters. So, analogously to the above `typedef` there exists a

```
typedef basic_ios<wchar_t>   wios;
```

This type definition can be used for the `wchar_t` type. Because of the existence of these type definitions, the `basic_` prefix was omitted from the C++ Annotations without loss of continuity. The C++ Annotations primarily focus on the standard 8-bits `char` type.

It must be stressed that it is *not* correct anymore to declare `iostream` objects using standard forward declarations, like:

```
class std::ostream;      // now erroneous
```

Instead, sources that must declare `iostream` classes must

```
#include <iosfwd>         // correct way to declare iostream classes
```

Using C++ I/O offers the additional advantage of *type safety*. Objects (or plain values) are inserted into streams. Compare this to the situation commonly encountered in C where the `fprintf` function is used to indicate by a format string what kind of value to expect where. Compared to this latter situation C++'s *iostream* approach immediately uses the objects where their values should appear, as in

```
cout << "There were " << nMaidens << " virgins present\n";
```

The compiler notices the type of the `nMaidens` variable, inserting its proper value at the appropriate place in the sentence inserted into the `cout` *iostream*.

Compare this to the situation encountered in C. Although C compilers are getting smarter and smarter, and although a well-designed C compiler may warn you for a mismatch between a format specifier and the type of a variable encountered in the corresponding position of the argument list of a `printf` statement, it can't do much more than *warn* you. The *type safety* seen in C++ *prevents* you from making type mismatches, as there are no types to match.

Apart from this, *iostreams* offer more or less the same set of possibilities as the standard FILE-based I/O used in C: files can be opened, closed, positioned, read, written, etc.. In C++ the basic FILE structure, as used in C, is still available. But C++ adds to this I/O based on classes, resulting in type safety, extensibility, and a clean design.

In the ANSI/ISO standard the intent was to create architecture independent I/O. Previous implementations of the *iostreams* library did not always comply with the standard, resulting in many extensions to the standard. The I/O sections of previously developed software may have to be partially rewritten. This is tough for those who are now forced to modify old software, but every feature and extension that was once available can be rebuilt easily using ANSI/ISO standard conforming I/O. Not all of these reimplementations can be covered in this chapter, as many reimplementations relies on inheritance and polymorphism, which will not be covered until chapters 13 and 14. Selected reimplementations will be provided in chapter 23, and in this chapter references to particular sections in other chapters will be given where appropriate. This chapter is organized as follows (see also Figure 6.1):

- The class `ios_base` is the foundation upon which the *iostreams* I/O library was built. It defines the core of all I/O operations and offers, among other things, facilities for inspecting the state of I/O streams and for output formatting.
- The class `ios` was directly derived from `ios_base`. Every class of the I/O library doing input or output is itself *derived* from this `ios` class, and so *inherits* its (and, by implication, `ios_base`'s) capabilities. The reader is urged to keep this in mind while reading this chapter. The concept of inheritance is not discussed here, but rather in chapter 13.

The class `ios` is important in that it implements the communication with a *buffer* that is used by streams. This buffer is a `streambuf` object which is responsible for the actual I/O to/from the underlying *device*. Consequently *iostream* objects do not perform I/O operations themselves, but leave these to the (stream)buffer objects with which they are associated.

- Next, basic C++ output facilities are discussed. The basic class used for output operations is `ostream`, defining the insertion operator as well as other facilities writing information to streams. Apart from inserting information into files it is possible to insert information into memory buffers, for which the `ostringstream` class is available. Formatting output is to a great extent possible using the facilities defined in the `ios` class, but it is also possible to *insert formatting commands* directly into streams using *manipulators*. This aspect of C++ output is discussed as well.
- Basic C++ input facilities are implemented by the `istream` class. This class defines the extraction operator and related input facilities. Comparably to insert information into to memory buffers (using `ostringstream`) a class `istream` is available to extract information from memory buffers.
- Finally, several advanced I/O-related topics are discussed. E.g., reading and writing from the same stream and mixing C and C++ I/O using `filebuf` objects. Other I/O related topics are covered elsewhere in the C++ Annotations, e.g., in chapter 23.




Figure 6.1: Central I/O Classes

Stream objects have a limited but important role: they are the interface between, on the one hand, the objects to be input or output and, on the other hand, the `streambuf`, which is responsible for the actual input and output to the device accessed by a `streambuf` object.

This approach allows us to construct a new kind of `streambuf` for a new kind of device, and use that `streambuf` in combination with the ‘good old’ `istream`- and `ostream`-class facilities. It is important to understand the distinction between the formatting roles of `istream` objects and the buffering interface to an external device as implemented in a `streambuf` object. Interfacing to new devices (like *sockets* or *file descriptors*) requires the construction of a new kind of `streambuf`, rather than a new kind of `istream` or `ostream` object. A *wrapper class* may be constructed around the `istream` or `ostream` classes, though, to ease the access to a special device. This is how the `stringstream` classes were constructed.

6.1 Special header files

Several `istream` related header files are available. Depending on the situation at hand, the following header files should be used:

- `iosfwd`: sources should include this header file if only a declaration of the stream classes is required. For example, if a function defines a reference parameter to an `ostream` then the compiler doesn’t need to know exactly what an `ostream` is. When declaring such a function the `ostream` class merely needs to be declared. One cannot use

```
class std::ostream; // erroneous declaration

void someFunction(std::ostream &str);
```

but, instead, one should use:

```
#include <iosfwd> // correctly declares class ostream

void someFunction(std::ostream &str);
```

- `<streambuf>`: sources should include this header file when using `streambuf` or `filebuf` classes. See sections [14.7](#) and [14.7.2](#).
- `<istream>`: sources should include this preprocessor directive when using the class `istream` or when using classes that do both input and output. See section [6.5.1](#).
- `<ostream>`: sources should include this header file when using the class `ostream` class or when using classes that do both input and output. See section [6.4.1](#).
- `<iostream>`: sources should include this header file when using the global stream objects (like `cin` and `cout`).
- `<fstream>`: sources should include this header file when using the file stream classes. See sections [6.4.2](#), [6.5.2](#), and [6.6.2](#).
- `<sstream>`: sources should include this header file when using the string stream classes. See sections [6.4.3](#) and [6.5.3](#).
- `<iomanip>`: sources should include this header file when using parameterized manipulators. See section [6.3.2](#).

6.2 The foundation: the class ‘ios_base’

The class `std::ios_base` forms the foundation of all I/O operations, and defines, among other things, facilities for inspecting the state of I/O streams and most output formatting facilities. Every stream

class of the I/O library is, through the class `ios`, *derived* from this class, and *inherits* its capabilities. As `ios_base` is the foundation on which all C++ I/O was built, we introduce it here as the first class of the C++ I/O library.

Note that, as in C, I/O in C++ is *not* part of the language (although it *is* part of the ANSI/ISO standard on C++). Although it is technically possible to ignore all predefined I/O facilities, nobody does so, and the I/O library therefore represents a *de facto* I/O standard for C++. Also note that, as mentioned before, the `iostream` classes themselves are not responsible for the eventual I/O, but delegate this to an auxiliary class: the class `streambuf` or its derivatives.

It is neither possible nor required to construct an `ios_base` object directly. Its construction is always a side-effect of constructing an object further down the class hierarchy, like `std::ios`. `ios` is the next class down the `iostream` hierarchy (see figure 6.1). Since all stream classes in turn inherit from `ios`, and thus also from `ios_base`, the distinction between `ios_base` and `ios` is in practice not important. Therefore, facilities actually provided by `ios_base` will be discussed as facilities provided by `ios`. The reader who is interested in the true class in which a particular facility is defined should consult the relevant header files (e.g., `ios_base.h` and `basic_ios.h`).

6.3 Interfacing ‘streambuf’ objects: the class ‘ios’

The `std::ios` class is derived directly from `ios_base`, and it defines *de facto* the foundation for all stream classes of the C++ I/O library.

Although it is possible to construct an `ios` object directly, this is seldom done. The purpose of the class `ios` is to provide the facilities of the class `basic_ios`, and to add several new facilities, all related to the `streambuf` object which is managed by objects of the class `ios`.

All other stream classes are either directly or indirectly derived from `ios`. This implies, as explained in chapter 13, that all facilities of the classes `ios` and `ios_base` are also available to other stream classes. Before discussing these additional stream classes, the features offered by the class `ios` (and by implication: by `ios_base`) are now introduced.

In some cases it may be required to include `ios` explicitly. An example is the situations where the formatting flags themselves (cf. section 6.3.2.2) are referred to in source code.

The class `ios` offers several member functions, most of which are related to formatting. Other frequently used member functions are:

- `std::streambuf *ios::rdbuf();`

A pointer to the `streambuf` object forming the interface between the `ios` object and the device with which the `ios` object communicates is returned. See section 23.1.2 for further information about the class `streambuf`.

- `std::streambuf *ios::rdbuf(std::streambuf *new);`

The current `ios` object is associated with another `streambuf` object. A pointer to the `ios` object’s original `streambuf` object is returned. The object to which this pointer points is not destroyed when the stream object goes out of scope, but is owned by the caller of `rdbuf`.

- `std::ostream *ios::tie();`

A pointer to the `ostream` object that is currently tied to the `ios` object is returned (see the next member). The return value 0 indicates that currently no `ostream` object is tied to the `ios` object. See section 6.5.5 for details.

- `std::ostream *ios::tie(std::ostream *outs);`

The `ostream` object is tied to current `ios` object. This means that the `ostream` object is *flushed* every time before an input or output action is performed by the current `ios`

object. A pointer to the `ios` object's original `ostream` object is returned. To break the tie, pass the argument 0. See section 6.5.5 for an example.

6.3.1 Condition states

Operations on streams may fail for various reasons. Whenever an operation fails, further operations on the stream are suspended. It is possible to inspect (and possibly: clear) the condition state of streams, allowing a program to repair the problem rather than having to abort.

Conditions are represented by the following *condition flags*:

- `ios::badbit`:

if this flag has been raised an illegal operation has been requested at the level of the `streambuf` object to which the stream interfaces. See the member functions below for some examples.

- `ios::eofbit`:

if this flag has been raised, the `ios` object has sensed end of file.

- `ios::failbit`:

if this flag has been raised, an operation performed by the stream object has failed (like an attempt to extract an `int` when no numeric characters are available on input). In this case the stream itself could not perform the operation that was requested of it.

- `ios::goodbit`:

this flag is raised when none of the other three condition flags were raised.

Several condition member functions are available to manipulate or determine the states of `ios` objects. Originally they returned `int` values, but their current return type is `bool`:

- `ios::bad()`:

the value `true` is returned when the stream's `badbit` has been set and `false` otherwise. If `true` is returned it indicates that an illegal operation has been requested at the level of the `streambuf` object to which the stream interfaces. What does this mean? It indicates that the `streambuf` itself is behaving unexpectedly. Consider the following example:

```
std::ostream error(0);
```

Here an `ostream` object is constructed *without* providing it with a working `streambuf` object. Since this 'streambuf' will never operate properly, its `badbit` flag is raised from the very beginning: `error.bad()` returns `true`.

- `ios::eof()`:

the value `true` is returned when end of file (EOF) has been sensed (i.e., the `eofbit` flag has been set) and `false` otherwise. Assume we're reading lines line-by-line from `cin`, but the last line is not terminated by a final `\n` character. In that case `std::getline` attempting to read the `\n` delimiter hits end-of-file first. This raises the `eofbit` flag and `cin.eof()` returns `true`. For example, assume `std::string str` and `main` executing the statements:

```
getline(cin, str);
cout << cin.eof();
```

Then

```
echo "hello world" | program
```

prints the value 0 (no EOF sensed). But after

```
echo -n "hello world" | program
```

the value 1 (EOF sensed) is printed.

- `ios::fail()`:

the value `true` is returned when `bad` returns `true` or when the `failbit` flag was set. The value `false` is returned otherwise. In the above example, `cin.fail()` returns `false`, whether we terminate the final line with a delimiter or not (as we've read a line). However, trying to execute a second `getline` will set the `failbit` flag, causing `cin::fail()` to return `true`. In general: `fail` returns `true` if the requested stream operation failed. A simple example showing this consists of an attempt to extract an `int` when the input stream contains the text `hello world`. The value `not fail()` is returned by the `bool` interpretation of a stream object (see below).

- `ios::good()`:

the value of the `goodbit` flag is returned. It equals `true` when none of the other condition flags (`badbit`, `eofbit`, `failbit`) was raised. Consider the following little program:

```
#include <iostream>
#include <string>

using namespace std;

void state()
{
    cout << "\n"
         << "Bad: " << cin.bad() << " "
         << "Fail: " << cin.fail() << " "
         << "Eof: " << cin.eof() << " "
         << "Good: " << cin.good() << '\n';
}

int main()
{
    string line;
    int x;

    cin >> x;
    state();

    cin.clear();
    getline(cin, line);
    state();

    getline(cin, line);
    state();
}
```

When this program processes a file having two lines, containing, respectively, `hello` and `world`, while the second line is not terminated by a `\n` character the following is shown:

```
Bad: 0 Fail: 1 Eof: 0 Good: 0

Bad: 0 Fail: 0 Eof: 0 Good: 1

Bad: 0 Fail: 0 Eof: 1 Good: 0
```


Thus, extracting `x` fails (good returning false). Then, the error state is cleared, and the first line is successfully read (good returning true). Finally the second line is read (incompletely): good returning false, and eof returning true.

- Interpreting streams as bool values:

streams may be used in expressions expecting logical values. Some examples are:

```
if (cin)                // cin itself interpreted as bool
if (cin >> x)           // cin interpreted as bool after an extraction
if (getline(cin, str))  // getline returning cin
```

When interpreting a stream as a logical value, it is actually `'not fail()'` that is interpreted. The above examples may therefore be rewritten as:

```
if (not cin.fail())
if (not (cin >> x).fail())
if (not getline(cin, str).fail())
```

The former incantation, however, is used almost exclusively.

The following members are available to manage error states:

- `ios::clear()`:

When an error condition has occurred, and the condition can be repaired, then `clear` can be used to clear the error state of the file. An overloaded version exists accepting state flags, that are set after first clearing the current set of flags: `clear(int state)`. Its return type is `void`

- `ios::rdstate()`:

The current set of flags that are set for an `ios` object are returned (as an `int`). To test for a particular flag, use the bitwise and operator:

```
if (!(iosObject.rdstate() & ios::failbit))
{
    // last operation didn't fail
}
```

Note that this test cannot be performed for the `goodbit` flag as its value equals zero. To test for 'good' use a construction like:

```
if (iosObject.rdstate() == ios::goodbit)
{
    // state is 'good'
}
```

- `ios::setstate(ios::iostate state)`:

A stream may be assigned a certain set of states using `setstate`. Its return type is `void`. E.g.,

```
cin.setstate(ios::failbit);    // set state to 'fail'
```

To set multiple flags in one `setstate()` call use the bitor operator:

```
cin.setstate(ios::failbit | ios::eofbit)
```

The member `clear` is a shortcut to clear all error flags. Of course, clearing the flags doesn't automatically mean the error condition has been cleared too. The strategy should be:

- An error condition is detected,
- The error is repaired
- The member `clear` is called.

C++ supports an *exception* mechanism to handle exceptional situations. According to the ANSI/ISO standard, exceptions can be used with stream objects. Exceptions are covered in chapter 9. Using exceptions with stream objects is covered in section 9.7.

6.3.2 Formatting output and input

The way information is written to streams (or, occasionally, read from streams) is controlled by *formatting flags*.

Formatting is used when it is necessary to, e.g., set the width of an output field or input buffer and to determine the form (e.g., the *radix*) in which values are displayed. Most formatting features belong to the realm of the `ios` class. Formatting is controlled by flags, defined by the `ios` class. These flags may be manipulated in two ways: using specialized member functions or using *manipulators*, which are directly inserted into or extracted from streams. There is no special reason for using either method; usually both methods are possible. In the following overview the various member functions are first introduced. Following this the flags and manipulators themselves are covered. Examples are provided showing how the flags can be manipulated and what their effects are.

Many manipulators are parameterless and are available once a stream header file (e.g., `iostream`) has been included. Some manipulators require arguments. To use the latter manipulators the header file `iosmanip` must be included.

6.3.2.1 Format modifying member functions

Several *member functions* are available manipulating the I/O formatting flags. Instead of using the members listed below *manipulators* are often available that may directly be inserted into or extracted from streams. The available members are listed in alphabetical order, but the most important ones in practice are `setf`, `unsetf` and `width`.

- `ios &ios::copyfmt(ios &obj):`

all format flags of `obj` are copied to the current `ios` object. The current `ios` object is returned.

- `ios::fill() const:`

the current padding character is returned. By default, this is the blank space.

- `ios::fill(char padding):`

the padding character is redefined, the *previous* padding character is returned. Instead of using this member function the *setfill manipulator* may be inserted directly into an ostream. Example:

```
cout.fill('0');           // use '0' as padding char
cout << setfill('+');     // use '+' as padding char
```

- `ios::fmtflags ios::flags() const:`

the current set of flags controlling the format state of the stream for which the member function is called is returned. To inspect whether a particular flag was set, use the `bit_and` operator. Example:

```
if (cout.flags() & ios::hex)
    cout << "Integral values are printed as hex numbers\n"
```

- `ios::fmtflags ios::flags(ios::fmtflags flagset):`

the *previous* set of flags are returned and the new set of flags are defined by `flagset`. Multiple flags are specified using the `bit_or` operator. Example:

```
// change the representation to hexadecimal
cout.flags(ios::hex | cout.flags() & ~ios::dec);
```

- `int ios::precision() const:`

the number of significant digits used when outputting floating point values is returned (default: 6).

- `int ios::precision(int signif):`

the number of significant digits to use when outputting real values is set to `signif`. The previously used number of significant digits is returned. If the number of required digits exceeds `signif` then the number is displayed in ‘scientific’ notation (cf. section 6.3.2.2). Manipulator: `setprecision`. Example:

```
cout.precision(3);           // 3 digits precision
cout << setprecision(3);     // same, using the manipulator

cout << 1.23 << " " << 12.3 << " " << 123.12 << " " << 1234.3 << '\n';
// displays: 1.23 12.3 123 1.23e+03
```

- `ios::fmtflags ios::setf(ios::fmtflags flags):`

sets one or more formatting flags (use the `bitor` operator to combine multiple flags). Already set flags are not affected. The *previous* set of flags is returned. Instead of using this member function the manipulator `setiosflags` may be used. Examples are provided in the next section (6.3.2.2).

- `ios::fmtflags ios::setf(ios::fmtflags flags, ios::fmtflags mask):`

clears all flags mentioned in `mask` and sets the flags specified in `flags`. The *previous* set of flags is returned. Some examples are (but see the next section (6.3.2.2) for a more thorough discussion):

```
// left-adjust information in wide fields
cout.setf(ios::left, ios::adjustfield);
// display integral values as hexadecimal numbers
cout.setf(ios::hex, ios::basefield);
// display floating point values in scientific notation
cout.setf(ios::scientific, ios::floatfield);
```

- `ios::fmtflags ios::unsetf(fmtflags flags):`

the specified formatting flags are cleared (leaving the remaining flags unaltered) and returns the *previous* set of flags. A request to unset an active default flag (e.g., `cout.unsetf(ios::dec)`) is ignored. Instead of this member function the manipulator `resetiosflags` may also be used. Example:

```
cout << 12.24;           // displays 12.24
cout << setf(ios::fixed);
cout << 12.24;           // displays 12.240000
cout.unsetf(ios::fixed); // undo a previous ios::fixed setting.
cout << 12.24;           // displays 12.24
cout << resetiosflags(ios::fixed); // using manipulator rather
                                // than unsetf
```

- `int ios::width() const:`

the currently active output field width to use on the next insertion is returned. The default value is 0, meaning ‘as many characters as needed to write the value’.

- `int ios::width(int nchars):`

the field width of the next insertion operation is set to `nchars`, returning the previously used field width. This setting is not persistent. It is reset to 0 after every insertion operation. Manipulator: `std::setw(int)`. Example:

```
cout.width(5);
cout << 12;           // using 5 chars field width
cout << setw(12) << "hello"; // using 12 chars field width
```

6.3.2.2 Formatting flags

Most *formatting flags* are related to outputting information. Information can be written to output streams in basically two ways: using *binary output* information is written directly to an output stream, without converting it first to some human-readable format and using *formatted output* by which values stored in the computer's memory are converted to human-readable text first. Formatting flags are used to define the way this conversion takes place. In this section all formatting flags are covered. Formatting flags may be (un)set using member functions, but often manipulators having the same effect may also be used. For each of the flags it is shown how they can be controlled by a member function or -if available- a manipulator.

To display information in wide fields:

- `ios::internal:`

to add fill characters (blanks by default) between the minus sign of negative numbers and the value itself. Other values and data types are right-adjusted. Manipulator: `std::internal`. Example:

```
cout.setf(ios::internal, ios::adjustfield);
cout << internal;           // same, using the manipulator

cout << '\'' << setw(5) << -5 << "'\n"; // displays '-    5'
```

- `ios::left:`

to left-adjust values in fields that are wider than needed to display the values. Manipulator: `std::left`. Example:

```
cout.setf(ios::left, ios::adjustfield);
cout << left;              // same, using the manipulator

cout << '\'' << setw(5) << "hi" << "'\n"; // displays 'hi    '
```

- `ios::right:`

to right-adjust values in fields that are wider than needed to display the values. Manipulator: `std::right`. This is the default. Example:

```
cout.setf(ios::right, ios::adjustfield);
cout << right;             // same, using the manipulator

cout << '\'' << setw(5) << "hi" << "'\n"; // displays '    hi'
```

Using various number representations:

- `ios::dec:`

to display integral values as decimal numbers. Manipulator: `std::dec`. This is the default. Example:

```
cout.setf(ios::dec, ios::basefield);
cout << dec;                // same, using the manipulator
cout << 0x10;              // displays 16
```

- `ios::hex:`

to display integral values as hexadecimal numbers. Manipulator: `std::hex`. Example:

```
cout.setf(ios::hex, ios::basefield);
cout << hex;               // same, using the manipulator
cout << 16;                // displays 10
```

- `ios::oct`:

to display integral values as octal numbers. Manipulator: `std::oct`. Example:

```
cout.setf(ios::oct, ios::basefield);
cout << oct;           // same, using the manipulator
cout << 16;           // displays 20
```

- `std::setbase(int radix)`:

This is a manipulator that can be used to change the number representation to decimal, hexadecimal or octal. Example:

```
cout << setbase(8);    // octal numbers, use 10 for
                        // decimal, 16 for hexadecimal
cout << 16;           // displays 20
```

Fine-tuning displaying values:

- `ios::boolalpha`:

logical values may be displayed as text using the text ‘true’ for the true logical value, and ‘false’ for the false logical value using `boolalpha`. By default this flag is not set. Complementary flag: `ios::noboolalpha`. Manipulators: `std::boolalpha` and `std::noboolalpha`. Example:

```
cout.setf(ios::boolalpha);
cout << boolalpha;    // same, using the manipulator
cout << (1 == 1);    // displays true
```

- `ios::showbase`:

to display the numeric base of integral values. With hexadecimal values the `0x` prefix is used, with octal values the prefix `0`. For the (default) decimal value no particular prefix is used. Complementary flag: `ios::noshowbase`. Manipulators: `std::showbase` and `std::noshowbase`. Example:

```
cout.setf(ios::showbase);
cout << showbase;    // same, using the manipulator
cout << hex << 16;   // displays 0x10
```

- `ios::showpos`:

to display the `+` sign with positive decimal (only) values. Complementary flag: `ios::noshowpos`. Manipulators: `std::showpos` and `std::noshowpos`. Example:

```
cout.setf(ios::showpos);
cout << showpos;    // same, using the manipulator
cout << 16;        // displays +16
cout.unsetf(ios::showpos); // Undo showpos
cout << 16;        // displays 16
```

- `ios::uppercase`:

to display letters in hexadecimal values using capital letters. Complementary flag: `ios::nouppercase`. Manipulators: `std::uppercase` and `std::nouppercase`. By default lower case letters are used. Example:

```
cout.setf(ios::uppercase);
cout << uppercase;    // same, using the manipulator
cout << hex << showbase <<
    3735928559;      // displays 0XDEADBEEF
```

Displaying floating point numbers

- `ios::fixed`:

to display real values using a fixed decimal point (e.g., 12.25 rather than 1.225e+01), the fixed formatting flag is used. It can be used to set a fixed number of digits behind the decimal point. Manipulator: `fixed`. Example:

```
cout.setf(ios::fixed, ios::floatfield);
cout.precision(3);           // 3 digits behind the .

    // Alternatively:
cout << setiosflags(ios::fixed) << setprecision(3);

cout << 3.0 << " " << 3.01 << " " << 3.001 << '\n';
    << 3.0004 << " " << 3.0005 << " " << 3.0006 << '\n'
    // Results in:
    // 3.000 3.010 3.001
    // 3.000 3.001 3.001
```

The example shows that 3.0005 is rounded away from zero, becoming 3.001 (likewise -3.0005 becomes -3.001). First setting precision and then fixed has the same effect.

- `ios::scientific`:

to display real values in *scientific notation* (e.g., 1.24e+03). Manipulator: `std::scientific`. Example:

```
cout.setf(ios::scientific, ios::floatfield);
cout << scientific;           // same, using the manipulator
cout << 12.25;                // displays 1.22500e+01
```

- `ios::showpoint`:

to display a trailing decimal point *and* trailing decimal zeros when real numbers are displayed. Complementary flag: `ios::noshowpoint`. Manipulators: `std::showpoint`, `std::noshowpoint`. Example:

```
cout << fixed << setprecision(3);    // 3 digits behind .

cout.setf(ios::showpoint);           // set the flag
cout << showpoint;                   // same, using the manipulator

cout << 16.0 << ", " << 16.1 << ", " << 16;
    // displays: 16.0000, 16.1000, 16
```

Note that the final 16 is an integral rather than a floating point number, so it has no decimal point. So `showpoint` has no effect. If `ios::showpoint` is not active trailing zeros are discarded. If the fraction is zero the decimal point is discarded as well. Example:

```
cout.unsetf(ios::fixed, ios::showpoint);    // unset the flags

cout << 16.0 << ", " << 16.1;
    // displays: 16, 16.1
```

Handling white space and flushing streams

- `std::endl`:

manipulator inserting a newline character and flushing the stream. Often flushing the stream is not required and doing so would needlessly slow down I/O processing. Consequently, using `endl` should be avoided (in favor of inserting '`\n`') unless flushing the stream is explicitly intended. Note that streams are automatically flushed when the

program terminates or when a stream is ‘tied’ to another stream (cf. `tie` in section 6.3).

Example:

```
cout << "hello" << endl;    // prefer: << '\n';
```

- `std::ends`:

manipulator inserting a 0-byte into a stream. It is usually used in combination with memory-streams (cf. section 6.4.3).

- `std::flush`:

a stream may be flushed using this member. Often flushing the stream is not required and doing so would needlessly slow down I/O processing. Consequently, using `flush` should be avoided unless it is explicitly required to do so. Note that streams are automatically flushed when the program terminates or when a stream is ‘tied’ to another stream (cf. `tie` in section 6.3). Example:

```
cout << "hello" << flush;    // avoid if possible.
```

- `ios::skipws`:

leading white space characters (blanks, tabs, newlines, etc.) are skipped when a value is extracted from a stream. This is the default. If the flag is not set, leading white space characters are not skipped. Complementary flag: `ios::noskipws`. Manipulators: `std::skipws`, `std::noskipws`. Example:

```
cin.setw(ios::skipws);
cin >> skipws;        // same, using the manipulator
int value;
cin >> value;         // skips initial blanks
```

- `ios::unitbuf`:

the stream for which this flag is set will flush its buffer after every output operation. Often flushing a stream is not required and doing so would needlessly slow down I/O processing. Consequently, setting `unitbuf` should be avoided unless flushing the stream is explicitly intended. Note that streams are automatically flushed when the program terminates or when a stream is ‘tied’ to another stream (cf. `tie` in section 6.3). Complementary flag: `ios::nounitbuf`. Manipulators: `std::unitbuf`, `std::nounitbuf`. Example:

```
cout.setf(ios::unitbuf);
cout << unitbuf;        // same, using the manipulator

cout.write("xyz", 3);    // flush follows write.
```

- `std::ws`:

manipulator removing all white space characters (blanks, tabs, newlines, etc.) at the current file position. White space are removed if present even if the flag `ios::noskipws` has been set. Example (assume the input contains 4 blank characters followed by the character X):

```
cin >> ws;              // skip white space
cin.get();              // returns 'X'
```

6.4 Output

In C++ output is primarily based on the `std::ostream` class. The `ostream` class defines the basic operators and members inserting information into streams: the *insertion operator* (`<<`), and special members like `write` writing unformatted information to streams.

The class `ostream` acts as *base class* for several other classes, all offering the functionality of the `ostream` class, but adding their own specialties. In the upcoming sections we will introduce:

- The class `ostream`, offering the basic output facilities;
- The class `ofstream`, allowing us to write files (comparable to C's `fopen(filename, "w")`);
- The class `ostringstream`, allowing us to write information to memory (comparable to C's `sprintf` function).

6.4.1 Basic output: the class ‘ostream’

The class `ostream` defines basic output facilities. The `cout`, `clog` and `cerr` objects are all `ostream` objects. All facilities related to output as defined by the `ios` class are also available in the `ostream` class.

We may define `ostream` objects using the following *ostream constructor*:

- `std::ostream object(std::streambuf *sb):`

this constructor creates an `ostream` object which is a wrapper around an existing `std::streambuf` object. It isn't possible to define a plain `ostream` object (e.g., using `std::ostream out;`) that can thereupon be used for insertions. When `cout` or its friends are used, we are actually using a predefined `ostream` object that has already been defined for us and interfaces to the standard output stream using a (also predefined) `streambuf` object handling the actual interfacing.

It is, however, possible to define an `ostream` object passing it a 0-pointer. Such an object cannot be used for insertions (i.e., it will raise its `ios::bad` flag when something is inserted into it), but it may be given a `streambuf` later. Thus it may be preliminary constructed, suspending its use until an appropriate `streambuf` becomes available.

To define the `ostream` class in C++ sources, the `ostream` header file must be included. To use the predefined `ostream` objects (`std::cin`, `std::cout` etc.) the `iostream` header must be included.

6.4.1.1 Writing to ‘ostream’ objects

The class `ostream` supports both formatted and *binary output*.

The *insertion operator* (`<<`) is used to insert values in a type safe way into `ostream` objects. This is called formatted output, as binary values which are stored in the computer's memory are converted to human-readable ASCII characters according to certain formatting rules.

The insertion operator points to the `ostream` object to receive the information. The normal associativity of `<<` remains unaltered, so when a statement like

```
cout << "hello " << "world";
```

is encountered, the leftmost two operands are evaluated first (`cout << "hello "`), and an `ostream` & object, which is actually the same `cout` object, is returned. Now, the statement is reduced to

```
cout << "world";
```

and the second string is inserted into `cout`.

The `<<` operator has a lot of (overloaded) variants, so many types of variables can be inserted into `ostream` objects. There is an overloaded `<<`-operator expecting an `int`, a `double`, a pointer, etc. etc..

Each operator will return the `ostream` object into which the information so far has been inserted, followed by the next insertion.

Streams lack facilities for formatted output like C's `printf` and `vprintf` functions. Although it is not difficult to implement these facilities in the world of streams, `printf`-like functionality is hardly ever required in C++ programs. Furthermore, as it is potentially *type-unsafe*, it might be better to avoid this functionality completely.

When binary files must be written, normally no text-formatting is used or required: an `int` value should be written as a series of raw bytes, not as a series of ASCII numeric characters 0 to 9. The following member functions of `ostream` objects may be used to write 'binary files':

- `ostream& put(char c):`

to write a single character to the output stream. Since a character is a byte, this member function could also be used for writing a single character to a text-file.

- `ostream& write(char const *buffer, int length):`

to write at most `length` bytes, stored in the `char const *buffer` to the `ostream` object. Bytes are written as they are stored in the buffer, no formatting is done whatsoever. Note that the first argument is a `char const *`: a *type cast* is required to write any other type. For example, to write an `int` as an unformatted series of byte-values use:

```
int x;
out.write(reinterpret_cast<char const *>(&x), sizeof(int));
```

The bytes written by the above `write` call will be written in an order depending on the *endian-ness* of the underlying hardware. Big-endian computers will write the most significant byte first, little-endian computers will first write the least significant byte.

6.4.1.2 'ostream' positioning

Although not every `ostream` object supports repositioning, they usually do. This means that it is possible to rewrite a section of the stream which was written earlier. Repositioning is frequently used in database applications where it must be possible to access the information in the database at random.

The current position can be obtained and modified using the following members:

- `ios::pos_type tellp():`

the current (absolute) position in the file where the next write-operation to the stream will take place is returned.

- `ostream &seekp(ios::off_type step, ios::seekdir org):`

modifies a stream's actual position. The function expects an `off_type` `step` representing the number of bytes the current stream position is moved with respect to `org`. The `step` value may be negative, zero or positive.

The origin of the `step`, `org` is a value in the `ios::seekdir` enumeration. Its values are:

- `ios::beg`:
the stepsize is computed relative to the beginning of the stream. This value is used by default.
- `ios::cur`:
the stepsize is computed relative to the current position of the stream (as returned by `tellp`).
- `ios::end`:
the stepsize is interpreted relative to the current end position of the stream.

It is OK to seek or write beyond the last file position. Writing bytes to a location beyond EOF will pad the intermediate bytes with ASCII-Z values: null-bytes. Seeking before `ios::beg` raises the `ios::fail` flag.

6.4.1.3 ‘ostream’ flushing

Unless the `ios::unitbuf` flag has been set, information written to an `ostream` object is not immediately written to the physical stream. Rather, an internal buffer is filled during the write-operations, and when full it is flushed.

The stream’s internal buffer can be flushed under program control:

- `ostream& flush();`

any buffered information stored internally by the `ostream` object is flushed to the device to which the `ostream` object interfaces. A stream is flushed automatically when:

- the object ceases to exist;
- the `endl` or `flush` *manipulators* (see section 6.3.2.2) are inserted into an `ostream` object;
- a stream supporting the `close`-operation is explicitly closed (e.g., a `std::ofstream` object, cf. section 6.4.2).

6.4.2 Output to files: the class ‘ofstream’

The `std::ofstream` class is derived from the `ostream` class: it has the same capabilities as the `ostream` class, but can be used to access files or create files for writing.

In order to use the `ofstream` class in C++ sources, the `fstream` header file must be included. Including `fstream` will not automatically make available the standard streams `cin`, `cout` and `cerr`. Include `iostream` to declare these standard streams.

The following constructors are available for `ofstream` objects:

- `ofstream` object:

this is the basic constructor. It defines an `ofstream` object which may be associated with an actual file later, using its `open()` member (see below).

- `ofstream` object(`char const *name`, `ios::openmode mode = ios::out`):

this constructor defines an `ofstream` object and associates it immediately with the file named `name` using output mode `mode`. Section 6.4.2.1 provides an overview of available output modes. Example:

```
ofstream out("/tmp/scratch");
```

It is not possible to open an `ofstream` using a *file descriptor*. The reason for this is (apparently) that file descriptors are not universally available over different operating systems. Fortunately, file descriptors can be used (indirectly) with a `std::streambuf` object (and in some implementations: with a `std::filebuf` object, which is also a `streambuf`). `Streambuf` objects are discussed in section 14.7, `filebuf` objects are discussed in section 14.7.2.

Instead of directly associating an `ofstream` object with a file, the object can be constructed first, and opened later.

- `void open(char const *name, ios::openmode mode = ios::out):`

this member function is used to associate an `ofstream` object with an actual file. If the `ios::fail` flag was set before calling `open` and opening succeeds the flag is cleared. Opening an already open stream fails. To reassociate a stream with another file it must first be closed:

```
ofstream out("/tmp/out");
```

```

out << "hello\n";
out.close();           // flushes and closes out
out.open("/tmp/out2");
out << "world\n";

```

- `void close()`:

an `ofstream` object is closed by this member function. The function sets the `ios::fail` flag of the closed object. Closing the file will flush any buffered information to the associated file. A file is automatically closed when the associated `ofstream` object ceases to exist.

- `bool is_open() const`:

assume a stream was properly constructed, but it has not yet been attached to a file. E.g., the statement `ofstream ostr` was executed. When we now check its status through `good()`, a non-zero (i.e., *OK*) value is returned. The ‘good’ status here indicates that the stream object has been constructed properly. It doesn’t mean the file is also open. To test whether a stream is actually open, `is_open` should be called. If it returns `true`, the stream is open. Example:

```

#include <fstream>
#include <iostream>

using namespace std;

int main()
{
    ofstream of;

    cout << "of's open state: " << boolalpha << of.is_open() << '\n';

    of.open("/dev/null");           // on Unix systems

    cout << "of's open state: " << of.is_open() << '\n';
}
/*
    Generated output:
of's open state: false
of's open state: true
*/

```

6.4.2.1 Modes for opening stream objects

The following file modes or file flags are available when constructing or opening `ofstream` (or `istream`, see section 6.5.2) objects. The values are of type `ios::openmode`. Flags may be combined using the bitor operator.

- `ios::app`:

reposition the stream to its end before every output command (see also `ios::ate` below). The file is created if it doesn’t yet exist. When opening a stream in this mode any existing contents of the file are kept.

- `ios::ate`:

start initially at the end of the file. Note that any existing contents are *only* kept if some other flag tells the object to do so. For example `ofstream out("gone", ios::ate)` will *rewrite* the file `gone`, because the implied `ios::out` will cause the rewriting. If rewriting of an existing file should be prevented, the `ios::in` mode should be specified too. However, when `ios::in` is specified the file must already exist. The `ate` mode

only initially positions the file at the end of file position. After that information may be written in the middle of the file using `seekp`. When the `app` mode is used information will *only* be written at end of file (effectively ignoring `seekp` operations).

- `ios::binary`:

open a file in binary mode (used on systems distinguishing text- and binary files, like MS-Windows).

- `ios::in`:

open the file for reading. The file must exist.

- `ios::out`:

open the file for writing. Create it if it doesn't yet exist. If it exists, the file is rewritten.

- `ios::trunc`:

start initially with an empty file. Any existing contents of the file are lost.

The following combinations of file flags have special meanings:

<code>in out</code> :	The stream may be read and written. However, the file must exist.
<code>in out trunc</code> :	The stream may be read and written. It is (re)created empty first.

An interesting subtlety is that the `open` members of the `ifstream`, `ofstream` and `fstream` classes have a second parameter of type `ios::openmode`. In contrast to this, the `bitor` operator returns an `int` when applied to two enum-values. The question why the `bitor` operator may nevertheless be used here is answered in a later chapter (cf. section [10.11](#)).

6.4.3 Output to memory: the class ‘`ostreamstream`’

To write information to memory using stream facilities, `std::ostreamstream` objects should be used. As the class `ostreamstream` is derived from the class `ostream` all `ostream`'s facilities are available to `ostreamstream` objects as well. To use and define `ostreamstream` objects the header file `sstream` must be included. In addition the class `ostreamstream` offers the following constructors and members:

- `ostreamstream ostr(string const &init, ios::openmode mode = ios::out)`:

when specifying `openmode` as `ios::ate`, the `ostreamstream` object is initialized by the string `init` and remaining insertions are appended to the contents of the `ostreamstream` object.

- `ostreamstream ostr(ios::openmode mode = ios::out)`:

this constructor can also be used as default constructor. Alternatively it allows, e.g., forced additions at the end of the information stored in the object so far (using `ios::app`).
Example:

```
std::ostreamstream out;
```

- `std::string str() const`:

a copy of the string that is stored inside the `ostreamstream` object is returned.

- `void str(std::string const &str)`:

the current object is reinitialized with new initial contents.

The following example illustrates the use of the `ostringstream` class: several values are inserted into the object. Then, the text contained by the `ostringstream` object is stored in a `std::string`, whose length and contents are thereupon printed. Such `ostringstream` objects are most often used for doing ‘type to string’ conversions, like converting `int` values to text. Formatting flags can be used with `ostringstreams` as well, as they are part of the `ostream` class.

Here is an example showing an `ostringstream` object being used:

```
#include <iostream>
#include <sstream>

using namespace std;

int main()
{
    ostringstream ostr("hello ", ios::ate);

    cout << ostr.str() << '\n';

    ostr.setf(ios::showbase);
    ostr.setf(ios::hex, ios::basefield);
    ostr << 12345;

    cout << ostr.str() << '\n';

    ostr << " -- ";
    ostr.unsetf(ios::hex);
    ostr << 12;

    cout << ostr.str() << '\n';

    ostr.str("new text");
    cout << ostr.str() << '\n';

    ostr.seekp(4, ios::beg);
    ostr << "world";
    cout << ostr.str() << '\n';
}
/*
    Output from this program:
hello
hello 0x3039
hello 0x3039 -- 12
new text
new world
*/
```

6.5 Input

In **C++** input is primarily based on the `std::istream` class. The `istream` class defines the basic operators and members extracting information from streams: the *extraction operator* (`>>`), and special members like `istream::read` reading unformatted information from streams.

The class `istream` acts as *base class* for several other classes, all offering the functionality of the `istream` class, but adding their own specialties. In the upcoming sections we will introduce:

- The class `istream`, offering the basic facilities for doing input;

- The class `ifstream`, allowing us to read files (comparable to C's `fopen(filename, "r")`);
- The class `istringstream`, allowing us to read information from text that is not stored on files (streams) but in memory (comparable to C's `sscanf` function).

6.5.1 Basic input: the class 'istream'

The class `istream` defines basic input facilities. The `cin` object, is an `istream` object. All facilities related to input as defined by the `ios` class are also available in the `istream` class.

We may define `istream` objects using the following *istream constructor*:

- `istream object(streambuf *sb):`

this constructor can be used to construct a wrapper around an existing `std::streambuf` object. Similarly to `ostream` objects, `istream` objects may be defined by passing it initially a 0-pointer. See section 6.4.1 for a discussion, and chapter 23 for examples.

To define the `istream` class in C++ sources, the `istream` header file must be included. To use the predefined `istream` object `cin`, the `iostream` header file must be included.

6.5.1.1 Reading from 'istream' objects

The class `istream` supports both formatted and unformatted *binary input*. The *extraction operator* (`operator>>`) is used to extract values in a type safe way from `istream` objects. This is called formatted input, whereby human-readable ASCII characters are converted, according to certain formatting rules, to binary values.

The extraction operator points to the objects or variables which receive new values. The normal associativity of `>>` remains unaltered, so when a statement like

```
cin >> x >> y;
```

is encountered, the leftmost two operands are evaluated first (`cin >> x`), and an `istream &` object, which is actually the same `cin` object, is returned. Now, the statement is reduced to

```
cin >> y
```

and the `y` variable is extracted from `cin`.

The `>>` operator has many (overloaded) variants and thus many types of variables can be extracted from `istream` objects. There is an overloaded `>>` available for the extraction of an `int`, of a `double`, of a string, of an array of characters, possibly to a pointer, etc. etc.. String or character array extraction by default first skips all white space characters, and will then extract all consecutive non-white space characters. Once an extraction operator has been processed the `istream` object from which the information was extracted is returned and it can immediately be used for additional `istream` operations that appear in the same expression.

Streams lack facilities for formatted input (as used by, e.g., C's `scanf` and `vscanf` functions). Although it is not difficult to add these facilities to the world of streams, `scanf`-like functionality is hardly ever required in C++ programs. Furthermore, as it is potentially type-unsafe, it might be better to avoid formatted input completely.

When binary files must be read, the information should normally not be formatted: an `int` value should be read as a series of unaltered bytes, not as a series of ASCII numeric characters 0 to 9. The following member functions for reading information from `istream` objects are available:

- `int gcount() const:`

the number of characters read from the input stream by the last unformatted input operation is returned.

- `int get():`

the next available single character is returned as an unsigned char value using an int return type. EOF is returned if no more character are available.

- `istream &get(char &ch):`

the next single character read from the input stream is stored in `ch`. The member function returns the stream itself which may be inspected to determine whether a character was obtained or not.

- `istream& get(char *buffer, int len, char delim = '\n'):`

At most `len - 1` characters are read from the input stream into the array starting at `buffer`, which should be at least `len` bytes long. Reading also stops when the delimiter `delim` is encountered. However, the delimiter itself is *not removed* from the input stream.

Having stored the characters into `buffer`, an ASCII-Z character is written beyond the last character stored into the buffer. The functions `eof` and `fail` (see section 6.3.1) return 0 (false) if the delimiter was encountered before reading `len - 1` characters or if the delimiter was not encountered after reading `len - 1` characters. It is OK to specify an ASCII-Z delimiter: this way strings terminating in ASCII-Z characters may be read from a (binary) file.

- `istream& getline(char *buffer, int len, char delim = '\n'):`

this member function operates analogously to the `get` member function, but `getline` removes `delim` from the stream if it is actually encountered. The delimiter itself, if encountered, is *not* stored in the buffer. If `delim` was *not* found (before reading `len - 1` characters) the `fail` member function, and possibly also `eof` returns true. Realize that the `std::string` class also offers a function `std::getline` which is generally preferred over this `getline` member function that is described here (see section 5.2.4).

- `istream& ignore():`

one character is skipped from the input stream.

- `istream& ignore(int n):`

`n` characters are skipped from the input stream.

- `istream& ignore(int n, int delim):`

at most `n` characters are skipped but skipping characters stops after having removed `delim` from the input stream.

- `int peek():`

this function returns the next available input character, but does not actually remove the character from the input stream. EOF is returned if no more characters are available.

- `istream& putback(char ch):`

The character `ch` is 'pushed back' into the input stream, to be read again as the next available character. EOF is returned if this is not allowed. Normally, it is OK to put back one character. Example:

```
string value;
cin >> value;
cin.putback('X');
           // displays: X
cout << static_cast<char>(cin.get());
```

- `istream &read(char *buffer, int len):`

At most `len` bytes are read from the input stream into the buffer. If EOF is encountered first, fewer bytes are read, with the member function `eof` returning `true`. This function is commonly used when reading *binary* files. Section 6.5.2 contains an example in which this member function is used. The member function `gcount()` may be used to determine the number of characters that were retrieved by `read`.

- `istream& readsome(char *buffer, int len):`

at most `len` bytes are read from the input stream into the buffer. All available characters are read into the buffer, but if EOF is encountered, fewer bytes are read, without setting the `ios::eofbit` or `ios::failbit`.

- `istream &unget():`

the last character that was read from the stream is put back.

6.5.1.2 ‘istream’ positioning

Although not every `istream` object supports repositioning, some do. This means that it is possible to read the same section of a stream repeatedly. Repositioning is frequently used in *database applications* where it must be possible to access the information in the database randomly.

The current position can be obtained and modified using the following members:

- `ios::i(pos_type) tellg():`

the current (absolute) position in the file where the next read-operation to the stream will take place is returned.

- `istream &seekg(ios::off_type step, ios::seekdir org):`

modifies a stream’s actual position. The function expects an `off_type` `step` representing the number of bytes the current stream position is moved with respect to `org`. The `step` value may be negative, zero or positive.

The origin of the step, `org` is a value in the `ios::seekdir` enumeration.

The origin of the step, `org` is a value in the `ios::seekdir` enumeration. Its values are:

- `ios::beg:`

the stepsize is computed relative to the beginning of the stream. This value is used by default.

- `ios::cur:`

the stepsize is computed relative to the current position of the stream (as returned by `tellp`).

`ittrq(end)(ios::end)` (the stepsize is interpreted relative to the current end position of the the stream.)

It is OK to seek beyond the last file position. Seeking before `ios::beg` raises the `ios::fail` flag.

6.5.2 Input from files: the class ‘ifstream’

The `std::ifstream` class is derived from the `istream` class: it has the same capabilities as the `istream` class, but can be used to access files for reading.

In order to use the `ifstream` class in C++ sources, the `fstream` header file must be included. Including `fstream` will not automatically make available the standard streams `cin`, `cout` and `cerr`. Include `iostream` to declare these standard streams.

The following constructors are available for `ifstream` objects:

- `ifstream` object:

this is the basic constructor. It defines an `ifstream` object which may be associated with an actual file later, using its `open()` member (see below).

- `ifstream` object(`char const *name`, `ios::openmode mode = ios::in`):

this constructor can be used to define an `ifstream` object and associate it immediately with the file named `name` using input mode `mode`. Section 6.4.2.1 provides an overview of available input modes. Example:

```
ifstream in("/tmp/input");
```

Instead of directly associating an `ifstream` object with a file, the object can be constructed first, and opened later.

- `void open(char const *name, ios::openmode mode = ios::in)`:

this member function is used to associate an `ifstream` object with an actual file. If the `ios::fail` flag was set before calling `open` and opening succeeds the flag is cleared. Opening an already open stream fails. To reassociate a stream with another file it must first be closed:

```
ifstream in("/tmp/in");
in >> variable;
in.close();           // closes in
in.open("/tmp/in2");
in >> anotherVariable;
```

- `void close()`:

an `ifstream` object is closed by this member function. The function sets the `ios::fail` flag of the closed object. Closing the file will flush any buffered information to the associated file. A file is automatically closed when the associated `ifstream` object ceases to exist.

- `bool is_open() const`:

assume a stream was properly constructed, but it has not yet been attached to a file. E.g., the statement `ifstream ostr` was executed. When we now check its status through `good()`, a non-zero (i.e., *OK*) value is returned. The ‘good’ status here indicates that the stream object has been constructed properly. It doesn’t mean the file is also open. To test whether a stream is actually open, `is_open` should be called. If it returns true, the stream is open. Also see the example in section 6.4.2. The following example illustrates reading from a binary file (see also section 6.5.1.1):

```
#include <fstream>
using namespace std;

int main(int argc, char **argv)
{
    ifstream in(argv[1]);
    double    value;

    // reads double in raw, binary form from file.
    in.read(reinterpret_cast<char *>(&value), sizeof(double));
}
```


6.5.3 Input from memory: the class ‘istringstream’

To read information from memory using stream facilities, `std::istringstream` objects should be used. As the class `istringstream` is derived from the class `istream` all `istream`’s facilities are available to `istringstream` objects as well. To use and define `istringstream` objects the header file `sstream` must be included. In addition the class `istringstream` offers the following constructors and members:

- `istringstream istr(string const &init, ios::openmode mode = ios::in):`
the object is initialized with `init`’s contents
- `istringstream istr(ios::openmode mode = ios::in)` (this constructor is usually used as the default constructor. Example:

```
std::istringstream in;
```


)
- `void str(std::string const &str):`
the current object is reinitialized with new initial contents.

The following example illustrates the use of the `istringstream` class: several values are extracted from the object. Such `istringstream` objects are most often used for doing ‘string to type’ conversions, like converting text to `int` values (cf. **C**’s `atoi` function). Formatting flags can be used with `istringstream`s as well, as they are part of the `istream` class. In the example note especially the use of the member `seekg`:

```
#include <iostream>
#include <sstream>
using namespace std;

int main()
{
    istringstream istr("123 345"); // store some text.
    int x;

    istr.seekg(2);                // skip "12"
    istr >> x;                    // extract int
    cout << x << '\n';            // write it out
    istr.seekg(0);                // retry from the beginning
    istr >> x;                    // extract int
    cout << x << '\n';            // write it out
    istr.str("666");              // store another text
    istr >> x;                    // extract it
    cout << x << '\n';            // write it out
}
/*
    output of this program:
3
123
666
*/
```

6.5.4 Copying streams

Usually, files are copied either by reading a source file character by character or line by line. The basic *mode* to process streams is as follows:

- Continuous loop:
 1. read from the stream
 2. if reading did not succeed (i.e., `fail` returns `true`), break from the loop
 3. process the information that was read

Note that reading must *precede* testing, as it is only possible to know after actually attempting to read from a file whether the reading succeeded or not. Of course, variations are possible: `getline(istream &, string &)` (see section 6.5.1.1) returns an `istream &`, so here reading and testing may be contracted using one expression. Nevertheless, the above mold represents the general case. So, the following program may be used to copy `cin` to `cout`:

```
#include <iostream>
using namespace::std;

int main()
{
    while (true)
    {
        char c;

        cin.get(c);
        if (cin.fail())
            break;
        cout << c;
    }
}
```

Contraction is possible here by combining `get` with the `if`-statement, resulting in:

```
if (!cin.get(c))
    break;
```

Even so, this would still follow the basic rule: ‘read first, test later’.

Simply copying a file isn’t required very often. More often a situation is encountered where a file is processed up to a certain point, followed by plain copying the file’s remaining information. The next program illustrates this. Using `ignore` to skip the first line (for the sake of the example it is assumed that the first line is at most 80 characters long), the second statement uses yet another overloaded version of the `<<`-operator, in which a `streambuf` pointer is inserted into a stream. As the member `rdbuf` returns a stream’s `streambuf *`, we have a simple means of inserting a stream’s contents into an `ostream`:

```
#include <iostream>
using namespace std;

int main()
{
    cin.ignore(80, '\n');    // skip the first line and...
    cout << cin.rdbuf();     // copy the rest through the streambuf *
}
```

This way of copying streams only assumes the existence of a `streambuf` object. Consequently it can be used with all specializations of the `streambuf` class.

6.5.5 Coupling streams

Ostream objects can be *coupled* to ios objects using the `tie` member function. Tying results in flushing the ostream's buffer whenever an input or output operation is performed on the ios object to which the ostream object is tied. By default `cout` is tied to `cin` (using `cin.tie(cout)`). This tie means that whenever an operation on `cin` is requested, `cout` is flushed first. To break the tie, `ios::tie(0)` can be called. In the example: `cin.tie(0)`.

Another useful coupling of streams is shown by the tie between `cerr` and `cout`. Because of the tie standard output and error messages written to the screen are shown in sync with the time at which they were generated:

```
#include <iostream>
using namespace std;

int main()
{
    cerr.tie(0);          // untie
    cout << "first (buffered) line to cout ";
    cerr << "first (unbuffered) line to cerr\n";
    cout << "\n";

    cerr.tie(&cout);      // tie cout to cerr
    cout << "second (buffered) line to cout ";
    cerr << "second (unbuffered) line to cerr\n";
    cout << "\n";
}
/*
Generated output:

first (unbuffered) line to cerr
first (buffered) line to cout
second (buffered) line to cout second (unbuffered) line to cerr
*/
```

An alternative way to couple streams is to make streams use a common `streambuf` object. This can be implemented using the `ios::rdbuf(streambuf *)` member function. This way two streams can use, e.g. their own formatting, one stream can be used for input, the other for output, and redirection using the stream library rather than operating system calls can be implemented. See the next sections for examples.

6.6 Advanced topics

6.6.1 Redirecting streams

Using `ios::rdbuf` streams can be forced to share their `streambuf` objects. Thus information written to one stream is actually written to another stream; a phenomenon normally called *redirection*. Redirection is commonly implemented at the operating system level, and sometimes that is still necessary (see section [23.3.1](#)).

A common situation where redirection is useful is when error messages should be written to file rather than to the standard error stream, usually indicated by its file descriptor number 2. In the Unix operating system using the bash shell, this can be realized as follows:

```
program 2>/tmp/error.log
```

Following this command any error messages written by program are saved on the file `/tmp/error.log`, instead of appearing on the screen.

Here is an example showing how this can be implemented using `stringstream` objects. Assume program expects an argument defining the name of the file to write the error messages to. It could be called as follows:

```
program /tmp/error.log
```

The program looks like this, an explanation is provided below the program's source text:

```
#include <iostream>
#include <fstream>
using namespace std;

int main(int argc, char **argv)
{
    ofstream errlog;                // 1
    stringstream *cerr_buffer = 0; // 2

    if (argc == 2)
    {
        errlog.open(argv[1]);        // 3
        cerr_buffer = cerr.rdbuf(errlog.rdbuf()); // 4
    }
    else
    {
        cerr << "Missing log filename\n";
        return 1;
    }

    cerr << "Several messages to stderr, msg 1\n";
    cerr << "Several messages to stderr, msg 2\n";

    cout << "Now inspect the contents of " <<
         argv[1] << "... [Enter] ";
    cin.get();                      // 5

    cerr << "Several messages to stderr, msg 3\n";

    cerr.rdbuf(cerr_buffer);        // 6
    cerr << "Done\n";               // 7
}
/*
Generated output on file argv[1]

at cin.get():

Several messages to stderr, msg 1
Several messages to stderr, msg 2

at the end of the program:

Several messages to stderr, msg 1
Several messages to stderr, msg 2
Several messages to stderr, msg 3
*/
```

- At lines 1-2 local variables are defined: `errlog` is the `ofstream` to write the error messages too,

and `cerr_buffer` is a pointer to a `streambuf`, to point to the original `cerr` buffer.

- At line 3 the alternate error stream is opened.
- At line 4 redirection takes place: `cerr` will write to the `streambuf` defined by `errlog`. It is important that the original buffer used by `cerr` is saved, as explained below.
- At line 5 we pause. At this point, two lines were written to the alternate error file. We get a chance to take a look at its contents: there were indeed two lines written to the file.
- At line 6 the redirection is terminated. This is very important, as the `errlog` object is destroyed at the end of `main`. If `cerr`'s buffer would not have been restored, then at that point `cerr` would refer to a non-existing `streambuf` object, which might produce unexpected results. It is the responsibility of the programmer to make sure that an original `streambuf` is saved before redirection, and is restored when the redirection ends.
- Finally, at line 7, `Done` is again written to the screen, as the redirection has been terminated.

6.6.2 Reading AND Writing streams

In order to both read and write to a stream an `std::fstream` object must be created. As with `ifstream` and `ofstream` objects, its constructor receives the name of the file to be opened:

```
fstream inout("iofile", ios::in | ios::out);
```

Note the use of the constants `ios::in` and `ios::out`, indicating that the file must be opened for both reading and writing. Multiple mode indicators may be used, concatenated by the `bitor` operator. Alternatively, instead of `ios::out`, `ios::app` could have been used and mere writing would become appending (at the end of the file).

Reading and writing to the same file is always a bit awkward: what to do when the file may not yet exist, but if it already exists it should not be rewritten? Having fought with this problem for some time I now use the following approach:

```
#include <fstream>
#include <iostream>
#include <string>

using namespace std;

int main()
{
    fstream rw("fname", ios::out | ios::in);

    if (!rw)                // file didn't exist yet
    {
        rw.clear();         // try again, creating it using ios::trunc
        rw.open("fname", ios::out | ios::trunc | ios::in);
    }

    if (!rw)                // can't even create it: bail out
    {
        cerr << "Opening 'fname' failed miserably" << '\n';
        return 1;
    }

    cerr << "We're at: " << rw.tellp() << '\n';

    // write something
```

```

    rw << "Hello world" << '\n';

    rw.seekg(0);           // go back and read what's written

    string s;
    getline(rw, s);

    cout << "Read: " << s << '\n';
}

```

Under this approach if the first construction attempt fails `fname` doesn't exist yet. But then open can be attempted using the `ios::trunc` flag. If the file already existed, the construction would have succeeded. By specifying `ios::ate` when defining `rw`, the initial read/write action would by default have taken place at EOF.

Under **DOS**-like operating systems that use the multiple character sequence `\r\n` to separate lines in text files the flag `ios::binary` is required to process binary files ensuring that `\r\n` combinations are processed as two characters. In general, `ios::binary` should be specified when binary (non-text) files are to be processed. By default files are opened as text files. Unix operating systems do not distinguish text files from binary files.

With `fstream` objects, combinations of file flags are used to make sure that a stream is or is not (re)created empty when opened. See section [6.4.2.1](#) for details.

Once a file has been opened in read and write mode, the `<<` operator can be used to insert information into the file, while the `>>` operator may be used to extract information from the file. These operations may be performed in any order, but a `seekg` or `seekp` operation is required when switching between insertions and extractions. The seek operation is used to activate the stream's data used for reading or those used for writing (and *vice versa*). The `istream` and `ostream` parts of `fstream` objects share the stream's data buffer and by performing the seek operation the stream either activates its `istream` or its `ostream` part. If the seek is omitted, reading after writing and writing after reading simply fails. The example shows a white space delimited word being read from a file, writing another string to the file, just beyond the point where the just read word terminated. Finally yet another string is read which is found just beyond the location where the just written strings ended:

```

fstream f("filename", ios::in | ios::out);
string str;

f >> str;           // read the first word

                    // write a well known text
f.seekg(0, ios::cur);
f << "hello world";

f.seekp(0, ios::cur);
f >> str;           // and read again

```

Since a *seek* or *clear* operation is required when alternating between read and write (extraction and insertion) operations on the same file it is not possible to execute a series of `<<` and `>>` operations in one expression statement.

Of course, random insertions and extractions are hardly ever used. Generally, insertions and extractions occur at well-known locations in a file. In those cases, the position where insertions or extractions are required can be controlled and monitored by the `seekg`, `seekp`, `tellg` and `tellp` members (see sections [6.4.1.2](#) and [6.5.1.2](#)).

Error conditions (see section [6.3.1](#)) occurring due to, e.g., reading beyond end of file, reaching end of file, or positioning before begin of file, can be cleared by the `clear` member function. Following `clear` processing may continue. E.g.,

```

fstream f("filename", ios::in | ios::out);
string str;

f.seekg(-10);    // this fails, but...
f.clear();       // processing f continues

f >> str;       // read the first word

```

A situation where files are both read and written is seen in *database* applications, using files consisting of records having fixed sizes, and where locations and sizes of pieces of information are known. For example, the following program adds text lines to a (possibly existing) file. It can also be used to retrieve a particular line, given its order-number in the file. A *binary file* index allows for the quick retrieval of the location of lines.

```

#include <iostream>
#include <fstream>
#include <string>
using namespace std;

void err(char const *msg)
{
    cout << msg << '\n';
}

void err(char const *msg, long value)
{
    cout << msg << value << '\n';
}

void read(fstream &index, fstream &strings)
{
    int idx;

    if (!(cin >> idx))                // read index
        return err("line number expected");

    index.seekg(idx * sizeof(long));  // go to index-offset

    long offset;

    if
    (
        !index.read                    // read the line-offset
        (
            reinterpret_cast<char *>(&offset),
            sizeof(long)
        )
    )
        return err("no offset for line", idx);

    if (!strings.seekg(offset))        // go to the line's offset
        return err("can't get string offset ", offset);

    string line;

    if (!getline(strings, line))       // read the line
        return err("no line at ", offset);

    cout << "Got line: " << line << '\n';    // show the line
}

```

```

}

void write(fstream &index, fstream &strings)
{
    string line;

    if (!getline(cin, line))                // read the line
        return err("line missing");

    strings.seekp(0, ios::end);              // to strings
    index.seekp(0, ios::end);              // to index

    long offset = strings.tellp();

    if
    (
        !index.write                        // write the offset to index
        (
            reinterpret_cast<char *>(&offset),
            sizeof(long)
        )
    )
        return err("Writing failed to index: ", offset);

    if (!(strings << line << '\n'))          // write the line itself
        return err("Writing to 'strings' failed");
                                           // confirm writing the line
    cout << "Write at offset " << offset << " line: " << line << '\n';
}

int main()
{
    fstream index("index", ios::trunc | ios::in | ios::out);
    fstream strings("strings", ios::trunc | ios::in | ios::out);

    cout << "enter 'r <number>' to read line <number> or "
          "w <line>' to write a line\n"
          "or enter 'q' to quit.\n";

    while (true)
    {
        cout << "r <nr>, w <line>, q ? ";    // show prompt

        index.clear();
        strings.clear();

        string cmd;
        cin >> cmd;                          // read cmd

        if (cmd == "q")                      // process the cmd.
            return 0;

        if (cmd == "r")
            read(index, strings);
        else if (cmd == "w")
            write(index, strings);
        else
            cout << "Unknown command: " << cmd << '\n';
    }
}

```



```
}
```

Another example showing reading *and* writing of files is provided by the next program. It also illustrates the processing of ASCII-Z delimited strings:

```
#include <iostream>
#include <fstream>
using namespace std;

int main()
{
    // r/w the file
    fstream f("hello", ios::in | ios::out | ios::trunc);

    f.write("hello", 6);           // write 2 ascii-z strings
    f.write("hello", 6);

    f.seekg(0, ios::beg);          // reset to begin of file

    char buffer[100];              // or: char *buffer = new char[100]
    char c;

    // read the first 'hello'
    cout << f.get(buffer, sizeof(buffer), 0).tellg() << '\n';
    f >> c;                        // read the ascii-z delim

    // and read the second 'hello'
    cout << f.get(buffer + 6, sizeof(buffer) - 6, 0).tellg() << '\n';

    buffer[5] = ' ';               // change asciiz to ' '
    cout << buffer << '\n';         // show 2 times 'hello'
}
/*
Generated output:
5
11
hello hello
*/
```

A completely different way to read and write streams may be implemented using `streambuf` members. All considerations mentioned so far remain valid (e.g., before a read operation following a write operation `seekg` must be used). When `streambuf` objects are used, either an `istream` is associated with the `streambuf` object of another `ostream` object, or an `ostream` object is associated with the `streambuf` object of another `istream` object. Here is the previous program again, now using *associated streams*:

```
#include <iostream>
#include <fstream>
#include <string>
using namespace std;

void err(char const *msg);        // see earlier example
void err(char const *msg, long value);

void read(istream &index, istream &strings)
{
    index.clear();
    strings.clear();

    // insert the body of the read() function of the earlier example
}
```

```

void write(ostream &index, ostream &strings)
{
    index.clear();
    strings.clear();

    // insert the body of the write() function of the earlier example
}

int main()
{
    ifstream index_in("index", ios::trunc | ios::in | ios::out);
    ifstream strings_in("strings", ios::trunc | ios::in | ios::out);
    ostream index_out(index_in.rdbuf());
    ostream strings_out(strings_in.rdbuf());

    cout << "enter 'r <number>' to read line <number> or "
           "w <line>' to write a line\n"
           "or enter 'q' to quit.\n";

    while (true)
    {
        cout << "r <nr>, w <line>, q ? ";           // show prompt

        string cmd;

        cin >> cmd;                                   // read cmd

        if (cmd == "q")                               // process the cmd.
            return 0;

        if (cmd == "r")
            read(index_in, strings_in);
        else if (cmd == "w")
            write(index_out, strings_out);
        else
            cout << "Unknown command: " << cmd << '\n';
    }
}

```

In this example

- the streams associated with the streambuf objects of existing streams are not ifstream or ofstream objects but basic istream and ostream objects.
- The streambuf object is not defined by an ifstream or ofstream object. Instead it is defined outside of the streams, using a filebuf (cf. section 14.7.2) and constructions like:

```

filebuf fb("index", ios::in | ios::out | ios::trunc);
istream index_in(&fb);
ostream index_out(&fb);

```

- An ifstream object can be constructed using stream modes normally used with ofstream objects. Conversely, an ofstream objects can be constructed using stream modes normally used with ifstream objects.
- If istream and ostreams share a streambuf, then their read and write pointers (should) point to the shared buffer: they are tightly coupled.

- The advantage of using an external (separate) `streambuf` over a predefined `fstream` object is (of course) that it opens the possibility of using `stream` objects with specialized `streambuf` objects. These `streambuf` objects may specifically be constructed to control and interface particular devices. Elaborating this (see also section [14.7](#)) is left as an exercise to the reader.

Chapter 7

Classes

In this chapter classes are introduced. Two special member functions, the constructor and the destructor, are presented.

In steps we will construct a class `Person`, which could be used in a database application to store a person's name, address and phone number.

Let's start by creating a class `Person` right away. From the onset, it is important to make the distinction between the class *interface* and its *implementation*. A class may loosely be defined as 'a set of data and all the functions operating on those data'. This definition will be refined later but for now it is sufficient to get us started.

A class interface is a definition, defining the organization of objects of that class. Normally a definition results in memory reservation. E.g., when defining `int variable` the compiler will make sure that some memory will be reserved in the final program storing `variable`'s values. Although it is a definition no memory is set aside by the compiler once it has processed the class definition. But a class definition follows the *one definition rule*: in **C++** entities may be defined only once. As a *class definition* does not imply that memory is being reserved the term *class interface* is preferred instead.

Class interfaces are normally contained in a class *header file*, e.g., `person.h`. We'll start our class `Person` interface here:

```
#include <string>

class Person
{
    std::string d_name;           // name of person
    std::string d_address;       // address field
    std::string d_phone;         // telephone number
    size_t      d_mass;          // the mass in kg.

public:                          // member functions
    void setName(std::string const &name);
    void setAddress(std::string const &address);
    void setPhone(std::string const &phone);
    void setMass(size_t mass);

    std::string const &name() const;
    std::string const &address() const;
    std::string const &phone() const;
    size_t mass() const;
};
```

The member functions that are *declared* in the interface must still be implemented. The implementa-

tion of these members is properly called their definition.

In addition to the member function a class defines the data manipulated by the member functions. These data are called the *data members*. In `Person` they are `d_name`, `d_address`, `d_phone` and `d_mass`. Data members should be given private access rights. Since the class uses private access rights by default they may simply be listed at the top of the interface.

All communication between the outer world and the class data is routed through the class's member functions. Data members may receive new values (e.g., using `setName`) or they may be retrieved for inspection (e.g., using `name`). Functions merely returning values stored inside the object, not allowing the caller to modify these internally stored values, are called *accessors*.

Syntactically there is only a marginal difference between a class and a struct. Classes by default define *private* members, structs define *public* members. Conceptually, though, there are differences. In **C++** structs are used in the way they are used in **C**: to aggregate data, which are all freely accessible. Classes, on the other hand, hide their data from access by the outside world (which is aptly called *data hiding*) and offer member functions to define the communication between the outer world and the class's data members.

Following *Lakos* (Lakos, J., 2001) **Large-Scale C++ Software Design** (Addison-Wesley) I suggest the following setup of class interfaces:

- All data members have *private access rights*, and are placed at the top of the interface.
- All data members start with `d_`, followed by a name suggesting their meaning (in chapter 11 we'll also encounter data members starting with `s_`).
- Non-private data members *do* exist, but one should be hesitant to define non-private access rights for data members (see also chapter 13).
- Two broad categories of member functions are *manipulators* and *accessors*. *Manipulators* allow the users of objects to modify the internal data of the objects. By convention, manipulators start with `set`. E.g., `setName`.
- With *accessors*, a `get`-prefix is still frequently encountered, e.g., `getName`. However, following the conventions promoted by the **Qt** (see <http://www.trolltech.com>) *Graphical User Interface Toolkit*, the `get`-prefix is now deprecated. So, rather than defining the member `getAddress`, it should simply be named `address`.
- Normally (exceptions exist) the public member functions of a class are listed first, immediately following the class's data members. They are the important elements of the interface as they define the features the class is offering to its users. It's a matter of convention to list them high up in the interface. The keyword `private` is needed beyond the public members to switch back from public members to private access rights which nicely separates the members that may be used 'by the general public' from the class's own support members.

Style conventions usually take a long time to develop. There is nothing obligatory about them, though. I suggest that readers who have compelling reasons *not* to follow the above style conventions use their own. All others are strongly advised to adopt the above style conventions.

7.1 The constructor

C++ classes may contain two special categories of member functions which are essential to the proper working of the class. These categories are the constructors and the destructor. The *destructor's* primary task is to return memory allocated by an object to the common pool when an object goes 'out of scope'. Allocation of memory is discussed in chapter 8, and destructors will therefore be discussed in depth in that chapter. In this chapter the emphasis will be on the class's organization and its constructors.

Constructors are recognized by their names which is equal to the class name. Constructors do not specify return values, not even `void`. E.g., the class `Person` may define a constructor `Person::Person()`.

The C++ run-time system ensures that the constructor of a class is called when a variable of the class is defined. It is possible to define a class lacking any constructor. In that case the compiler will define a default constructor that is called when an object of that class is defined. What actually happens in that case depends on the data members that are defined by that class (cf. section 7.2.1).

Objects may be defined locally or globally. However, in C++ most objects are defined locally. Globally defined objects are hardly ever required and are somewhat deprecated.

When a local object is defined its constructor is called every time the function is called. The object's constructor is activated at the point where the object is defined (a subtlety is that an object may be defined implicitly as, e.g., a temporary variable in an expression).

When an object is defined as a static object is called when the program starts. In this case the constructor is called even before the function `main` starts. Example:

```
#include <iostream>
using namespace std;

class Demo
{
    public:
        Demo();
};

Demo::Demo()
{
    cout << "Demo constructor called\n";
}

Demo d;

int main()
{}

/*
    Generated output:
    Demo constructor called
*/
```

The program contains one global object of the class `Demo` with `main` having an empty body. Nonetheless, the program produces some output generated by the constructor of the globally defined `Demo` object.

Constructors have a very important and well-defined role. They must ensure that all the class's data members have sensible or at least well-defined values once the object has been constructed. We'll get back to this important task shortly. The *default constructor* has no argument. It is defined by the compiler unless another constructor is defined and unless its definition is suppressed (cf. section 7.4). If a default constructor is required in addition to another constructor then the default constructor must explicitly be defined as well. The C++0x standard provides special syntax to do that as well, which is also covered by section 7.4.

7.1.1 A first application

Our example class `Person` has three string data members and a `size_t d_mass` data member. Access to these data members is controlled by interface functions.

Whenever an object is defined the class's constructor(s) ensure that its data members are given 'sensible' values. Thus, objects never suffer from uninitialized values. Data members may be given new values, but that should never be directly allowed. It is a core principle (called *data hiding*) of good class design that its data members are private. The modification of data members is therefore fully

controlled by member functions and thus, indirectly, by the class-designer. The class *encapsulates* all actions performed on its data members and due to this *encapsulation* the class object may assume the ‘responsibility’ for its own data-integrity. Here is a minimal definition of `Person`’s manipulating members:

```
#include "person.h"                // given earlier

void Person::setName(string const &name)
{
    d_name = name;
}
void Person::setAddress(string const &address)
{
    d_address = address;
}
void Person::setPhone(string const &phone)
{
    d_phone = phone;
}
void Person::setMass(size_t mass)
{
    d_mass = mass;
}
```

It’s a minimal definition in that no checks are performed. But it should be clear that checks are easy to implement. E.g., to ensure that a phone number only contains digits one could define:

```
void Person::setPhone(string const &phone)
{
    if (phone.find_first_not_of("0123456789") == string::npos)
        d_phone = phone;
    else
        cout << "A phone number may only contain digits\n";
}
```

Similarly, access to the data members is controlled by encapsulating *accessor* members. Accessors ensure that data members cannot suffer from uncontrolled modifications. Since accessors conceptually do not modify the object’s data (but only retrieve the data) these member functions are given the predicate `const`. They are called *const member functions*, which, as they are guaranteed not to modify their object’s data, are available to both modifiable and constant objects (cf. section 7.5).

To prevent *backdoors* we must also make sure that the data member is not modifiable through an accessor’s return value. For values of built-in primitive types that’s easy, as they are usually returned by value, which are copies of the values found in variables. But since objects may be fairly large making copies are usually prevented by returning objects by reference. A backdoor is created by returning a data member by reference, as in the following example, showing the allowed abuse below the function definition:

```
string &Person::name() const
{
    return d_name;
}

Person somebody;
somebody.setName("Nemo");

somebody.name() = "Eve";    // Oops, backdoor changing the name
```


To prevent the backdoor objects are returned as *const references* from accessors. Here are the implementations of `Person`'s accessors:

```
#include "person.h"                // given earlier

string const &Person::name() const
{
    return d_name;
}
string const &Person::address() const
{
    return d_address;
}
string const &Person::phone() const
{
    return d_phone;
}
size_t Person::mass() const
{
    return d_mass;
}
```

The `Person` class interface remains the starting point for the class design: its member functions define what can be asked of a `Person` object. In the end the implementation of its members merely is a technicality allowing `Person` objects to do their jobs.

The next example shows how the class `Person` may be used. An object is initialized and passed to a function `printperson()`, printing the person's data. Note the reference operator in the parameter list of the function `printperson`. Only a reference to an existing `Person` object is passed to the function, rather than a complete object. The fact that `printperson` does not modify its argument is evident from the fact that the parameter is declared `const`.

```
#include <iostream>
#include "person.h"                // given earlier

void printperson(Person const &p)
{
    cout << "Name      : " << p.name()      << "\n"
         << "Address  : " << p.address()    << "\n"
         << "Phone    : " << p.phone()      << "\n"
         << "Mass     : " << p.mass()        << '\n';
}

int main()
{
    Person p;

    p.setName("Linus Torvalds");
    p.setAddress("E-mail: Torvalds@cs.helsinki.fi");
    p.setPhone(" - not sure - ");
    p.setMass(75);                // kg.

    printperson(p);
}

/*
Produced output:

Name      : Linus Torvalds
Address  : E-mail: Torvalds@cs.helsinki.fi
```

```

Phone    : - not sure -
Mass     : 75

*/

```

7.1.2 Constructors: with and without arguments

The class `Person`'s constructor so far has no parameters. **C++** allows constructors to be defined with or without parameter lists. The arguments are supplied when an object is defined.

For the class `Person` a constructor expecting three strings and a `size_t` might be useful. Representing, respectively, the person's name, address, phone number and mass. This constructor is:

```

Person::Person(string const &name, string const &address,
               string const &phone, size_t mass)
{
    d_name = name;
    d_address = address;
    d_phone = phone;
    d_mass = mass;
}

```

It must of course also be declared in the class interface:

```

class Person
{
    // data members (not altered)

public:
    Person(std::string const &name, std::string const &address,
           std::string const &phone, size_t mass);

    // rest of the class interface (not altered)
};

```

Now that this constructor has been declared, the default constructor must explicitly be declared as well if we still want to be able to construct a plain `Person` object without any specific initial values for its data members. The class `Person` would thus support two constructors, and the part declaring the constructors now becomes:

```

class Person
{
    // data members
public:
    Person();
    Person(std::string const &name, std::string const &address,
           std::string const &phone, size_t mass);

    // additional members
};

```

In this case, the default constructor doesn't have to do very much, as it doesn't have to initialize the string data members of the `Person` object. As these data members are objects themselves, they are initialized to empty strings by their own default constructor. However, there is also a `size_t` data member. That member is a variable of a built-in type and such variables do not have constructors and

so are not initialized automatically. Therefore, unless the value of the `d_mass` data member is explicitly initialized it will be

- a *random* value for local `Person` objects;
- 0 for global and static `Person` objects.

The 0-value might not be too bad, but normally we don't want a *random* value for our data members. So, even the default constructor has a job to do: initializing the data members which are not initialized to sensible values automatically. Its implementation can be:

```
Person::Person()
{
    d_mass = 0;
}
```

Using constructors with and without arguments is illustrated next. The object `karel` is initialized by the constructor defining a non-empty parameter list while the default constructor is used with the anon object:

```
int main()
{
    Person karel("Karel", "Rietveldlaan 37", "542 6044", 70);
    Person anon;
}
```

The two `Person` objects are defined when `main` starts as they are *local* objects, living only for as long as `main` is active.

If `Person` objects must be definable using other arguments, corresponding constructors must be added to `Person`'s interface. Apart from overloading class constructors it is also possible to provide constructors with default argument values. These default arguments must be specified with the constructor declarations in the class interface, like so:

```
class Person
{
public:
    Person(std::string const &name,
           std::string const &address = "--unknown--",
           std::string const &phone   = "--unknown--",
           size_t mass = 0);
};
```

Often, constructors use highly similar implementations. This results from the fact that the constructor's parameters are often defined for convenience: a constructor not requiring a phone number but requiring a mass cannot be defined using default arguments, since `phone` is not the constructor's last parameter. Consequently a special constructor is required not having `phone` in its parameter list.

In pre C++0x C++ this situation is commonly tackled as follows: all constructors *must* initialize their reference and `const` data members, or the compiler will (rightfully) complain. To initialize the remaining members (non-`const` and non-reference members) we have two options:

- If the body of the construction process is sizeable but (parameterizable) identical to other constructors bodies then factorize. Define a private member `init` which is called by the constructors to provide the object's data members with their appropriate values.
- If the constructors act fundamentally differently, then there's nothing to factorize and each constructor must be implemented by itself.

C++0x allows constructors to call each other. This is illustrated in section 7.2.3 below.

7.1.2.1 The order of construction

The possibility to pass arguments to constructors allows us to monitor the construction order of objects during program execution. This is illustrated by the next program using a class `Test`. The program defines a global `Test` object and two local `Test` objects. The order of construction is as expected: first global, then `main`'s first local object, then `func`'s local object, and then, finally, `main`'s second local object:

```
#include <iostream>
#include <string>
using namespace std;

class Test
{
public:
    Test(string const &name);    // constructor with an argument
};

Test::Test(string const &name)
{
    cout << "Test object " << name << " created" << '\n';
}

Test globaltest("global");

void func()
{
    Test functest("func");
}

int main()
{
    Test first("main first");
    func();
    Test second("main second");
}

/*
Generated output:
Test object global created
Test object main first created
Test object func created
Test object main second created
*/
```

7.2 Objects inside objects: composition

In the class `Person` objects are used as data members. This construction technique is called *composition*.

Composition is neither extraordinary nor C++ specific: in C a `struct` or `union` field is commonly used in other compound types. In C++ it requires some special thought as their initialization sometimes is subject to restrictions, as discussed in the next few sections.

7.2.1 Composition and const objects: const member initializers

Unless specified otherwise object data members of classes are initialized by their default constructors. Using the default constructor might not always be the optimal way to initialize an object and it might not even be possible: a class might simply not define a default constructor.

Earlier we've encountered the following constructor of the `Person`:

```
Person::Person(string const &name, string const &address,
               string const &phone, size_t mass)
{
    d_name = name;
    d_address = address;
    d_phone = phone;
    d_mass = mass;
}
```

Think briefly about what is going on in this constructor. In the constructor's body we encounter assignments to string objects. Since assignments are used in the constructor's body their left-hand side objects must exist. But when objects are coming into existence constructors *must* have been called. The initialization of those objects is thereupon immediately undone by the body of `Person`'s constructor. That is not only inefficient but sometimes downright impossible. Assume that the class interface mentions a `string const` data member: a data member whose value is not supposed to change at all (like a birthday, which usually doesn't change very much and is therefore a good candidate for a `string const` data member). Constructing a birthday object and providing it with an initial value is OK, but changing the initial value isn't.

The body of a constructor allows assignments to data members. The *initialization* of data members happens before that. **C++** defines the *member initializer* syntax allowing us to specify the way data members are initialized at construction time. Member initializers are specified as a list of constructor specifications between a colon following a constructor's parameter list and the opening curly brace of a constructor's body, as follows:

```
Person::Person(string const &name, string const &address,
               string const &phone, size_t mass)
:
    d_name(name),
    d_address(address),
    d_phone(phone),
    d_mass(mass)
{ }
```

Member initialization *always* occurs when objects are composed in classes: if *no* constructors are mentioned in the member initializer list the default constructors of the objects are called. Note that this only holds true for *objects*. Data members of primitive data types are *not* initialized automatically.

Member initialization can, however, also be used for primitive data members, like `int` and `double`. The above example shows the initialization of the data member `d_mass` from the parameter `mass`. When member initializers are used the data member could even have the same name as the constructor's parameter (although this is deprecated) as there is no ambiguity and the first (left) identifier used in a member initializer is always a data member that is initialized whereas the identifier between parentheses is interpreted as the parameter.

The *order* in which class type data members are initialized is defined by the order in which those members are defined in the composing class interface. If the order of the initialization in the constructor differs from the order in the class interface, the compiler complains, and reorders the initialization so as to match the order of the class interface.

Member initializers should be used as often as possible. As shown it may be required to use them (e.g., to initialize `const` data members, or to initialize objects of classes lacking default constructors) but *not*

using member initializers also results in inefficient code as the default constructor of a data member is always automatically called unless an explicit member initializer is specified. Reassignment in the constructor's body following default construction is then clearly inefficient. Of course, sometimes it is fine to use the default constructor, but in those cases the explicit member initializer can be omitted.

As a rule of thumb: if a value is assigned to a data member in the constructor's body then try to avoid that assignment in favor of using a member initializer.

7.2.2 Composition and reference objects: reference member initializers

Apart from using member initializers to initialize composed objects (be they `const` objects or not), there is another situation where member initializers must be used. Consider the following situation.

A program uses an object of the class `Configfile`, defined in `main` to access the information in a configuration file. The configuration file contains parameters of the program which may be set by changing the values in the configuration file, rather than by supplying command line arguments.

Assume another object used in `main` is an object of the class `Process`, doing 'all the work'. What possibilities do we have to tell the object of the class `Process` that an object of the class `Configfile` exists?

- The objects could have been declared as *global* objects. This is a possibility, but not a very good one, since all the advantages of local objects are lost.
- The `Configfile` object may be passed to the `Process` object at construction time. Bluntly passing an object (i.e., by value) might not be a very good idea, since the object must be copied into the `Configfile` parameter, and then a data member of the `Process` class can be used to make the `Configfile` object accessible throughout the `Process` class. This might involve yet another object-copying task, as in the following situation:

```
Process::Process(Configfile conf)    // a copy from the caller
{
    d_conf = conf;                  // copying to d_conf member
}
```

- The copy-instructions can be avoided if *pointers* to the `Configfile` objects are used, as in:

```
Process::Process(Configfile *conf)  // pointer to external object
{
    d_conf = conf;                  // d_conf is a Configfile *
}
```

This construction as such is OK, but forces us to use the '`->`' field selector operator, rather than the '`.`' operator, which is (disputably) awkward. Conceptually one tends to think of the `Configfile` object as an object, and not as a pointer to an object. In `C` this would probably have been the preferred method, but in `C++` we can do better.

- Rather than using value or pointer parameters, the `Configfile` parameter could be defined as a *reference parameter* of `Process`'s constructor. Next, use a `Config` reference data member in the class `Process`.

But a reference variable cannot be initialized using an assignment, and so the following is incorrect:

```
Process::Process(Configfile &conf)
{
    d_conf = conf;                // wrong: no assignment
}
```

The statement `d_conf = conf` fails, because it is not an initialization, but an assignment of one `Configfile` object (i.e., `conf`), to another (`d_conf`). An assignment to a reference variable is actually an assignment to the variable the reference variable refers to. But which variable does `d_conf` refer to? To no variable at all, since we haven't initialized `d_conf`. After all, the whole purpose of the statement `d_conf = conf` was to initialize `d_conf`....

How to initialize `d_conf`? We once again use the member initializer syntax. Here is the correct way to initialize `d_conf`:

```
Process::Process(Configfile &conf)
:
    d_conf(conf)          // initializing reference member
{ }
```

The above syntax must be used in all cases where reference data members are used. E.g., if `d_ir` would have been an `int` reference data member, a construction like

```
Process::Process(int &ir)
:
    d_ir(ir)
{ }
```

would have been required.

7.2.3 Constructors calling constructors (C++0x, ?)

Often constructors are specializations of each other, allowing objects to be constructed using subsets of arguments for its data members, and/or using default argument values for other data members. In many cases classes define initialization members that are called by the various constructors. Here is an example. A class `Stat` is designed as a wrapper class around C's `stat` function. It might define three constructors: one expecting no arguments and initializing all data members to appropriate values; a second one doing the same, but it calls `stat` with the filename provided to the constructor and a third one expecting a filename and a search path for the provided file name. Rather than repeating the initialization code in each constructor, the common code can be factorized into a member `init()` which is thereupon called by the constructors.

The C++0x standard offers an alternative to this design by allowing constructors to call each other. The C++0x standard allows constructors to call each other as shown in the following example:

```
class Stat
{
public:
    Stat()
    :
        // default initialization of members
    {}
    Stat(std::string const &fileName)
    :
        Stat()
    {
        set(fileName);
    }
    Stat(std::string const &fileName, std::string const &searchPath)
    :
        Stat()
    {
        set(fileName, searchPath);
    }
};
```

```

    }
    ...
};

```

There is one *caveat*: **C++** considers the object as fully constructed once a constructor has normally finished. Once a constructor has finished the class's destructor is guaranteed to be called (cf. chapter 8) and so remaining code must make sure that, e.g., all the class's pointer data members remain in a valid state. Also, as a prelude to chapter 9, realize that a destructor *will* be called if a constructor throws an exception after having completed the call to another constructor.

C++ allows static const integral data members to be initialized within the class interfaces (cf. chapter 11). The C++0x standard adds to this the facility to provide all data members (const or non-const, integral or non-integral) with a default initialization that is specified by the class interface.

These default initializations may be overruled by constructors. E.g., if the class `Stat` uses a data member `bool d_hasPath` which is `false` by default but the third constructor (see above) should initialize it to `true` then the following approach is possible:

```

class Stat
{
    bool d_hasPath = false;

public:
    Stat(std::string const &fileName, std::string const &searchPath)
    :
        d_hasPath(true)    // overrule the interface-specified
                           // value
    {}
};

```

Here `d_hasPath` receives its value only once: it's always initialized to `false` except when the shown constructor is used in which case it is initialized to `true`.

7.3 Uniform initialization (C++0x, 4.4)

When defining variables and objects they may immediately be given initial values. Class type objects are always initialized using one of their available constructors. **C** already supports the array and struct *initializer list* consisting of a list of constant expressions surrounded by a pair of curly braces. A comparable initialization, called *uniform initialization* is added to **C++** by the C++0x standard. It uses the following syntax:

```
Type object {value list};
```

When defining objects using a list of objects each individual object may use its own uniform initialization.

The advantage of uniform initialization over using constructors is that using constructor arguments may sometimes result in an ambiguity as constructing an object may sometimes be confused with using the object's overloaded function call operator (cf. section 10.10). As initializer lists can only be used with *plain old data* (POD) types (cf. section 8.8) and with classes that are 'initializer list aware' (like `std::vector`) the ambiguity does not arise when initializer lists are used.

Uniform initialization can be used to initialize an object or variable, but also to initialize data members in a constructor or implicitly in the return statement of functions. Examples:

```
class Person
```



```

{
    // data members
public:
    Person(std::string const &name, size_t mass)
    :
        d_name {name},
        d_mass {mass}
    {}

    Person copy() const
    {
        return {d_name, d_mass};
    }
};

```

Although the uniform initialization syntax is slightly different from the syntax of an initializer list (the latter using the assignment operator) the compiler nevertheless uses the initializer list if a constructor supporting an initializer list is available. As an example consider:

```

class Vector
{
public:
    Vector(size_t size);
    Vector(std::initializer_list<int> const &values);
};

Vector vi = {4};

```

When defining `vi` the constructor expecting the initializer list is called rather than the constructor expecting a `size_t` argument. If the latter constructor is required the definition using the standard constructor syntax must be used. I.e., `Vector vi(4)`.

Initializer lists are themselves objects that may be constructed using another initializer list. However, values stored in an initializer list are immutable. Once the initializer list has been defined their values remain as-is. Initializer lists support a basic set of member functions and constructors:

- `initializer_list<Type> object`:
 defines object as an empty initializer list
- `initializer_list<Type> object { list of Type values }`:
 defines object as an initializer list containing Type values
- `initializer_list<Type> object(other)`:
 initializes object using the values stored in other
- `size_t size() const`:
 returns the number of elements in the initializer list
- `Type const *begin() const`:
 returns a pointer to the first element of the initializer list
- `Type const *end() const`:
 returns a pointer just beyond the location of the last element of the initializer list

7.4 Defaulted and deleted class members (C++0x, 4.4)

In everyday class design two situation are frequently encountered:

- A class offering constructors explicitly has to define a default constructor;
- A class (e.g., a class implementing a stream) cannot initialize objects by copying the values from an existing object of that class (called *copy construction*) and cannot assign objects to each other.

Once a class defines at least one constructor its default constructor is not automatically defined by the compiler. The C++0x standard relaxes that restriction somewhat by offering the ‘= default’ syntax. A class specifying ‘= default’ with its default constructor declaration indicates that the trivial default constructor should be provided by the compiler. A trivial default constructor performs the following actions:

- Its data members of built-in or primitive types are not initialized;
- Its composed (class type) data members are initialized by their default constructors.
- If the class is derived from a base class (cf. chapter 13) the base class is initialized by its default constructor.

Trivial implementations can also be provided for the *copy constructor*, the *overloaded assignment operator*, and the *destructor*. Those members are introduced in chapter 8.

Conversely, situations exist where some (otherwise automatically provided) members should *not* be made available. This is realized by specifying ‘= delete’. Using = default and = delete is illustrated by the following example. The default constructor receives its trivial implementation, copy-construction is prevented:

```
class Strings
{
    public:
        Strings() = default;
        Strings(std::string const *sp, size_t size);

        Strings(Strings const &other) = delete;
};
```

7.5 Const member functions and const objects

The keyword `const` is often used behind the parameter list of member functions. This keyword indicates that a member function does not alter the data members of its object. Such member functions are called *const member functions*. In the class `Person`, we see that the accessor functions were declared `const`:

```
class Person
{
    public:
        std::string const &name()    const;
        std::string const &address() const;
        std::string const &phone()   const;
        size_t mass()                const;
};
```

The rule of thumb given in section 3.1.3 applies here too: whichever appears to the *left* of the keyword `const`, is not altered. With member functions this should be interpreted as ‘doesn’t alter its own data’.

When implementing a const member function the `const` attribute must be repeated:

```
string const &Person::name() const
{
    return d_name;
}
```

The compiler will prevent the data members of a class from being modified by one of its const member functions. Therefore a statement like

```
d_name[0] = toupper(static_cast<unsigned char>(d_name[0]));
```

results in a compiler error when added to the above function’s definition.

Const member functions are used to prevent inadvertent data modification. Except for constructors and the destructor (cf. chapter 8) only const member functions can be used with (plain, references or pointers to) const objects.

Const objects are frequently encountered as `const &` parameters of functions. Inside such functions only the object’s const members may be used. Here is an example:

```
void displayMass(ostream &out, Person const &person)
{
    out << person.name() << " weighs " << person.mass() << " kg.\n";
}
```

Since `person` is defined as a `Person const &` the function `displayMass` cannot call, e.g., `person.setMass(75)`.

The const member function attribute can be used to overload member functions. When functions are overloaded by their const attribute the compiler will use the member function matching most closely the const-qualification of the object:

- When the object is a const object, only const member functions can be used.
- When the object is not a const object, non-const member functions will be used, *unless* only a const member function is available. In that case, the const member function will be used.

The next example illustrates how (non) const member functions are selected:

```
#include <iostream>
using namespace std;

class Members
{
public:
    Members();
    void member();
    void member() const;
};

Members::Members()
{}
void Members::member()
{
```

```

        cout << "non const member\n";
    }
    void Members::member() const
    {
        cout << "const member\n";
    }

    int main()
    {
        Members const constObject;
        Members      nonConstObject;

        constObject.member();
        nonConstObject.member();
    }
    /*
        Generated output:

        const member
        non const member
    */

```

As a general principle of design: member functions should always be given the `const` attribute, unless they actually modify the object's data.

7.5.1 Anonymous objects

Sometimes objects are used because they offer a certain functionality. The objects only exist because of their functionality, and nothing in the objects themselves is ever changed. The following class `Print` offers a facility to print a string, using a configurable prefix and suffix. A partial class interface could be:

```

class Print
{
    public:
        Print(ostream &out);
        print(std::string const &prefix, std::string const &text,
              std::string const &suffix) const;
};

```

An interface like this would allow us to do things like:

```

Print print(cout);
for (int idx = 0; idx < argc; ++idx)
    print.print("arg: ", argv[idx], "\n");

```

This works fine, but it could greatly be improved if we could pass `print`'s invariant arguments to `Print`'s constructor. This would simplify `print`'s prototype (only one argument would need to be passed rather than three) and we could wrap the above code in a function expecting a `Print` object:

```

void allArgs(Print const &print, int argc, char *argv[])
{
    for (int idx = 0; idx < argc; ++idx)
        print.print(argv[idx]);
}

```

The above is a fairly generic piece of code, at least it is with respect to `Print`. Since prefix and suffix don't change they can be passed to the constructor which could be given the prototype:

```
Print(ostream &out, string const &prefix = "", string const &suffix = "");
```

Now `allArgs` may be used as follows:

```
Print p1(cout, "arg: ", "\n");           // prints to cout
Print p2(cerr, "err: --", "--\n");       // prints to cerr

allArgs(p1, argc, argv);                 // prints to cout
allArgs(p2, argc, argv);                 // prints to cerr
```

But now we note that `p1` and `p2` are only used inside the `allArgs` function. Furthermore, as we can see from `Print`'s prototype, `Print` doesn't modify the internal data of the `Print` object it is using.

In such situations it is actually not necessary to define objects before they are used. Instead *anonymous objects* may be used. Anonymous objects can be used:

- to initialize a function parameter which is a `const` reference to an object;
- if the object is *only* used inside the function call.

These anonymous objects are considered constant as they merely exist for passing the information of (class type) objects to functions. They are not considered 'variables'. Of course, a `const_cast` could be used to cast away the `const` reference's constness, but any change will be lost when the function returns. These anonymous objects used to initialize `const` references should not be confused with rvalue references (section 3.3.2) which have a completely different purpose in life. Rvalue references primarily exist to be 'swallowed' by functions receiving them. Thus, the information made available by rvalue references outlives the rvalue reference objects which are also anonymous.

Anonymous objects are defined when a constructor is used without providing a name for the constructed object. Here is the corresponding example:

```
allArgs(Print(cout, "arg: ", "\n"), argc, argv);    // prints to cout
allArgs(Print(cerr, "err: --", "--\n"), argc, argv); // prints to cerr
```

In this situation the `Print` objects are constructed and immediately passed as first arguments to the `allArgs` functions, where they are accessible as the function's `Print` parameter. While the `allArgs` function is executing they can be used, but once the function has completed, the anonymous `Print` objects are no longer accessible.

7.5.1.1 Subtleties with anonymous objects

Anonymous objects can be used to initialize function parameters that are `const` references to objects. These objects are created just before such a function is called, and are destroyed once the function has terminated. **C++**'s grammar allows us to use anonymous objects in other situations as well. Consider the following snippet of code:

```
int main()
{
    // initial statements
    Print("hello", "world");
    // later statements
}
```

In this example an anonymous `Print` object is constructed, and it is immediately destroyed thereafter. So, following the ‘initial statements’ our `Print` object is constructed. Then it is destroyed again followed by the execution of the ‘later statements’.

The example illustrates that the standard lifetime rules do not apply to anonymous objects. Their lifetimes are limited to the *statements*, rather than to the *end of the block* in which they are defined.

Plain anonymous object are at least useful in one situation. Assume we want to put *markers* in our code producing some output when the program’s execution reaches a certain point. An object’s constructor could be implemented so as to provide that marker-functionality allowing us to put markers in our code by defining anonymous, rather than named objects.

C++’s grammar contains another remarkable characteristic illustrated by the next example:

```
int main(int argc, char **argv)
{
    Print p(cout, "", "");           // 1
    allArgs(Print(p), argc, argv);   // 2
}
```

In this example a non-anonymous object `p` is constructed in statement 1, which is then used in statement 2 to *initialize* an anonymous object. The anonymous object, in turn, is then used to initialize `allArgs`’s `const` reference parameter. This use of an existing object to initialize another object is common practice, and is based on the existence of a so-called *copy constructor*. A copy constructor creates an object (as it is a constructor) using an existing object’s characteristics to initialize the data of the object that’s created. Copy constructors are discussed in depth in chapter 8, but presently only the concept of a copy constructor is used.

In the above example a copy constructor is used to initialize an anonymous object. The anonymous object was then used to initialize a parameter of a function. However, when we try to apply the same trick (i.e., using an existing object to initialize an anonymous object) to a plain statement, the compiler generates an error: the object `p` can’t be redefined (in statement 3, below):

```
int main(int argc, char *argv[])
{
    Print p("", "");                // 1
    allArgs(Print(p), argc, argv);   // 2
    Print(p);                        // 3 error!
}
```

Does this mean that using an existing object to initialize an anonymous object that is used as function argument is OK, while an existing object can’t be used to initialize an anonymous object in a plain statement?

The compiler actually provides us with the answer to this apparent contradiction. About statement 3 the compiler reports something like:

```
error: redeclaration of 'Print p'
```

which solves the problem when realizing that within a compound statement objects and variables may be defined. Inside a compound statement, a *type name* followed by a *variable name* is the grammatical form of a variable definition. *Parentheses* can be used to break priorities, but if there are no priorities to break, they have no effect, and are simply ignored by the compiler. In statement 3 the parentheses allowed us to get rid of the blank that’s required between a type name and the variable name, but to the compiler we wrote

```
Print (p);
```

which is, since the parentheses are superfluous, equal to

```
Print p;
```

thus producing `p`’s redeclaration.

As a further example: when we define a variable using a built-in type (e.g., `double`) using superfluous parentheses the compiler will quietly remove these parentheses for us:

```
double (((a)));          // weird, but OK.
```

To summarize our findings about anonymous variables:

- Anonymous objects are great for initializing `const` reference parameters.
- The same syntax, however, can also be used in stand-alone statements, in which they are interpreted as variable definitions if our intention actually was to initialize an anonymous object using an existing object.
- Since this may cause confusion, it’s probably best to restrict the use of anonymous objects to the first (and main) form: initializing function parameters.

7.6 The keyword ‘*inline*’

Let us take another look at the implementation of the function `Person::name()`:

```
std::string const &Person::name() const
{
    return d_name;
}
```

This function is used to retrieve the name field of an object of the class `Person`. Example:

```
void showName(Person const &person)
{
    cout << person.name();
}
```

To insert person’s name the following actions are performed:

- The function `Person::name()` is called.
- This function returns person’s `d_name` as a reference.
- The referenced name is inserted into `cout`.

Especially the first part of these actions causes some time loss, since an extra function call is necessary to retrieve the value of the `name` field. Sometimes a faster procedure immediately making the `d_name` data member available is preferred without ever actually calling a function `name`. This can be realized using `inline` functions. An `inline` function is a request to the compiler to insert the function’s code at the location of the function’s call. This may speed up execution by avoiding a function call, which typically comes with some (stack handling and parameter passing) overhead. Note that `inline` is a *request* to the compiler: the compiler may decide to ignore it, and *will* probably ignore it when the function’s body contains much code. Good programming discipline suggests to be aware of this, and to avoid `inline` unless the function’s body is fairly small. More on this in section [7.6.2](#).

7.6.1 Defining members inline

Inline functions may be implemented *in the class interface itself*. For the class `Person` this results in the following implementation of `name`:

```
class Person
{
    public:
        std::string const &name() const
        {
            return d_name;
        }
};
```

Note that the inline code of the function `name` now literally occurs inline in the interface of the class `Person`. The keyword `const` is again added to the function's header.

Although members can be defined *in-class* (i.e., inside the class interface itself), it is considered bad practice for the following reasons:

- Defining members inside the interface contaminates the interface with implementations. The interface's purpose is to document what functionality the class offers. Mixing member declarations and implementation details complicates understanding the interface. Readers need to skip implementation details which takes time and makes it hard to grab the 'broad picture', and thus to understand at a glance what functionality the class's objects are offering.
- In-class implementations of private member functions may usually be avoided altogether (as they are private members). They should be moved to the internal header file (*unless* inline public members use such inline private members).
- Although members that are eligible for inline-coding should remain inline, situations do exist where such inline members migrate from an inline to a non-inline definition. In-class inline definitions still need editing (sometimes considerable editing) before they can be compiled. This additional editing is undesirable.

Because of the above considerations inline members should not be defined in-class. Rather, they should be defined following the class interface. The `Person::name` member is therefore preferably defined as follows:

```
class Person
{
    public:
        std::string const &name() const;
};

inline std::string const &Person::name() const
{
    return d_name;
}
```

If it is ever necessary to cancel `Person::name`'s inline implementation, then this becomes its non-inline implementation:

```
#include "person.ih"

std::string const &Person::name() const
{
    return d_name;
}
```


Only the `inline` keyword needs to be removed to obtain the correct non-inline implementation.

Defining members inline has the following effect: whenever an inline-defined function is called, the compiler may *insert the function's body* at the location of the function call. It may be that the function itself is never actually called.

This construction, where the function code itself is inserted rather than a call to the function, is called an inline function. Note that using inline functions may result in multiple occurrences of the code of those functions in a program: one copy for each invocation of the inline function. This is probably OK if the function is a small one, and needs to be executed fast. It's not so desirable if the code of the function is extensive. The compiler knows this too, and handles the use of inline functions as a *request* rather than a *command*. If the compiler considers the function too long, it will not grant the request. Instead it will treat the function as a normal function.

7.6.2 When to use inline functions

When should inline functions be used, and when not? There are some rules of thumb which may be followed:

- In general inline functions should **not** be used. *Voilà*; that's simple, isn't it?
- Consider defining a function inline once a fully developed and tested program runs too slowly and shows 'bottlenecks' in certain functions, and the bottleneck is removed by defining inline members. A profiler, which runs a program and determines where most of the time is spent, is necessary to perform such optimizations.
- Defining inline functions may be considered when they consist of one very simple statement (such as the return statement in the function `Person::name`).
- When a function is defined inline, its implementation is inserted in the code wherever the function is used. As a consequence, when the *implementation* of the inline function changes, all sources using the inline function must be recompiled. In practice that means that all functions must be recompiled that include (either directly or indirectly) the header file of the class in which the inline function is defined. Not a very attractive prospect.
- It is only useful to implement an inline function when the time spent during a function call is long compared to the time spent by the function's body. An example of an inline function which will hardly have any effect on the program's speed is:

```
inline void Person::printname() const
{
    cout << d_name << '\n';
}
```

This function contains only one statement. However, the statement takes a relatively long time to execute. In general, functions which perform input and output take lots of time. The effect of the conversion of this function `printname()` to inline would therefore lead to an insignificant gain in execution time.

All inline functions have one disadvantage: the actual code is inserted by the compiler and must therefore be known compile-time. Therefore, as mentioned earlier, an inline function can never be located in a run-time library. Practically this means that an inline function is found near the interface of a class, usually in the same header file. The result is a header file which not only shows the **declaration** of a class, but also part of its **implementation**, thus always blurring the distinction between interface and implementation.

7.7 Local classes: classes inside functions

Classes are usually defined at the global or namespace level. However, it is entirely possible to define a local class, i.e., inside a function. Such classes are called *local classes*.

Local classes can be very useful in advanced applications involving inheritance or templates (cf. section 13.8). At this point in the C++ Annotations they have limited use, although their main features can be described. At the end of this section an example is provided.

- Local classes may use almost all characteristics of normal classes. They may have constructors, destructors, data members, and member functions;
- Local classes cannot define static data members. Static member functions, however, *can* be defined.
- Since a local class may define static member functions, it is possible to define *nested functions* in C++ somewhat comparable to the way programming languages like **Pascal** allow nested functions to be defined.
- If a local class needs access to a constant integral value, a local *enum* can be used. The enum may be anonymous, exposing only the enum values.
- Local classes cannot directly access the non-static variables of their surrounding context. For example, in the example shown below the class `Local` cannot directly access `main`'s `argc` parameter.
- Local classes may directly access global data and static variables defined by their surrounding function. This includes variables defined in the anonymous namespace of the source file containing the local class.
- Local class objects can be defined inside the function body, but they cannot leave the function as objects of their own type. I.e., a local class name cannot be used for either the return type or for the parameter types of its surrounding function.
- As a prelude to *inheritance* (chapter 13): a local class may be derived from an existing class allowing the surrounding function to return a dynamically allocated locally constructed class object, pointer or reference could be returned via a base class pointer or reference.

```
#include <iostream>
#include <string>

using namespace std;

int main(int argc, char *argv[])
{
    static size_t staticValue = 0;

    class Local
    {
        int d_argc;                // non-static data members OK

    public:
        enum                      // enums OK
        {
            VALUE = 5
        };
        Local(int argc)           // constructors and member functions OK
        :                         // in-class implementation required
            d_argc(argc)
        {
```

```

        // global data: accessible
        cout << "Local constructor\n";
        // static function variables: accessible
        staticValue += 5;
    }
    static void hello() // static member functions: OK
    {
        cout << "hello world\n";
    }
};
Local::hello();           // call Local static member
Local loc(argc);         // define object of a local class.
}

```

7.8 The keyword 'mutable'

Earlier, in section 7.5, the concepts of const member functions and const objects were introduced.

C++ also allows the declaration of data members which may be modified, even by const member function. The declaration of such data members in the class interface start with the keyword `mutable`.

Mutable should be used for those data members that may be modified without logically changing the object, which might therefore still be considered a constant object.

An example of a situation where mutable is appropriately used is found in the implementation of a string class. Consider the `std::string`'s `c_str` and data members. The actual data returned by the two members are identical, but `c_str` must ensure that the returned string is terminated by an ASCII-Z byte. As a string object has both a length and a capacity an easy way to implement `c_str` is to ensure that the string's capacity exceeds its length by at least one character. This invariant allows `c_str` to be implemented as follows:

```

char const *string::c_str() const
{
    d_data[d_length] = 0;
    return d_data;
}

```

This implementation logically does not modify the object's data as the bytes beyond the object's initial (length) characters have undefined values. But in order to use this implementation `d_data` must be declared mutable:

```
mutable char *d_data;
```

The keyword `mutable` is also useful in classes implementing, e.g., reference counting. Consider a class implementing reference counting for textstrings. The object doing the reference counting might be a const object, but the class may define a copy constructor. Since const objects can't be modified, how would the copy constructor be able to increment the reference count? Here the `mutable` keyword may profitably be used, as it can be incremented and decremented, even though its object is a const object.

The keyword `mutable` should sparingly be used. Data modified by const member functions should never logically modify the object, and it should be easy to demonstrate this. As a rule of thumb: do not use `mutable` unless there is a very clear reason (the object is logically not altered) for violating this rule.

7.9 Header file organization

In section 2.5.10 the requirements for header files when a C++ program also uses C functions were discussed. Header files containing class interfaces have additional requirements.

First, source files. With the exception of the occasional classless function, source files contain the code of member functions of classes. here there are basically two approaches:

- All required header files for a member function are included in each individual source file.
- All required header files (for all member functions of a class) are included in a header file that is included by each of the source files defining class members.

The first alternative has the advantage of economy for the compiler: it only needs to read the header files that are necessary for a particular source file. It has the disadvantage that the program developer must include multiple header files again and again in sourcefiles: it both takes time to type the include-directives and to think about the header files which are needed in a particular source file.

The second alternative has the advantage of economy for the program developer: the header file of the class accumulates header files, so it tends to become more and more generally useful. It has the disadvantage that the compiler frequently has to process many header files which aren't actually used by the function to compile.

With computers running faster and faster (and compilers getting smarter and smarter) I think the second alternative is to be preferred over the first alternative. So, as a starting point source files of a particular class `MyClass` could be organized according to the following example:

```
#include <myclass.h>

int MyClass::aMemberFunction()
{ }
```

There is only one include-directive. Note that the directive refers to a header file in a directory mentioned in the INCLUDE-file environment variable. Local header files (using `#include "myclass.h"`) could be used too, but that tends to complicate the organization of the class header file itself somewhat.

The organization of the header file itself requires some attention. Consider the following example, in which two classes `File` and `String` are used.

Assume the `File` class has a member `gets(String &destination)`, while the class `String` has a member function `getLine(File &file)`. The (partial) header file for the class `String` is then:

```
#ifndef STRING_H_
#define STRING_H_

#include <project/file.h>    // to know about a File

class String
{
public:
    void getLine(File &file);
};
#endif
```

Unfortunately a similar setup is required for the class `File`:

```
#ifndef FILE_H_
#define FILE_H_
```

```
#include <project/string.h>    // to know about a String

class File
{
    public:
        void gets(String &string);
};
#endif
```

Now we have created a problem. The compiler, trying to compile the source file of the function `File::gets` proceeds as follows:

- The header file `project/file.h` is opened to be read;
- `FILE_H_` is defined
- The header file `project/string.h` is opened to be read
- `STRING_H_` is defined
- The header file `project/file.h` is (again) opened to be read
- Apparently, `FILE_H_` is already defined, so the remainder of `project/file.h` is skipped.
- The interface of the class `String` is now parsed.
- In the class interface a reference to a `File` object is encountered.
- As the class `File` hasn't been parsed yet, a `File` is still an undefined type, and the compiler quits with an error.

The solution to this problem is to use a *forward class reference before* the class interface, and to include the corresponding class header file *beyond* the class interface. So we get:

```
#ifndef STRING_H_
#define STRING_H_

class File;                // forward reference

class String
{
    public:
        void getLine(File &file);
};

#include <project/file.h>    // to know about a File

#endif
```

A similar setup is required for the class `File`:

```
#ifndef FILE_H_
#define FILE_H_

class String;              // forward reference

class File
{
    public:
```

```

        void gets(String &string);
};

#include <project/string.h>    // to know about a String

#endif

```

This works well in all situations where either references or pointers to other classes are involved and with (non-inline) member functions having class-type return values or parameters.

This setup doesn't work with composition, nor with in-class inline member functions. Assume the class `File` has a *composed* data member of the class `String`. In that case, the class interface of the class `File` *must* include the header file of the class `String` before the class interface itself, because otherwise the compiler can't tell how big a `File` object will be, as it doesn't know the size of a `String` object once the interface of the `File` class is completed.

In cases where classes contain composed objects (or are derived from other classes, see chapter 13) the header files of the classes of the composed objects must have been read *before* the class interface itself. In such a case the class `File` might be defined as follows:

```

#ifndef FILE_H_
#define FILE_H_

#include <project/string.h>    // to know about a String

class File
{
    String d_line;            // composition !

public:
    void gets(String &string);
};

#endif

```

The class `String` can't declare a `File` object as a composed member: such a situation would again result in an undefined class while compiling the sources of these classes.

All remaining header files (appearing below the class interface itself) are required only because they are used by the class's source files.

This approach allows us to introduce yet another refinement:

- Header files defining a class interface should *declare* what can be declared before defining the class interface itself. So, classes that are mentioned in a class interface should be specified using forward declarations *unless*
 - They are a *base class* of the current class (see chapter 13);
 - They are the class types of composed data members;
 - They are used in inline member functions.

In particular: additional actual header files are *not* required for:

- class-type return values of functions;
- class-type value parameters of functions.

Class header files of objects that are either composed or inherited or that are used in inline functions, *must* be known to the compiler before the interface of the current class starts. The information in the header file itself is protected by the `#ifndef ... #endif` construction introduced in section 2.5.10.

- Program sources in which the class is used only need to include this header file. *Lakos*, (2001) refines this process even further. See his book **Large-Scale C++ Software Design** for further details. This header file should be made available in a well-known location, such as a directory or subdirectory of the standard `INCLUDE` path.
- To implement member functions the class's header file is required and usually additional header files (like the `string` header file) as well. The class header file itself as well as these additional header files should be included in a separate internal header file (for which the extension `.ih` ('internal header') is suggested).

The `.ih` file should be defined in the same directory as the source files of the class. It has the following characteristics:

- There is *no* need for a protective `#ifndef .. #endif` shield, as the header file is never included by other header files.
- The standard `.h` header file defining the class interface is included.
- The header files of all classes used as forward references in the standard `.h` header file are included.
- Finally, all other header files that are required in the source files of the class are included.

An example of such a header file organization is:

- First part, e.g., `/usr/local/include/myheaders/file.h`:

```
#ifndef FILE_H_
#define FILE_H_

#include <fstream>          // for composed 'ifstream'

class Buffer;              // forward reference

class File                // class interface
{
    std::ifstream d_instream;

public:
    void gets(Buffer &buffer);
};
#endif
```

- Second part, e.g., `~/myproject/file/file.ih`, where all sources of the class `File` are stored:

```
#include <myheaders/file.h> // make the class File known

#include <buffer.h>          // make Buffer known to File
#include <string>            // used by members of the class
#include <sys/stat.h>        // File.
```

7.9.1 Using namespaces in header files

When entities from namespaces are used in header files, no `using` directive should be specified in those header files if they are to be used as general header files declaring classes or other entities from a library. When the `using` directive is used in a header file then users of such a header file are forced to accept and use the declarations in all code that includes the particular header file.

For example, if in a namespace `special` an object `serter` `cout` is declared, then `special::cout` is of course a different object than `std::cout`. Now, if a class `Flaw` is constructed, in which the constructor expects a reference to a `special::serter`, then the class should be constructed as follows:

```
class special::serter;
```

```
class Flaw
{
    public:
        Flaw(special::Inserter &ins);
};
```

Now the person designing the class `Flaw` may be in a lazy mood, and might get bored by continuously having to prefix `special::` before every entity from that namespace. So, the following construction is used:

```
using namespace special;

class Inserter;
class Flaw
{
    public:
        Flaw(Inserter &ins);
};
```

This works fine, up to the point where somebody wants to include `flaw.h` in other source files: because of the `using` directive, this latter person is now by implication also using namespace `special`, which could produce unwanted or unexpected effects:

```
#include <flaw.h>
#include <iostream>

using std::cout;

int main()
{
    cout << "starting\n";           // won't compile
}
```

The compiler is confronted with two interpretations for `cout`: first, because of the `using` directive in the `flaw.h` header file, it considers `cout` a `special::Inserter`, then, because of the `using` directive in the user program, it considers `cout` a `std::ostream`. Consequently, the compiler reports an error.

As a rule of thumb, header files intended for general use should not contain `using` declarations. This rule does not hold true for header files which are only included by the sources of a class: here the programmer is free to apply as many `using` declarations as desired, as these directives never reach other sources.

7.10 `sizeof` applied to class data members (C++0x, 4.4)

In the C++0x standard the `sizeof` operator can be applied to data members of classes without the need to specify an object as well. Consider:

```
class Data
{
    std::string d_name;
    ...
};
```

To obtain the size of `Data`'s `d_name` member C++0x allows the following expression:

```
sizeof(Data::d_name);
```


However, note that the compiler observes data protection here as well. `sizeof(Data::d_name)` can only be used where `d_name` may be visible as well, i.e., by `Data`'s member functions and friends.

7.11 Unrestricted Unions (C++0x, ?)

The C++0x standard allows unions to be defined consisting of objects for which a non-trivial constructor is defined. The example illustrates how such an *unrestricted union* may be defined. The data field `u_string` is an object of the class `std::string` for which non-trivial constructors are available:

```
union Union
{
    int u_int;
    double u_double;
    std::string u_string;
};
```


Chapter 8

Classes And Memory Allocation

In contrast to the set of functions that handle memory allocation in **C** (i.e., `malloc` etc.), memory allocation in **C++** is handled by the operators `new` and `delete`. Important differences between `malloc` and `new` are:

- The function `malloc` doesn't 'know' what the allocated memory will be used for. E.g., when memory for `ints` is allocated, the programmer must supply the correct expression using a multiplication by `sizeof(int)`. In contrast, `new` requires a type to be specified; the `sizeof` expression is implicitly handled by the compiler. Using `new` is therefore *type safe*.
- Memory allocated by `malloc` is initialized by `calloc`, initializing the allocated characters to a configurable initial value. This is not very useful when objects are available. As operator `new` knows about the type of the allocated entity it may (and will) call the constructor of an allocated class type object. This constructor may be also supplied with arguments.
- All **C**-allocation functions must be inspected for `NULL`-returns. This is not required anymore when `new` is used. In fact, `new`'s behavior when confronted with failing memory allocation is configurable through the use of a *`new_handler`* (cf. section 8.2.2).

A comparable relationship exists between `free` and `delete`: `delete` makes sure that when an object is deallocated, its destructor is automatically called.

The automatic calling of constructors and destructors when objects are created and destroyed has consequences which we shall discuss in this chapter. Many problems encountered during **C** program development are caused by incorrect memory allocation or memory leaks: memory is not allocated, not freed, not initialized, boundaries are overwritten, etc.. **C++** does not 'magically' solve these problems, but it *does* provide us with tools to prevent these kinds of problems.

As a consequence of `malloc` and friends becoming deprecated the very frequently used `str...` functions, like `strdup`, that are all `malloc` based, should be avoided in **C++** programs. Instead, the facilities of the `string` class and operators `new` and `delete` should be used instead.

Memory allocation procedures influence the way classes dynamically allocating their own memory should be designed. Therefore, in this chapter these topics are discussed in addition to discussions about operators `new` and `delete`. We'll first cover the peculiarities of operators `new` and `delete`, followed by a discussion about:

- the destructor: the member function that's called when an object ceases to exist;
- the assignment operator, allowing us to assign an object to another object of its own class;
- the `this` pointer, allowing explicit references to the object for which a member function was called;
- the copy constructor: the constructor creating a copy of an object;
- the move constructor: a constructor creating an object from an anonymous temporary object.

8.1 Operators ‘new’ and ‘delete’

C++ defines two operators to allocate memory and to return it to the ‘common pool’. These operators are, respectively `new` and `delete`.

Here is a simple example illustrating their use. An `int` pointer variable points to memory allocated by operator `new`. This memory is later released by operator `delete`.

```
int *ip = new int;
delete ip;
```

Here are some characteristics of operators `new` and `delete`:

- `new` and `delete` are *operators* and therefore do not require parentheses, as required for *functions* like `malloc` and `free`;
- `new` returns a pointer to the kind of memory that’s asked for by its operand (e.g., it returns a pointer to an `int`);
- `new` uses a *type* as its operand, which has the important benefit that the correct amount of memory, given the type of the object to be allocated, is made available;
- as a consequence, `new` is a type safe operator as it always returns a pointer to the type that was mentioned as its operand. In addition, the type of the receiving pointer must match the type specified with operator `new`;
- `new` may fail, but this is normally of *no* concern to the programmer. In particular, the program does *not* have to test the success of the memory allocation, as is required for `malloc` and friends. Section 8.2.2 delves into this aspect of `new`;
- `delete` returns `void`;
- for each call to `new` a matching `delete` should eventually be executed, lest a memory leak occurs;
- `delete` can safely operate on a 0-pointer (doing nothing);
- otherwise `delete` must only be used to return memory allocated by `new`. It should *not* be used to return memory allocated by `malloc` and friends.
- in C++ `malloc` and friends are *deprecated* and should be avoided.

Operator `new` can be used to allocate primitive types but also to allocate objects. When a primitive type or a struct type without a constructor is allocated the allocated memory is *not* guaranteed to be initialized to 0, but an initialization expression may be provided:

```
int *v1 = new int;           // not guaranteed to be initialized to 0
int *v1 = new int();         // initialized to 0
int *v2 = new int(3);        // initialized to 3
int *v3 = new int(3 * *v2);  // initialized to 9
```

When a class-type object is allocated, the arguments of its constructor (if any) are specified immediately following the type specification in the `new` expression and the object will be initialized according to the thus specified constructor. For example, to allocate `string` objects the following statements could be used:

```
string *s1 = new string;      // uses the default constructor
string *s2 = new string();    // same
string *s3 = new string(4, ' '); // initializes to 4 blanks.
```

In addition to using `new` to allocate memory for a single entity or an array of entities there is also a variant that allocates *raw memory*: `operator new(sizeofBytes)`. Raw memory is returned as a `void *`. Here `new` allocates a block of memory for unspecified purpose. Although raw memory may consist of multiple characters it should not be interpreted as an array of characters. Since raw memory returned by `new` is returned as a `void *` its return value can be assigned to a `void *` variable. More often it is assigned to a `char *` variable, using a cast. Here is an example:

```
char *chPtr = static_cast<char *>(operator new(numberOfBytes));
```

The use of raw memory is frequently encountered in combination with the *placement new* operator, discussed in section 8.1.5.

8.1.1 Allocating arrays

Operator `new[]` is used to allocate arrays. The generic notation `new[]` is used in the **C++** Annotations. Actually, the number of elements to be allocated must be specified between the square brackets and it must, in turn, be *prefixed* by the type of the entities that must be allocated. Example:

```
int *intarr = new int[20];           // allocates 20 ints
string *stringarr = new string[10]; // allocates 10 strings.
```

Operator `new` is a different operator than operator `new[]`. A consequence of this difference is discussed in the next section (8.1.2).

Arrays allocated by operator `new[]` are called *dynamic arrays*. They are constructed during the execution of a program, and their lifetime may exceed the lifetime of the function in which they were created. Dynamically allocated arrays may last for as long as the program runs.

When `new[]` is used to allocate an array of primitive values or an array of objects, `new[]` must be specified with a type and an (unsigned) expression between its square brackets. The type and expression together are used by the compiler to determine the required size of the block of memory to make available. When `new[]` is used the array's elements are stored consecutively in memory. An array index expression may thereafter be used to access the array's individual elements: `intarr[0]` represents the first `int` value, immediately followed by `intarr[1]`, and so on until the last element (`intarr[19]`). With non-class types (primitive types, `struct` types without constructors) the block of memory returned by operator `new[]` is *not* guaranteed to be initialized to 0.

When operator `new[]` is used to allocate arrays of objects their constructors are automatically used. Consequently `new string[20]` results in a block of 20 *initialized* `string` objects. When allocating arrays of objects the class's *default constructor* is used to initialize each individual object in turn. A non-default constructor cannot be called, but often it is possible to work around that as discussed in section 13.8.

The expression between brackets of operator `new[]` represents the number of elements of the array to allocate. The **C++** standard allows allocation of 0-sized arrays. The statement `new int[0]` is correct **C++**. However, it is also pointless and confusing and should be avoided. It is pointless as it doesn't refer to any element at all, it is confusing as the returned pointer has a useless non-0 value. A pointer intending to point to an array of values should be initialized (like any pointer that isn't yet pointing to memory) to 0, allowing for expressions like `if (ptr) ...`

Without using operator `new[]`, arrays of variable sizes can also be constructed as *local arrays*. Such arrays are not dynamic arrays and their lifetimes are restricted to the lifetime of the block in which they were defined.

Once allocated, all arrays have fixed sizes. There is no *simple* way to enlarge or shrink arrays. **C++** has no operator 'renew'. Section 8.1.3 illustrates how to enlarge arrays.

8.1.2 Deleting arrays

Dynamically allocated arrays are deleted using operator `delete[]`. It expects a pointer to a block of memory, previously allocated by operator `new[]`.

When operator `delete[]`'s operand is a pointer to an array of objects two actions will be performed:

- First, the class's destructor is called for each of the objects in the array. The destructor, as explained later in this chapter, performs all kinds of cleanup operations that are required by the time the object ceases to exist.
- Second, the memory pointed at by the pointer is returned to the common pool.

Here is an example showing how to allocate and delete an array of 10 string objects:

```
std::string *sp = new std::string[10];
delete[] sp;
```

No special action is performed if a dynamically allocated array of primitive typed values is deleted. Following `int *it = new int[10]` the statement `delete[] it` simply returns the memory pointed at by `it` is returned. Realize that, as a pointer is a primitive type, deleting a dynamically allocated array of pointers to objects will *not* result in the proper destruction of the objects the array's elements point at. So, the following example results in a *memory leak*:

```
string **sp = new string *[5];
for (size_t idx = 0; idx != 5; ++idx)
    sp[idx] = new string;
delete[] sp;           // MEMORY LEAK !
```

In this example the only action performed by `delete[]` is to return an area the size of five pointers to strings to the common pool.

Here's how the destruction in such cases *should* be performed:

- Call `delete` for each of the array's elements;
- Delete the array itself

Example:

```
for (size_t idx = 0; idx != 5; ++idx)
    delete sp[idx];
delete[] sp;
```

One of the consequences is of course that by the time the memory is going to be returned not only the pointer must be available but also the number of elements it contains. This can easily be accomplished by storing pointer and number of elements in a simple class and then using an object of that class.

Operator `delete[]` is a different operator than operator `delete`. The rule of thumb is: if `new[]` was used, also use `delete[]`.

8.1.3 Enlarging arrays

Once allocated, all arrays have fixed sizes. There is no simple way to enlarge or shrink arrays. C++ has no `renew` operator. The basic steps to take when enlarging an array are the following:

- Allocate a new block of memory of larger size;

- Copy the old array contents to the new array;
- Delete the old array;
- Let the pointer to the array point to the newly allocated array.

Static and local arrays cannot be resized. Resizing is only possible for dynamically allocated arrays. Example:

```
#include <string>
using namespace std;

string *enlarge(string *old, unsigned oldsize, unsigned newsize)
{
    string *tmp = new string[newsize]; // allocate larger array

    for (size_t idx = 0; idx != oldsize; ++idx)
        tmp[idx] = old[idx];           // copy old to tmp

    delete[] old;                       // delete the old array
    return tmp;                         // return new array
}

int main()
{
    string *arr = new string[4];         // initially: array of 4 strings
    arr = enlarge(arr, 4, 6);           // enlarge arr to 6 elements.
}
```

The procedure to enlarge shown in the example also has several drawbacks.

- The new array requires `newsize` constructors to be called;
- Having initialized the strings in the new array, `oldsize` of them are immediately reassigned to the corresponding values in the original array;
- All the objects in the old arrays are destroyed.

Depending on the context various solutions exist to improve the efficiency of this rather inefficient procedure. An array of pointers could be used (requiring only the pointers to be copied, no destruction, no superfluous initialization) or raw memory in combination with the placement `new` operator could be used (an array of objects remains available, no destruction, no superfluous construction).

8.1.4 Managing 'raw' memory

As we've seen operator `new` allocates the memory for an object and subsequently initialize that object calling one of its constructors. Likewise, operator `delete` calls an object's destructor and subsequently returns the memory allocated by operator `new` to the common pool.

In the next section we'll encounter another use of `new`, allowing us to initialize objects in so-called *raw memory*: memory merely consisting of bytes that have been made available either by static or dynamic allocation.

Raw memory is made available by operator `new(sizeInBytes)`. This should not be interpreted as an array of any kind but just a series of memory locations that were dynamically made available. operator `new` returns a `void *` so a (static) cast is required to use it as memory of some type. Here are two examples:

```
// room for 5 ints
```

```
int *ip = static_cast<int *>(operator new(5 * sizeof(int)));
           // room for 5 strings
string *sp = static_cast<int *>(operator new(5 * sizeof(string)));
```

As `operator new` has no concept of data types the size of the intended data type must be specified when allocating raw memory for a certain number of objects of an intended type. The use of `operator new` therefore somewhat resembles the use of `malloc`.

The counterpart of `operator new` is `operator delete`. `Operator new` expects a `void *` (so a pointer to any type can be passed to it). The pointer is interpreted as a pointer to raw memory and is returned to the common pool. `Operator delete` does *not* call a destructor. The use of `operator delete` therefore resembles the use of `free`. To return the memory pointed at by the abovementioned variables `ip` and `sp` `operator delete` should be used:

```
           // delete raw memory allocated by operator new
operator delete(ip);
operator delete(sp);
```

8.1.5 The ‘placement new’ operator

A remarkable form of `operator new` is called the *placement new* operator. Before using `placement new` the `<memory>` header file must have been included.

With `placement new` `operator new` is provided with an existing block of memory in which an object or value is initialized. The block of memory should of course be large enough to contain the object, but apart from that no other requirements exist. It is easy to determine how much memory is used by an entity (object or variable) of type `Type`: the `sizeof` operator returns the number of bytes required by an `Type` entity. Entities may of course dynamically allocate memory for their own use. Dynamically allocated memory, however, is not part of the entity’s memory ‘footprint’ but it is always made available externally to the entity itself. This is why `sizeof` returns the same value when applied to different `string` objects returning different length and capacity values.

The `placement new` operator uses the following syntax (using `Type` to indicate the used data type):

```
Type *new(void *memory) Type(arguments);
```

Here, `memory` is a block of memory of at least `sizeof(Type)` bytes and `Type(arguments)` is any constructor of the class `Type`.

The `placement new` operator is useful in situations where classes set aside memory to be used later. This is used, e.g., by `std::string` to change its capacity. Calling `string::reserve` may enlarge that capacity without making memory beyond the string’s length immediately available. But the object itself may access its additional memory and so when information is added to a `string` object it can draw memory from its capacity rather than having to perform a reallocation for each single addition of information.

Let’s apply that philosophy to a class `Strings` storing `std::string` objects. The class defines a `char *d_memory` accessing the memory holding its `d_size` `string` objects as well as `d_capacity - d_size` reserved memory. Assuming that a default constructor initializes `d_capacity` to 1, doubling `d_capacity` whenever an additional `string` must be stored, the class must support the following essential operations:

- doubling its capacity when all its spare memory (e.g., made available by `reserve`) has been consumed;
- adding another `string` object
- properly deleting the installed strings and memory when a `Strings` object ceases to exist.

To double the capacity new memory is allocated, old memory is copied into the newly allocated memory, and the old memory is deleted. This is implemented by the member `void Strings::reserve`, assuming `d_capacity` has already been given its proper value:

```
void Strings::reserve()
{
    using std::string;

    string *newMemory =
        static_cast<string *>(memcpy(
                                operator new(d_capacity),
                                d_memory,
                                d_size * sizeof(string)
                            ));

    delete d_memory;
    d_memory = newMemory;
}
```

The member `append` adds another `string` object to a `Strings` object. A (public) member `reserve(request)` ensures that the `String` object's capacity is sufficient. Then the placement `new` operator is used to install the next `string` into the raw memory's appropriate location:

```
void Strings::append(std::string const &next)
{
    reserve(d_size + 1);
    new (d_memory + d_size) std::string(next);
    ++d_size;
}
```

At the end of the `String` object's lifetime all its dynamically allocated memory must be returned. This is the responsibility of the destructor, as explained in the next section. The destructor's full definition is postponed to that section, but its actions when placement `new` is involved can be discussed here.

With placement `new` an interesting situation is encountered. Objects, possibly themselves allocating memory, are installed in memory that may or may not have been allocated dynamically, but that is definitely not completely filled with such objects. So a simple `delete[]` can't be used, but a `delete` for each of the objects that *are* available can't be used either, since that would also delete the memory of the objects themselves, which wasn't dynamically allocated.

This peculiar situation is solved in a peculiar way, only encountered in cases where the placement `new` operator has been used: memory allocated by objects initialized using placement `new` is returned by *explicitly* calling the object's destructor. The destructor is declared as a member having the class preceded by a tilde as its name, not using any arguments. So, `std::string`'s destructor is named `~string`. The memory allocated by our class `Strings` is therefore properly destroyed as follows (in the example assume that using namespace `std` was specified):

```
for (string *sp = d_memory + d_size; sp-- != d_memory; )
    sp->~string();

operator delete(d_memory);
```

So far, so good. All is well as long as we're using but one object. What about allocating an array of objects? Initialization is performed as usual. But as with `delete`, `delete[]` cannot be called when the buffer was allocated statically. Instead, when multiple objects were initialized using the placement `new` operator in combination with a statically allocated buffer all the objects' destructors must be called explicitly, as in the following example:

```
char buffer[3 * sizeof(string)];
```

```
string *sp = new(buffer) string [3];

for (size_t idx = 0; idx < 3; ++idx)
    sp[idx].~string();
```

8.2 The destructor

Comparable to the constructor, classes may define a *destructor*. This function is the constructor's counterpart in the sense that it is invoked when an object ceases to exist. A destructor is usually called automatically, but that's not always true. The destructors of dynamically allocated objects are not automatically activated, but in addition to that: when a program is interrupted by an `exit` call, only the destructors of already initialized global objects are called. In that situation destructors of objects defined *locally* by functions are also *not* called. This is one (good) reason for avoiding `exit` in **C++** programs.

Destructors obey the following syntactical requirements:

- a destructor's name is equal to its class name prefixed by a tilde;
- a destructor has no arguments;
- a destructor has no return value.

Destructors are declared in their class interfaces. Example:

```
class Strings
{
    public:
        Strings();
        ~Strings();    // the destructor
};
```

By convention the constructors are declared first. The destructor is declared next, to be followed by other member functions.

A destructor's main task is to ensure that memory allocated by an object is properly returned when the object ceases to exist. Consider the following interface of the class `Strings`:

```
class Strings
{
    std::string *d_string;
    size_t d_size;

    public:
        Strings();
        Strings(char const *const *cStrings, size_t n);
        ~Strings();

        std::string const &at(size_t idx) const;
        size_t size() const;
};
```

The constructor's task is to initialize the data fields of the object. E.g, its constructors are defined as follows:

```
Strings::Strings()
```

```

:
    d_string(0),
    d_size(0)
{}

Strings::Strings(char const *const *cStrings, size_t size)
:
    d_string(new string[size]),
    d_size(size)
{
    for (size_t idx = 0; idx != size; ++idx)
        d_string[idx] = cStrings[idx];
}

```

As objects of the class `Strings` allocate memory a destructor is clearly required. Destructors may or may not be called automatically. Here are the rules:

- A destructor is *never* called unless its constructor completed successfully. The remaining rules only apply when this rule holds true;
- Destructors of local non-static objects are called automatically when the execution flow leaves the block in which they were defined; the destructors of objects defined somewhere in the outer block of a function are called just before the function terminates.
- Destructors of static or global objects are called when the program itself terminates.
- The destructor of a dynamically allocated object is called by `delete` using the object's address as its operand;
- The destructors of a dynamically allocated array of objects are called by `delete[]` using the address of the array's first element as its operand;
- The destructor of an object initialized by placement `new` is activated by explicitly calling the object's destructor.

The destructor's task is to ensure that all memory that is dynamically allocated and controlled only by the object itself is returned. The task of the `Strings`'s destructor would therefore be to delete the memory to which `d_string` points. Its implementation is:

```

Strings::~~Strings()
{
    delete[] d_string;
}

```

The next example shows `Strings` at work. In process a `Strings` store is created, and its data are displayed. It returns a dynamically allocated `Strings` object to `main`. A `Strings *` receives the address of the allocated object and deletes the object again. Another `Strings` object is then created in a block of memory made available locally in `main`, and an explicit call to `~Strings` is required to return the memory allocated by that object. In the example only once a `Strings` object is automatically destroyed: the local `Strings` object defined by `process`. The other two `Strings` objects require explicit actions to prevent memory leaks.

```

#include "strings.h"
#include <iostream>

using namespace std;;

void display(Strings const &store)
{

```

```

        for (size_t idx = 0; idx != store.size(); ++idx)
            cout << store.at(idx) << '\n';
    }

    Strings *process(char *argv[], int argc)
    {
        Strings store(argv, argc);
        display(store);
        return new Strings(argv, argc);
    }

    int main(int argc, char *argv[])
    {
        Strings *sp = process(argv, argc);
        delete sp;

        char buffer[sizeof(Strings)];
        sp = new (buffer) Strings(argv, argc);
        sp->~Strings();
    }

```

8.2.1 Object pointers revisited

Operators `new` and `delete` are used when an object or variable is allocated. One of the advantages of the operators `new` and `delete` over functions like `malloc` and `free` is that `new` and `delete` call the corresponding object constructors and destructors.

The allocation of an object by operator `new` is a two-step process. First the memory for the object itself is allocated. Then its constructor is called, initializing the object. Analogously to the construction of an object, the destruction is also a two-step process: first, the destructor of the class is called deleting the memory controlled by the object. Then the memory used by the object itself is freed.

Dynamically allocated arrays of objects can also be handled by `new` and `delete`. When allocating an array of objects using operator `new` the default constructor is called for each object in the array. In cases like this operator `delete[]` must be used to ensure that the destructor is called for each of the objects in array.

However, the addresses returned by `new Type` and `new Type[size]` are of identical types, in both cases a `Type *`. Consequently it cannot be determined by the type of the pointer whether a pointer to dynamically allocated memory points to a single entity or to an array of entities.

What happens if `delete` rather than `delete[]` is used? Consider the following situation, in which the destructor `~Strings` is modified so that it tells us that it is called. In a `main` function an array of two `Strings` objects is allocated by `new`, to be deleted by `delete []`. Next, the same actions are repeated, albeit that the `delete` operator is called without `[]`:

```

#include <iostream>
#include "strings.h"
using namespace std;

Strings::~~Strings()
{
    cout << "Strings destructor called" << '\n';
}

int main()
{
    Strings *a = new Strings[2];

```

```

    cout << "Destruction with []'s" << '\n';
    delete[] a;

    a = new Strings[2];

    cout << "Destruction without []'s" << '\n';
    delete a;
}
/*
    Generated output:
Destruction with []'s
Strings destructor called
Strings destructor called
Destruction without []'s
Strings destructor called
*/

```

From the generated output, we see that the destructors of the individual `Strings` objects are called when `delete[]` is used, while only the first object's destructor is called if the `[]` is omitted.

Conversely, if `delete[]` is called in a situation where `delete` should have been called the results are unpredictable, and will most likely cause the program to crash. This problematic behavior is caused by the way the run-time system stores information about the size of the allocated array (usually right *before* the array's first element). If a single object is allocated the array-specific information is not available, but it is nevertheless assumed present by `delete[]`. This latter operator will interpret bogus values before the array's first element as size information, thus usually causing the program to fail.

If no destructor is defined, a *trivial destructor* is defined by the compiler. The trivial destructor ensures that the destructors of composed objects (as well as the destructors of *base classes* if a class is a derived class, cf. chapter 13) are called. This has serious implications: objects allocating memory will cause a memory leak unless precautionary measures are taken (by defining an appropriate destructor). Consider the following program:

```

#include <iostream>
#include "strings.h"
using namespace std;

Strings::~Strings()
{
    cout << "Strings destructor called" << '\n';
}

int main()
{
    Strings **ptr = new Strings* [2];

    ptr[0] = new Strings[2];
    ptr[1] = new Strings[2];

    delete[] ptr;
}

```

This program produces no output at all. Why is this? The variable `ptr` is defined as a pointer to a pointer. The dynamically allocated array therefore consists of pointer variables and pointers are of a primitive type. No destructors exist for primitive typed variables. Consequently only the array itself is returned, and no `Strings` destructor is called.

Of course, we don't want this, but require the `Strings` objects pointed to by the elements of `ptr` to be deleted too. In this case we have two options:

- In a for-statement visit all the elements of the `ptr` array, calling `delete` for each of the array's elements. This procedure was demonstrated in the previous section.
- A wrapper class is designed around a pointer (to, e.g., an object of some class, like `Strings`). Rather than using a pointer to a pointer to `Strings` objects a pointer to an array of wrapper-class objects is used. As a result `delete[] ptr` calls the destructor of each of the wrapper class objects, in turn calling the `Strings` destructor for their `d_strings` members. Example:

```
#include <iostream>
using namespace std;

class Strings    // partially implemented
{
    public:
        ~Strings();
};

inline Strings::~~Strings()
{
    cout << "destructor called\n";
}

class Wrapper
{
    Strings *d_strings;

    public:
        Wrapper();
        ~Wrapper();
};

inline Wrapper::Wrapper()
:
    d_strings(new Strings())
{}
inline Wrapper::~~Wrapper()
{
    delete d_strings;
}

int main()
{
    delete[] new Strings *[4]; // memory leak: no destructor called
    cout << "=====\n";
    delete[] new Wrapper[4];    // OK: 4 x destructor called
}
/*
    Generated output:
=====
destructor called
destructor called
destructor called
destructor called
*/
```

8.2.2 The function `set_new_handler()`

The C++ run-time system ensures that when memory allocation fails an error function is activated. By default this function throws a *bad_alloc* exception (see section 9.8), terminating the program. Therefore

it is not necessary to check the return value of `operator new`. Operator `new`'s default behavior may be modified in various ways. One way to modify its behavior is to redefine the function that's called when memory allocation fails. Such a function must comply with the following requirements:

- it has no parameters;
- its return type is `void`.

A redefined error function might, e.g., print a message and terminate the program. The user-written error function becomes part of the allocation system through the function `set_new_handler`.

Such an error function is illustrated below¹:

```
#include <iostream>
#include <string>
#include <cstring>

using namespace std;

void outOfMemory()
{
    cout << "Memory exhausted. Program terminates." << '\n';
    exit(1);
}

int main()
{
    long allocated = 0;

    set_new_handler(outOfMemory);          // install error function

    while (true)                          // eat up all memory
    {
        memset(new int [100000], 0, 100000 * sizeof(int));
        allocated += 100000 * sizeof(int);
        cout << "Allocated " << allocated << " bytes\n";
    }
}
```

Once the new error function has been installed it is automatically invoked when memory allocation fails, and the program is terminated. Memory allocation may fail in indirectly called code as well, e.g., when constructing or using streams or when strings are duplicated by low-level functions.

So far for the theory. On some systems the 'out of memory' condition may actually never be reached, as the operating system may interfere before the run-time support system gets a chance to stop the program (see also this [link](#)²).

The standard **C** functions allocating memory (like `strdup`, `malloc`, `realloc` etc.) do not trigger the new handler when memory allocation fails and should be avoided in **C++** programs.

8.3 The assignment operator

In **C++** struct and class type objects can be directly assigned new values in the same way as this is possible in **C**. The default action of such an assignment for non-class type data members is a straight

¹ This implementation applies to the Gnu **C/C++** requirements. Actually using the program given in the next example is not advised, as it will probably slow down your computer enormously due to the resulting use of the operating system's *swap area*.

²<http://www.linuxdevcenter.com/pub/a/linux/2006/11/30/linux-out-of-memory.html>

byte-by-byte copy from one data member to another. For now we'll use the following simple class `Person`:

```
class Person
{
    char *d_name;
    char *d_address;
    char *d_phone;

public:
    Person();
    Person(char const *name, char const *addr, char const *phone);
    ~Person();
private:
    char *strdupnew(char const *src);    // returns a copy of src.
};
```

`Person`'s data members are initialized to zeroes or to copies of the ASCII-Z strings passed to `Person`'s constructor, using some variant of `strdup`. Its destructor will return the allocated memory again.

Now consider the consequences of using `Person` objects in the following example:

```
void tmpPerson(Person const &person)
{
    Person tmp;
    tmp = person;
}
```

Here's what happens when `tmpPerson` is called:

- it expects a reference to a `Person` as its parameter `person`.
- it defines a local object `tmp`, whose data members are initialized to zeroes.
- the object referenced by `person` is copied to `tmp`: `sizeof(Person)` number of bytes are copied from `person` to `tmp`.

Now a potentially dangerous situation has been created. The actual values in `person` are *pointers*, pointing to allocated memory. After the assignment this memory is addressed by two objects: `person` and `tmp`.

- The potentially dangerous situation develops into an acutely dangerous situation once the function `tmpPerson` terminates: `tmp` is destroyed. The destructor of the class `Person` releases the memory pointed to by the fields `d_name`, `d_address` and `d_phone`: unfortunately, this memory is also pointed at by `person`....

This problematic assignment is illustrated in Figure 8.1.

Having executed `tmpPerson`, the object referenced by `person` now contains pointers to deleted memory.

This is undoubtedly not a desired effect of using a function like `tmpPerson`. The deleted memory will likely be reused by subsequent allocations. The pointer members of `person` have effectively become *wild pointers*, as they don't point to allocated memory anymore. In general it can be concluded that

every class containing pointer data members is a potential candidate for trouble.

Fortunately, it is possible to prevent these troubles, as discussed next.




Figure 8.1: Private data and public interface functions of the class `Person`, using byte-by-byte assignment

8.3.1 Overloading the assignment operator

Obviously, the right way to assign one `Person` object to another, is **not** to copy the contents of the object byte-wise. A better way is to make an equivalent object. One having its own allocated memory containing copies of the original strings.

The way to assign a `Person` object to another is illustrated in Figure 8.2. There are several ways to assign a `Person` object to another. One way would be to define a special member function to handle the assignment. The purpose of this member function would be to create a copy of an object having its own name, address and phone strings. Such a member function could be:

```
void Person::assign(Person const &other)
{
    // delete our own previously used memory
    delete[] d_name;
    delete[] d_address;
    delete[] d_phone;

    // copy the other Person's data
    d_name = strdupnew(other.d_name);
    d_address = strdupnew(other.d_address);
    d_phone = strdupnew(other.d_phone);
}
```

Using `assign` we could rewrite the offending function `tmpPerson`:

```
void tmpPerson(Person const &person)
{
    Person tmp;

    // tmp (having its own memory) holds a copy of person
    tmp.assign(person);

    // now it doesn't matter that tmp is destroyed..
```




Figure 8.2: Private data and public interface functions of the class `Person`, using the ‘correct’ assignment.

```
}
```

This solution is valid, although it only tackles a symptom. It requires the programmer to use a specific member function instead of the assignment operator. The original problem (assignment produces wild pointers) is still not solved. Since it is hard to ‘strictly adhere to a rule’ a way to solve the original problem is of course preferred.

Fortunately a solution exists using *operator overloading*: the possibility `C++` offers to redefine the actions of an operator in a given context. Operator overloading was briefly mentioned earlier, when the operators `<<` and `>>` were redefined to be used with streams (like `cin`, `cout` and `cerr`), see section 3.1.4.

Overloading the assignment operator is probably the most common form of operator overloading in `C++`. A word of warning is appropriate, though. The fact that `C++` allows operator overloading does not mean that this feature should indiscriminately be used. Here’s what you should keep in mind:

- operator overloading should be used in situations where an operator has a defined action, but this default action has undesired side effects in a given context. A clear example is the above assignment operator in the context of the class `Person`.
- operator overloading can be used in situations where the operator is commonly applied and no surprise is introduced when it’s redefined. An example where operator overloading is appropriately used is found in the class `std::string`: assigning one string object to another provides the destination string with a copy of the contents of the source string. No surprises here.
- in all other cases a member function should be defined instead of redefining an operator.

An operator should simply do what it is designed to do. The phrase that’s often encountered in the context of operator overloading is *do as the ints do*. The way operators behave when applied to `ints` is what is expected, all other implementations probably cause surprises and confusion. Therefore, overloading the insertion (`<<`) and extraction (`>>`) operators in the context of streams is probably ill-chosen: the stream operations have nothing in common with bitwise shift operations.

8.3.1.1 The member 'operator=()'

To add operator overloading to a class, the class interface is simply provided with a (usually *public*) member function naming the particular operator. That member function is thereupon implemented.

To overload the assignment operator =, a member `operator=(Class const &rhs)` is added to the class interface. Note that the function name consists of two parts: the keyword `operator`, followed by the operator itself. When we augment a class interface with a member function `operator=`, then that operator is *redefined* for the class, which prevents the default operator from being used. In the previous section the function `assign` was provided to solve the problems resulting from using the default assignment operator. Rather than using an ordinary member function **C++** commonly uses a dedicated operator generalizing the operator's default behavior to the class in which it is defined.

The `assign` member mentioned before may be redefined as follows (the member `operator=` presented below is a first, rather unsophisticated, version of the overloaded assignment operator. It will shortly be improved):

```
class Person
{
    public:                                // extension of the class Person
                                           // earlier members are assumed.
    void operator=(Person const &other);
};
```

Its implementation could be

```
void Person::operator=(Person const &other)
{
    delete[] d_name;                      // delete old data
    delete[] d_address;
    delete[] d_phone;

    d_name = strdupnew(other.d_name);    // duplicate other's data
    d_address = strdupnew(other.d_address);
    d_phone = strdupnew(other.d_phone);
}
```

This member's actions are similar to those of the previously mentioned member `assign`, but this member is automatically called when the assignment operator = is used. Actually there are *two* ways to call overloaded operators as shown in the next example:

```
void tmpPerson(Person const &person)
{
    Person tmp;

    tmp = person;
    tmp.operator=(person); // the same thing
}
```

Overloaded operators are seldom called explicitly, but explicit calls must be used (rather than using the plain operator syntax) when you explicitly *want* to call the overloaded operator from a pointer to an object (it is also possible to dereference the pointer first and then use the plain operator syntax, see the next example):

```
void tmpPerson(Person const &person)
{
    Person *tmp = new Person;
```

```

    tmp->operator=(person);
    *tmp = person;           // yes, also possible...

    delete tmp;
}

```

8.4 The ‘this’ pointer

A member function of a given class is always called in combination with an object of its class. There is always an implicit ‘substrate’ for the function to act on. **C++** defines a keyword, `this`, to reach this substrate.

The `this` keyword is a pointer variable that always contains the address of the object for which the member function was called. The `this` pointer is implicitly declared by each member function (whether public, protected, or private). The `this` pointer is a constant pointer to an object of the member function’s class. For example, the members of the class `Person` implicitly declare:

```
extern Person *const this;
```

A member function like `Person::name` could be implemented in two ways: with or without using the `this` pointer:

```

char const *Person::name() const    // implicitly using ‘this’
{
    return d_name;
}

char const *Person::name() const    // explicitly using ‘this’
{
    return this->d_name;
}

```

The `this` pointer is seldom explicitly used, but situations do exist where the `this` pointer is actually required (cf. chapter 16).

8.4.1 Sequential assignments and this

C++’s syntax allows for sequential assignments, with the assignment operator associating from right to left. In statements like:

```
a = b = c;
```

the expression `b = c` is evaluated first, and its result in turn is assigned to `a`.

The implementation of the overloaded assignment operator we’ve encountered thus far does not permit such constructions, as it returns `void`.

This imperfection can easily be remedied using the `this` pointer. The overloaded assignment operator expects a reference to an object of its class. It can also *return* a reference to an object of its class. This reference can then be used as an argument in sequential assignments.

The overloaded assignment operator commonly returns a reference to the current object (i.e., `*this`). The next version of the overloaded assignment operator for the class `Person` thus becomes:

```
Person &Person::operator=(Person const &other)
```

```

{
    delete[] d_address;
    delete[] d_name;
    delete[] d_phone;

    d_address = strdupnew(other.d_address);
    d_name = strdupnew(other.d_name);
    d_phone = strdupnew(other.d_phone);

    // return current object as a reference
    return *this;
}

```

Overloaded operators may themselves be overloaded. Consider the `string` class, having overloaded assignment operators `operator=(std::string const &rhs)`, `operator=(char const *rhs)`, and several more overloaded versions. These additional overloaded versions are there to handle different situations which are, as usual, recognized by their argument types. These overloaded versions all follow the same mold: when necessary dynamically allocated memory controlled by the object is deleted; new values are assigned using the overloaded operator's parameter values and `*this` is returned.

8.5 The copy constructor: initialization vs. assignment

Consider the class `Strings`, introduced in section 8.2, once again. As it contains several primitive type data members as well as a pointer to dynamically allocated memory it needs a constructor, a destructor, and an overloaded assignment operator. In fact the class offers two constructors: in addition to the default constructor it offers a constructor expecting a `char const *const *` and a `size_t`.

Now consider the following code fragment. The statement references are discussed following the example:

```

int main(int argc, char **argv)
{
    Strings s1(argv, argc);      // (1)
    Strings s2;                  // (2)
    Strings s3(s1);              // (3)

    s2 = s1;                     // (4)
}

```

- At 1 we see an initialization. The object `s1` is initialized using `main`'s parameters: `Strings`'s second constructor is used.
- At 2 `Strings`'s *default constructor* is used, initializing an empty `Strings` object.
- At 3 yet another `Strings` object is created, using a constructor accepting an existing `Strings` object. This form of initializations has not yet been discussed. It is called a *copy construction* and the constructor performing the initialization is called the *copy constructor*. Copy constructions are also encountered in the following form:

```
Strings s3 = s1;
```

This is a *construction* and therefore an *initialization*. It is not an *assignment* as an assignment needs a left-hand operand that has already been defined. **C++** allows the assignment syntax to be used for constructors having only one parameter. It is somewhat deprecated, though.

- At 4 we see a plain assignment.

In the above example three objects were defined, each using a different constructor. The actually used constructor was deduced from the constructor's argument list.

The copy constructor encountered here is new. It does not result in a compilation error even though it hasn't been declared in the class interface. This takes us to the following rule:

A copy constructor is always available, even if it isn't declared in the class's interface.

The copy constructor made available by the compiler is also called the trivial copy constructor. Starting with the C++0x standard it can easily be suppressed (using the `= delete` idiom). The trivial copy constructor performs a byte-wise copy operation of the existing object's primitive data to the newly created object, calls copy constructors to initialize the object's class data members from their counterparts in the existing object and, when inheritance is used, calls the copy constructors of the base class(es) to initialize the new object's base classes.

Consequently, in the above example the trivial copy constructor is used. As it performs a byte-by-byte copy operation of the object's primitive type data members that is exactly what happens at statement 3. By the time `s3` ceases to exist its destructor will delete its array of strings. Unfortunately `d_string` is of a primitive data type and so it also deletes `s1`'s data. Once again we encounter wild pointers as a result of an object going out of scope.

The remedy is easy: instead of using the trivial copy constructor a copy constructor must explicitly be added to the class's interface and its definition must prevent the wild pointers, comparably to the way this was realized in the overloaded assignment operator. An object's dynamically allocated memory is *duplicated*, so that it will contain its own allocated data. The copy constructor is simpler than the overloaded assignment operator in that it doesn't have to delete previously allocated memory. Since the object is going to be created no previously allocated memory already exists.

Strings's copy constructor can be implemented as follows:

```
Strings::Strings(Strings const &other)
:
    d_string(new string[other.d_size]),
    d_size(other.d_size)
{
    for (size_t idx = 0; idx != d_size; ++idx)
        d_string[idx] = other.d_string[idx];
}
```

The copy constructor is always called when an object is initialized using another object of its class. Apart from the plain copy construction that we encountered thus far, here are other situations where the copy constructor is used:

- it is used when a function defines a class type value parameter rather than a pointer or a reference. The function's argument initializes the function's parameter using the copy constructor. Example:

```
void process(Strings store) // no pointer, no reference
{
    store.at(3) = "modified";    // doesn't modify 'outer'
}

int main(int argc, char **argv)
{
    Strings outer(argv, argc);
    process(outer);
}
```

- it is used when a function defines a class type value return type. Example:

```
Strings copy(Strings const &store)
```

```

{
    return store;
}

```

Here `store` is used to initialize `copy`'s return value. The returned `Strings` object is a temporary, anonymous object that may be immediately used by code calling `copy` but no assumptions can be made about its lifetime thereafter.

8.5.1 Revising 'operator=()'

The overloaded assignment operator has characteristics also encountered with the copy constructor and the destructor:

- The *copying of (private) data* occurs (1) in the copy constructor and (2) in the overloaded assignment function.
- Allocated memory is deleted (1) in the overloaded assignment function and (2) in the destructor.

The copy constructor and the destructor clearly are required. If the overloaded assignment operator also needs to return allocated memory and to assign new values to its data members couldn't the destructor and copy constructor be used for that?

As we've seen in our discussion of the destructor (section 8.2) the destructor can explicitly be called, but that doesn't hold true for the (copy) constructor. But let's briefly summarize what an overloaded assignment operator is supposed to do:

- It should delete the dynamically allocated memory controlled by the current object;
- It should reassign the current object's data members using a provided existing object of its class.

The second part surely looks like a copy construction. Copy construction becomes even more attractive after realizing that the copy constructor also initializes any reference data members the class might have. Realizing the copy construction part is easy: just define a local object and initialize it using the assignment operator's `const` reference parameter, like this:

```

Strings &operator=(Strings const &other)
{
    Strings tmp(other);
    // more to follow
    return *this;
}

```

The optimization `operator=(String tmp)` is enticing, but let's postpone that for a little while (at least until section 8.6).

Now that we've done the copying part, what about the deleting part? And isn't there another slight problem as well? After all we copied all right, but not into our intended (`current`, `*this`) object.

At this point it's time to introduce *swapping*. Swapping two variables means that the two variables exchange their values. Many classes (e.g., `std::string`) offer `swap` members allowing us to swap two of their objects. The *Standard Template Library* (STL, cf. chapter 18) offers various functions related to swapping. There is even a *swap generic algorithm* (cf. section 19.1.61). That latter algorithm, however, begs the current question, as it is customarily implemented using the assignment operator, so it's somewhat problematic to use it when implementing the assignment operator.

As we've seen with the placement `new` operator objects can be constructed in blocks of memory of `sizeof(Class)` bytes large. And so, two objects of the same class each occupy `sizeof(Class)` bytes.

To swap these objects we merely have to swap the contents of those `sizeof(Class)` bytes. This procedure may be applied to classes whose objects may be swapped using a member-by-member swapping operation and can also be used for classes having reference data members. Here is its implementation for a hypothetical class `Class`, resulting in very fast swapping:

```
#include <cstring>

void Class::swap(Class &other)
{
    char buffer[sizeof(Class)];
    memcpy(buffer, &other, sizeof(Class));
    memcpy(&other, this, sizeof(Class));
    memcpy(this, buffer, sizeof(Class));
}
```

Let's add `void swap(Strings &other)` to the class `Strings` and complete its `operator=` implementation:

```
Strings &operator=(Strings const &other)
{
    Strings tmp(other);
    swap(tmp);
    return *this;
}
```

This `operator=` implementation is generic: it can be applied to every class whose objects are directly swappable. How does it work?

- The information in the `other` object is used to initialize a local `tmp` object. This takes care of the copying part of the assignment operator.
- Calling `swap` ensures that the current object receives its new values.
- When `operator=` terminates its local `tmp` object ceases to exist and its destructor is called. But by now it contains the data previously owned by the current object, so *those* data are now returned. Which takes care of the destruction part of the assignment operation.

Nice?

8.6 The move constructor (C++0x)

Before the advent of the C++0x standard C++ offered basically two ways to assign the information pointed to by a data member of a temporary object to an *lvalue* object. Either a copy constructor or reference counting had to be used. The C++0x standard adds *move semantics* to these two, allowing *transfer* of the data pointed to by a temporary object to its destination.

Our class `Strings` has, among other members a data member `string *d_string`. Clearly, `Strings` should define a copy constructor, a destructor and an overloaded assignment operator.

Now design a function `loadStrings(std::istream &in)` extracting the strings of a `Strings` object from `in`. As the `Strings` object doesn't exit yet, the `Strings` object filled by `loadStrings` is returned by value. The function `loadStrings` returns a temporary object, which is then used to initialize an external `Strings` object:

```
Strings loadStrings(std::istream &in)
{
```



```

    Strings ret;
    // load the strings into 'ret'
    return ret;
}
// usage:
Strings store(loadStrings(cin));

```

In this example two full copies of a `Strings` object are required:

- initializing `loadString`'s value return type from its local `Strings ret` object;
- initializing `store` from `loadString`'s return value

The *rvalue reference* concept allows us to improve this procedure. An *rvalue reference* binds to an anonymous temporary (r)value and the compiler is required to do so whenever possible. We, as programmers, must inform the compiler in what situations rvalue references can be handled. We do this by providing overloaded members defining rvalue reference parameters.

One such overloaded member is the *move constructor*. The move constructor is a constructor defining an rvalue reference to an object of its own class as parameter. Here is the declaration of the `Strings` class move constructor:

```
Strings(Strings &&tmp);
```

Move constructors are allowed to simply assign the values of pointer data members to their own pointer data members without requiring them to make a copy of the source's data first. Having done so the temporary's pointer value is set to zero to prevent its destructor from destroying data now owned by the just constructed object. The move constructor has *grabbed* or *stolen* the data from the temporary object. This is OK as the temporary cannot be referred to again (as it is anonymous, it cannot be accessed by other code) and ceases to exist shortly after the constructor's call anyway. Here is the implementation of `Strings` move constructor:

```

Strings::Strings(Strings &&tmp)
:
    d_memory(tmp.d_memory),
    d_size(tmp.d_size),
    d_capacity(tmp.d_capacity)
{
    tmp.d_memory = 0;
}

```

Once a class becomes a *move-aware* class this awareness must extend to its destructor as well. With `Strings` this is not an issue as its destructor only executes `delete[] d_string`, but it becomes an issue in classes using, e.g., pointers to pointer data members. Their destructors must visit each of the array's pointers to delete the objects pointed to by the array's elements. Assuming that `Strings d_string` data member was defined as `string **d_string` the implementation of `String`'s move constructor may remain as-is, but the destructor must now inspect `d_string` to prevent the destruction loop from executing when it is zero:

```

Strings::~~Strings()
{
    if (d_string == 0)
        return;
    for (string **end = d_string + d_size; end-- != d_string; )
        delete *end;
    delete[] d_string;
}

```

In addition to the move constructor other members defining `Class const &` parameters may also be overloaded with members expecting `Class &&` parameters. Here too the compiler will select these latter overloads if an anonymous temporary argument is provided. Let's consider the implications for a minute using the next example, assuming `Class` offers a move constructor and a copy constructor:

```

Class factory();

void fun(Class const &other);    // a
void fun(Class &&tmp);           // b

void callee(Class &&tmp);
{
    Class object(factory());    // 1
    Class object2(object);      // 2
    fun(object);                // 3
    fun(factory());             // 4
    fun(tmp);                   // 5
}

int main()
{
    callee(factory());
}

```

- At 1 the move constructor is called. Object is initialized by an anonymous temporary `Class` object;
- At 2 the copy constructor is called. The constructor's argument is an existing local object;
- At 3 function a is called: `fun`'s argument is an existing local object;
- At 4 function b is called: `fun`'s argument is an anonymous temporary object;
- At 5 function a is called. At first sight this might be surprising, but `fun`'s argument is not an *anonymous* temporary object but a *named* temporary object. Overloads expecting rvalue references are *only* selected when passed *anonymous* temporary objects.

Realizing that `fun(tmp)` might be called twice the compiler's choice is understandable. If `tmp`'s data would have been grabbed at the first call, the second call would receive `tmp` without any data. But at the last call we might know that `tmp` is never used again and so we might like to ensure that `fun(Class &&)` is called. This can be realized by the following cast:

```
fun(reinterpret_cast<Class &&>(tmp)); // last call!
```

More often, though the shorthand `fun(std::move(tmp))` is used, already performing the required cast for us. `std::move` is indirectly declared by many header files. If no header is already declaring `std::move` then include `utility`.

It is pointless to provide a function with an rvalue reference return type. The compiler decides whether or not to use an overloaded member expecting an rvalue reference on the basis of the provided argument: if it is an anonymous temporary it will call the overloaded member defining the rvalue reference parameter.

Classes not using pointer members pointing to memory controlled by its objects (and not having base classes doing so, see chapter 13) do not benefit from overloaded members expecting rvalue references.

The compiler, when selecting a function to call applies a fairly simple algorithm, and also considers copy elision. This is covered shortly (section 8.7).

8.6.1 Move-only classes (C++0x)

Classes may very well allow move semantics without offering copy semantics. Most stream classes belong to this category. Extending their definition with move semantics greatly enhances their usability. Once move semantics becomes available for such classes, so called *factory functions* (functions returning an object constructed by the function) can easily be implemented. E.g.,

```
// assume char *filename
ifstream inStream(openIstream(filename));
```

For this example to work an `ifstream` constructor must offer a move constructor. This way there will at any time be only one object referring to the open `istream`.

Once classes offer move semantics their objects can also safely be stored in standard containers. When such containers performs reallocation (e.g., when their sizes are enlarged) they will use the object's move constructors rather than their copy constructors. As move-only classes suppress copy semantics containers storing objects of move-only classes implement the correct behavior in that it is impossible to assign such containers to each other.

8.7 Copy Elision and Return Value Optimization

When the compiler selects a member function (or constructor) it will do so according to a simple set of rules, matching arguments with parameter types.

Below two tables are provided. The first table should be used in cases where a function argument has a name, the second table should be used in cases where the argument is anonymous. In each table select the `const` or `non-const` column and then use the topmost overloaded function that is available having the specified parameter type.

The tables do not handle functions defining value parameters. If a function has overloads expecting, respectively, a value parameter and some form of reference parameter the compiler reports an ambiguity when such a function is called. In the following selection procedure we may assume, without loss of generality, that this ambiguity does not occur and that all parameter types are reference parameters.

Parameter types matching a function's argument of type `T` if the argument is:

- a *named* argument (an lvalue or a named rvalue)

non-const	const
(T &)	
(T const &)	(T const &)

Example: for an `int x` argument a function `fun(int &)` is selected rather than a function `fun(int const &)`. If no `fun(int &)` is available the `fun(int const &)` function is used. If neither is available the compiler reports an error.

- an *anonymous* argument (an anonymous temporary or a literal value)

non-const	const
(T &&)	
(T const &&)	(T const &&)
(T const &)	(T const &)

Example: for an `int arg()` argument a function `fun(int &&)` is selected rather than a function `fun(int const &&)`. If both functions are unavailable but a `fun(int const &)` is available, that function is used. If none of these functions is available the compiler reports an error.

The tables show that eventually *all* arguments can be used with a function specifying a `T const &` parameter. For *anonymous* arguments a similar *catch all* is available having a higher priority: `T const &&` matches all anonymous arguments. Thus, if named and anonymous arguments are to be distinguished a `T const &&` overloaded function will catch all temporaries.

As we've seen the move constructor grabs the information from a temporary for its own use. That is OK as the temporary is going to be destroyed after that anyway. It also means that the temporary's data members are modified. This modification can safely be considered a *non-mutating operation* on the temporary. It may thus be modified even if it was passed to a function specifying a `T const &&` parameter. In cases like these consider using a `const_cast` to cast away the const-ness of the rvalue reference. The `Strings` move constructor encountered before might therefore also have been implemented as follows, handling both `Strings` and `Strings const` anonymous temporaries:

```
Strings::Strings(Strings const &&tmp)
:
    d_string(tmp.d_string),
    d_size(tmp.d_size)
{
    const_cast<Strings &>(tmp).d_string = 0;
}
```

Having defined appropriate copy and/or move constructors it may be somewhat surprising to learn that the compiler may decide to stay clear of a copy or move operation. After all making *no* copy and *not* moving is more efficient than copying or moving.

The option the compiler has to avoid making copies (or perform move operations) is called *copy elision* or *return value optimization*. In all situations where copy or move constructions are appropriate the compiler may apply copy elision. Here are the rules. In sequence the compiler considers the following options, stopping once an option can be selected:

- if a copy or move constructor exists, try copy elision
- if a move constructor exists, move.
- if a copy constructor exists, copy.
- report an error

All modern compilers apply copy elision. Here are some examples where it may be encountered:

```
class Elide;

Elide fun()           // 1
{
    Elide ret;
    return ret;
}

void gun(Elide par);

Elide elide(fun()); // 2

gun(fun());          // 3
```

- At 1 `ret` may never exist. Instead of using `ret` and copying `ret` eventually to `fun`'s return value it may directly use the area used to contain `fun`'s return value.
- At 2 `fun`'s return value may never exist. Instead of defining an area containing `fun`'s return value and copying that return value to `elide` the compiler may decide to use `elide` to create `fun`'s return value in.

- At 3 the compiler may decide to do the same for `fun`'s `par` parameter: `fun`'s return value is directly created in `par`'s area, thus eliding the copy operation from `fun`'s return value to `par`.

8.8 Plain Old Data (C++0x)

C++ inherited the struct concept from **C** and extended it with the class concept. Structs are still used in **C++**, mainly to store and pass around aggregates of different data types. A commonly term for these structs is *plain old data* (pod). Plain old data is commonly used in **C++** programs to aggregate data. E.g., when a function needs to return a `double`, `bool` and `std::string` these three different data types may be aggregated using a struct that merely exists to pass along values. Data protection and functionality is hardly ever an issue. For such cases **C** and **C++** use structs. But as a **C++** struct is just a class with special access rights some members (constructors, destructor, overloaded assignment operator) may implicitly be defined. The plain old data capitalizes on this concept by requiring that its definition remains as simple as possible. Specifically the C++0x standard considers pod to be a class or struct having the following characteristics:

- it has a trivial default constructor.
If a type has some *trivial member* then the type (or its base class(es), cf. chapter 13) does not explicitly define that member. Rather, it is supplied by the compiler. A trivial default constructor leaves all its non-class data members uninitialized and will call the default constructors of all its class data members. A class having a trivial default constructor does not define any constructor at all (nor does/do its base class/classes). It may also define the default constructor using the default constructor syntax introduced in section 7.4;
- it has a trivial copy constructor.
A trivial copy constructor byte-wise copies the non-class data members from the provided existing class object and uses copy constructors to initialize its base class(es) and class data members with the information found in the provided existing class object;
- it has a trivial overloaded assignment operator.
A trivial assignment operator performs a byte-wise copy of the non-class data members of the provided right-hand class object and uses overloaded assignment operators to assign new values to its class data members using the corresponding members of the provided right-hand class object;
- it has a trivial destructor.
A trivial destructor calls the destructors of its base class(es) and class-type data members;
- it has a *standard layout*.

A *standard-layout* class or struct

- has only non-static data members that are themselves showing the standard-layout;
- has identical access control (public, private, protected) for all its non-static members;

Furthermore, in the context of class derivation (cf. chapters 14 and 13), a *standard-layout* class or struct:

- has only base classes that themselves show the standard-layout;
- has at most one (in)direct base class having non-static members;
- has no base classes of the same type as its first non-static data member;
- has no virtual base classes;
- has no virtual members.

8.9 Conclusion

Four important extensions to classes were introduced in this chapter: the destructor, the copy constructor, the move constructor and the overloaded assignment operator. In addition the importance of *swapping*, especially in combination with the overloaded assignment operator, was stressed.

Classes having pointer data members, pointing to dynamically allocated memory controlled by the objects of those classes, are potential sources of memory leaks. The extensions introduced in this chapter implement the standard defense against such memory leaks.

Encapsulation (data hiding) allows us to ensure that the object's data integrity is maintained. The automatic activation of constructors and destructors greatly enhance our capabilities to ensure the data integrity of objects doing dynamic memory allocation.

A simple conclusion is therefore that classes whose objects allocate memory controlled by themselves must at least implement a *destructor*, an *overloaded assignment operator* and a *copy constructor*. Implementing a *move constructor* remains optional, but it allows us to use *factory functions* with classes *not* allowing copy construction and/or assignment.

In the end, assuming the availability of at least a copy or move constructor, the compiler might avoid them using *copy elision*. The compiler is free to use copy elision wherever possible; it is, however, never a requirement. The compiler may therefore always decide not to use copy elision. In all situations where otherwise a copy or move constructor would have been used the compiler may consider to use copy elision.

Chapter 9

Exceptions

C supports several ways for a program to react to situations breaking the normal unhampered flow of a program:

- The function may notice the abnormality and issue a message. This is probably the least disastrous reaction a program may show.
- The function in which the abnormality is observed may decide to stop its intended task, returning an error code to its caller. This is a great example of postponing decisions: now the *calling function* is faced with a problem. Of course the calling function may act similarly, by passing the error code up to *its* caller.
- The function may decide that things are going out of hand, and may call `exit` to terminate the program completely. A tough way to handle a problem if only because the destructors of local objects aren't activated.
- The function may use a combination of the functions `setjmp` and `longjmp` to enforce non-local exits. This mechanism implements a kind of `goto` jump, allowing the program to continue at an outer level, skipping the intermediate levels which would have to be visited if a series of returns from nested functions would have been used.

In C++ all these flow-breaking methods are still available. However, of the mentioned alternatives, `setjmp` and `longjmp` isn't frequently encountered in C++ (or even in C) programs, due to the fact that the program flow is completely disrupted.

C++ offers *exceptions* as the preferred alternative to, e.g., `setjmp` and `longjmp`. Exceptions allow C++ programs to perform a controlled non-local return, without the disadvantages of `longjmp` and `setjmp`.

Exceptions are the proper way to bail out of a situation which cannot be handled easily by a function itself, but which is not disastrous enough for a program to terminate completely. Also, exceptions provide a flexible layer of control between the short-range `return` and the crude `exit`.

In this chapter exceptions are covered. First an example will be given of the different impact exceptions and the `setjmp/longjmp` combination have on programs. This example is followed by a discussion of the formal aspects of exceptions. In this part the guarantees our software should be able to offer when confronted with exceptions are presented. Exceptions and their guarantees have consequences for constructors and destructors. We'll encounter these consequences at the end of this chapter.

9.1 Exception syntax

Before contrasting the traditional C way of handling non-local gotos with exceptions let's introduce the syntactic elements that are involved when using exceptions.

- Exceptions are generated by a `throw` statement. The keyword `throw`, followed by an expression of a certain type, throws the expression value as an exception. In **C++** anything having value semantics may be thrown as an exception: an `int`, a `bool`, a `string`, etc. However, there also exists a *standard exception* type (cf. section 9.8) that may be used as *base class* (cf. chapter 13) when defining new exception types.
- Exceptions are generated within a well-defined local environment, called a `try`-block. The run-time support system ensures that all of the program's code is itself surrounded by a *global try block*. Thus, every exception generated by our code will always reach the boundary of at least one `try`-block. A program terminates when an exception reaches the boundary of the global `try` block, and when this happens destructors of local and global objects that were alive at the point where the exception was generated are not called. This is not a desirable situation and therefore all exceptions should be generated within a `try`-block explicitly defined by the program. Here is an example of a `string` exception thrown from within a `try`-block:

```
try
{
    // any code can be defined here
    if (someConditionIsTrue)
        throw string("this is the std::string exception");
    // any code can be defined here
}
```

- `catch`: Immediately following the `try`-block, one or more `catch`-clauses must be defined. A `catch`-clause consists of a `catch`-header defining the type of the exception it can catch followed by a compound statement defining what to do with the caught exception:

```
catch (string const &msg)
{
    // statements in which the caught string object are handled
}
```

Multiple `catch` clauses may appear underneath each other, one for each exception type that has to be caught. In general the `catch` clauses may appear in any order, but there are exceptions requiring a specific order. To avoid confusion it's best to put a `catch` clause for the most general exception last. At most *one* exception clause will be activated. **C++** does not support a **Java**-style *finally*-clause activated after completing a `catch` clause.

9.2 An example using exceptions

In the following examples the same basic program is used. The program uses two classes, `Outer` and `Inner`.

First, an `Outer` object is defined in `main`, and its member `Outer::fun` is called. Then, in `Outer::fun` an `Inner` object is defined. Having defined the `Inner` object, its member `Inner::fun` is called.

That's about it. The function `Outer::fun` terminates calling `inner`'s destructor. Then the program terminates, activating `outer`'s destructor. Here is the basic program:

```
#include <iostream>
using namespace std;

class Inner
{
public:
    Inner();
    ~Inner();
    void fun();
}
```



```

};
Inner::Inner()
{
    cout << "Inner constructor\n";
}
Inner::~~Inner()
{
    cout << "Inner destructor\n";
}
void Inner::fun()
{
    cout << "Inner fun\n";
}

class Outer
{
public:
    Outer();
    ~Outer();
    void fun();
};
Outer::Outer()
{
    cout << "Outer constructor\n";
}
Outer::~~Outer()
{
    cout << "Outer destructor\n";
}
void Outer::fun()
{
    Inner in;
    cout << "Outer fun\n";
    in.fun();
}

int main()
{
    Outer out;
    out.fun();
}

/*
    Generated output:
Outer constructor
Inner constructor
Outer fun
Inner fun
Inner destructor
Outer destructor
*/

```

After compiling and running, the program's output is entirely as expected: the destructors are called in their correct order (reversing the calling sequence of the constructors).

Now let's focus our attention on two variants in which we simulate a non-fatal disastrous event in the `Inner::fun` function. This event must supposedly be handled near `main`'s end.

We'll consider two variants. In the first variant the event is handled by `setjmp` and `longjmp`; in the

second variant the event is handled using C++'s exception mechanism.

9.2.1 Anachronisms: 'setjmp' and 'longjmp'

The basic program from the previous section is slightly modified to contain a variable `jmp_buf jmpBuf` used by `setjmp` and `longjmp`.

The function `Inner::fun` calls `longjmp`, simulating a disastrous event, to be handled near `main`'s end. In `main` a target location for the long jump is defined through the function `setjmp`. `Setjmp`'s zero return indicates the initialization of the `jmp_buf` variable, in which case `Outer::fun` is called. This situation represents the 'normal flow'.

The program's return value is zero *only* if `Outer::fun` terminates normally. The program, however, is designed in such a way that this won't happen: `Inner::fun` calls `longjmp`. As a result the execution flow returns to the `setjmp` function. Now it will *not* return a zero return value. Consequently, after calling `Inner::fun` from `Outer::fun` `main`'s if-statement is entered and the program terminates with return value 1. Try to follow these steps when studying the following program source, which is a direct modification of the basic program given in section 9.2:

```
#include <iostream>
#include <setjmp.h>
#include <cstdlib>

using namespace std;

jmp_buf jmpBuf;

class Inner
{
public:
    Inner();
    ~Inner();
    void fun();
};

Inner::Inner()
{
    cout << "Inner constructor\n";
}

void Inner::fun()
{
    cout << "Inner fun\n";
    longjmp(jmpBuf, 0);
}

Inner::~~Inner()
{
    cout << "Inner destructor\n";
}

class Outer
{
public:
    Outer();
    ~Outer();
    void fun();
};

Outer::Outer()
```

```

{
    cout << "Outer constructor\n";
}
Outer::~~Outer()
{
    cout << "Outer destructor\n";
}
void Outer::fun()
{
    Inner in;
    cout << "Outer fun\n";
    in.fun();
}

int main()
{
    Outer out;

    if (setjmp(jmpBuf) != 0)
        return 1;

    out.fun();
}
/*
    Generated output:
Outer constructor
Inner constructor
Outer fun
Inner fun
Outer destructor
*/

```

This program's output clearly shows that inner's destructor is not called. This is a direct consequence of the non-local jump performed by `longjmp`. Processing proceeds immediately from the `longjmp` call inside `Inner::fun` to `setjmp` in `main`. There, its return value is unequal zero, and the program terminates with return value 1. Because of the non-local jump `Inner::~~Inner` is never executed: upon return to `main`'s `setjmp` the existing stack is simply broken down disregarding any destructors waiting to be called.

This example illustrates that the destructors of objects can easily be skipped when `longjmp` and `setjmp` are used and **C++** programs should therefore avoid those functions like the plague.

9.2.2 Exceptions: the preferred alternative

Exceptions are **C++**'s answer to the problems caused by `setjmp` and `longjmp`. Here is an example using exceptions. The program is once again derived from the basic program of section 9.2:

```

#include <iostream>
using namespace std;

class Inner
{
public:
    Inner();
    ~Inner();
    void fun();
};

Inner::Inner()

```

```

{
    cout << "Inner constructor\n";
}
Inner::~Inner()
{
    cout << "Inner destructor\n";
}
void Inner::fun()
{
    cout << "Inner fun\n";
    throw 1;
    cout << "This statement is not executed\n";
}

class Outer
{
public:
    Outer();
    ~Outer();
    void fun();
};

Outer::Outer()
{
    cout << "Outer constructor\n";
}
Outer::~~Outer()
{
    cout << "Outer destructor\n";
}
void Outer::fun()
{
    Inner in;
    cout << "Outer fun\n";
    in.fun();
}

int main()
{
    Outer out;
    try
    {
        out.fun();
    }
    catch (int x)
    {}
}
/*
    Generated output:
Outer constructor
Inner constructor
Outer fun
Inner fun
Inner destructor
Outer destructor
*/

```

`Inner::fun` now throws an `int` exception where a `longjmp` was previously used. Since `in.fun` is called by `out.fun`, the exception is generated within the `try` block surrounding the `out.fun` call. As

an `int` value was thrown this value will reappear in the `catch` clause beyond the `try` block.

Now `Inner::fun` terminates by throwing an exception instead of calling `longjmp`. The exception is caught in `main`, and the program terminates. Now we see that `inner`'s destructor is properly called. It is interesting to note that `Inner::fun`'s execution really terminates at the `throw` statement: The `cout` statement, placed just beyond the `throw` statement, isn't executed.

What did this example teach us?

- Exceptions provide a means to break a function's (and program's) normal flow without having to use a cascade of `return`-statements, and without the need to terminate the program using blunt tools like the function `exit`.
- Exceptions do not disrupt the proper activation of destructors. Since `setjmp` and `longjmp` *do* disrupt the proper activation of destructors their use is strongly deprecated in **C++**.

9.3 Throwing exceptions

Exceptions are generated by `throw` statements. The `throw` keyword is followed by an expression, defining the thrown exception value. Example:

```
throw "Hello world";           // throws a char *
throw 18;                      // throws an int
throw string("hello");         // throws a string
```

Local objects cease to exist when a function terminates. This is no different for exceptions.

Objects defined locally in functions are automatically destroyed once exceptions thrown by these functions leave these functions. This also happens to objects thrown as exceptions. However, just before leaving the function context the object is copied and it is this copy that eventually reaches the appropriate `catch` clause.

The following examples illustrates this process. `Object::fun` defines a local `Object` `toThrow`, that is thrown as an exception. The exception is caught in `main`. But by then the object originally thrown doesn't exist anymore, and `main` received a copy:

```
#include <iostream>
#include <string>
using namespace std;

class Object
{
    string d_name;

public:
    Object(string name)
    :
        d_name(name)
    {
        cout << "Constructor of " << d_name << "\n";
    }
    Object(Object const &other)
    :
        d_name(other.d_name + " (copy)")
    {
        cout << "Copy constructor for " << d_name << "\n";
    }
}
```

```

    ~Object()
    {
        cout << "Destructor of " << d_name << "\n";
    }
    void fun()
    {
        Object toThrow("local object");
        cout << "Calling fun of " << d_name << "\n";
        throw toThrow;
    }
    void hello()
    {
        cout << "Hello by " << d_name << "\n";
    }
};

int main()
{
    Object out("main object");
    try
    {
        out.fun();
    }
    catch (Object o)
    {
        cout << "Caught exception\n";
        o.hello();
    }
}

```

Object's copy constructor is special in that it defines its name as the other object's name to which the string " (copy)" is appended. This allow us to monitor the construction and destruction of objects more closely. `Object::fun` generates an exception, and throws its locally defined object. Just before throwing the exception the program has produced the following output:

```

Constructor of 'main object'
Constructor of 'local object'
Calling fun of 'main object'

```

When the exception is generated the next line of output is produced:

```

Copy constructor for 'local object' (copy)

```

The local object is passed to `throw` where it is treated as a value argument, creating a copy of `toThrow`. This copy is thrown as the exception, and the local `toThrow` object ceases to exist. The thrown exception is now caught by the `catch` clause, defining an `Object` value parameter. Since this is a *value* parameter yet another copy is created. Thus, the program writes the following text:

```

Destructor of 'local object'
Copy constructor for 'local object' (copy) (copy)

```

The `catch` block now displays:

```

Caught exception

```

Following this `o's hello` member is called, showing us that we indeed received a *copy of the copy* of the original `toThrow` object:

```
Hello by 'local object' (copy) (copy)
```

Then the program terminates and its remaining objects are now destroyed, reversing their order of creation:

```
Destructor of 'local object' (copy) (copy)
Destructor of 'local object' (copy)
Destructor of 'main object'
```

The copy created by the catch clause clearly is superficial. It can be avoided by defining object *reference parameters* in catch clauses: `'catch (Object &o)'`. The program now produces the following output:

```
Constructor of 'main object'
Constructor of 'local object'
Calling fun of 'main object'
Copy constructor for 'local object' (copy)
Destructor of 'local object'
Caught exception
Hello by 'local object' (copy)
Destructor of 'local object' (copy)
Destructor of 'main object'
```

Only a single copy of `toThrow` was created.

It's a bad idea to throw a *pointer* to a locally defined object. The pointer is thrown, but the object to which the pointer refers ceases to exist once the exception is thrown. The catcher receives a wild pointer. Bad news....

Let's summarize the above findings:

- Local objects are thrown as copied objects;
- Don't throw pointers to local objects;
- It is possible to throw pointers to *dynamically* generated objects. In this case one must take care that the generated object is properly deleted by the exception handler to prevent a memory leak.

Exceptions are thrown in situations where a function can't complete its assigned task, but the program is still able to continue. Imagine a program offering an interactive calculator. The program expects numeric expressions, which are evaluated. Expressions may show syntactic errors or it may be mathematically impossible to evaluate them. Maybe the calculator allows us to define and use variables and the user might refer to non-existing variables: plenty of reasons for the expression evaluation to fail, and so many reasons for exceptions to be thrown. None of those should terminate the program. Instead, the program's user is informed about the nature of the problem and is invited to enter another expression. Example:

```
if (!parse(expressionBuffer))           // parsing failed
    throw "Syntax error in expression";

if (!lookup(variableName))              // variable not found
    throw "Variable not defined";

if (divisionByZero())                   // unable to do division
    throw "Division by zero is not defined";
```

Where these throw statements are located is irrelevant: they may be found deeply nested inside the program, or at a more superficial level. Furthermore, *functions* may be used to generate the exception

to be thrown. An `Exception` object might support stream-like insertion operations allowing us to do, e.g.,

```
if (!lookup(variableName))
    throw Exception() << "Undefined variable '" << variableName << "'";
```

9.3.1 The empty ‘throw’ statement

Sometimes it is required to inspect a thrown exception. An exception catcher may decide to ignore the exception, to process the exception, to rethrow it after inspection or to change it into another kind of exception. For example, in a server-client application the client may submit requests to the server by entering them into a queue. Normally every request is eventually answered by the server. The server may reply that the request was successfully processed, or that some sort of error has occurred. On the other hand, the server may have died, and the client should be able to discover this calamity, by not waiting indefinitely for the server to reply.

In this situation an intermediate exception handler is called for. A thrown exception is first inspected at the middle level. If possible it is processed there. If it is not possible to process the exception at the middle level, it is passed on, unaltered, to a more superficial level, where the really tough exceptions are handled.

By placing an *empty* `throw` statement in the exception handler’s code the received exception is passed on to the next level that might be able to process that particular type of exception. The *retrown* exception is never handled by one of its neighboring exception handlers; it is always transferred to an exception handler at a more superficial level.

In our server-client situation a function

```
initialExceptionHandler(string &exception)
```

could be designed to handle the `string` exception. The received message is inspected. If it’s a simple message it’s processed, otherwise the exception is passed on to an outer level. In `initialExceptionHandler`’s implementation the empty `throw` statement is used:

```
void initialExceptionHandler(string &exception)
{
    if (!plainMessage(exception))
        throw;

    handleMessage(exception);
}
```

Below (section 9.5), the empty `throw` statement is used to pass on the exception received by a `catch`-block. Therefore, a function like `initialExceptionHandler` can be used for a variety of thrown exceptions, as long as their types match `initialExceptionHandler`’s parameter, which is a `string`.

The next example jumps slightly ahead, using some of the topics covered in chapter 14. The example may be skipped, though, without loss of continuity.

A basic exception handling class can be constructed from which specific exception types are derived. Suppose we have a class `Exception`, having a member function `ExceptionType Exception::severity`. This member function tells us (little wonder!) the severity of a thrown exception. It might be `Info`, `Notice`, `Warning`, `Error` or `Fatal`. The information contained in the exception depends on its severity and is processed by a function `handle`. In addition, all exceptions support a member function like `textMsg`, returning textual information about the exception in a `string`.

By defining a polymorphic function `handle` it can be made to behave differently, depending on the nature of a thrown exception, when called from a basic `Exception` pointer or reference.

In this case, a program may throw any of these five exception types. Let's assume that classes `Message` and `Warning` were derived from the class `Exception`, then the `handle` function matching the exception type will automatically be called by the following exception catcher:

```
catch(Exception &ex)
{
    cout << e.textMsg() << '\n';

    if
    (
        ex.severity() != ExceptionWarning
        &&
        ex.severity() != ExceptionMessage
    )
        throw;                // Pass on other types of Exceptions

    ex.handle();               // Process a message or a warning
}
```

Now anywhere in the `try` block preceding the exception handler `Exception` objects or objects of one of its derived classes may be thrown, that will all be caught by the above handler. E.g.,

```
throw Info();
throw Warning();
throw Notice();
throw Error();
throw Fatal();
```

9.4 The try block

The `try`-block surrounds `throw` statements. Remember that a program is always surrounded by a global `try` block, so `throw` statements may appear anywhere in your code. More often, though, `throw` statements are used in function bodies and such functions may be called from within `try` blocks.

A `try` block is defined by the keyword `try` followed by a compound statement. This block, in turn, *must* be followed by at least one `catch` handler:

```
try
{
    // any statements here
}
catch(...) // at least one catch clause here
{}
```

`Try`-blocks are commonly nested, creating exception *levels*. For example, `main`'s code is surrounded by a `try`-block, forming an outer level handling exceptions. Within `main`'s `try`-block functions are called which may also contain `try`-blocks, forming the next exception level. As we have seen (section 9.3.1), exceptions thrown in inner level `try`-blocks may or may not be processed at that level. By placing an empty `throw` statement in an exception handler, the thrown exception is passed on to the next (outer) level.

9.5 Catching exceptions

A `catch` clause consists of the keyword `catch` followed by a parameter list defining one parameter specifying type and (parameter) name of the exception the `catch` handler will catch. This name may

then be used as a variable in the compound statement following the `catch` clause. Example:

```
catch (string &message)
{
    // code to handle the message
}
```

Primitive types and objects may be thrown as exceptions. It's a bad idea to throw a pointer or reference to a local object, but a pointer to a *dynamically* allocated object may be thrown if the exception handler deletes the allocated memory to prevent a memory leak. Nevertheless, throwing such a pointer is dangerous as the exception handler won't be able to distinguish dynamically allocated memory from non-dynamically allocated memory, as illustrated by the next example:

```
try
{
    static int x;
    int *xp = &x;

    if (condition1)
        throw xp;

    xp = new int(0);
    if (condition2)
        throw xp;
}
catch (int *ptr)
{
    // delete ptr or not?
}
```

Close attention should be paid to the nature of the parameter of the exception handler, to make sure that when pointers to dynamically allocated memory are thrown the memory is returned once the handler has processed the pointer. In general pointers should not be thrown as exceptions. If dynamically allocated memory must be passed to an exception handler then the pointer should be wrapped in a smart pointer, like `unique_ptr` or `shared_ptr` (cf. sections 18.3 and 18.4).

Multiple `catch` handlers may follow a `try` block, each handler defining its own exception type. The *order* of the exception handlers is important. When an exception is thrown, the first exception handler matching the type of the thrown exception is used and remaining exception handlers are ignored. Eventually at most one exception handler following a `try`-block will be used. Normally this is of no concern as each exception has its own unique type.

Example: if exception handlers are defined for `char *`s and `void *`s then ASCII-Z strings will be caught by the former handler. Note that a `char *` can also be considered a `void *`, but the exception type matching procedure is smart enough to use the `char *` handler with the thrown ASCII-Z string. Handlers should be designed very type specific to catch the correspondingly typed exception. For example, `int`-exceptions are not caught by `double`-catchers, `char`-exceptions are not caught by `int`-catchers. Here is a little example illustrating that the order of the catchers is not important for types not having any hierarchical relationship to each other (i.e., `int` is not derived from `double`; `string` is not derived from ASCII-Z):

```
#include <iostream>
using namespace std;

int main()
{
    while (true)
    {
```

```

try
{
    string s;
    cout << "Enter a,c,i,s for ascii-z, char, int, string "
           "exception\n";

    getline(cin, s);
    switch (s[0])
    {
        case 'a':
            throw "ascii-z";
        case 'c':
            throw 'c';
        case 'i':
            throw 12;
        case 's':
            throw string();
    }
}
catch (string const &)
{
    cout << "string caught\n";
}
catch (char const *)
{
    cout << "ASCII-Z string caught\n";
}
catch (double)
{
    cout << "isn't caught at all\n";
}
catch (int)
{
    cout << "int caught\n";
}
catch (char)
{
    cout << "char caught\n";
}
}
}

```

Rather than defining specific exception handlers a specific class can be designed whose objects contain information about the exception. Such an approach was mentioned earlier, in section [9.3.1](#). Using this approach, there's only one handler required, since we *know* we don't throw other types of exceptions:

```

try
{
    // code throws only Exception pointers
}
catch (Exception &ex)
{
    ex.handle();
}

```

When the code of an exception handler has been processed, execution continues beyond the last exception handler directly following the matching `try`-block (assuming the handler doesn't itself use flow control statements (like `return` or `throw`) to break the default flow of execution). The following cases can be distinguished:

- If *no* exception was thrown within the `try`-block no exception handler is activated, and execution continues from the last statement in the `try`-block to the first statement beyond the last `catch`-block.
- If an exception *was* thrown within the `try`-block but neither the current level nor another level contains an appropriate exception handler, the program's default exception handler is called, aborting the program.
- If an exception was thrown from the `try`-block and an appropriate exception handler is available, then the code of that exception handler is executed. Following that, the program's execution continues at the first statement beyond the last `catch`-block.

All statements in a `try` block following an executed `throw`-statement are ignored. However, objects that were successfully constructed within the `try` block before executing the `throw` statement *are* destroyed before any exception handler's code is executed.

9.5.1 The default catcher

At a certain level of the program only a limited set of handlers may actually be required. Exceptions whose types belong to that limited set are processed, all other exceptions are passed on to exception handlers of an outer level `try` block.

An intermediate type of exception handling may be implemented using the default exception handler, which must be (due to the hierarchal nature of exception catchers, discussed in section 9.5) placed beyond all other, more specific exception handlers.

This default exception handler cannot determine the actual type of the thrown exception and cannot determine the exception's value but it could do some default processing. The exception is not lost, however, and the default exception handler may still use the empty `throw` statement (see section 9.3.1) to pass the exception on to an outer level. Here is an example showing this use of a default exception handler:

```
#include <iostream>
using namespace std;

int main()
{
    try
    {
        try
        {
            throw 12.25;    // no specific handler for doubles
        }
        catch (int value)
        {
            cout << "Inner level: caught int\n";
        }
        catch (...)
        {
            cout << "Inner level: generic handling of exceptions\n";
            throw;
        }
    }
    catch(double d)
    {
        cout << "Outer level may use the thrown double: " << d << '\n';
    }
}
```

```

/*
    Generated output:
    Inner level: generic handling of exceptions
    Outer level may use the thrown double: 12.25
*/

```

The program's output illustrates that an empty `throw` statement in a default exception handler throws the received exception to the next (outer) level of exception catchers, keeping type and value of the thrown exception. Thus basic or generic exception handling can be accomplished at an inner level and specific handling, based on the type of the thrown expression, can then be provided at an outer level.

9.6 Declaring exception throwers

Functions defined elsewhere may be linked to code that uses these functions. Such functions are normally declared in header files, either as stand alone functions or as class member functions.

Those functions may of course throw exceptions. Declarations of such functions may contain a *function throw list* or *exception specification list* specifying the types of the exceptions that can be thrown by the function. For example, a function that may throw `'char *'` and `'int'` exceptions can be declared as

```
void exceptionThrower() throw(char *, int);
```

A function throw list immediately follows the function header (and it also follows a possible `const` specifier). Throw lists may be empty. It has the following general form:

```
throw([type1 [, type2, type3, ...]])
```

If a function is guaranteed not to throw exceptions an empty function throw list may be used. E.g.,

```
void noExceptions() throw ();
```

In all cases, the function header used in the function definition must exactly match the function header used in the declaration, including a possibly empty function throw list.

A function for which a function throw list is specified may only throw exceptions of the types mentioned in its throw list. A *run-time error* occurs if it throws other types of exceptions than those mentioned in the function throw list. Example: the function `charPintThrower` shown below clearly throws a `char const *` exception. Since `intThrower` may throw an `int` exception, the function throw list of `charPintThrower` must *also* contain `int`.

```

#include <iostream>
using namespace std;

void charPintThrower() throw(char const *, int);

class Thrower
{
public:
    void intThrower(int) const throw(int);
};

void Thrower::intThrower(int x) const throw(int)
{
    if (x)
        throw x;
}

```

```

}

void charPintThrower() throw(char const *, int)
{
    int x;

    cerr << "Enter an int: ";
    cin >> x;

    Thrower().intThrower(x);
    throw "this text is thrown if 0 was entered";
}

void runTimeError() throw(int)
{
    throw 12.5;
}

int main()
{
    try
    {
        charPintThrower();
    }
    catch (char const *message)
    {
        cerr << "Text exception: " << message << '\n';
    }
    catch (int value)
    {
        cerr << "Int exception: " << value << '\n';
    }
    try
    {
        cerr << "Generating a run-time error\n";
        runTimeError();
    }
    catch(...)
    {
        cerr << "not reached\n";
    }
}

```

A function without a throw list may throw any kind of exception. Without a function throw list the program's designer is responsible for providing the correct handlers.

For various reason declaring exception throwers is a questionable activity. Declaring exception throwers does not mean that the compiler will check whether an improper exception is thrown. Rather, the function will be surrounded by additional code in which the actual exception that is thrown is processed. Instead of compile time checks one gets run-time overhead, resulting in additional code (and execution time) that is added to the function's code. One could write, e.g.,

```

void fun() throw (int)
{
    // code of this function, throwing exceptions
}

```

but the function would be compiled to something like the following (cf. section 9.10 for the use of `try` immediately following the function's header and section 9.8 for a description of `bad_exception`):

```

void fun()
try          // this code resulting from throw(int)
{
    // the function's code, throwing all kinds of exceptions
}
catch (int) // remaining code resulting from throw(int)
{
    throw; // rethrow the exception, so it can be caught by the
           // 'intended' handler
}
catch (...) // catch any other exception
{
    throw bad_exception;
}

```

Run-time overhead is caused by doubling the number of thrown and caught exceptions. Without a throw list a thrown `int` is simply caught by its intended handler; with a throw list the `int` is *first* caught by the 'safeguarding' handler added to the function. In there it is *rethrown* to be caught by its intended handler next.

9.7 Iostreams and exceptions

The C++ I/O library was used well before exceptions were available in C++. Hence, normally the classes of the `iostream` library do not throw exceptions. However, it is possible to modify that behavior using the `ios::exceptions` member function. This function has two overloaded versions:

- `ios::exceptions()`:
this member returns the state flags for which the stream will throw exceptions;
- `void exceptions(ios::state state)`
this member causes the stream to throw an exception when state `state` is observed.

In the I/O library, exceptions are objects of the class `ios::failure`, derived from `ios::exception`. A `std::string const &message` may be specified when defining a failure object. Its message may then be retrieved using its virtual `char const *what() const` member.

Exceptions should be used in exceptional circumstances. Therefore, we think it is questionable to have stream objects throw exceptions for fairly normal situations like EOF. Using exceptions to handle input errors might be defensible (e.g., in situations where input errors should not occur and imply a corrupted file) but often aborting the program with an appropriate error message would probably be the more appropriate action. As an example consider the following interactive program using exceptions to catch incorrect input:

```

#include <iostream>
#include <climits>
using namespace::std;

int main()
{
    cin.exceptions(ios::failbit); // throw exception on fail
    while (true)
    {
        try
        {
            cout << "enter a number: ";

```

```

        int value;
        cin >> value;
        cout << "you entered " << value << '\n';
    }
    catch (ios::failure const &problem)
    {
        cout << problem.what() << '\n';
        cin.clear();
        cin.ignore(INT_MAX, '\n'); // ignore the faulty line
    }
}
}

```

9.8 Standard Exceptions

All data types may be thrown as exceptions. Several additional exception classes are now defined by the C++ standard. Before using those additional exception classes the `<stdexcept>` header file must have been included. All of these *standard exceptions* are class types by themselves, but also offer all facilities of the `std::exception` class and objects of the standard exception classes may also be considered objects of the `std::exception` class.

The `std::exception` class offers the member

```
char const *what() const;
```

describing in a short textual message the nature of the exception.

C++ defines the following standard exception classes:

- `std::bad_alloc`: thrown when operator `new` fails;
- `std::bad_exception`: thrown when a function tries to generate another type of exception than declared in its function throw list;
- `std::bad_cast`: thrown in the context of *polymorphism* (see section [14.5.1](#));
- `std::bad_typeid`: also thrown in the context of *polymorphism* (see section [14.5.2](#));

All additional exception classes were derived from `std::exception`. The constructors of all these additional classes accept `std::string const &` arguments summarizing the reason for the exception (retrieved by the `exception::what` member). The additionally defined exception classes are:

- `std::domain_error`: a (mathematical) domain error is detected;
- `std::invalid_argument`: the argument of a function has an invalid value;
- `std::length_error`: thrown when an object would have exceeded its maximum permitted length;
- `std::logic_error`: a logic error should be thrown when a problem is detected in the internal logic of the program. Example: a function like C's `printf` is called with more arguments than there are format specifiers in its format string;
- `std::out_of_range`: thrown when an argument exceeds its permitted range. Example: thrown by `at` members when their arguments exceed the range of admissible index values;
- `std::overflow_error`: an overflow error should be thrown when an arithmetic overflow is detected. Example: dividing a value by a very small value;

- `std::range_error`: a range error should be thrown when an internal computation results in a value exceeding a permissible range;
- `std::runtime_error`: a runtime error should be thrown when a problem is encountered that can only be detected while the program is being executed. Example: a non-integral is entered when the program's input expects an integral value.
- `std::underflow_error`: an underflow error should be thrown when an arithmetic underflow is detected. Example: dividing a very small value by a very large value.

9.9 Exception guarantees

Software should be *exception safe*: the program should continue to work according to its specifications in the face of exceptions. It is not always easy to realize exception safety. In this section some guidelines and terminology is introduced when discussing exception safety.

Since exceptions may be generated from within all C++ functions, exceptions may be generated in many situations. Not all of these situations will be immediately and intuitively recognized as situations where exceptions can be thrown. Consider the following function and ask yourself at which points exceptions may be thrown:

```
void fun()
{
    X x;
    cout << x;
    X *xp = new X(x);
    cout << (x + *xp);
    delete xp;
}
```

If it can be assumed that `cout` as used above does not throw an exception there are at least 13 opportunities for exceptions to be thrown:

- `X x`: the default constructor could throw an exception (#1)
- `cout << x`: the overloaded insertion operator could throw an exception (#2), but its rvalue argument might not be an `X` but, e.g., an `int`, and so `X::operator int() const` could be called which offers yet another opportunity for an exception (#3).
- `*xp = new X(x)`: the copy constructor may throw an exception (#4) and operator `new` (#5a) too. But did you realize that this latter exception might not be thrown from `::new`, but from, e.g., `X`'s own overload of operator `new`? (#5b)
- `cout << (x + *xp)`: we might be seduced into thinking that two `X` objects are added. But it doesn't have to be that way. A separate class `Y` might exist and `X` may have a conversion operator `operator Y() const`, and `operator+(Y const &lhs, X const &rhs)`, `operator+(X const &lhs, Y const &rhs)`, and `operator+(X const &lhs, X const &rhs)` might all exist. So, if the conversion operator exists, then depending on the kind of overload of `operator+` that is defined either the addition's left-hand side operand (#6), right-hand side operand (#7), or `operator+` itself (#8) may throw an exception. The resulting value may again be of any type and so the overloaded `cout << return-type-of-operator+` operator may throw an exception (#9). Since `operator+` returns a temporary object it is destroyed shortly after its use. `X`'s destructor *could* throw an exception (#10).
- `delete xp`: whenever operator `new` is overloaded operator `delete` should be overloaded as well and may throw an exception (#11). And of course, `X`'s destructor might again throw an exception (#12).

- `}`: when the function terminates the local `x` object is destroyed: again an exception could be thrown (#13).

It is stressed here (and further discussed in section 9.11) that although it is possible for exceptions to leave destructors this would violate the C++ standard and so it must be prevented in well-behaving C++ programs.

How can we expect to create working programs when exceptions might be thrown at this many situations?

Exceptions may be generated in a great many situations, but serious problems will be prevented when we're able to provide at least one of the following exception guarantees:

- The *basic guarantee*: no resources are leaked. In practice this means: all allocated memory is properly returned when exceptions are thrown.
- The *strong guarantee*: the program's state remains unaltered when an exception is thrown (as an example: the canonical form of the overloaded assignment operator provides this guarantee)
- The *nothrow guarantee*: this applies to code for which it can be proven that no exception will be thrown from it.

9.9.1 The basic guarantee

The *basic guarantee* dictates that functions that fail to complete their assigned tasks must return all allocated resources, usually memory, before terminating. Since practically all functions and operators may throw exceptions and since a function may repeatedly allocate resources the blueprint of a function allocating resources shown below defines a try block to catch all exceptions that might be thrown. The catch handler's task is to return all allocated resources and then rethrow the exception.

```
void allocator(X **xDest, Y **yDest)
{
    X *xp = 0;           // non-throwing preamble
    Y *yp = 0;

    try                  // this part might throw
    {
        xp = new X[nX];  // alternatively: allocate one object
        yp = new Y[nY];
    }
    catch(...)
    {
        delete xp;
        throw;
    }

    delete[] *xDest;     // non-throwing postamble
    *xDest = xp;
    delete[] *yDest;
    *yDest = yp;
}
```

In the pre-try code the pointers to receive the addresses returned by the operator new calls are initialized to 0. Since the catch handler must be able to return allocated memory they must be available outside of the try block. If the allocation succeeds the memory pointed to by the destination pointers is returned and then the pointers are given new values.

Allocation and or initialization might fail. If allocation fails new throws a `std::bad_alloc` exception and the catch handler simply deletes 0 pointers which is OK.

If allocation succeeds but the construction of (some) of the objects fails by throwing an exception then the following is *guaranteed* to happen:

- The destructors of all successfully allocated objects are called;
- The dynamically allocated memory to contain the objects is returned

Consequently, no memory will leak when `new` fails. Inside the above `try` block `new X` may fail: this will keep the 0-pointers intact and so the catch handler merely deletes 0 pointers. When `new Y` fails `xp` will point to allocated memory and so it must be returned. This happens inside the catch handler. The final pointer (here: `yp`) will only be unequal zero when `new Y` properly completes, so there's no need for the catch handler to return the memory pointed at by `yp`.

9.9.2 The strong guarantee

The *strong guarantee* dictates that an object's state should not change in the face of exceptions. This is realized by performing all operations that might throw on a separate copy of the data. If all this succeeds then the current object and its (now successfully modified) copy are swapped. An example of this approach can be observed in the canonical overloaded assignment operator:

```
Class &operator=(Class const &other)
{
    Class tmp(other);
    swap(tmp);
    return *this;
}
```

The copy construction might throw an exception, but this keeps the current object's state intact. If the copy construction succeeds `swap` swaps the current object's contents with `tmp`'s contents and returns a reference to the current object. For this to succeed it must be guaranteed that `swap` won't throw an exception. Returning a reference (or a value of a primitive data type) is also guaranteed not to throw exceptions. The canonical form of the overloaded assignment operator therefore meets the requirements of the strong guarantee.

Some rules of thumb were formulated that relate to the strong guarantee (cf. Sutter, H., *Exceptional C++*, Addison-Wesley, 2000). E.g.,

- All the code that might throw an exception affecting the current state of an object should perform its tasks separately from the data controlled by the object. Once this code has performed its tasks without throwing an exception replace the object's data by the new data.
- Member functions modifying their object's data should not return original (contained) objects by value.

The canonical assignment operator is a good example of the first rule of thumb. Another example is found in classes storing objects. Consider a class `PersonDb` storing multiple `Person` objects. Such a class might offer a member `void add(Person const &next)`. A plain implementation of this function (merely intended to show the application of the first rule of thumb, but otherwise completely disregarding efficiency considerations) might be:

```
void PersonDb::newAppend(Person const &next)
{
    Person *tmp = 0;
    try
    {
        tmp = new Person[d_size + 1];
    }
```

```

        for (size_t idx = 0; idx < d_size; ++idx)
            tmp[idx] = d_data[idx];
        tmp[d_size] = next;
    }
    catch (...)
    {
        delete[] tmp;
        throw;
    }
    return tmp;
}

void PersonDb::add(Person const &next)
{
    Person *tmp = newAppend(next);
    delete[] d_data;
    d_data = tmp;
    ++d_size;
}

```

The (private) `newAppend` member's task is to create a copy of the currently allocated `Person` objects, including the data of the next `Person` object. Its `catch` handler catches any exception that might be thrown during the allocation or copy process and will return all memory allocated so far, rethrowing the exception. The function is *exception neutral* as it propagates all its exceptions to its caller. The function also doesn't modify the `PersonDb` object's data, so it meets the strong exception guarantee. Returning from `newAppend` the member `add` may now modify its data. Its existing data are returned and its `d_data` pointer is made to point to the newly created array of `Person` objects. Finally its `d_size` is incremented. As these three steps don't throw exceptions `add` too meets the strong guarantee.

The second rule of thumb (member functions modifying their object's data should not return original (contained) objects by value) may be illustrated using a member `PersonDb::erase(size_t idx)`. Here is an implementation attempting to return the original `d_data[idx]` object:

```

Person PersonData::erase(size_t idx)
{
    if (idx >= d_size)
        throw string("Array bounds exceeded");
    Person ret(d_data[idx]);
    Person *tmp = copyAllBut(idx);
    delete[] d_data;
    d_data = tmp;
    --d_size;
    return ret;
}

```

Although copy elision will usually prevent the copy constructor from being used when returning `ret`, this is not guaranteed to happen and a copy constructor *may* throw an exception. If that happens the function has irrevocably mutated the `PersonDb`'s data, thus losing the strong guarantee.

Rather than returning `d_data[idx]` by value it might be assigned to an external `Person` object before mutating `PersonDb`'s data:

```

void PersonData::erase(Person *dest, size_t idx)
{
    if (idx >= d_size)
        throw string("Array bounds exceeded");
    *dest = d_data[idx];
    Person *tmp = copyAllBut(idx);
    delete[] d_data;
}

```

```

    d_data = tmp;
    --d_size;
}

```

This modification works, but changes the original assignment of creating a member returning the original object. However, both functions suffer from a task overload as they modify `PersonDb`'s data and also return an original object. In situations like these the *one-function-one-responsibility* rule of thumb should be kept in mind: a function should have a single, well defined responsibility.

The preferred approach is to retrieve `PersonDb`'s objects using a member like `Person const &at(size_t idx) const` and to erase an object using a member like `void PersonData::erase(size_t idx)`.

9.9.3 The nothrow guarantee

Exception safety can only be realized if some functions and operations are guaranteed *not* to throw exceptions. This is called the *nothrow guarantee*. An example of a function that must offer the nothrow guarantee is the swap function. Consider once again the canonical overloaded assignment operator:

```

Class &operator=(Class const &other)
{
    Class tmp(other);
    swap(tmp);
    return *this;
}

```

If swap were allowed to throw exceptions then it would most likely leave the current object in a partially swapped state. As a result the current object's state would most likely have been changed. As `tmp` will have been destroyed by the time a catch handler receives the thrown exception it will be very difficult (as in: impossible) to retrieve the object's original state. Losing the strong guarantee as a consequence.

The swap function must therefore offer the nothrow guarantee. It must have been designed as if using the following prototype (don't do this: see also section 9.6):

```
void Class::swap(Class &other) throw();
```

Likewise, `operator delete` and `operator delete[]` offer the nothrow guarantee, and according to the C++ standard destructors may themselves not throw exceptions (if they do their behavior is formally undefined, see also section 9.11 below).

Since the C programming language does not define the exception concept functions from the standard C library offer the nothrow guarantee by implication. This allowed us to define the generic swap function in section 8.5.1 using `memcpy`.

Operations on primitive types offer the nothrow guarantee. Pointers may be reassigned, references may be returned etc. etc. without having to worry about exceptions that might be thrown.

9.10 Function try blocks

Exceptions may be generated while a constructor is initializing its members. How can exceptions generated in such situations be caught by the constructor itself, rather than outside the constructor? The intuitive solution, nesting the object construction in a try block does not solve the problem. The exception by then has left the constructor and the object we intended to construct isn't visible anymore.

Using a nested try block is illustrated in the next example, where `main` defines an object of class `PersonDb`. Assuming that `PersonDb`'s constructor throws an exception, there is no way we can access

the resources that might have been allocated by `PersonDb`'s constructor from the catch handler as the `pdb` object is out of scope:

```
int main(int argc, char **argv)
{
    try
    {
        PersonDb pdb(argc, argv);    // may throw exceptions
        ...                          // main()'s other code
    }
    catch(...)                       // and/or other handlers
    {
        ...                          // pdb is inaccessible from here
    }
}
```

Although all objects and variables defined inside a `try` block are inaccessible from its associated catch handlers, object data members were available before starting the `try` block and so they may be accessed from a catch handler. In the following example the catch handler in `PersonDb`'s constructor is able to access its `d_data` member:

```
PersonDb::PersonDb(int argc, char **argv)
:
    d_data(0),
    d_size(0)
{
    try
    {
        initialize(argc, argv);
    }
    catch(...)
    {
        // d_data, d_size: accessible
    }
}
```

Unfortunately, this does not help us much. The `initialize` member will not be able to reassign `d_data` and `d_size` if `PersonDb const pdb` was defined; the `initialize` member should at least offer the basic exception guarantee and return any resources it has acquired before terminating due to a thrown exception; and although `d_data` and `d_size` offer the `nothrow` guarantee as they are of primitive data types a class type data member might throw an exception, possibly resulting in violation of the basic guarantee.

In the next implementation of `PersonDb` assume that constructor receives a pointer to an already allocated block of `Person` objects. It will own the data and is responsible for its eventual destruction. Moreover, `d_data` and `d_size` are also used by a composed object `PersonDbSupport`, having a constructor expecting a `Person const *` and `size_t` argument. Our next implementation may then look something like this:

```
PersonDb::PersonDb(Person *pData, size_t size)
:
    d_data(pData),
    d_size(size),
    d_support(d_data, d_size)
{
    // no further actions
}
```

This setup allows us to define a `PersonDb` `const &pdb`. Unfortunately, `PersonDb` cannot offer the basic guarantee. If `PersonDbSupport`'s constructor throws an exception it isn't caught although `d_data` already points to allocated memory.

The *function try block* offers a solution for this problem. A function try block consists of a `try` block and its associated handlers. The function try block starts *immediately* after the function header, and its block defines the function body. With constructors base class and data member initializers may be placed between the `try` keyword and the opening curly brace. Here is our final implementation of `PersonDb`, now offering the basic guarantee:

```
PersonDb::PersonDb(Person *pData, size_t size)
try
:
    d_data(pData),
    d_size(size),
    d_support(d_data, d_size)
{}
catch (...)
{
    delete[] d_data;
}
```

Let's have a look at a stripped-down example. A constructor defines a function try block. The exception thrown by the `Throw` object is initially caught by the object itself. Then it is rethrown. The surrounding `Composer`'s constructor also defines a function try block, `Throw`'s rethrown exception is properly caught by `Composer`'s exception handler, even though the exception was generated from within its member initializer list:

```
#include <iostream>

class Throw
{
public:
    Throw(int value)
    try
    {
        throw value;
    }
    catch(...)
    {
        std::cout << "Throw's exception handled locally by Throw()\n";
        throw;
    }
};

class Composer
{
    Throw d_t;
public:
    Composer()
    try // NOTE: try precedes initializer list
    :
        d_t(5)
    {}
    catch(...)
    {
        std::cout << "Composer() caught exception as well\n";
    }
};
```

```
int main()
{
    Composer c;
}
```

When running this example, we're in for a nasty surprise: the program runs and then breaks with an *abort exception*. Here is the output it produces, the last two lines being added by the system's final catch-all handler, catching all remaining uncaught exceptions:

```
Throw's exception handled locally by Throw()
Composer() caught exception as well
terminate called after throwing an instance of 'int'
Abort
```

The reason for this is documented in the **C++** standard: at the end of a catch-handler belonging to a constructor or destructor function try block, the original exception is automatically rethrown.

The exception is not rethrown if the handler itself throws another exception, offering the constructor or destructor a way to replace a thrown exception by another one. The exception is only rethrown if it reaches the end of the catch handler of a constructor or destructor function try block. Exceptions caught by nested catch handlers are not automatically rethrown.

As only constructors and destructors rethrow exceptions caught by their function try block catch handlers the run-time error encountered in the above example may simply be repaired by providing `main` with its own function try block:

```
int main()
try
{
    Composer c;
}
catch (...)
{}
```

Now the program runs as planned, producing the following output:

```
Throw's exception handled locally by Throw()
Composer() caught exception as well
```

A final note: if a function defining a function try block also declares an exception throw list then only the types of rethrown exceptions must match the types mentioned in the throw list.

9.11 Exceptions in constructors and destructors

Only completely constructed objects are automatically destroyed by the **C++** run-time system. Although this may sound like a truism, there is a subtlety here. If the construction of an object fails for some reason, the object's destructor will not be called once the object goes out of scope. This could happen if an exception generated by the constructor is not caught by the constructor. If the exception is thrown *after* the object has allocated some memory, then that memory will not be returned by the object's destructor as the destructor isn't called because the object hasn't completely been constructed.

The following example illustrates this situation in its prototypical form. The constructor of the class `Incomplete` first displays a message and then throws an exception. Its destructor also displays a message:

```
class Incomplete
```



```

{
    public:
        Incomplete()
        {
            cerr << "Allocated some memory\n";
            throw 0;
        }
        ~Incomplete()
        {
            cerr << "Destroying the allocated memory\n";
        }
};

```

Next, `main()` creates an `Incomplete` object inside a `try` block. Any exception that may be generated is subsequently caught:

```

int main()
{
    try
    {
        cerr << "Creating 'Incomplete' object\n";
        Incomplete();
        cerr << "Object constructed\n";
    }
    catch(...)
    {
        cerr << "Caught exception\n";
    }
}

```

When this program is run, it produces the following output:

```

Creating 'Incomplete' object
Allocated some memory
Caught exception

```

Thus, if `Incomplete`'s constructor would actually have allocated some memory, the program would suffer from a memory leak. To prevent this from happening, the following counter measures are available:

- Prevent the exceptions from leaving the constructor.
If part of the constructor's body may generate exceptions, then this part may be surrounded by a `try` block, allowing the exception to be caught by the constructor itself. This approach is defensible when the constructor is able to repair the cause of the exception and to complete its construction as a valid object.
- If an exception is generated by a base class constructor or by a member initializing constructor then a `try` block within the constructor's body won't be able to catch the thrown exception. This *always* results in the exception leaving the constructor and the object is not considered to have been properly constructed. A `try` block may include the member initializers, and the `try` block's compound statement becomes the constructor's body as in the following example:

```

class Incomplete2
{
    Composed d_composed;
    public:
        Incomplete2()
        try

```

```

        :
          d_composed(/* arguments */)
        {
            // body
        }
        catch (...)
        {}
    };

```

An exception thrown by either the member initializers or the body will result in the execution never reaching the body's closing curly brace. Instead the catch clause is reached. Since the constructor's body isn't properly completed the object is not considered properly constructed and eventually the object's destructor won't be called.

The catch clause of a constructor's function try block behaves slightly different than a catch clause of an ordinary function try block. An exception reaching a constructor's function try block may be transformed into another exception (which is thrown from the catch clause) but if no exception is explicitly thrown from the catch clause the exception originally reaching the catch clause is always rethrown. Consequently, there's no way to confine an exception thrown from a base class constructor or from a member initializer to the constructor: such an exception will *always* propagate to a more shallow block and the object's construction will always be considered incomplete.

Consequently, if incompletely constructed objects throw exceptions then the constructor's catch clause is responsible for preventing memory (generally: resource) leaks. There are several ways to realize this:

- When multiple inheritance is used: if initial base classes have properly been constructed and a later base class throws, then the initial base class objects will automatically be destroyed (as they are themselves fully constructed objects)
- When composition is used: already constructed composed objects will automatically be destroyed (as they are fully constructed objects)
- Instead of using plain pointers *smart pointers* (cf. section 18.4) should be used to manage dynamically allocated memory. In this case, if the constructor throws either before or after the allocation of the dynamic memory allocated memory will properly be returned as `shared_ptr` objects are objects.
- If plain pointer data members *must* be used then the constructor's body should first, in its member initialization section, initialize its plain pointer data members. Then, in its body it can dynamically allocate memory, reassigning the plain pointer data members. The constructor must be provided with a function try block whose generic catch clause deletes the memory pointed at by the class's plain pointer data members. Example:

```

class Incomplete2
{
    Composed d_composed;
    char *d_cp;           // plain pointers
    int *d_ip;

public:
    Incomplete2(size_t nChars, size_t nInts)
    try
    :
        d_composed(/* arguments */),    // might throw
        d_cp(0),
        d_ip(0)
    {
        preamble();                    // might throw
        d_cp = new char[nChars];       // might throw
    }
};

```

```

        d_ip = new int[nChars];           // might throw
        postamble();                     // might throw
    }
    catch (...)
    {
        delete[] d_cp;                   // clean up
        delete[] d_ip;
    }
};

```

According to the **C++** standard exceptions thrown by destructors may not leave their bodies. Consequently a destructor cannot sensibly be provided with a function `try` block as exceptions caught by a function `try` block's catch clause has already left the destructor's body (and will be rethrown as with exceptions reaching a constructor's function `try` block's catch clause).

The consequences of an exception leaving the destructor's body is not defined, and may result in unexpected behavior. Consider the following example:

Assume a carpenter builds a cupboard having a single drawer. The cupboard is finished, and a customer, buying the cupboard, finds that the cupboard can be used as expected. Satisfied with the cupboard, the customer asks the carpenter to build another cupboard, this time having *two* drawers. When the second cupboard is finished, the customer takes it home and is utterly amazed when the second cupboard completely collapses immediately after it is used for the first time.

Weird story? Then consider the following program:

```

int main()
{
    try
    {
        cerr << "Creating Cupboard1\n";
        Cupboard1();
        cerr << "Beyond Cupboard1 object\n";
    }
    catch (...)
    {
        cerr << "Cupboard1 behaves as expected\n";
    }
    try
    {
        cerr << "Creating Cupboard2\n";
        Cupboard2();
        cerr << "Beyond Cupboard2 object\n";
    }
    catch (...)
    {
        cerr << "Cupboard2 behaves as expected\n";
    }
}

```

When this program is run it produces the following output:

```

Creating Cupboard1
Drawer 1 used
Cupboard1 behaves as expected
Creating Cupboard2
Drawer 2 used
Drawer 1 used
terminate called after throwing an instance of 'int'

```

Abort

The final Abort indicates that the program has aborted instead of displaying a message like Cupboard2 behaves as expected.

Let's have a look at the three classes involved. The class Drawer has no particular characteristics, except that its destructor throws an exception:

```
class Drawer
{
    size_t d_nr;
public:
    Drawer(size_t nr)
    :
        d_nr(nr)
    {}
    ~Drawer()
    {
        cerr << "Drawer " << d_nr << " used\n";
        throw 0;
    }
};
```

The class Cupboard1 has no special characteristics at all. It merely has a single composed Drawer object:

```
class Cupboard1
{
    Drawer left;
public:
    Cupboard1()
    :
        left(1)
    {}
};
```

The class Cupboard2 is constructed comparably, but it has two composed Drawer objects:

```
class Cupboard2
{
    Drawer left;
    Drawer right;
public:
    Cupboard2()
    :
        left(1),
        right(2)
    {}
};
```

When Cupboard1's destructor is called Drawer's destructor is eventually called to destroy its composed object. This destructor throws an exception, which is caught beyond the program's first try block. This behavior is completely as expected.

A subtlety here is that Cupboard1's destructor (and hence Drawer's destructor) is activated *immediately* subsequent to its construction. Its destructor is called immediately subsequent to its construction as Cupboard1() defines an anonymous object. As a result the Beyond Cupboard1 object text is never inserted into std::cerr.

Because of `Drawer`'s destructor throwing an exception a problem occurs when `Cupboard2`'s destructor is called. Of its two composed objects, the second `Drawer`'s destructor is called first. This destructor throws an exception, which ought to be caught beyond the program's second `try` block. However, although the flow of control by then has left the context of `Cupboard2`'s destructor, that object hasn't completely been destroyed yet as the destructor of its other (left) `Drawer` still has to be called.

Normally that would not be a big problem: once an exception is thrown from `Cupboard2`'s destructor any remaining actions would simply be ignored, albeit that (as both drawers are properly constructed objects) `left`'s destructor would still have to be called.

This happens here too and `left`'s destructor *also* needs to throw an exception. But as we've already left the context of the second `try` block, the current flow control is now thoroughly mixed up, and the program has no other option but to abort. It does so by calling `terminate()`, which in turn calls `abort()`. Here we have our collapsing cupboard having two drawers, even though the cupboard having one drawer behaves perfectly.

The program aborts since there are multiple composed objects whose destructors throw exceptions leaving the destructors. In this situation one of the composed objects would throw an exception by the time the program's flow control has already left its proper context causing the program to abort.

The **C++** standard therefore understandably stipulates that exceptions may *never* leave destructors. Here is the skeleton of a destructor whose code might throw exceptions. No function `try` block but all the destructor's actions are encapsulated in a `try` block nested under the destructor's body.

```
Class::~~Class()
{
    try
    {
        maybe_throw_exceptions();
    }
    catch (...)
    {}
}
```


Chapter 10

More Operator Overloading

Having covered the overloaded assignment operator in chapter 8, and having shown several examples of other overloaded operators as well (i.e., the insertion and extraction operators in chapters 3 and 6), we will now take a look at operator overloading in general.

10.1 Overloading ‘operator[]()’

As our next example of operator overloading, we introduce a class `IntArray` encapsulating an array of ints. Indexing the array elements is possible using the standard array index operator `[]`, but additionally checks for array bounds overflow will be performed. Furthermore, the index operator (`operator[]`) is interesting in that it can be used in expressions as both lvalue and as rvalue.

Here is an example showing the basic use of the class:

```
int main()
{
    IntArray x(20);                // 20 ints

    for (int i = 0; i < 20; i++)
        x[i] = i * 2;              // assign the elements

    for (int i = 0; i <= 20; i++)    // produces boundary overflow
        cout << "At index " << i << ": value is " << x[i] << '\n';
}
```

First, the constructor is used to create an object containing 20 ints. The elements stored in the object can be assigned or retrieved. The first for-loop assigns values to the elements using the index operator, the second for-loop retrieves the values but also results in a run-time error once the non-existing value `x[20]` is addressed. The `IntArray` class interface is:

```
class IntArray
{
    int      *d_data;
    size_t d_size;

public:
    IntArray(size_t size = 1);
    IntArray(IntArray const &other);
    ~IntArray();
    IntArray const &operator=(IntArray const &other);
}
```

```

// overloaded index operators:
int &operator[](size_t index);           // first
int const &operator[](size_t index) const; // second

void swap(IntArray &other);           // trivial

private:
    void boundary(size_t index) const;
    int &operatorIndex(size_t index) const;
};

```

This class has the following characteristics:

- One of its constructors has a `size_t` parameter having a default argument value, specifying the number of `int` elements in the object.
- The class internally uses a pointer to reach allocated memory. Hence, the necessary tools are provided: a copy constructor, an overloaded assignment operator and a destructor.
- Note that there are two overloaded index operators. Why are there two?

The first overloaded index operator allows us to reach and modify the elements of non-constant `IntArray` objects. This overloaded operator's prototype is a function returning *a reference* to an `int`. This allows us to use expressions like `x[10]` as rvalues or lvalues.

With non-const `IntArray` objects `operator[]` can therefore be used to retrieve and to assign values. The return value of the non-const `operator[]` member is *not* an `int const &`, but an `int &`. In this situation we don't use `const`, as we must be able to modify the element we want to access when the operator is used as lvalue.

This whole scheme fails if there's nothing to assign. Consider the situation where we have an `IntArray const stable(5)`. Such an object is an immutable *const* object. The compiler detects this and refuses to compile this object definition if only the non-const `operator[]` is available. Hence the second overloaded index operator is added to the class's interface. Here the return value is an `int const &`, rather than an `int &`, and the member function itself is a `const` member function. This second form of the overloaded index operator is only used with `const` objects. It is used for value *retrieval* instead of value assignment. That, of course, is precisely what we want when using `const` objects. In this situation members are overloaded only by their `const` attribute. This form of function overloading was introduced earlier in the C++ Annotations (sections 2.5.4 and 7.5).

Since `IntArray` stores values of a primitive type `IntArray's operator[] const` could also have defined a value return type. However, with objects one usually doesn't want the extra copying that's implied with value return types. In those cases `const &` return values are preferred for `const` member functions. So, in the `IntArray` class an `int` return value could have been used as well, resulting in the following prototype:

```
int IntArray::operator[](int index) const;
```

- As there is only one pointer data member, the destruction of the memory allocated by the object is a simple `delete[] data`.

Now, the implementation of the members (omitting the trivial implementation of `swap`, cf. chapter 8) are:

```

#include "intarray.ih"

IntArray::IntArray(size_t size)
:
    d_size(size)

```



```

{
    if (d_size < 1)
        throw string("IntArray: size of array must be >= 1");

    d_data = new int[d_size];
}

IntArray::IntArray(IntArray const &other)
:
    d_size(other.d_size);
    d_data(new int[d_size]);
{
    memcpy(d_data, other.d_data, d_size * sizeof(int));
}

IntArray::~IntArray()
{
    delete[] d_data;
}

IntArray const &IntArray::operator=(IntArray const &other)
{
    IntArray tmp(other);
    swap(tmp);
    return *this;
}

int &IntArray::operatorIndex(size_t index) const
{
    boundary(index);
    return d_data[index];
}

int &IntArray::operator[](size_t index)
{
    return operatorIndex(index);
}

int const &IntArray::operator[](size_t index) const
{
    return operatorIndex(index);
}

void IntArray::boundary(size_t index) const
{
    if (index < d_size)
        return;
    ostream out;
    out << "IntArray: boundary overflow, index = " <<
        index << ", should be < " << d_size << '\n';
    throw out.str();
}

```

Note how the `operator[]` members were implemented: as non-const members may call const member functions and as the implementation of the const member function is identical to the non-const member function's implementation both `operator[]` members could be defined inline using an auxiliary function `int &operatorIndex(size_t index) const`. A const member function may return a non-const reference (or pointer) return value, referring to one of the data members of its object. Of course, this is a potentially dangerous backdoor that may break data hiding. However, the members in

the public interface prevent this breach and so the two public `operator[]` members may themselves safely call the same `int &operatorIndex() const` member, that defines a *private backdoor*.

10.2 Overloading the insertion and extraction operators

Classes may be adapted in such a way that their objects may be inserted into and extracted from, respectively, a `std::ostream` and `std::istream`.

The class `std::ostream` defines insertion operators for primitive types, such as `int`, `char *`, etc.. In this section we will learn how to extend the existing functionality of classes (in particular `std::istream` and `std::ostream`) in such a way that they can be used also in combination with classes developed much later in history.

In this section we will show how the insertion operator can be overloaded allowing the insertion of any type of object, say `Person` (see chapter 8), into an `ostream`. Having defined such an overloaded operator the following will be possible:

```
Person kr("Kernighan and Ritchie", "unknown", "unknown");

cout << "Name, address and phone number of Person kr:\n" << kr << '\n';
```

The statement `cout << kr` uses `operator<<`. This member function has two operands: an `ostream` & and a `Person` &. The required action is defined in an overloaded *free function* `operator<<` expecting two arguments:

```
// declared in 'person.h'
std::ostream &operator<<(std::ostream &out, Person const &person);

// defined in some source file
ostream &operator<<(ostream &out, Person const &person)
{
    return
        out <<
            "Name:      " << person.name() << ", "
            "Address:  " << person.address() << ", "
            "Phone:    " << person.phone();
}
```

The free function `operator<<` has the following noteworthy characteristics:

- The function returns a reference to an `ostream` object, to enable ‘chaining’ of the insertion operator.
- The two operands of `operator<<` are passed to the free function as its arguments. In the example, the parameter `out` was initialized by `cout`, the parameter `person` by `kr`.

In order to overload the *extraction* operator for, e.g., the `Person` class, members are needed modifying the class’s private data members. Such *modifiers* are normally offered by the class interface. For the `Person` class these members could be the following:

```
void setName(char const *name);
void setAddress(char const *address);
void setPhone(char const *phone);
```

These members may easily be implemented: the memory pointed to by the corresponding data member must be deleted, and the data member should point to a copy of the text pointed to by the parameter. E.g.,

```
void Person::setAddress(char const *address)
{
    delete[] d_address;
    d_address = strdupnew(address);
}
```

A more elaborate function should check the reasonableness of the new address (`address` also shouldn't be a 0-pointer). This however, is not further pursued here. Instead, let's have a look at the final operator<>. A simple implementation is:

```
istream &operator>>(istream &in, Person &person)
{
    string name;
    string address;
    string phone;

    if (in >> name >> address >> phone)    // extract three strings
    {
        person.setName(name.c_str());
        person.setAddress(address.c_str());
        person.setPhone(phone.c_str());
    }
    return in;
}
```

Note the stepwise approach that is followed here. First, the required information is extracted using available extraction operators. Then, if that succeeds, *modifiers* are used to modify the data members of the object to be extracted. Finally, the stream object itself is returned as a reference.

10.3 Conversion operators

A class may be constructed around a built-in type. E.g., a class `String`, constructed around the `char *` type. Such a class may define all kinds of operations, like assignments. Take a look at the following class interface, designed after the `string` class:

```
class String
{
    char *d_string;

public:
    String();
    String(char const *arg);
    ~String();
    String(String const &other);
    String const &operator=(String const &rvalue);
    String const &operator=(char const *rvalue);
};
```

Objects of this class can be initialized from a `char const *`, and also from a `String` itself. There is an overloaded assignment operator, allowing the assignment from a `String` object and from a `char const *`¹.

Usually, in classes that are less directly linked to their data than this `String` class, there will be an *accessor member function*, like a member `char const *String::c_str() const`. However, the

¹Note that the assignment from a `char const *` also allows the null-pointer. An assignment like `stringObject = 0` is perfectly in order.

need to use this latter member doesn't appeal to our intuition when an array of `String` objects is defined by, e.g., a class `StringArray`. If this latter class provides the `operator[]` to access individual `String` members, it would most likely offer at least the following class interface:

```
class StringArray
{
    String *d_store;
    size_t d_n;

public:
    StringArray(size_t size);
    StringArray(StringArray const &other);
    StringArray const &operator=(StringArray const &rvalue);
    ~StringArray();

    String &operator[](size_t index);
};
```

This interface allows us to assign `String` elements to each other:

```
StringArray sa(10);

sa[4] = sa[3]; // String to String assignment
```

But it is also possible to assign a `char const *` to an element of `sa`:

```
sa[3] = "hello world";
```

Here, the following steps are taken:

- First, `sa[3]` is evaluated. This results in a `String` reference.
- Next, the `String` class is inspected for an overloaded assignment, expecting a `char const *` to its right-hand side. This operator is found, and the string object `sa[3]` receives its new value.

Now we try to do it the other way around: how to *access* the `char const *` that's stored in `sa[3]`? The following attempt fails:

```
char const *cp = sa[3];
```

It fails since we would need an overloaded assignment operator for the 'class `char const *`'. Unfortunately, there isn't such a class, and therefore we can't build that overloaded assignment operator (see also section 10.12). Furthermore, *casting* won't work as the compiler doesn't know how to cast a `String` to a `char const *`. How to proceed?

One possibility is to define an accessor member function `c_str()`:

```
char const *cp = sa[3].c_str()
```

This compiles fine but looks clumsy... A far better approach would be to use a *conversion operator*.

A *conversion operator* is a kind of overloaded operator, but this time the overloading is used to cast the object to another type. In class interfaces, the general form of a conversion operator is:

```
operator <type>() const;
```

Conversion operators usually are `const` member functions: they are automatically called when their objects are used as *rvalues* in expressions having a type *lvalue*. Using a conversion operator a `String` object may be interpreted as a `char const * rvalue`, allowing us to perform the above assignment.

Conversion operators are somewhat dangerous. The conversion is automatically performed by the compiler and unless its use is perfectly transparent it may confuse those who read code in which conversion operators are used. E.g., novice C++ programmers are frequently confused by statements like `if (cin) ...`.

As a rule of thumb: classes should define at most one conversion operator. Multiple conversion operators may be defined but frequently result in ambiguous code. E.g., if a class defines `operator bool() const` and `operator int() const` then passing an object of this class to a function expecting a `size_t` argument results in an ambiguity as an `int` and a `bool` may both be used to initialize a `size_t`.

In the current example, the class `String` could define the following conversion operator for `char const *`:

```
String::operator char const *() const
{
    return d_string;
}
```

Notes:

- Conversion operators do not define return types. The conversion operator returns a value of the type specified beyond the `operator` keyword.
- In certain situations (e.g., when a `String` argument is passed to a function specifying an ellipsis parameter) the compiler needs a hand to disambiguate our intentions. A `static_cast` will solve the problem.
- With *template functions* conversion operators may not work immediately as expected. For example, when defining a conversion operator `X::operator std::string const() const` then `cout << X()` won't compile. The reason for this is explained in section 20.8, but a shortcut allowing the conversion operator to work is to define the following overloaded `operator<<` function:

```
std::ostream &operator<<(std::ostream &out, std::string const &str)
{
    return out.write(str.data(), str.length());
}
```

Conversion operators are also used when objects of classes defining conversion operators are inserted into streams. Realize that the right hand sides of insertion operators are function parameters that are initialized by the operator's right hand side arguments. The rules are simple:

- If a class `X` defining a conversion operator also defines an insertion operator accepting an `X` object the insertion operator is used;
- Otherwise, if the type returned by the conversion operator is insertable then the conversion operator is used;
- Otherwise, a compilation error results. Note that this happens if the type returned by the conversion operator itself defines a conversion operator to a type that may be inserted into a stream.

In the following example an object of class `Insertable` is directly inserted; an object of the class `Convertible` uses the conversion operator; an object of the class `Error` cannot be inserted since it does not define an insertion operator and the type returned by its conversion operator cannot be inserted

either (Text *does* define an operator `int()` `const`, but the fact that a Text itself cannot be inserted causes the error):

```
#include <iostream>
#include <string>
using namespace std;

struct Insertable
{
    operator int() const
    {
        cout << "op int()\n";
    }
};
ostream &operator<<(ostream &out, Insertable const &ins)
{
    return out << "insertion operator";
}
struct Convertor
{
    operator Insertable() const
    {
        return Insertable();
    }
};
struct Text
{
    operator int() const
    {
        return 1;
    }
};
struct Error
{
    operator Text() const
    {
        return Text();
    }
};

int main()
{
    Insertable insertable;
    cout << insertable << '\n';
    Convertor convertor;
    cout << convertor << '\n';
    Error error;
    cout << error << '\n';
}
```

Some final remarks regarding conversion operators:

- A conversion operator should be a ‘natural extension’ of the facilities of the object. For example, the stream classes define `operator bool()`, allowing constructions like `if (cin)`.
- A conversion operator should return an *rvalue*. It should do so to enforce data-hiding and because it is the intended use of the conversion operator. Defining a conversion operator as an *lvalue* (e.g., defining an operator `int &()` conversion operator) opens up a back door, and the operator can only be used as *lvalue* when explicitly called (as in: `x.operator int&() = 5`). Don’t use it.

- Conversion operators should be defined as `const` member functions as they don't modify their object's data members.
- Conversion operators returning composed objects should return `const` references to these objects whenever possible to avoid calling the composed object's copy constructor.

10.4 The keyword 'explicit'

Conversions are not only performed by conversion operators, but also by constructors accepting one argument (i.e., constructors having one or multiple parameters, specifying default argument values for all parameters or for all but the first parameter).

Assume a data base class `DataBase` is defined in which `Person` objects can be stored. It defines a `Person *d_data` pointer, and so it offers a copy constructor and an overloaded assignment operator.

In addition to the copy constructor `DataBase` offers a default constructor and several additional constructors:

- `DataBase(Person const &):` the `DataBase` initially contains a single `Person` object;
- `DataBase(istream &in):` the data about multiple persons are read from `in`.
- `DataBase(size_t count, istream &in = cin):` the data of `count` persons are read from `in`, by default the standard input stream.

The above constructors all are perfectly reasonable. But they also allow the compiler to compile the following code without producing any warning at all:

```
DataBase db;
DataBase db2;
Person person;

db2 = db;           // 1
db2 = person;       // 2
db2 = 10;           // 3
db2 = cin;          // 4
```

Statement 1 is perfectly reasonable: `db` is used to redefine `db2`. Statement 2 might be understandable since we designed `DataBase` to contain `Person` objects. Nevertheless, we might question the logic that's used here as a `Person` is not some kind of `DataBase`. The logic becomes even more opaque when looking at statements 3 and 4. Statement 3 in effect will wait for the data of 10 persons to appear at the standard input stream. Nothing like that is suggested by `db2 = 10`.

All four statements are the result of implicit promotions. Since constructors accepting, respectively a `Person`, a `size_t` and an `istream` have been defined for `PersonData` and since the assignment operator expects a `PersonData` right-hand side (rhs) argument the compiler will first convert the rhs arguments to anonymous `DataBase` objects which are then assigned to `db2`.

It is good practice to prevent implicit promotions by using the `explicit` modifier when declaring a constructor. Constructors using the `explicit` modifier can only be used to construct objects explicitly. Statements 2-4 would not have compiled if the constructors expecting one argument would have been declared using `explicit`. E.g.,

```
explicit DataBase(Person const &person);
explicit DataBase(size_t count, std::istream &in);
```

Having declared all constructors accepting one argument as `explicit` the above assignments would have required the explicit specification of the appropriate constructors, thus clarifying the programmer's intent:

```
DataBase db;
DataBase db2;
Person person;

db2 = db;                // 1
db2 = DataBase(person); // 2
db2 = DataBase(10);      // 3
db2 = DataBase(cin);     // 4
```

As a rule of thumb prefix one argument constructors with the `explicit` keyword unless implicit promotions are perfectly natural (string's `char const *` accepting constructor is a case in point).

10.4.1 Explicit conversion operators (C++0x, 4.5)

In addition to explicit constructors, the C++0x standard adds *explicit conversion operators* to C++.

For example, a class might define operator `bool()` `const` returning `true` if an object of that class is in a usable state and `false` if not. Since the type `bool` is an arithmetic type this could result in unexpected or unintended behavior. Consider:

```
class StreamHandler
{
public:
    operator bool() const;    // true: object is fit for use
    ...
};

int fun(StreamHandler &sh)
{
    int sx;

    if (sh)                  // intended use of operator bool()
        ... use sh as usual; also use 'sx'

    process(sh);             // typo: 'sx' was intended
}
```

In this example `process` unintentionally receives the value returned by operator `bool` using the implicit conversion from `bool` to `int`.

With explicit conversion operators implicit conversions like the one shown in the example are prevented and such conversion operators will only be used in situations where the converted type is explicitly required. E.g., in the condition sections of `if` or repetition statements where a `bool` value is expected. In such cases an explicit operator `bool()` conversion operator would automatically be used.

10.5 Overloading the increment and decrement operators

Overloading the increment operator (`operator++`) and decrement operator (`operator--`) introduces a small problem: there are two versions of each operator, as they may be used as *postfix operator* (e.g., `x++`) or as *prefix operator* (e.g., `++x`).

Used as *postfix* operator, the value's object is returned as an *rvalue*, temporary const object and the post-incremented variable itself disappears from view. Used as *prefix* operator, the variable is incremented, and its value is returned as *lvalue* and it may be altered again by modifying the prefix operator's return value. Whereas these characteristics are not *required* when the operator is overloaded, it is strongly advised to implement these characteristics in any overloaded increment or decrement operator.

Suppose we define a *wrapper class* around the `size_t` value type. Such a class could offer the following (partially shown) interface:

```
class Unsigned
{
    size_t d_value;

public:
    Unsigned();
    explicit Unsigned(size_t init);

    Unsigned &operator++();
}
```

The class's last member declares the *prefix* overloaded increment operator. The returned *lvalue* is `Unsigned &`. The member is easily implemented:

```
Unsigned &Unsigned::operator++()
{
    ++d_value;
    return *this;
}
```

To define the *postfix* operator, an overloaded version of the operator is defined, expecting a (dummy) `int` argument. This might be considered a *kludge*, or an acceptable application of function overloading. Whatever your opinion in this matter, the following can be concluded:

- Overloaded increment and decrement operators *without parameters* are *prefix* operators, and should return *references* to the current object.
- Overloaded increment and decrement operators *having an int parameter* are *postfix* operators, and should return a constant value which is a copy of the object at the point where its postfix operator is used.

The postfix increment operator is declared as follows in the class `Unsigned`'s interface:

```
Unsigned const operator++(int);
```

It may be implemented as follows:

```
Unsigned const Unsigned::operator++(int)
{
    Unsigned tmp(*this);
    ++d_value;
    return tmp;
}
```

Note that the operator's parameter is not used. It is only part of the implementation to *disambiguate* the prefix- and postfix operators in implementations and declarations.

In the above example the statement incrementing the current object offers the *nothrow* guarantee as it only involves an operation on a primitive type. If the initial copy construction throws then the

original object is not modified, if the return statement throws the object has safely been modified. But incrementing an object could itself throw exceptions. How to implement the increment operators in that case? Once again, `swap` is our friend. Here are the pre- and postfix operators offering the strong guarantee when the member `increment` performing the increment operation may throw:

```
Unsigned &Unsigned::operator++()
{
    Unsigned tmp(*this);
    tmp.increment();
    swap(tmp);
    return *this;
}
Unsigned const Unsigned::operator++(int)
{
    Unsigned tmp(*this);
    tmp.increment();
    swap(tmp);
    return tmp;
}
```

The postfix increment operator first creates a copy of the current object. That copy is incremented and then swapped with the current object. If `increment` throws the current object remains unaltered; the `swap` operation ensures that the original object is returned and the current object becomes the incremented object.

When calling the postfix increment or decrement operator using its full member function name then any `int` argument passed to the member function will result in calling the postfix operator. Example:

```
Unsigned uns(13);

uns.operator++();      // prefix-incrementing uns
uns.operator++(0);    // postfix-incrementing uns
```

10.6 Overloading binary operators

In various classes overloading binary operators (like `operator+`) can be a very natural extension of the class's functionality. For example, the `std::string` class has various overloaded forms of `operator+`.

Most binary operators come in two flavors: the plain binary operator (like the `+` operator) and the arithmetic assignment variant (like the `+=` operator). Whereas the plain binary operators return `const` expression values, the arithmetic assignment operators return a (non-`const`) reference to the object to which the operator was applied. For example, with `std::string` objects the following code (annotations below the example) may be used:

```
std::string s1;
std::string s2;
std::string s3;

s1 = s2 += s3;           // 1
(s2 += s3) + " postfix"; // 2
s1 = "prefix " + s3;     // 3
"prefix " + s3 + "postfix"; // 4
("prefix " + s3) += "postfix"; // 5
```

- at // 1 the contents of `s3` is added to `s2`. Next, `s2` is returned, and its new contents are assigned to `s1`. Note that `+=` returns `s2` itself.

- at `// 2` the contents of `s3` is also added to `s2`, but as `+=` returns `s2` itself, it's possible to add some more to `s2`
- at `// 3` the `+` operator returns a `std::string` containing the concatenation of the text `prefix` and the contents of `s3`. This string returned by the `+` operator is thereupon assigned to `s1`.
- at `// 4` the `+` operator is applied twice. The effect is:
 1. The first `+` returns a `std::string` containing the concatenation of the text `prefix` and the contents of `s3`.
 2. The second `+` operator takes this returned string as its left hand value, and returns a string containing the concatenated text of its left and right hand operands.
 3. The string returned by the second `+` operator represents the value of the expression.
- statement `// 5` is interesting in that it should not compile (it does compile with the Gnu compiler). It should not compile, as the `+` operator should return a `const` string. This should prevent its modification by the subsequent `+=` operator (compare this situation with `int` values: `(3 + intValue) += 4` won't compile. Clearly, `std::string` does *not* do 'as the ints do'). In the **C++ Annotations** binary arithmetic operators return `const` values to render statements like statement `// 5` incompilable.

Consider the following code, in which a class `Binary` supports an overloaded operator`+`:

```
class Binary
{
    public:
        Binary();
        Binary(int value);
        Binary const operator+(Binary const &rvalue);
};

int main()
{
    Binary b1;
    Binary b2(5);

    b1 = b2 + 3;           // 1
    b1 = 3 + b2;           // 2
}
```

Compilation of this little program fails for statement `// 2`, with the compiler reporting an error like:

```
error: no match for 'operator+' in '3 + b2'
```

Why is statement `// 1` compiled correctly whereas statement `// 2` won't compile?

In order to understand this remember *promotions*. As we have seen in section 10.4, constructors expecting a single argument may be implicitly activated when an argument of an appropriate type is provided. We've encountered this repeatedly with `std::string` objects, where an ASCII-Z string may be used to initialize a `std::string` object.

Analogously, in statement `// 1`, the `+` operator is called for the `b2` object. This operator expects another `Binary` object as its right hand operand. However, an `int` is provided. As a constructor `Binary(int)` exists, the `int` value is first promoted to a `Binary` object. Next, this `Binary` object is passed as argument to the `operator+` member.

In statement `// 2` no promotions are available: here the `+` operator is applied to an lvalue that is an `int`. An `int` is a primitive type and primitive types have no concept of 'constructors', 'member functions' or 'promotions'.

How, then, are promotions of left-hand operands implemented in statements like "prefix " + s3? Since promotions are applied to function arguments, we must make sure that both operands of binary operators are arguments. This means that plain binary arithmetic operators should be declared as *free operators*, also called *free functions*. Functions like the plain binary arithmetic operators conceptually belong to the class for which they implement the binary operator. Consequently they should be declared *within* the class's header file. We will cover their implementations shortly, but here is our first revision of the declaration of the class `Binary`, declaring an overloaded `+` operator as a free function:

```
class Binary
{
    public:
        Binary();
        Binary(int value);
};

Binary const operator+(Binary const &l_hand, Binary const &r_hand);
```

By defining binary operators as free functions, the following promotions are possible:

- If the left-hand operand is of the intended class type, the right hand argument will be promoted whenever possible;
- If the right-hand operand is of the intended class type, the left hand argument will be promoted whenever possible;
- No promotions occur when none of the operands are of the intended class type;
- An ambiguity occurs when promotions to different classes are possible for the two operands. For example:

```
class A;

class B
{
    public:
        B(A const &a);
};

class A
{
    public:
        A();
        A(B const &b);
};

A const operator+(A const &a, B const &b);
B const operator+(B const &b, A const &a);

int main()
{
    A a;

    a + a;
};
```

Here, both overloaded `+` operators are possible when compiling the statement `a + a`. The ambiguity must be solved by explicitly promoting one of the arguments, e.g., `a + B(a)` will allow the compiler to resolve the ambiguity to the first overloaded `+` operator.

The next step is to implement the corresponding overloaded arithmetic assignment operator. As this operator *always* has a left-hand operand which is an object of its own class, it is implemented as a true member function. Furthermore, the arithmetic assignment operator should return a reference to the object to which the arithmetic operation applies, as the object might be modified in the same statement. E.g., `(s2 += s3) + " postfix"`. Here is our second revision of the class `Binary`, showing both the declaration of the plain binary operator and the corresponding arithmetic assignment operator:

```
class Binary
{
    public:
        Binary();
        Binary(int value);
        Binary const operator+(Binary const &rvalue);

        Binary &operator+=(Binary const &other);
};

Binary const operator+(Binary const &lhs, Binary const &rhs);
```

If a class benefits from being move-aware then for each `const` reference parameter an overloaded function expecting a `const rvalue` reference may be considered. With the class `Binary` and its `operator+` this would boil down to the following overloaded `operator+` functions:

```
Binary const operator+(Binary const &&lttmp, Binary const &rhs);
Binary const operator+(Binary const &lhs, Binary const &&rtmp);
Binary const operator+(Binary const &&lttmp, Binary const &&rtmp);
```

When implementing the arithmetic assignment operator the strong guarantee should again be kept in mind. Use a temporary object and swap if the arithmetic operation might throw. Example:

```
Binary &operator+=(Binary const &other)
{
    Binary tmp(*this);
    tmp.add(other);    // this may throw
    swap(tmp);
    return *this;
}
```

Here, too, defining `operator+=(Binary const &&tmp)` should be considered if `Binary` must be a move-aware class.

Having available the arithmetic assignment operator, implementating the plain binary operator is easy. The `lhs` argument is copied into a `Binary tmp` to which the `rhs` operand is added. Then `tmp` is returned. The copy construction and two statements may be contracted into one single return statement, but then compilers usually aren't able to apply copy elision resulting in two copy constructions. Usually copy elision is performed when the steps are taken separately:

```
class Binary
{
    public:
        Binary();
        Binary(int value);
        Binary const operator+(Binary const &rvalue);

        Binary &operator+=(Binary const &other);
};
```

```

Binary const operator+(Binary const &lhs, Binary const &rhs)
{
    Binary tmp(lhs);
    tmp += rhs;
    return tmp;
}

```

10.7 Overloading ‘operator new(size_t)’

When `operator new` is overloaded, it must define a `void *` return type, and its first parameter must be of type `size_t`. The default `operator new` defines only one parameter, but overloaded versions may define multiple parameters. The first one is not explicitly specified but is deducted from the size of objects of the class for which `operator new` is overloaded. In this section overloading `operator new` is discussed. Overloading `new[]` is discussed in section [10.9](#).

It is possible to define multiple versions of the `operator new`, as long as each version defines its own unique set of arguments. When overloaded `operator new` members must dynamically allocate memory they can do so using the global `operator new`, applying the scope resolution operator `::`. In the next example the overloaded `operator new` of the class `String` will initialize the substrate of dynamically allocated `String` objects to 0-bytes:

```

#include <cstdint>
#include <iosfwd>

class String
{
    std::string *d_data;

public:
    void *operator new(size_t size)
    {
        return memset(::operator new(size), 0, size);
    }
    bool empty() const
    {
        return d_data == 0;
    }
};

```

The above `operator new` is used in the following program, illustrating that even though `String`’s default constructor does nothing the object’s data are initialized to zeroes:

```

#include "string.h"
#include <iostream>
using namespace std;

int main()
{
    String *sp = new String;

    cout << boolalpha << sp->empty() << '\n';    // shows: true
}

```

At new `String` the following took place:

- First, `String::operator new` was called, allocating and initializing a block of memory, the size of a `String` object.

- Next, a pointer to this block of memory was passed to the (default) `String` constructor. Since no constructor was defined, the constructor itself didn't do anything at all.

As `String::operator new` initialized the allocated memory to zero bytes the allocated `String` object's `d_data` member had already been initialized to a 0-pointer by the time it started to exist.

All member functions (including constructors and destructors) we've encountered so far define a (hidden) pointer to the object on which they should operate. This hidden pointer becomes the function's `this` pointer.

In the next example of *pseudo C++ code*, the pointer is explicitly shown to illustrate what's happening when `operator new` is used. In the first part a `String` object `str` is directly defined, in the second part of the example the (overloaded) `operator new` is used:

```
String::String(String *const this);    // real prototype of the default
                                      // constructor

String *sp = new String;               // This statement is implemented
                                      // as follows:

String *sp = reinterpret_cast<String *>(    // allocation
    String::operator new(sizeof(String))
);
String::String(sp);                     // initialization
```

In the above fragment the member functions were treated as *object-less* member functions of the class `String`. Such members are called *static member functions* (cf. chapter 11). Actually, `operator new` is such a static member function. Since it has no `this` pointer it cannot reach data members of the object for which it is expected to make memory available. It can only allocate and initialize the allocated memory, but cannot reach the object's data members by name as there is as yet no data object layout defined.

Following the allocation, the memory is passed (as the `this` pointer) to the constructor for further processing.

`Operator new` can have multiple parameters. The first parameter is initialized as an implicit argument and is always a `size_t` parameter. Additional overloaded operators may define additional parameters. An interesting additional `operator new` is the *placement new* operator. With the *placement new* operator a block of memory has already been set aside and one of the class's constructors will be used to initialize that memory. Overloading *placement new* requires an `operator new` having two parameters: `size_t` and `char *`, pointing to the memory that was already available. The `size_t` parameter is implicitly initialized, but the remaining parameters must explicitly be initialized using arguments to `operator new`. Hence we reach the familiar syntactical form of the *placement new* operator in use:

```
char buffer[sizeof(String)];           // predefined memory
String *sp = new(buffer) String;       // placement new call
```

The declaration of the *placement new* operator in our class `String` looks like this:

```
void *operator new(size_t size, char *memory);
```

It could be implemented like this (also initializing the `String`'s memory to 0-bytes):

```
void *String::operator new(size_t size, char *memory)
{
    return memset(memory, 0, size);
}
```

Any other overloaded version of `operator new` could also be defined. Here is an example showing the use and definition of an overloaded `operator new` storing the object's address immediately in an existing array of pointers to `String` objects (assuming the array is large enough):

```
// use:
String *next(String **pointers, size_t *idx)
{
    return new(pointers, (*idx)++) String;
}

// implementation:
void *String::operator new(size_t size, String **pointers, size_t idx)
{
    return pointers[idx] = ::operator new(size);
}
```

10.8 Overloading ‘operator delete(void *)’

The `delete` operator may also be overloaded. In fact it's good practice to overload `operator delete` whenever `operator new` is also overloaded.

`Operator delete` must define a `void *` parameter. A second overloaded version defining a second parameter of type `size_t` is related to overloading `operator new[]` and is discussed in section 10.9.

Overloaded `operator delete` members return `void`.

The ‘home-made’ `operator delete` is called when deleting a dynamically allocated object after executing the destructor of the associated class. So, the statement

```
delete ptr;
```

with `ptr` being a pointer to an object of the class `String` for which the `operator delete` was overloaded, is a shorthand for the following statements:

```
ptr->~String(); // call the class's destructor

// and do things with the memory pointed to by ptr
String::operator delete(ptr);
```

The overloaded `operator delete` may do whatever it wants to do with the memory pointed to by `ptr`. It could, e.g., simply delete it. If that would be the preferred thing to do, then the default `delete` operator can be called using the `::` scope resolution operator. For example:

```
void String::operator delete(void *ptr)
{
    // any operation considered necessary, then, maybe:
    ::delete ptr;
}
```

To declare the above overloaded `operator delete` simply add the following line to the class's interface:

```
void operator delete(void *ptr);
```

Like `operator new` `operator delete` is a static member function (see also chapter 11).

10.9 Operators 'new[]' and 'delete[]'

In sections 8.1.1, 8.1.2 and 8.2.1 operator `new[]` and operator `delete[]` were introduced. Like operator `new` and operator `delete` the operators `new[]` and `delete[]` may be overloaded.

As it is possible to overload `new[]` and `delete[]` as well as operator `new` and operator `delete`, one should be careful in selecting the appropriate set of operators. The following rule of thumb should always be applied:

If `new` is used to allocate memory, `delete` should be used to deallocate memory. If `new[]` is used to allocate memory, `delete[]` should be used to deallocate memory.

By default these operators act as follows:

- operator `new` is used to allocate a single object or primitive value. With an object, the object's constructor is called.
- operator `delete` is used to return the memory allocated by operator `new`. Again, with class-type objects, the class's destructor is called.
- operator `new[]` is used to allocate a series of primitive values or objects. If a series of objects is allocated, the class's default constructor is called to initialize each object individually.
- operator `delete[]` is used to delete the memory previously allocated by `new[]`. *If* objects were previously allocated, then the destructor will be called for each individual object. Be careful, though, when pointers to objects were allocated. If *pointers to objects* were allocated the destructors of the objects to which the allocated pointers point won't automatically be called. A pointer is a primitive type and so no further action is taken when it is returned to the common pool.

10.9.1 Overloading 'new[]'

To overload operator `new[]` in a class (e.g., in the class `String`) add the following line to the class's interface:

```
void *operator new[](size_t size);
```

The member's `size` parameter is implicitly provided and is initialized by C++'s run-time system to the amount of memory that must be allocated. Like the simple one-object operator `new` it should return a `void *`. The number of objects that must be initialized can easily be computed from `size / sizeof(String)` (and of course replacing `String` by the appropriate class name when overloading operator `new[]` for another class). The overloaded `new[]` member may allocate raw memory using e.g., the default operator `new[]` or the default operator `new`:

```
void *operator new[](size_t size)
{
    return ::operator new[](size);
    // alternatively:
    // return ::operator new(size);
}
```

Before returning the allocated memory the overloaded operator `new[]` has a chance to do something special. It could, e.g., initialize the memory to zero-bytes.

Once the overloaded operator `new[]` has been defined, it will be used automatically in statements like:

```
String *op = new String[12];
```

Like `operator new` additional overloads of `operator new[]` may be defined. One opportunity for an `operator new[]` overload is overloading *placement new* specifically for arrays of objects. This operator is available by default but becomes unavailable once at least one overloaded `operator new[]` is defined. Implementing *placement new* is not difficult. Here is an example, initializing the available memory to 0-bytes before returning:

```
void *String::operator new[](size_t size, char *memory)
{
    return memset(memory, 0, size);
}
```

To use this overloaded operator, the second parameter must again be provided, as in:

```
char buffer[12 * sizeof(String)];
String *sp = new(buffer) String[12];
```

10.9.2 Overloading ‘delete[]’

To overload `operator delete[]` in a class `String` add the following line to the class’s interface:

```
void operator delete[](void *memory);
```

Its parameter is initialized to the address of a block of memory previously allocated by `String::new[]`.

There are some subtleties to be aware of when implementing `operator delete[]`. Although the addresses returned by `new` and `new[]` point to the allocated object(s), there is an additional `size_t` value available immediately before the address returned by `new` and `new[]`. This `size_t` value is part of the allocated block and contains the actual size of the block. This of course does not hold true for the *placement new* operator.

When a class defines a destructor the `size_t` value preceding the address returned by `new[]` does not contain the size of the allocated block, but the *number* of objects specified when calling `new[]`. Normally that is of no interest, but when overloading `operator delete[]` it might become a useful piece of information. In those cases `operator delete[]` will *not* receive the address returned by `new[]` but rather the address of the initial `size_t` value. Whether this is at all useful is not clear. By the time `delete[]`’s code is executed all objects have already been destroyed, so `operator delete[]` is only to determine how many objects were destroyed but the objects themselves cannot be used anymore.

Here is an example showing this behavior of `operator delete[]` for a minimal `Demo` class:

```
struct Demo
{
    size_t idx;
    Demo()
    {
        cout << "default cons\n";
    }
    ~Demo()
    {
        cout << "destructor\n";
    }
    void *operator new[](size_t size)
    {
        return ::operator new(size);
    }
    void operator delete[](void *vp)
    {

```

```

        cout << "delete[] for: " << vp << '\n';
        ::operator delete[](vp);
    }
};

int main()
{
    Demo *xp;
    cout << ((int *) (xp = new Demo[3]))[-1] << '\n';
    cout << xp << '\n';
    cout << "=====\n";
    delete[] xp;
}
// This program displays (your 0x?????? addresses might differ, but
// the difference between the two should be sizeof(size_t)):
// default cons
// default cons
// default cons
// 3
// 0x8bdd00c
// =====
// destructor
// destructor
// destructor
// delete[] for: 0x8bdd008

```

Having overloaded operator `delete[]` for a class `String`, it will be used automatically in statements like:

```
delete[] new String[5];
```

Operator `delete[]` may also be overloaded using an additional `size_t` parameter:

```
void operator delete[](void *p, size_t size);
```

Here `size` is automatically initialized to the size (in bytes) of the block of memory to which `void *p` points. If this form is defined, then `void operator[](void *)` should *not* be defined, to avoid ambiguities. An example of this latter form of operator `delete[]` is:

```

void String::operator delete[](void *p, size_t size)
{
    cout << "deleting " << size << " bytes\n";
    ::operator delete[](ptr);
}

```

Additional overloads of operator `delete[]` may be defined, but to use them they must explicitly be called as static member functions (cf. chapter 11). Example:

```

// declaration:
void String::operator delete[](void *p, ostream &out);
// usage:
String *xp = new String[3];
String::operator delete[](xp, cout);

```

10.9.3 ‘new[]’, ‘delete[]’ and exceptions

When an exception is thrown while executing a `new[]` expression, what will happen? In this section we'll show that `new[]` is exception safe even when only some of the objects were properly constructed.

To begin, `new[]` might throw while trying to allocate the required memory. In this case a `bad_alloc` is thrown and we don't leak as nothing was allocated.

Having allocated the required memory the class's default constructor will be called for each of the objects in turn. At some point a constructor might throw. What happens next is defined by the C++ standard: the destructors of the already constructed objects will be called and the memory allocated for the objects themselves is returned to the common pool. Assuming that the failing constructor offers the basic guarantee `new[]` is therefore exception safe even if a constructor may throw.

The following example illustrates this behavior. A request to allocate and initialize five objects is made, but after constructing two objects construction fails by throwing an exception. The output shows that the destructors of properly constructed objects are called and that the allocated *substrate memory* is properly returned:

```
#include <iostream>
using namespace std;

static size_t count = 0;

class X
{
    int x;

public:
    X()
    {
        if (count == 2)
            throw 1;
        cout << "Object " << ++count << '\n';
    }
    ~X()
    {
        cout << "Destroyed " << this << "\n";
    }
    void *operator new[](size_t size)
    {
        cout << "Allocating objects: " << size << " bytes\n";
        return ::operator new(size);
    }
    void operator delete[](void *mem)
    {
        cout << "Deleting memory at " << mem << ", containing: " <<
            *reinterpret_cast<int *>(mem) << "\n";
        ::operator delete(mem);
    }
};

int main()
try
{
    X *xp = new X[5];
    cout << "Memory at " << xp << '\n';
    delete[] xp;
}
```

```

catch (...)
{
    cout << "Caught exception.\n";
}
// Output from this program (your 0x??? addresses might differ)
// Allocating objects: 24 bytes
// Object 1
// Object 2
// Destroyed 0x8428010
// Destroyed 0x842800c
// Deleting memory at 0x8428008, containing: 5
// Caught exception.

```

10.10 Function Objects

Function Objects are created by overloading the *function call operator* `operator()`. By defining the function call operator an object masquerades as a function, hence the term *function objects*.

Function objects are important when using *generic algorithms*. The use of function objects is preferred over alternatives like pointers to functions. The fact that they are important in the context of generic algorithms leaves us with a didactic dilemma. At this point in the **C++ Annotations** it would have been nice if generic algorithms would already have been covered, but for the discussion of the generic algorithms knowledge of function objects is required. This bootstrapping problem is solved in a well known way: by ignoring the dependency for the time being, for now concentrating on the function object concept.

Function objects are objects for which `operator()` has been defined. Function objects are not just used in combination with generic algorithms, but also as a (preferred) alternative to pointers to functions.

Function objects are frequently used to implement *predicate* functions. Predicate functions return boolean values. Predicate functions and predicate function objects are commonly referred to as ‘predicates’. Predicates are frequently used by generic algorithms such as the `count_if` generic algorithm, covered in chapter 19, returning the number of times its function object has returned `true`. In the *standard template library* two kinds of predicates are used: *unary predicates* receive one argument, *binary predicates* receive two arguments.

Assume we have a class `Person` and an array of `Person` objects. Further assume that the array is not sorted. A well known procedure for finding a particular `Person` object in the array is to use the function `lsearch`, which performs a *linear search* in an array. Example:

```

Person &target = targetPerson();    // determine the person to find
Person *pArray;
size_t n = fillPerson(&pArray);

cout << "The target person is";

if (!lsearch(&target, pArray, &n, sizeof(Person), compareFunction))
    cout << " not";
cout << "found\n";

```

The function `targetPerson` determines the person we’re looking for, and `fillPerson` is called to fill the array. Then `lsearch` is used to locate the target person.

The comparison function must be available, as its address is one of the arguments of `lsearch`. It must be a real function having an address. If it is defined inline then the compiler has no choice but to ignore that request as inline functions don’t have addresses. `CompareFunction` could be implemented like this:

```

int compareFunction(void const *p1, void const *p2)
{
    return *reinterpret_cast<Person const *>(p1)    // lsearch wants 0
           !=                                       // for equal objects
           *reinterpret_cast<Person const *>(p2);
}

```

This, of course, assumes that the `operator!=` has been overloaded in the class `Person`. But overloading `operator!=` is no big deal, so let's assume that that operator is actually available.

On average $n / 2$ times *at least* the following actions take place:

1. The two arguments of the compare function are pushed on the stack;
2. The value of the final parameter of `lsearch` is determined, producing `compareFunction`'s address;
3. The compare function is called;
4. Then, inside the compare function the address of the right-hand argument of the `Person::operator!=` argument is pushed on the stack;
5. `Person::operator!=` is evaluated;
6. The argument of the `Person::operator!=` function is popped off the stack;
7. The two arguments of the compare function are popped off the stack.

Using function objects results in a different picture. Assume we have constructed a function `PersonSearch`, having the following prototype (this, however, is not the preferred approach. Normally a generic algorithm is preferred over a home-made function. But for now we focus on `PersonSearch` to illustrate the use and implementation of a function object):

```

Person const *PersonSearch(Person *base, size_t nmemb,
                           Person const &target);

```

This function can be used as follows:

```

Person &target = targetPerson();
Person *pArray;
size_t n = fillPerson(&pArray);

cout << "The target person is";

if (!PersonSearch(pArray, n, target))
    cout << " not";

cout << "found\n";

```

So far, not much has been changed. We've replaced the call to `lsearch` with a call to another function: `PersonSearch`. Now look at `PersonSearch` itself:

```

Person const *PersonSearch(Person *base, size_t nmemb,
                           Person const &target)
{
    for (int idx = 0; idx < nmemb; ++idx)
        if (target(base[idx]))
            return base + idx;
    return 0;
}

```

`PersonSearch` implements a plain linear search. However, in the for-loop we see `target(base[idx])`. Here `target` is used as a *function object*. Its implementation is simple:

```
bool Person::operator()(Person const &other) const
{
    return *this == other;
}
```

Note the somewhat peculiar syntax: `operator()`. The first set of parentheses define the operator that is overloaded: the function call operator. The second set of parentheses define the parameters that are required for this overloaded operator. In the class header file this overloaded operator is declared as:

```
bool operator()(Person const &other) const;
```

Clearly `Person::operator()` is a simple function. It contains but one statement, and we could consider defining it inline. Assuming we do, then this is what happens when `operator()` is called:

1. The address of the right-hand argument of the `Person::operator==` argument is pushed on the stack;
2. The `operator==` function is evaluated (which probably also is a *semantic* improvement over calling `operator!=` when looking for an object *equal to* a specified target object);
3. The argument of `Person::operator==` argument is popped off the stack.

Due to the fact that `operator()` is an inline function, it is not actually called. Instead `operator==` is called immediately. Moreover, the required stack operations are fairly modest.

Function objects may truly be defined inline. Functions that are called indirectly (i.e., using pointers to functions) can never be defined inline as their addresses must be known. Therefore, even if the function object needs to do very little work it is defined as an ordinary function if it is going to be called through pointers. The overhead of performing the indirect call may annihilate the advantage of the flexibility of calling functions indirectly. In these cases using inline function objects can result in an increase of a program's efficiency.

An added benefit of function objects is that they may access the private data of their objects. In a search algorithm where a compare function is used (as with `lsearch`) the target and array elements are passed to the compare function using pointers, involving extra stack handling. Using function objects, the target person doesn't vary within a single search task. Therefore, the target person could be passed to the function object's class constructor. This is in fact what happens in the expression `target(base[idx])` receiving as its only argument the subsequent elements of the array to search.

10.10.1 Constructing manipulators

In chapter 6 we saw constructions like `cout << hex << 13 <<` to display the value 13 in hexadecimal format. One may wonder by what magic the `hex` manipulator accomplishes this. In this section the construction of manipulators like `hex` is covered.

Actually the construction of a manipulator is rather simple. To start, a definition of the manipulator is needed. Let's assume we want to create a manipulator `w10` which will set the field width of the next field to be written by the `ostream` object to 10. This manipulator is constructed as a function. The `w10` function will have to know about the `ostream` object in which the width must be set. By providing the function with an `ostream &` parameter, it obtains this knowledge. Now that the function knows about the `ostream` object we're referring to, it can set the width in that object.

Next, it must be possible to use the manipulator in an insertion sequence. This implies that the return value of the manipulator must be a reference to an `ostream` object also.

From the above considerations we're now able to construct our `w10` function:

```
#include <ostream>
#include <iomanip>

std::ostream &w10(std::ostream &str)
{
    return str << std::setw(10);
}
```

The `w10` function can of course be used in a 'stand alone' mode, but it can also be used as a manipulator. E.g.,

```
#include <iostream>
#include <iomanip>

using namespace std;

extern ostream &w10(ostream &str);

int main()
{
    w10(cout) << 3 << " ships sailed to America\n";
    cout << "And " << w10 << 3 << " more ships sailed too.\n";
}
```

The `w10` function can be used as a manipulator because the class `ostream` has an overloaded `operator<<` accepting a pointer to a function expecting an `ostream &` and returning an `ostream &`. Its definition is:

```
ostream& operator<<(ostream ostream &(*func)(ostream &str))
{
    return (*func)(*this);
}
```

In addition to the above overloaded `operator<<` another one is defined

```
ostream &operator<<(ios_base &(*func)(ios_base &base))
{
    (*func)(*this);
    return *this;
}
```

This latter function is used when inserting, e.g., hex or internal.

The above procedure does not work for manipulators requiring arguments. It is of course possible to overload `operator<<` to accept an `ostream` reference and the address of a function expecting an `ostream &` and, e.g., an `int`, but while the address of such a function may be specified with the `<<`-operator, the arguments itself cannot be specified. So, one wonders how the following construction has been implemented:

```
cout << setprecision(3)
```

In this case the manipulator is defined as a macro. Macro's, however, are the realm of the preprocessor, and may easily suffer from unwelcome side-effects. In **C++** programs they should be avoided whenever possible. The following section introduces a way to implement manipulators requiring arguments without resorting to macros, but using anonymous objects.

10.10.1.1 Manipulators requiring arguments

Manipulators taking arguments are implemented as macros: they are handled by the preprocessor, and are not available beyond the preprocessing stage. The problem appears to be that you can't call a function in an insertion sequence: when using multiple `operator<<` operators in one statement the compiler will call the functions, save their return values, and will then use their return values in the insertion sequence. That invalidates the ordering of the arguments passed to your `<<`-operators.

So, one might consider constructing another overloaded `operator<<` accepting the address of a function receiving not just the `ostream` reference, but a series of other arguments as well. But this creates the problem that it isn't clear how the function should receive its arguments: you can't just call it since that takes us back to the abovementioned problem. Merely passing its address is fine, but then no arguments can't be passed to the function.

There exists a solution, based on the use of anonymous objects:

- First, a class is constructed, e.g. `Align`, whose constructor expects multiple arguments. In our example representing, respectively, the field width and the alignment.
- Furthermore, we define the function:

```
ostream &operator<<(ostream &ostr, Align const &align)
```

so we can insert an `Align` object into the `ostream`.

Here is an example of a little program using such a *home-made* manipulator expecting multiple arguments:

```
#include <iostream>
#include <iomanip>

class Align
{
    unsigned d_width;
    std::ios::fmtflags d_alignment;

public:
    Align(unsigned width, std::ios::fmtflags alignment);
    std::ostream &operator()(std::ostream &ostr) const;
};

Align::Align(unsigned width, std::ios::fmtflags alignment)
:
    d_width(width),
    d_alignment(alignment)
{}

std::ostream &Align::operator()(std::ostream &ostr) const
{
    ostr.setf(d_alignment, std::ios::adjustfield);
    return ostr << std::setw(d_width);
}

std::ostream &operator<<(std::ostream &ostr, Align const &align)
{
    return align(ostr);
}

using namespace std;
```

```

int main()
{
    cout
        << "" << Align(5, ios::left) << "hi" << ""
        << "" << Align(10, ios::right) << "there" << "\n";
}

/*
    Generated output:

    'hi    ' '      there'
*/

```

Note that in order to insert an anonymous `Align` object into the ostream, the operator `<<` function *must* define a `Align const &` parameter (note the `const` modifier).

10.11 The case of `[io]fstream::open()`

Earlier, in section 6.4.2.1, it was noted that the `[io]fstream::open` members expect an `ios::openmode` value as their final argument. E.g., to open an `fstream` object for writing you could do as follows:

```

fstream out;
out.open("/tmp/out", ios::out);

```

Combinations are also possible. To open an `fstream` object for *both* reading and writing the following stanza is often seen:

```

fstream out;
out.open("/tmp/out", ios::in | ios::out);

```

When trying to combine enum values using a ‘home made’ enum we may run into problems. Consider the following:

```

enum Permission
{
    READ =      1 << 0,
    WRITE =     1 << 1,
    EXECUTE =    1 << 2
};

void setPermission(Permission permission);

int main()
{
    setPermission(READ | WRITE);
}

```

When offering this little program to the compiler it will reply with an error message like this:

```
invalid conversion from 'int' to 'Permission'
```

The question is of course: why is it OK to combine `ios::openmode` values passing these combined values to the stream’s `open` member, but not OK to combine `Permission` values.

Combining enum values using arithmetic operators results in `int`-typed values. *Conceptually* this never was our intention. Conceptually it can be considered correct to combine enum values if the resulting value conceptually makes sense as a value that is still within the original enumeration domain. Note that after adding a value `READWRITE = READ | WRITE` to the above enum we're still not allowed to specify `READ | WRITE` as an argument to `setPermission`.

To answer the question about combining enumeration values and yet stay within the enumeration's domain we turn to operator overloading. Up to this point operator overloading has been applied to class types. Free functions like `operator<<` have been overloaded, and those overloads are conceptually within the domain of their class.

As **C++** is a strongly typed language realize that defining an enum is really something beyond the mere association of `int`-values with symbolic names. An enumeration type is really a type of its own, and as with any type its operators can be overloaded. When writing `READ | WRITE` the compiler will perform the default conversion from enum values to `int` values and thus will apply the operator to `ints`. It does so when it has no alternative.

But it is also possible to overload the enum type's operators. Thus we may ensure that we'll remain within the enum's domain even though the resulting value wasn't defined by the enum. The advantage of type-safety and conceptual clarity is considered to outweigh the somewhat peculiar introduction of values hitherto not defined by the enum.

Here is an example of such an overloaded operator:

```
Permission operator|(Permission left, Permission right)
{
    return static_cast<Permission>(static_cast<int>(left) | right);
}
```

Other operators can easily and analogously be constructed.

Operators like the above were defined for the `ios::openmode` enumeration type, allowing us to specify `ios::in | ios::out` as argument to `open` while specifying the corresponding parameter as `ios::openmode` as well. Clearly, operator overloading can be used in many situations, not necessarily only involving class-types.

10.12 Overloadable operators

The following operators can be overloaded:

+	-	*	/	%	^	&	
~	!	,	=	<	>	<=	>=
++	--	<<	>>	==	!=	&&	
+=	-=	*=	/=	%=	^=	&=	=
<<=	>>=	[]	()	->	->*	new	new[]
delete	delete[]						

Several operators have *textual alternatives*:

textual alternative	operator	
and	&&	
and_eq	&=	
bitand	&	
bitor		
compl	~	‘Textual’ alternatives of
not	!	
not_eq	!=	
or		
or_eq	=	
xor	^	
xor_eq	^=	

operators are also overloadable (e.g., `operator and`). However, note that textual alternatives are not *additional* operators. So, within the same context `operator&&` and `operator and` can not *both* be overloaded.

Several of these operators may only be overloaded as member functions *within* a class. This holds true for the `'=`', the `'[]`', the `'()`' and the `'->`' operators. Consequently, it isn't possible to redefine, e.g., the assignment operator globally in such a way that it accepts a `char const *` as an lvalue and a `String &` as an *rvalue*. Fortunately, that isn't necessary either, as we have seen in section 10.3.

Finally, the following operators cannot be overloaded:

`.` `.*` `::` `?:` `sizeof` `typeid`

Chapter 11

Static Data And Functions

In the previous chapters we provided examples of classes where each object had its own set of data members data. Each of the class's member functions could access any member of any object of its class.

In some situations it may be desirable to define *common data fields*, that may be accessed by *all* objects of the class. For example, the name of the startup directory, used by a program that recursively scans the directory tree of a disk. A second example is a variable that indicates whether some specific initialization has occurred. In that case the object that was constructed first would perform the initialization and would set the flag to 'done'.

Such situations are also encountered in **C**, where several functions need to access the same variable. A common solution in **C** is to define all these functions in one source file and to define the variable `static`: the variable name will not be visible beyond the scope of the source file. This approach is quite valid, but violates our philosophy of using only one function per source file. Another **C**-solution is to give the variable in question an unusual name, e.g., `_6uldv8`, hoping that other program parts won't use this name by accident. Neither the first, nor the second legacy **C** solution is elegant.

C++ solves the problem by defining `static` members: data and functions, common to all objects of a class and (when defined in the private section) inaccessible outside of the class. These static members are this chapter's topic.

Static members cannot be defined as virtual functions. A virtual member function is an ordinary member in that it has a `this` pointer. As static member functions have no `this` pointer, they cannot be declared virtual.

11.1 Static data

Any data member of a class can be declared `static`; be it in the `public` or `private` section of the class interface. Such a data member is created and initialized only once, in contrast to non-static data members which are created again and again for each object of the class.

Static data members are created as soon as the program starts. Even though they're created at the very beginning of a program's execution cycle they are nevertheless true members of their classes.

It is suggested to prefix the names of static member with `s_` so they may easily distinguished (in class member functions) from the class's data members (which should preferably start with `d_`).

Public static data members are global variables. They may be accessed by *all of the program's code*, simply by using their class names, the scope resolution operator and their member names. Example:

```
class Test
{
    static int s_private_int;
```

```

    public:
        static int s_public_int;
};

int main()
{
    Test::s_public_int = 145;    // OK
    Test::s_private_int = 12;    // wrong, don't touch
                                // the private parts
}

```

No executable program will result from the example. It merely illustrates the *interface*, and not the *implementation* of static data members, which is discussed next.

11.1.1 Private static data

To illustrate the use of a static data member which is a private variable in a class, consider the following:

```

class Directory
{
    static char s_path[];

    public:
        // constructors, destructors, etc.
};

```

The data member `s_path[]` is a private static data member. During the program's execution only *one* `Directory::s_path[]` exists, even though multiple objects of the class `Directory` may exist. This data member could be inspected or altered by the constructor, destructor or by any other member function of the class `Directory`.

Since constructors are called for each new object of a class, static data members are not *initialized* by constructors. At most they are *modified*. The reason for this is that static data members exist *before* any constructor of the class has been called. Static data members are initialized when they are defined, outside of any member function, exactly like the initialization of ordinary (non-class) global variables.

The definition and initialization of a static data member usually occurs in one of the source files of the class functions, preferably in a source file dedicated to the definition of static data members, called `data.cc`.

The data member `s_path[]`, used above, could thus be defined and initialized as follows in a file `data.cc`:

```

include "directory.ih"

char Directory::s_path[200] = "/usr/local";

```

In the class interface the static member is actually only *declared*. In its implementation (definition) its type and class name are explicitly mentioned. Note also that the size specification can be left out of the interface, as shown above. However, its size *is* (either explicitly or implicitly) required when it is defined.

Note that *any* source file could contain the definition of the static data members of a class. A separate `data.cc` source file is advised, but the source file containing, e.g., `main()` could be used as well. Of course, any source file defining static data of a class must also include the header file of that class, in order for the static data member to be known to the compiler.

A second example of a useful private static data member is given below. Assume that a class `Graphics` defines the communication of a program with a graphics-capable device (e.g., a VGA screen). The initialization of the device, which in this case would be to switch from text mode to graphics mode, is an action of the constructor and depends on a static flag variable `s_nobjects`. The variable `s_nobjects` simply counts the number of `Graphics` objects which are present at one time. Similarly, the destructor of the class may switch back from graphics mode to text mode when the last `Graphics` object ceases to exist. The class interface for this `Graphics` class might be:

```
class Graphics
{
    static int s_nobjects;           // counts # of objects

    public:
        Graphics();
        ~Graphics();                // other members not shown.
    private:
        void setgraphicsmode();      // switch to graphics mode
        void settextmode();          // switch to text-mode
}
```

The purpose of the variable `s_nobjects` is to count the number of objects existing at a particular moment in time. When the first object is created, the graphics device is initialized. At the destruction of the last `Graphics` object, the switch from graphics mode to text mode is made:

```
int Graphics::s_nobjects = 0;        // the static data member

Graphics::Graphics()
{
    if (!s_nobjects++)
        setgraphicsmode();
}

Graphics::~~Graphics()
{
    if (--s_nobjects)
        settextmode();
}
```

Obviously, when the class `Graphics` would define more than one constructor, each constructor would need to increase the variable `s_nobjects` and would possibly have to initialize the graphics mode.

11.1.2 Public static data

Data members could also be declared in the public section of a class. This, however, is deprecated (as it violates the principle of data hiding). The static data member `s_path[]` (cf. section 11.1) could be declared in the public section of the class definition. This would allow all the program's code to access this variable directly:

```
int main()
{
    getcwd(Directory::s_path, 199);
}
```

A declaration is not a definition. Consequently the variable `s_path` still has to be defined. This implies that some source file still needs to contain `s_path[]` array's definition.

11.1.3 Initializing static const data

Static const data members may be initialized in the class interface if these data members are of integral or built-in primitive data types. So, in the following example the first three static data members can be initialized since `int` and `double` are primitive built-in types and `int` and `enum` types are integral types. The static data member `s_str` cannot be initialized in the class interface since `string` is neither a primitive built-in nor an integral data type:

```
class X
{
    public:
        enum Enum
        {
            FIRST,
        };

        static int const s_x = 34;
        static Enum const s_type = FIRST;

        static double const s_d = 1.2;
        static string const s_str = "a";    // won't compile
};
```

The compiler *may* decide to initialize static const data members as mere constant values, in which they don't have addresses. If the compiler does so, such static const data members behave as though they were values of an enum defined by the class. Consequently they are not variables and so it is not possible to determine their addresses. Note that trying to obtain the address of such a constant value does not create a compilation problem, but it *does* create a linking problem as the static const variable that is initialized as a mere constant value does not exist in addressable memory.

A statement like `int *ip = &X::s_x` may therefore *compile* correctly, but may then fail to *link*. Static variables that are explicitly defined in a source file *can* be linked correctly, though. So, in the following example the address of `X::s_x` cannot be solved by the linker, but the address of `X::s_y` *can* be determined:

```
class X
{
    public:
        static int const s_x = 34;
        static int const s_y;
};

int const X::s_y = 12;

int main()
{
    int const *ip = &X::s_x;    // compiles, but fails to link
    ip = &X::s_y;              // compiles and links correctly
}
```

11.2 Static member functions

In addition to static data members, **C++** allows us to define *static member functions*. Similar to static data that are shared by all objects of the class, static member functions also exist without any associated object of their class.

Static member functions can access all static members of their class, but *also* the members (private or public) of objects of their class *if* they are informed about the existence of these objects (as in the upcoming example). As static member functions are not associated with any object of their class they do not have a `this` pointer. In fact, a static member function is completely comparable to a global function, not associated with any class (i.e., in practice they are. See the next section (11.2.1) for a subtle note). Since static member functions do not require an associated object, static member functions declared in the public section of a class interface may be called without specifying an object of its class. The following example illustrates this characteristic of static member functions:

```
class Directory
{
    string d_currentPath;
    static char s_path[];

public:
    static void setpath(char const *newpath);
    static void preset(Directory &dir, char const *path);
};
inline void Directory::preset(Directory &dir, char const *newpath)
{
    // see the text below
    dir.d_currentPath = newpath; // 1
}

char Directory::s_path[200] = "/usr/local"; // 2

void Directory::setpath(char const *newpath)
{
    if (strlen(newpath) >= 200)
        throw "newpath too long";

    strcpy(s_path, newpath); // 3
}

int main()
{
    Directory dir;

    Directory::setpath("/etc"); // 4
    dir.setpath("/etc"); // 5

    Directory::preset(dir, "/usr/local/bin"); // 6
    dir.preset(dir, "/usr/local/bin"); // 7
}
```

- at 1 a static member function modifies a private data member of an object. However, the object whose member must be modified is given to the member function as a reference parameter.

Note that static member functions can be defined as inline functions.

- at 2 a relatively long array is defined to be able to accomodate long paths. Alternatively, a `string` or a pointer to dynamic memory could be used.
- at 3 a (possibly longer, but not too long) new pathname is stored in the static data member `s_path[]`. Note that only static members are used.
- at 4, `setpath()` is called. It is a static member, so no object is required. But the compiler must know to which class the function belongs, so the class is mentioned using the scope resolution operator.

- at 5, the same is implemented as in 4. Here `dir` is used to tell the compiler that we're talking about a function in the `Directory` class. Static member functions *can* be called as normal member functions, but this does not imply that the static member function receives the object's address as a `this` pointer. Here the member-call syntax is used as an alternative for the classname plus scope resolution operator syntax.
- at 6, `currentPath` is altered. As in 4, the class and the scope resolution operator are used.
- at 7, the same is implemented as in 6. But here `dir` is used to tell the compiler that we're talking about a function in the `Directory` class. Here in particular note that this is *not* using `preset()` as an ordinary member function of `dir`: the function still has no `this`-pointer, so `dir` must be passed as argument to inform the static member function `preset` about the object whose `currentPath` member it should modify.

In the example only public static member functions were used. **C++** also allows the definition of private static member functions. Such functions can only be called by member functions of their class.

11.2.1 Calling conventions

As noted in the previous section, static (public) member functions are comparable to classless functions. However, formally this statement is not true, as the **C++** standard does not prescribe the same calling conventions for static member functions as for classless global functions.

In practice the calling conventions are identical, implying that the address of a static member function could be used as an argument of functions having parameters that are pointers to (global) functions.

If unpleasant surprises must be avoided at all cost, it is suggested to create global classless *wrapper functions* around static member functions that must be used as *call back* functions for other functions.

Recognizing that the traditional situations in which call back functions are used in **C** are tackled in **C++** using template algorithms (cf. chapter 19), let's assume that we have a class `Person` having data members representing the person's name, address, phone and mass. Furthermore, assume we want to sort an array of pointers to `Person` objects, by comparing the `Person` objects these pointers point to. Keeping things simple, we assume that the following public static member exists:

```
int Person::compare(Person const *const *p1, Person const *const *p2);
```

A useful characteristic of this member is that it may directly inspect the required data members of the two `Person` objects passed to the member function using double pointers.

Most compilers will allow us to pass this function's address as the address of the comparison function for the standard **C** `qsort()` function. E.g.,

```
qsort
(
    personArray, nPersons, sizeof(Person *),
    reinterpret_cast<int(*)>(const void *, const void *)>(Person::compare)
);
```

However, if the compiler uses different calling conventions for static members and for classless functions, this might not work. In such a case, a classless wrapper function like the following may be used profitably:

```
int compareWrapper(void const *p1, void const *p2)
{
    return
        Person::compare
        (
```

```
        reinterpret_cast<Person const *const *>(p1),  
        reinterpret_cast<Person const *const *>(p2)  
    );  
}
```

resulting in the following call of the `qsort()` function:

```
qsort(personArray, nPersons, sizeof(Person *), compareWrapper);
```

Note:

- The wrapper function takes care of any mismatch in the calling conventions of static member functions and classless functions;
- The wrapper function handles the required type casts;
- The wrapper function might perform small additional services (like dereferencing pointers if the static member function expects references to `Person` objects rather than double pointers);
- As an aside: in **C++** programs functions like `qsort()`, requiring the specification of call back functions are seldom used. Instead using existing generic template algorithms is preferred (cf. chapter [19](#)).

Chapter 12

Abstract Containers

C++ offers several predefined datatypes, all part of the Standard Template Library, which can be used to implement solutions to frequently occurring problems. The datatypes discussed in this chapter are all *containers*: you can put stuff inside them, and you can retrieve the stored information from them.

The interesting part is that the kind of data that can be stored inside these containers has been left unspecified at the time the containers were constructed. That's why they are spoken of as *abstract* containers.

Abstract containers rely heavily on *templates*, covered in chapter 20 and beyond. To use abstract containers, only a minimal grasp of the template concept is required. In **C++** a template is in fact a recipe for constructing a function or a complete class. The recipe tries to abstract the functionality of the class or function as much as possible from the data on which the class or function operates. As the data types on which the templates operate were not known when the template was implemented, the datatypes are either inferred from the context in which a function template is used, or they are mentioned explicitly when a class template is used (the term that's used here is *instantiated*). In situations where the types are explicitly mentioned, the *angle bracket notation* is used to indicate which data types are required. For example, below (in section 12.2) we'll encounter the `pair` container, which requires the explicit mentioning of two data types. Here is a `pair` object containing both an `int` and a `string`:

```
pair<int, string> myPair;
```

The object `myPair` is defined as an object holding both an `int` and a `string`.

The angle bracket notation is used intensively in the upcoming discussion of abstract containers. Actually, understanding this part of templates is the only real requirement for using abstract containers. Now that we've introduced this notation, we can postpone the more thorough discussion of templates to chapter 20, and concentrate on their use in this chapter.

Most of the abstract containers are *sequential* containers: they contain data that can be stored and retrieved in some sequential way. Examples are the `vector`, implementing an extendable array; the `list`, implementing a datastructure that allows for the easy insertion or deletion of data; the `queue`, also called a *FIFO* (first in, first out) structure, in which the first element that is entered will be the first element that will be retrieved; and the `stack`, which is a *first in, last out* (FILO or LIFO) structure.

In addition to sequential containers several special containers are available. The `pair` is a basic container in which a pair of values (of types that are left open for further specification) can be stored, like two strings, two ints, a string and a double, etc.. Pairs are often used to return data elements that naturally come in pairs. For example, the `map` is an abstract container storing keys and their associated values. Elements of these maps are returned as `pairs`.

A variant of the `pair` is the `complex` container, implementing operations that are defined on *complex numbers*.

All abstract containers described in this chapter as well as the `string` and stream datatypes (cf. chap-

ters 5 and 6) are part of the Standard Template Library.

All containers support the following operators:

- The overloaded assignment operator, so we can assign two containers of the same types to each other.
- Tests for equality: `==` and `!=` The equality operator applied to two containers returns `true` if the two containers have the same number of elements, which are pairwise equal according to the equality operator of the contained data type. The inequality operator does the opposite.
- Ordering operators: `<`, `<=`, `>` and `>=`. The `<` operator returns `true` if each element in the left-hand side container is less than each corresponding element in the right-hand side container. Additional elements in either the left-hand side container or the right-hand side container are ignored.

```
container left;
container right;

left = {0, 2, 4};
right = {1, 3};           // left < right

right = {1, 3, 6, 1, 2};  // left < right
```

Note that before a user-defined type (usually a `class`-type) can be stored in a container, the user-defined type should at least support:

- A default-value (e.g., a default constructor)
- The equality operator (`==`)
- The less-than operator (`<`)

With the advent of the C++0x standard sequential containers can also be initialized using *initializer lists*.

Most containers (exceptions are the stack (section 12.3.10), `priority_queue` (section 12.3.4), and `queue` (section 12.3.3) containers) support members to determine their maximum sizes (through their member function `max_size`).

Closely linked to the standard template library are the *generic algorithms*. These algorithms may be used to perform frequently occurring tasks or more complex tasks than is possible with the containers themselves, like counting, filling, merging, filtering etc.. An overview of generic algorithms and their applications is given in chapter 19. Generic algorithms usually rely on the availability of *iterators*, representing begin and end-points for processing data stored inside containers. The abstract containers usually support constructors and members expecting iterators, and they often have members returning iterators (comparable to the `string::begin` and `string::end` members). In this chapter the iterator concept is not further investigated. Refer to chapter 18 for this.

The url <http://www.sgi.com/Technology/STL> is worth visiting as it offers more extensive coverage of abstract containers and the standard template library than can be provided by the C++ annotations.

Containers often collect data during their lifetimes. When a container goes out of scope, its destructor tries to destroy its data elements. This only succeeds if the data elements themselves are stored inside the container. If the data elements of containers are pointers to dynamically allocated memory then the data pointed to by these pointers will not be destroyed, resulting in a memory leak. A consequence of this scheme is that the data stored in a container should often be considered the ‘property’ of the container: the container should be able to destroy its data elements when the container’s destructor is called. So, normally containers should not contain pointers to data. Also, a container should not be required to contain `const` data, as `const` data prevent the use of many of the container’s members, like the assignment operator.

12.1 Notations used in this chapter

In this chapter about containers, the following notational conventions are used:

- Containers live in the standard namespace. In code examples this will be clearly visible, but in the text `std::` is usually omitted.
- A container without angle brackets represents any container of that type. Mentally add the required type in angle bracket notation. E.g., `pair` may represent `pair<string, int>`.
- The notation `Type` represents the generic type. `Type` could be `int`, `string`, etc.
- Identifiers `object` and `container` represent objects of the container type under discussion.
- The identifier `value` represents a value of the type that is stored in the container.
- Simple, one-letter identifiers, like `n` represent unsigned values.
- Longer identifiers represent iterators. Examples are `pos`, `from`, `beyond`

Some containers, e.g., the `map` container, contain pairs of values, usually called ‘keys’ and ‘values’. For such containers the following notational convention is used in addition:

- The identifier `key` indicates a value of the used key-type
- The identifier `keyvalue` indicates a value of the ‘`value_type`’ used with the particular container.

12.2 The ‘pair’ container

The `pair` container is a rather basic container. It is used to store two elements, called `first` and `second`, and that’s about it. Before using `pair` containers the header file `<utility>` must have been included.

The `pair`’s data types are specified when the `pair` object is defined (or declared) using the template’s angle bracket notation (cf. chapter 20). Examples:

```
pair<string, string> piper("PA28", "PH-ANI");
pair<string, string> cessna("C172", "PH-ANG");
```

here, the variables `piper` and `cessna` are defined as `pair` variables containing two strings. Both strings can be retrieved using the `first` and `second` fields of the `pair` type:

```
cout << piper.first << '\n' <<          // shows 'PA28'
      cessna.second << '\n';           // shows 'PH-ANG'
```

The `first` and `second` members can also be used to reassign values:

```
cessna.first = "C152";
cessna.second = "PH-ANW";
```

If a `pair` object must be completely reassigned, an *anonymous* `pair` object can be used as the right-hand operand of the assignment. An anonymous variable defines a temporary variable (which receives no name) solely for the purpose of (re)assigning another variable of the same type. Its generic form is

```
type(initializer list)
```

Note that when a `pair` object is used the type specification is not completed by just mentioning the containername `pair`. It also requires the specification of the data types which are stored within the `pair`. For this the (template) angle bracket notation is used again. E.g., the reassignment of the `cessna` `pair` variable could have been accomplished as follows:

```
cessna = pair<string, string>("C152", "PH-ANW");
```

In cases like these, the type specification can become quite elaborate, which has caused a revival of interest in the possibilities offered by the `typedef` keyword. If many `pair<type1, type2>` clauses are used in a source, the typing effort may be reduced and readability might be improved by first defining a name for the clause, and then using the defined name later. E.g.,

```
typedef pair<string, string> pairStrStr;

cessna = pairStrStr("C152", "PH-ANW");
```

Apart from this (and the basic set of operations (assignment and comparisons)) the `pair` offers no further functionality. It is, however, a basic ingredient of the upcoming abstract containers `map`, `multimap` and `hash_map`.

The C++0x standard offers a *generalized pair* container: the *tuple*, covered in section [21.5.5](#).

12.3 Sequential Containers

12.3.1 The ‘vector’ container

The `vector` class implements an expandable array. Before using the `vector` container the `<vector>` header file must have been included.

The following constructors, operators, and member functions are available:

- Constructors:

- A vector may be constructed empty:

```
vector<string> object;
```

Note the specification of the data type to be stored in the `vector`: the data type is given between angle brackets, just after the ‘vector’ container name. This is common practice with containers.

- A vector may be initialized to a certain number of elements. One of the nicer characteristics of vectors (and other containers) is that it initializes its data elements to the data type’s default value. The data type’s *default constructor* is used for this initialization. With non-class data types the value 0 is used. So, for the `int` vector we know its initial values are zero. With the advent of the C++0x standard (starting g++ release 4.4) it has also become possible to use initializer lists. Some examples:

```
vector<string> object(5, string("Hello")); // initialize to 5 Hello's,
vector<string> container(10);              // and to 10 empty strings
vector<string> names = {"george", "frank", "tony", "karel"}; // g++ 4.4
```

- A vector may be initialized using iterators. To initialize a vector with elements 5 until 10 (including the last one) of an existing `vector<string>` the following construction may be used:

```
extern vector<string> container;
vector<string> object(&container[5], &container[11]);
```


Note here that the last element pointed to by the second iterator (`&container[11]`) is *not* stored in `object`. This is a simple example of the use of *iterators*, in which the range of values that is used starts at the first value, and includes all elements up to but not including the element to which the second iterator refers. The standard notation for this is `[begin, end)`.

- A vector may be initialized using a copy constructor:

```
extern vector<string> container;
vector<string> object(container);
```

- In addition to the standard operators for containers, the `vector` supports the index operator, which may be used to retrieve or reassign individual elements of the vector. Note that the elements which are indexed must exist. For example, having defined an empty vector a statement like `ivect[0] = 18` produces an error, as the vector is empty. So, the vector is *not* automatically expanded, and it *does* respect its array bounds. In this case the vector should be resized first, or `ivect.push_back(18)` should be used (see below).

- The vector class offers the following member functions:

- `Type &back()`:

this member returns a reference to the last element in the vector. It is the responsibility of the programmer to use the member only if the vector is not empty.

- `vector::iterator begin()`:

this member returns an iterator pointing to the first element in the vector, returning `end` if the vector is empty.

- `size_t capacity()`:

Number of elements for which memory has been allocated. It returns at least the value returned by `size`

- `void clear()`:

this member erases all the vector's elements.

- `bool empty()`

this member returns `true` if the vector contains no elements.

- `vector::iterator end()`:

this member returns an iterator pointing beyond the last element in the vector.

- `vector::iterator erase()`:

this member can be used to erase a specific range of elements in the vector:

* `erase(pos)` erases the element pointed to by the iterator `pos`. The iterator `++pos` is returned.

* `erase(first, beyond)` erases elements indicated by the iterator range `[first, beyond)`, returning `beyond`.

- `Type &front()`:

this member returns a reference to the first element in the vector. It is the responsibility of the programmer to use the member only if the vector is not empty.

- ... `insert()`:

elements may be inserted starting at a certain position. The return value depends on the version of `insert()` that is called:

* `vector::iterator insert(pos)` inserts a default value of type `Type` at `pos`, `pos` is returned.

* `vector::iterator insert(pos, value)` inserts `value` at `pos`, `pos` is returned.

* `void insert(pos, first, beyond)` inserts the elements in the iterator range `[first, beyond)`.

* `void insert(pos, n, value)` inserts `n` elements having value `value` at position `pos`.

- `void pop_back()`:
this member removes the last element from the vector. With an empty vector nothing happens.
- `void push_back(value)`:
this member adds value to the end of the vector.
- `void reserve(size_t request)`:
if request is less than or equal to capacity, this call has no effect. Otherwise, it is a request to allocate additional memory. If the call is successful, then capacity returns a value of at least request. Otherwise, capacity is unchanged. In either case, size's return value won't change, until a function like `resize` is called, actually changing the number of accessible elements.
- `void resize()`:
this member can be used to alter the number of elements that are currently stored in the vector:

* `resize(n, value)` may be used to resize the vector to a size of n. Value is optional. If the vector is expanded and value is not provided, the additional elements are initialized to the default value of the used data type, otherwise value is used to initialize extra elements.
- `vector::reverse_iterator rbegin()`:
this member returns an iterator pointing to the last element in the vector.
- `vector::reverse_iterator rend()`:
this member returns an iterator pointing before the first element in the vector.
- `size_t size()`
this member returns the number of elements in the vector.
- `void swap()`
this member can be used to swap two vectors using identical data types. Example:


```
#include <iostream>
#include <vector>
using namespace std;

int main()
{
    vector<int> v1(7);
    vector<int> v2(10);

    v1.swap(v2);
    cout << v1.size() << " " << v2.size() << '\n';
}
/*
    Produced output:
10 7
*/
```

12.3.2 The 'list' container

The `list` container implements a list data structure. Before using a `list` container the header file `<list>` must have been included.

The organization of a `list` is shown in figure 12.1. Figure 12.1 shows that a list consists of separate list-elements, connected by pointers. The list can be traversed in two directions: starting at *Front* the list may be traversed from left to right, until the 0-pointer is reached at the end of the rightmost list-element. The list can also be traversed from right to left: starting at *Back*, the list is traversed from right to left, until eventually the 0-pointer emanating from the leftmost list-element is reached.




Figure 12.1: A list data-structure

As a subtlety note that the representation given in figure 12.1 is not necessarily used in actual implementations of the list. For example, consider the following little program:

```
int main()
{
    list<int> l;
    cout << "size: " << l.size() << ", first element: " <<
        l.front() << '\n';
}
```

When this program is run it might actually produce the output:

```
size: 0, first element: 0
```

Its front element can even be assigned a value. In this case the implementor has chosen to provide the list with a hidden element. The list actually is a *circular* list, where the hidden element serves as terminating element, replacing the 0-pointers in figure 12.1. As noted, this is a subtlety, which doesn't affect the conceptual notion of a list as a data structure ending in 0-pointers. Note also that it is well known that various implementations of list-structures are possible (cf. Aho, A.V., Hopcroft J.E. and Ullman, J.D., (1983) *Data Structures and Algorithms* (Addison-Wesley)).

Both lists and vectors are often appropriate data structures in situations where an unknown number of data elements must be stored. However, there are some rules of thumb to follow when selecting the appropriate data structure.

- When most accesses are random, a vector is the preferred data structure. Example: in a program counting character frequencies in a textfile, a `vector<int> frequencies(256)` is the datastructure of choice, as the values of the received characters can be used as indices into the frequencies vector.
- The previous example illustrates a second rule of thumb, also favoring the vector: if the number of elements is known in advance (and does not notably change during the lifetime of the program), the vector is also preferred over the list.
- In cases where insertions or deletions prevail and the data structure is large the list is generally preferred.

At present lists aren't as useful anymore as they used to be (when computers were much slower and more memory-constrained). Except maybe for some rare cases, a vector should be the preferred container; even when implementing algorithms traditionally using lists.

Other considerations related to the choice between lists and vectors should also be given some thought. Although it is true that the vector is able to grow dynamically, the dynamic growth requires data-copying. Clearly, copying a million large data structures takes a considerable amount of time, even on fast computers. On the other hand, inserting a large number of elements in a list doesn't require us to copy non-involved data. Inserting a new element in a list merely requires us to juggle some pointers. In figure 12.2 this is shown: a new element is inserted between the second and third element, creating a new list of four elements. Removing an element from a list is also fairly easy. Starting again from the




Figure 12.2: Adding a new element to a list




Figure 12.3: Removing an element from a list

situation shown in figure 12.1, figure 12.3 shows what happens if element two is removed from our list. Again: only pointers need to be juggled. In this case it's even simpler than adding an element: only two pointers need to be rerouted. To summarize the comparison between lists and vectors: it's probably best to conclude that there is no clear-cut answer to the question what data structure to prefer. There are rules of thumb, which may be adhered to. But if worse comes to worst, a profiler may be required to find out what's best.

The `list` container offers the following constructors, operators, and member functions are available:

- Constructors:

- A `list` may be constructed empty:

```
list<string> object;
```

As with the `vector`, it is an error to refer to an element of an empty list.

- A `list` may be initialized to a certain number of elements. By default, if the initialization value is not explicitly mentioned, the default value or default constructor for the actual data type is used. For example:

```
list<string> object(5, string("Hello")); // initialize to 5 Hello's
list<string> container(10);               // and to 10 empty strings
```

- A `list` may be initialized using a two iterators. To initialize a list with elements 5 until 10 (including the last one) of a `vector<string>` the following construction may be used:

```
extern vector<string> container;
list<string> object(&container[5], &container[11]);
```

- A `list` may be initialized using a copy constructor:

```
extern list<string> container;
list<string> object(container);
```

- The `list` does not offer specialized operators, apart from the standard operators for containers.

- The following member functions are available:

- `Type &back()`:
this member returns a reference to the last element in the list. It is the responsibility of the programmer to use this member only if the list is not empty.
- `list::iterator begin()`:
this member returns an iterator pointing to the first element in the list, returning end if the list is empty.
- `void clear()`:
this member erases all elements from the list.
- `bool empty()`:
this member returns true if the list contains no elements.
- `list::iterator end()`:
this member returns an iterator pointing beyond the last element in the list.
- `list::iterator erase()`:
this member can be used to erase a specific range of elements in the list:
 - * `erase(pos)` erases the element pointed to by `pos`. The iterator `++pos` is returned.
 - * `erase(first, beyond)` erases elements indicated by the iterator range `[first, beyond)`. `Beyond` is returned.
- `Type &front()`:
this member returns a reference to the first element in the list. It is the responsibility of the programmer to use this member only if the list is not empty.
- `... insert()`:
this member can be used to insert elements into the list. The return value depends on the version of `insert` that is called:
 - * `list::iterator insert(pos)` inserts a default value of type `Type` at `pos`, `pos` is returned.
 - * `list::iterator insert(pos, value)` inserts `value` at `pos`, `pos` is returned.
 - * `void insert(pos, first, beyond)` inserts the elements in the iterator range `[first, beyond)`.
 - * `void insert(pos, n, value)` inserts `n` elements having value `value` at position `pos`.
- `void merge(list<Type> other)`:
this member function assumes that the current and other lists are sorted (see below, the member `sort`), and will, based on that assumption, insert the elements of `other` into the current list in such a way that the modified list remains sorted. If both list are not sorted, the resulting list will be ordered 'as much as possible', given the initial ordering of the elements in the two lists. `list<Type>::merge` uses `Type::operator<` to sort the data in the list, which operator must therefore be available. The next example illustrates the use of the `merge` member: the list 'object' is not sorted, so the resulting list is ordered 'as much as possible'.

```
#include <iostream>
#include <string>
#include <list>
using namespace std;

void showlist(list<string> &target)
{
    for
    (
        list<string>::iterator from = target.begin();
        from != target.end();
```

```

        ++from
    )
    cout << *from << " ";

    cout << '\n';
}

int main()
{
    list<string> first;
    list<string> second;

    first.push_back(string("alpha"));
    first.push_back(string("bravo"));
    first.push_back(string("golf"));
    first.push_back(string("quebec"));

    second.push_back(string("oscar"));
    second.push_back(string("mike"));
    second.push_back(string("november"));
    second.push_back(string("zulu"));

    first.merge(second);
    showlist(first);
}

```

A subtlety is that `merge` doesn't alter the list if the list itself is used as argument: `object.merge(object)` won't change the list 'object'.

- `void pop_back()`:
this member removes the last element from the list. With an empty list nothing happens.
- `void pop_front()`:
this member removes the first element from the list. With an empty list nothing happens.
- `void push_back(value)`:
this member adds `value` to the end of the list.
- `void push_front(value)`:
this member adds `value` before the first element of the list.
- `void resize()`:
this member can be used to alter the number of elements that are currently stored in the list:
 - * `resize(n, value)` may be used to resize the list to a size of `n`. `Value` is optional. If the list is expanded and `value` is not provided, the extra elements are initialized to the default value of the used data type, otherwise `value` is used to initialize extra elements.
- `list::reverse_iterator rbegin()`:
this member returns an iterator pointing to the last element in the list.
- `void remove(value)`:
this member removes all occurrences of `value` from the list. In the following example, the two strings 'Hello' are removed from the list object:

```

#include <iostream>
#include <string>
#include <list>
using namespace std;

int main()

```

```

    {
        list<string> object;

        object.push_back(string("Hello"));
        object.push_back(string("World"));
        object.push_back(string("Hello"));
        object.push_back(string("World"));

        object.remove(string("Hello"));

        while (object.size())
        {
            cout << object.front() << '\n';
            object.pop_front();
        }
    }
    /*
        Generated output:
        World
        World
    */
- list::reverse_iterator rend():
    this member returns an iterator pointing before the first element in the list.
- size_t size():
    this member returns the number of elements in the list.
- void reverse():
    this member reverses the order of the elements in the list. The element back will
    become front and vice versa.
- void sort():
    this member will sort the list. Once the list has been sorted, An example of its use is
    given at the description of the unique member function below. list<Type>::sort
    uses Type::operator< to sort the data in the list, which operator must therefore
    be available.
- void splice(pos, object):
    this member function transfers the contents of object to the current list, starting
    the insertion at the iterator position pos of the object using the splice member.
    Following splice, object is empty. For example:
#include <iostream>
#include <string>
#include <list>
using namespace std;

int main()
{
    list<string> object;

    object.push_front(string("Hello"));
    object.push_back(string("World"));

    list<string> argument(object);

    object.splice(++object.begin(), argument);

    cout << "Object contains " << object.size() << " elements, " <<
        "Argument contains " << argument.size() <<
        " elements,\n";
}

```

```

while (object.size())
{
    cout << object.front() << '\n';
    object.pop_front();
}

```

Alternatively, argument may be followed by an iterator of argument, indicating the first element of argument that should be spliced, or by two iterators begin and end defining the iterator-range [begin, end) on argument that should be spliced into object.

- void swap():

this member can be used to swap two lists using identical data types.

- void unique():

operating on a sorted list, this member function will remove all consecutively identical elements from the list. `list<Type>::unique` uses `Type::operator==` to identify identical data elements, which operator must therefore be available. Here's an example removing all multiply occurring words from the list:

```

#include <iostream>
#include <string>
#include <list>
using namespace std;

// see the merge() example
void showlist(list<string> &target);
void showlist(list<string> &target)
{
    for
    (
        list<string>::iterator from = target.begin();
        from != target.end();
        ++from
    )
        cout << *from << " ";

    cout << '\n';
}

int main()
{
    string
        array[] =
        {
            "charley",
            "alpha",
            "bravo",
            "alpha"
        };

    list<string>
        target
        (
            array, array + sizeof(array)
            / sizeof(string)
        );

    cout << "Initially we have:\n";
    showlist(target);
}

```





Figure 12.4: A queue data-structure

```

target.sort();
cout << "After sort() we have:\n";
showlist(target);

target.unique();
cout << "After unique() we have:\n";
showlist(target);
}
/*
Generated output:

Initially we have:
charley alpha bravo alpha
After sort() we have:
alpha alpha bravo charley
After unique() we have:
alpha bravo charley
*/

```

12.3.3 The ‘queue’ container

The queue class implements a queue data structure. Before using a queue container the header file `<queue>` must have been included.

A queue is depicted in figure 12.4. In figure 12.4 it is shown that a queue has one point (the *back*) where items can be added to the queue, and one point (the *front*) where items can be removed (read) from the queue. A queue is therefore also called a *FIFO* data structure, for *first in, first out*. It is most often used in situations where events should be handled in the same order as they are generated.

The following constructors, operators, and member functions are available for the queue container:

- Constructors:

- A queue may be constructed empty:

```
queue<string> object;
```

As with the vector, it is an error to refer to an element of an empty queue.

- A queue may be initialized using a copy constructor:

```
extern queue<string> container;
queue<string> object(container);
```

- The queue container only supports the basic container operators.

- The following member functions are available for queues:

- Type `&back()`:

this member returns a reference to the last element in the queue. It is the responsibility of the programmer to use the member only if the queue is not empty.

- `bool empty()`:
this member returns `true` if the queue contains no elements.
- `Type &front()`:
this member returns a reference to the first element in the queue. It is the responsibility of the programmer to use the member only if the queue is not empty.
- `void push(value)`:
this member adds `value` to the back of the queue.
- `void pop()`:
this member removes the element at the front of the queue. Note that the element is *not* returned by this member. Nothing happens if the member is called for an empty queue. One might wonder why `pop` returns `void`, instead of a value of type `Type` (cf. `front`). One reason is found in the principles of good software design: functions should perform one task. Combining the removal and return of the removed element breaks this principle. Moreover, when this principle is abandoned `pop`'s implementation will always be flawed. Consider the prototypical implementation of a `pop` member that is supposed to return the just popped value:


```
Type queue::pop()
{
    Type ret(top());
    erase_top();
    return ret;
}
```

The venom, as usual, is in the tail: since `queue` has no control over `Type`'s behavior the final statement (`return ret`) might throw. By that time the queue's topmost element has already been removed from the queue and so it is lost. Thus, a `Type` returning `pop` member cannot offer the *strong guarantee* and consequently `pop` should not return the former `top` element. Because of all this, we must first use `front`, and then `pop` to obtain and remove the queue's front element.
- `size_t size()`:
this member returns the number of elements in the queue.

Note that the queue does not support iterators or a subscript operator. The only elements that can be accessed are its front and back element. A queue can be emptied by:

- repeatedly removing its front element;
- assigning an empty queue using the same data type to it;
- having its destructor called.

12.3.4 The 'priority_queue' container

The `priority_queue` class implements a priority queue data structure. Before using a `priority_queue` container the `<queue>` header file must have been included.

A priority queue is identical to a queue, but allows the entry of data elements according to *priority rules*. A real-life priority queue is found, e.g., at airport check-in terminals. At a terminal the passengers normally stand in line to wait for their turn to check in, but late passengers are usually allowed to jump the queue: they receive a higher priority than other passengers.

The priority queue uses `operator<` of the data type stored in the priority queue to decide about the priority of the data elements. The *smaller* the value, the *lower* the priority. So, the priority queue *could* be used to sort values while they arrive. A simple example of such a priority queue application is the following program: it reads words from `cin` and writes a sorted list of words to `cout`:

```
#include <iostream>
```

```

#include <string>
#include <queue>
using namespace std;

int main()
{
    priority_queue<string> q;
    string word;

    while (cin >> word)
        q.push(word);

    while (q.size())
    {
        cout << q.top() << '\n';
        q.pop();
    }
}

```

Unfortunately, the words are listed in reversed order: because of the underlying <-operator the words appearing later in the ASCII-sequence appear first in the priority queue. A solution to that problem is to define a *wrapper class* around the string datatype, reversing string's operator<. Here is the modified program:

```

#include <iostream>
#include <string>
#include <queue>

class Text
{
    std::string d_s;

public:
    Text(std::string const &str)
    :
        d_s(str)
    {}
    operator std::string const &() const
    {
        return d_s;
    }
    bool operator<(Text const &right) const
    {
        return d_s > right.d_s;
    }
};

using namespace std;

int main()
{
    priority_queue<Text> q;
    string word;

    while (cin >> word)
        q.push(word);

    while (q.size())
    {

```

```

        word = q.top();
        cout << word << '\n';
        q.pop();
    }
}

```

Other possibilities to achieve the same exist. One would be to store the contents of the priority queue in, e.g., a vector, from which the elements can be read in reversed order.

The following constructors, operators, and member functions are available for the `priority_queue` container:

- Constructors:

- A `priority_queue` may be constructed empty:

```
priority_queue<string> object;
```

As with the vector, it is an error to refer to an element of an empty priority queue.

- A priority queue may be initialized using a copy constructor:

```
extern priority_queue<string> container;
priority_queue<string> object(container);
```

- The `priority_queue` only supports the basic operators of containers.

- The following member functions are available for priority queues:

- `bool empty()`:

this member returns `true` if the priority queue contains no elements.

- `void push(value)`:

this member inserts `value` at the appropriate position in the priority queue.

- `void pop()`:

this member removes the element at the top of the priority queue. Note that the element is *not* returned by this member. Nothing happens if this member is called for an empty priority queue. See section 12.3.3 for a discussion about the reason why `pop` has return type `void`.

- `size_t size()`:

this member returns the number of elements in the priority queue.

- `Type &top()`:

this member returns a reference to the first element of the priority queue. It is the responsibility of the programmer to use the member only if the priority queue is not empty.

Note that the priority queue does not support iterators or a subscript operator. The only element that can be accessed is its top element. A priority queue can be emptied by:

- repeatedly removing its top element;
- assigning an empty queue using the same data type to it;
- having its destructor called.

12.3.5 The ‘deque’ container

The deque (pronounce: ‘deck’) class implements a doubly ended queue data structure (deque). Before using a deque container the header file `<deque>` must have been included.

A deque is comparable to a queue, but it allows for reading and writing at both ends. Actually, the deque data type supports a lot more functionality than the queue, as will be clear from the following overview of available member functions. A deque is a combination of a vector and two queues, operating at both ends of the vector. In situations where random insertions and the addition and/or removal of elements at one or both sides of the vector occurs frequently using a deque should be considered.

The following constructors, operators, and member functions are available for deques:

- Constructors:

- A deque may be constructed empty:

```
deque<string>
    object;
```

As with the vector, it is an error to refer to an element of an empty deque.

- A deque may be initialized to a certain number of elements. By default, if the initialization value is not explicitly mentioned, the default value or default constructor for the actual data type is used. For example:

```
deque<string> object(5, string("Hello")), // initialize to 5 Hello's
deque<string> container(10);               // and to 10 empty strings
```

- A deque may be initialized using two iterators. To initialize a deque with elements 5 until 10 (including the last one) of a vector<string> the following construction may be used:

```
extern vector<string> container;
deque<string> object(&container[5], &container[11]);
```

- A deque may be initialized using a copy constructor:

```
extern deque<string> container;
deque<string> object(container);
```

- In addition to the standard operators for containers, the deque supports the index operator, which may be used to retrieve or reassign random elements of the deque. Note that the indexed elements must exist.

- The following member functions are available for deques:

- Type `&back()`:

this member returns a reference to the last element in the deque. It is the responsibility of the programmer to use the member only if the deque is not empty.

- `deque::iterator begin()`:

this member returns an iterator pointing to the first element in the deque.

- `void clear()`:

this member erases all elements in the deque.

- `bool empty()`:

this member returns true if the deque contains no elements.

- `deque::iterator end()`:

this member returns an iterator pointing beyond the last element in the deque.

- `deque::iterator erase()`:

the member can be used to erase a specific range of elements in the deque:

* `erase(pos)` erases the element pointed to by `pos`. The iterator `++pos` is returned.

- * `erase(first, beyond)` erases elements indicated by the iterator range `[first, beyond)`. `Beyond` is returned.
- `Type &front()`:
this member returns a reference to the first element in the deque. It is the responsibility of the programmer to use the member only if the deque is not empty.
- ... `insert()`:
this member can be used to insert elements starting at a certain position. The return value depends on the version of `insert` that is called:
 - * `deque::iterator insert(pos)` inserts a default value of type `Type` at `pos`, `pos` is returned.
 - * `deque::iterator insert(pos, value)` inserts `value` at `pos`, `pos` is returned.
 - * `void insert(pos, first, beyond)` inserts the elements in the iterator range `[first, beyond)`.
 - * `void insert(pos, n, value)` inserts `n` elements having value `value` starting at iterator position `pos`.
- `void pop_back()`:
this member removes the last element from the deque. With an empty deque nothing happens.
- `void pop_front()`:
this member removes the first element from the deque. With an empty deque nothing happens.
- `void push_back(value)`:
this member adds `value` to the end of the deque.
- `void push_front(value)`:
this member adds `value` before the first element of the deque.
- `void resize()`:
this member can be used to alter the number of elements that are currently stored in the deque:
 - * `resize(n, value)` may be used to resize the deque to a size of `n`. `Value` is optional. If the deque is expanded and `value` is not provided, the additional elements are initialized to the default value of the used data type, otherwise `value` is used to initialize extra elements.
- `deque::reverse_iterator rbegin()`:
this member returns an iterator pointing to the last element in the deque.
- `deque::reverse_iterator rend()`:
this member returns an iterator pointing before the first element in the deque.
- `size_t size()`:
this member returns the number of elements in the deque.
- `void swap(argument)`:
this member can be used to swap two deques using identical data types.

12.3.6 The ‘map’ container

The `map` class offers a (sorted) associative array. Before using a `map` container the `<map>` header file must have been included.

A `map` is filled with *key/value* pairs, which may be of any container-accepted type. Since types are associated with both the key and the value, we must specify *two types* in the angle bracket notation, comparable to the specification we’ve seen with the `pair` container (cf. section 12.2). The first type represents the key’s type, the second type represents the value’s type. For example, a `map` in which the key is a `string` and the value is a `double` can be defined as follows:

```
map<string, double> object;
```

The *key* is used to access its associated information. That information is called the *value*. For example, a phone book uses the names of people as the key, and uses the telephone number and maybe other information (e.g., the zip-code, the address, the profession) as value. Since a map sorts its keys, the key's `operator<` must be defined, and it must be sensible to use it. For example, it is generally a bad idea to use pointers for keys, as sorting pointers is something different than sorting the values pointed at by those pointers.

The two fundamental operations on maps are the storage of *Key/Value* combinations, and the retrieval of values, given their keys. The index operator using a key as the index, can be used for both. If the index operator is used as *lvalue*, insertion will be performed. If it is used as *rvalue*, the key's associated value is retrieved. Each key can be stored only once in a map. If the same key is entered again, the new value replaces the formerly stored value, which is lost.

A specific key/value combination can implicitly or explicitly be inserted into a map. If explicit insertion is required, the key/value combination must be constructed first. For this, every map defines a `value_type` which may be used to create values that can be stored in the map. For example, a value for a `map<string, int>` can be constructed as follows:

```
map<string, int>::value_type siValue("Hello", 1);
```

The `value_type` is associated with the `map<string, int>`: the type of the key is `string`, the type of the value is `int`. Anonymous `value_type` objects are also often used. E.g.,

```
map<string, int>::value_type("Hello", 1);
```

Instead of using the line `map<string, int>::value_type(...)` over and over again, a typedef is frequently used to reduce typing and to improve readability:

```
typedef map<string, int>::value_type StringIntValue
```

Using this typedef, values for the `map<string, int>` may now be constructed using:

```
StringIntValue("Hello", 1);
```

Alternatively, `pairs` may be used to represent key/value combinations used by maps:

```
pair<string, int>("Hello", 1);
```

The following constructors, operators, and member functions are available for the map container:

- Constructors:

- A map may be constructed empty:

```
map<string, int> object;
```

Note that the values stored in maps may be containers themselves. For example, the following defines a map in which the value is a `pair`: a container nested under another container:

```
map<string, pair<string, string>> object;
```

Note the use of the two consecutive closing angle brackets. Before the advent of the C++0x standard consecutive closing brackets in container type specifications (and generally: in the context of template type specifications) resulted in a compilation error, as the immediate concatenation of the two closing angle brackets would be interpreted by the compiler as a right shift operator (`operator>>`), which is not what we want here. In compilers supporting the C++0x standard this construction is accepted. Compilers not yet implementing this feature require a separating blank between two consecutive closing angle brackets.

- A map may be initialized using two iterators. The iterators may either point to `value_type` values for the map to be constructed, or to plain pair objects. If pairs are used, their first element represents the type of the keys, and their second element represents the type of the values. Example:

```
pair<string, int> pa[] =
{
    pair<string,int>("one", 1),
    pair<string,int>("two", 2),
    pair<string,int>("three", 3),
};

map<string, int> object(&pa[0], &pa[3]);
```

In this example, `map<string, int>::value_type` could have been written instead of `pair<string, int>` as well.

If `begin` represents the first iterator that us used to construct a map and if `end` represents the second iterator, `[begin, end)` will be used to initialize the map. Maybe contrary to intuition, the map constructor will only enter *new* keys. If the last element of `pa` would have been "one", 3, only *two* elements would have entered the map: "one", 1 and "two", 2. The value "one", 3 would silently have been ignored.

The map receives its own copies of the data to which the iterators point as illustrated by the following example:

```
#include <iostream>
#include <map>
using namespace std;

class MyClass
{
public:
    MyClass()
    {
        cout << "MyClass constructor\n";
    }
    MyClass(const MyClass &other)
    {
        cout << "MyClass copy constructor\n";
    }
    ~MyClass()
    {
        cout << "MyClass destructor\n";
    }
};

int main()
{
    pair<string, MyClass> pairs[] =
    {
        pair<string, MyClass>("one", MyClass())
    };
    cout << "pairs constructed\n";

    map<string, MyClass> mapsm(&pairs[0], &pairs[1]);
    cout << "mapsm constructed\n";
}
/*
    Generated output:
MyClass constructor
MyClass copy constructor
MyClass destructor
```



```

pairs constructed
MyClass copy constructor
MyClass copy constructor
MyClass destructor
mapsm constructed
MyClass destructor
MyClass destructor
*/

```

When tracing the output of this program, we see that, first, the constructor of a `MyClass` object is called to initialize the anonymous element of the array `pairs`. This object is then copied into the first element of the array `pairs` by the copy constructor. Next, the original element is not required anymore and is destroyed. At that point the array `pairs` has been constructed. Thereupon, the `map` constructs a temporary pair object, which is used to construct the map element. Having constructed the map element, the temporary pair object is destroyed. Eventually, when the program terminates, the pair element stored in the map is destroyed too.

- A map may be initialized using a copy constructor:

```

extern map<string, int> container;
map<string, int> object(container);

```

- Apart from the standard operators for containers, the `map` supports the index operator, which may be used to retrieve or reassign individual elements of the map. Here, the argument of the index operator is a key. If the provided key is not available in the map, a new data element is automatically added to the map using the default value or default constructor to initialize the value part of the new element. This default value is returned if the index operator is used as an rvalue.

When initializing a new or reassigning another element of the map, the type of the right-hand side of the assignment operator must be equal to (or promotable to) the type of the map's value part. E.g., to add or change the value of element "two" in a map, the following statement can be used:

```
mapsm["two"] = MyClass();
```

- The `map` class has the following member functions:

- `map::iterator begin()`:
this member returns an iterator pointing to the first element of the map.
- `void clear()`:
this member erases all elements from the map.
- `size_t count(key)`:
this member returns 1 if the provided key is available in the map, otherwise 0 is returned.
- `bool empty()`:
this member returns true if the map contains no elements.
- `map::iterator end()`:
this member returns an iterator pointing beyond the last element of the map.
- `pair<map::iterator, map::iterator> equal_range(key)`:
this member returns a pair of iterators, being respectively the return values of the member functions `lower_bound` and `upper_bound`, introduced below. An example illustrating these member functions is given at the discussion of the member function `upper_bound`.
- ... `erase()`:
this member can be used to erase a specific element or range of elements from the map:

- * `bool erase(key)` erases the element having the given key from the map. True is returned if the value was removed, false if the map did not contain an element using the given key.
- * `void erase(pos)` erases the element pointed to by the iterator `pos`.
- * `void erase(first, beyond)` erases all elements indicated by the iterator range `[first, beyond)`.

- `map::iterator find(key):`

this member returns an iterator to the element having the given key. If the element isn't available, `end` is returned. The following example illustrates the use of the `find` member function:

```
#include <iostream>
#include <map>
using namespace std;

int main()
{
    map<string, int> object;

    object["one"] = 1;

    map<string, int>::iterator it = object.find("one");

    cout << "'one' " <<
        (it == object.end() ? "not " : "") << "found\n";

    it = object.find("three");

    cout << "'three' " <<
        (it == object.end() ? "not " : "") << "found\n";
}
/*
    Generated output:
    'one' found
    'three' not found
*/
```

- ... `insert():`

this member can be used to insert elements into the map. It will, however, not replace the values associated with already existing keys by new values. Its return value depends on the version of `insert` that is called:

- * `pair<map::iterator, bool> insert(keyvalue)` inserts a new `value_type` into the map. The return value is a `pair<map::iterator, bool>`. If the returned `bool` field is true, `keyvalue` was inserted into the map. The value false indicates that the key that was specified in `keyvalue` was already available in the map, and so `keyvalue` was not inserted into the map. In both cases the `map::iterator` field points to the data element having the key that was specified in `keyvalue`. The use of this variant of `insert` is illustrated by the following example:

```
#include <iostream>
#include <string>
#include <map>
using namespace std;

int main()
{
    pair<string, int> pa[] =
    {
        pair<string,int>("one", 10),
```

```

        pair<string,int>("two", 20),
        pair<string,int>("three", 30),
    };
    map<string, int> object(&pa[0], &pa[3]);

    // {four, 40} and 'true' is returned
    pair<map<string, int>::iterator, bool>
        ret = object.insert
            (
                map<string, int>::value_type
                ("four", 40)
            );

    cout << boolalpha;

    cout << ret.first->first << " " <<
        ret.first->second << " " <<
        ret.second << " " << object["four"] << '\n';

    // {four, 40} and 'false' is returned
    ret = object.insert
        (
            map<string, int>::value_type
            ("four", 0)
        );

    cout << ret.first->first << " " <<
        ret.first->second << " " <<
        ret.second << " " << object["four"] << '\n';
    }
    /*
    Generated output:

    four 40 true 40
    four 40 false 40
    */

```

Note the somewhat peculiar constructions like

```
cout << ret.first->first << " " << ret.first->second << ...
```

Note that 'ret' is equal to the pair returned by the insert member function. Its 'first' field is an iterator into the map<string, int>, so it can be considered a pointer to a map<string, int>::value_type. These value types themselves are pairs too, having 'first' and 'second' fields. Consequently, 'ret.first->first' is the *key* of the map value (a string), and 'ret.first->second' is the *value* (an int).

* map::iterator insert(pos, keyvalue). This way a map::value_type may also be inserted into the map. pos is ignored, and an iterator to the inserted element is returned.

* void insert(first, beyond) inserts the (map::value_type) elements pointed to by the iterator range [first, beyond).

- map::iterator lower_bound(key):

this member returns an iterator pointing to the first keyvalue element of which the key is at least equal to the specified key. If no such element exists, the function returns end.

- map::reverse_iterator rbegin():

this member returns an iterator pointing to the last element of the map.

- map::reverse_iterator rend():

this member returns an iterator pointing before the first element of the map.

- `size_t size()`:

this member returns the number of elements in the map.

- `void swap(argument)`:

this member can be used to swap two maps using identical key/value types.

- `map::iterator upper_bound(key)`:

this member returns an iterator pointing to the first keyvalue element having a key exceeding the specified key. If no such element exists, the function returns end. The following example illustrates the member functions `equal_range`, `lower_bound` and `upper_bound`:

```
#include <iostream>
#include <map>
using namespace std;

int main()
{
    pair<string, int> pa[] =
    {
        pair<string,int>("one", 10),
        pair<string,int>("two", 20),
        pair<string,int>("three", 30),
    };
    map<string, int> object(&pa[0], &pa[3]);
    map<string, int>::iterator it;

    if ((it = object.lower_bound("tw")) != object.end())
        cout << "lower-bound 'tw' is available, it is: " <<
            it->first << '\n';

    if (object.lower_bound("twoo") == object.end())
        cout << "lower-bound 'twoo' not available" << '\n';

    cout << "lower-bound two: " <<
        object.lower_bound("two")->first <<
        " is available\n";

    if ((it = object.upper_bound("tw")) != object.end())
        cout << "upper-bound 'tw' is available, it is: " <<
            it->first << '\n';

    if (object.upper_bound("twoo") == object.end())
        cout << "upper-bound 'twoo' not available" << '\n';

    if (object.upper_bound("two") == object.end())
        cout << "upper-bound 'two' not available" << '\n';

    pair
    <
        map<string, int>::iterator,
        map<string, int>::iterator
    >
        p = object.equal_range("two");

    cout << "equal range: 'first' points to " <<
        p.first->first << ", 'second' is " <<
        (
            p.second == object.end() ?
                "not available"
            :

```

```

        p.second->first
    ) <<
    '\n';
}
/*
    Generated output:

    lower-bound 'tw' is available, it is: two
    lower-bound 'twoo' not available
    lower-bound two: two is available
    upper-bound 'tw' is available, it is: two
    upper-bound 'twoo' not available
    upper-bound 'two' not available
    equal range: 'first' points to two, 'second' is not available
*/

```

As mentioned at the beginning of this section, the map represents a sorted associative array. In a map the keys are sorted. If an application must visit all elements in a map the begin and end iterators must be used. The following example shows how to make a simple table listing all keys and values found in a map:

```

#include <iostream>
#include <iomanip>
#include <map>

using namespace std;

int main()
{
    pair<string, int>
    pa[] =
    {
        pair<string,int>("one", 10),
        pair<string,int>("two", 20),
        pair<string,int>("three", 30),
    };
    map<string, int>
    object(&pa[0], &pa[3]);

    for
    (
        map<string, int>::iterator it = object.begin();
        it != object.end();
        ++it
    )
        cout << setw(5) << it->first.c_str() <<
            setw(5) << it->second << '\n';
}
/*
    Generated output:
    one    10
    three  30
    two    20
*/

```

12.3.7 The ‘multimap’ container

Like the `map`, the `multimap` class implements a (sorted) associative array. Before using a `multimap` container the header file `<map>` must have been included.

The main difference between the `map` and the `multimap` is that the `multimap` supports multiple values associated with the same key, whereas the `map` contains single-valued keys. Note that the `multimap` also accepts multiple identical values associated with identical keys.

The `map` and the `multimap` have the same set of member functions, with the exception of the index operator which is not supported with the `multimap`. This is understandable: if multiple entries of the same key are allowed, which of the possible values should be returned for `object[key]`?

Refer to section 12.3.6 for an overview of the `multimap` member functions. Some member functions, however, deserve additional attention when used in the context of the `multimap` container. These members are discussed below.

- `size_t map::count(key):`
 this member returns the number of entries in the `multimap` associated with the given key.
- `... erase():`
 this member can be used to erase elements from the map:
 - `size_t erase(key)` erases all elements having the given key. The number of erased elements is returned.
 - `void erase(pos)` erases the single element pointed to by `pos`. Other elements possibly having the same keys are not erased.
 - `void erase(first, beyond)` erases all elements indicated by the iterator range `[first, beyond)`.
- `pair<multimap::iterator, multimap::iterator> equal_range(key):`
 this member function returns a pair of iterators, being respectively the return values of `lower_bound` and `upper_bound`, introduced below. The function provides a simple means to determine all elements in the `multimap` that have the same keys. An example illustrating the use of these member functions is given at the end of this section.
- `multimap::iterator find(key):`
 this member returns an iterator pointing to the first value whose key is `key`. If the element isn't available, `end` is returned. The iterator could be incremented to visit all elements having the same key until it is either `end`, or the iterator's first member is not equal to `key` anymore.
- `multimap::iterator insert():`
 this member function normally succeeds, and so a *multimap::iterator* is returned, instead of a `pair<multimap::iterator, bool>` as returned with the `map` container. The returned iterator points to the newly added element.

Although the functions `lower_bound` and `upper_bound` act identically in the `map` and `multimap` containers, their operation in a `multimap` deserves some additional attention. The next example illustrates `lower_bound`, `upper_bound` and `equal_range` applied to a `multimap`:

```
#include <iostream>
#include <map>
using namespace std;
```

```

int main()
{
    pair<string, int> pa[] =
    {
        pair<string,int>("alpha", 1),
        pair<string,int>("bravo", 2),
        pair<string,int>("charley", 3),
        pair<string,int>("bravo", 6),    // unordered 'bravo' values
        pair<string,int>("delta", 5),
        pair<string,int>("bravo", 4),
    };
    multimap<string, int> object(&pa[0], &pa[6]);

    typedef multimap<string, int>::iterator msiIterator;

    msiIterator it = object.lower_bound("brava");

    cout << "Lower bound for 'brava': " <<
        it->first << ", " << it->second << '\n';

    it = object.upper_bound("bravu");

    cout << "Upper bound for 'bravu': " <<
        it->first << ", " << it->second << '\n';

    pair<msiIterator, msiIterator>
        itPair = object.equal_range("bravo");

    cout << "Equal range for 'bravo':\n";
    for (it = itPair.first; it != itPair.second; ++it)
        cout << it->first << ", " << it->second << '\n';
    cout << "Upper bound: " << it->first << ", " << it->second << '\n';

    cout << "Equal range for 'brav':\n";
    itPair = object.equal_range("brav");
    for (it = itPair.first; it != itPair.second; ++it)
        cout << it->first << ", " << it->second << '\n';
    cout << "Upper bound: " << it->first << ", " << it->second << '\n';
}
/*
Generated output:

Lower bound for 'brava': bravo, 2
Upper bound for 'bravu': charley, 3
Equal range for 'bravo':
bravo, 2
bravo, 6
bravo, 4
Upper bound: charley, 3
Equal range for 'brav':
Upper bound: bravo, 2
*/

```

In particular note the following characteristics:

- `lower_bound` and `upper_bound` produce the same result for non-existing keys: they both return the first element having a key that exceeds the provided key.
- Although the keys are ordered in the `multimap`, the values for equal keys are not ordered: they

are retrieved in the order in which they were entered.

12.3.8 The ‘set’ container

The `set` class implements a sorted collection of values. Before using `set` containers the `<set>` header file must have been included.

A `set` contains unique values (of a container-acceptable type). Each value is stored only once.

A specific value can be explicitly created: Every `set` defines a `value_type` which may be used to create values that can be stored in the `set`. For example, a value for a `set<string>` can be constructed as follows:

```
set<string>::value_type setValue("Hello");
```

The `value_type` is associated with the `set<string>`. Anonymous `value_type` objects are also often used. E.g.,

```
set<string>::value_type("Hello");
```

Instead of using the line `set<string>::value_type(...)` over and over again, a `typedef` is often used to reduce typing and to improve readability:

```
typedef set<string>::value_type StringSetValue
```

Using this `typedef`, values for the `set<string>` may be constructed as follows:

```
StringSetValue("Hello");
```

Alternatively, values of the `set`’s type may be used immediately. In that case the value of type `Type` is implicitly converted to a `set<Type>::value_type`.

The following constructors, operators, and member functions are available for the `set` container:

- Constructors:

- A `set` may be constructed empty:

```
set<int> object;
```

- A `set` may be initialized using two iterators. For example:

```
int intarr[] = {1, 2, 3, 4, 5};
```

```
set<int> object(&intarr[0], &intarr[5]);
```

Note that all values in the `set` must be different: it is not possible to store the same value repeatedly when the `set` is constructed. If the same value occurs repeatedly, only the first instance of the value will be entered, the other values will be silently ignored.

Like the `map`, the `set` receives its own copy of the data it contains.

- A `set` may be initialized using a copy constructor:

```
extern set<string> container;
set<string> object(container);
```

- The `set` container only supports the standard set of operators that are available for containers.

- The `set` class has the following member functions:

- `set::iterator begin()`:
this member returns an iterator pointing to the first element of the set. If the set is empty `end` is returned.
- `void clear()`:
this member erases all elements from the set.
- `size_t count(key)`:
this member returns 1 if the provided key is available in the set, otherwise 0 is returned.
- `bool empty()`:
this member returns `true` if the set contains no elements.
- `set::iterator end()`:
this member returns an iterator pointing beyond the last element of the set.
- `pair<set::iterator, set::iterator> equal_range(key)`:
this member returns a pair of iterators, being respectively the return values of the member functions `lower_bound` and `upper_bound`, introduced below.
- ... `erase()`:
this member can be used to erase a specific element or range of elements from the set:
 - * `bool erase(value)` erases the element having the given value from the set. `True` is returned if the value was removed, `false` if the set did not contain an element 'value'.
 - * `void erase(pos)` erases the element pointed to by the iterator `pos`.
 - * `void erase(first, beyond)` erases all elements indicated by the iterator range `[first, beyond)`.
- `set::iterator find(value)`:
this member returns an iterator to the element having the given value. If the element isn't available, `end` is returned.
- ... `insert()`:
this member can be used to insert elements into the set. If the element already exists, the existing element is left untouched and the element to be inserted is ignored. The return value depends on the version of `insert` that is called:
 - * `pair<set::iterator, bool> insert(keyvalue)` inserts a new `set::value_type` into the set. The return value is a `pair<set::iterator, bool>`. If the returned `bool` field is `true`, value was inserted into the set. The value `false` indicates that the value that was specified was already available in the set, and so the provided value was not inserted into the set. In both cases the `set::iterator` field points to the data element in the set having the specified value.
 - * `set::iterator insert(pos, keyvalue)`. This way a `set::value_type` may also be inserted into the set. `pos` is ignored, and an iterator to the inserted element is returned.
 - * `void insert(first, beyond)` inserts the (`set::value_type`) elements pointed to by the iterator range `[first, beyond)` into the set.
- `set::iterator lower_bound(key)`:
this member returns an iterator pointing to the first `keyvalue` element of which the key is at least equal to the specified key. If no such element exists, the function returns `end`.
- `set::reverse_iterator rbegin()`:
this member returns an iterator pointing to the last element of the set.
- `set::reverse_iterator rend`:
this member returns an iterator pointing before the first element of the set.

- `size_t size()`:
this member returns the number of elements in the set.
- `void swap(argument)`:
this member can be used to swap two sets (argument being the second set) that use identical data types.
- `set::iterator upper_bound(key)`:
this member returns an iterator pointing to the first keyvalue element having a key exceeding the specified key. If no such element exists, the function returns end.

12.3.9 The ‘multiset’ container

Like the `set`, the `multiset` class implements a sorted collection of values. Before using `multiset` containers the header file `<set>` must have been included.

The main difference between the `set` and the `multiset` is that the `multiset` supports multiple entries of the same value, whereas the `set` contains unique values.

The `set` and the `multiset` have the same set of member functions. Refer to section 12.3.8 for an overview of the `multiset` member functions. Some member functions, however, behave slightly different than their counterparts of the `set` container. Those members are mentioned here.

- `size_t count(value)`:
this member returns the number of entries in the `multiset` associated with the given value.
- `... erase()`:
this member can be used to erase elements from the set:
 - `size_t erase(value)` erases all elements having the given value. The number of erased elements is returned.
 - `void erase(pos)` erases the element pointed to by the iterator `pos`. Other elements possibly having the same values are not erased.
 - `void erase(first, beyond)` erases all elements indicated by the iterator range `[first, beyond)`.
- `pair<multiset::iterator, multiset::iterator> equal_range(value)`:
this member function returns a pair of iterators, being respectively the return values of `lower_bound` and `upper_bound`, introduced below. The function provides a simple means to determine all elements in the `multiset` that have the same values.
- `multiset::iterator find(value)`:
this member returns an iterator pointing to the first element having the specified value. If the element isn't available, end is returned. The iterator could be incremented to visit all elements having the given value until it is either end, or the iterator doesn't point to 'value' anymore.
- `... insert()`:
this member function normally succeeds and returns a `multiset::iterator` rather than a `pair<multiset::iterator, bool>` as returned with the `set` container. The returned iterator points to the newly added element.

Although the functions `lower_bound` and `upper_bound` act identically in the `set` and `multiset` containers, their operation in a `multiset` deserves some additional attention. With a `multiset` container `lower_bound` and `upper_bound` produce the same result for non-existing keys: they both return the first element having a key exceeding the provided key.

Here is an example showing the use of various member functions of a `multiset`:

```
#include <iostream>
#include <set>

using namespace std;

int main()
{
    string
        sa[] =
        {
            "alpha",
            "echo",
            "hotel",
            "mike",
            "romeo"
        };

    multiset<string>
        object(&sa[0], &sa[5]);

    object.insert("echo");
    object.insert("echo");

    multiset<string>::iterator
        it = object.find("echo");

    for (; it != object.end(); ++it)
        cout << *it << " ";
    cout << '\n';

    cout << "Multiset::equal_range(\"ech\")\n";
    pair
    <
        multiset<string>::iterator,
        multiset<string>::iterator
    >
        itpair = object.equal_range("ech");

    if (itpair.first != object.end())
        cout << "lower_bound() points at " << *itpair.first << '\n';
    for (; itpair.first != itpair.second; ++itpair.first)
        cout << *itpair.first << " ";

    cout << '\n' <<
        object.count("ech") << " occurrences of 'ech'" << '\n';

    cout << "Multiset::equal_range(\"echo\")\n";
    itpair = object.equal_range("echo");

    for (; itpair.first != itpair.second; ++itpair.first)
        cout << *itpair.first << " ";
```

```

cout << '\n' <<
    object.count("echo") << " occurrences of 'echo'" << '\n';

cout << "Multiset::equal_range(\"echoo\")\n";
itpair = object.equal_range("echoo");

for (; itpair.first != itpair.second; ++itpair.first)
    cout << *itpair.first << " ";

cout << '\n' <<
    object.count("echoo") << " occurrences of 'echoo'" << '\n';
}
/*
Generated output:

echo echo echo hotel mike romeo
Multiset::equal_range("ech")
lower_bound() points at echo

0 occurrences of 'ech'
Multiset::equal_range("echo")
echo echo echo
3 occurrences of 'echo'
Multiset::equal_range("echoo")

0 occurrences of 'echoo'
*/

```

12.3.10 The 'stack' container

The `stack` class implements a stack data structure. Before using `stack` containers the header file `<stack>` must have been included.

A stack is also called a first in, last out (FILO or LIFO) data structure as the first item to enter the stack is the last item to leave. A stack is an extremely useful data structure in situations where data must temporarily remain available. For example, programs maintain a stack to store local variables of functions: the lifetime of these variables is determined by the time these functions are active, contrary to global (or static local) variables, which live for as long as the program itself lives. Another example is found in calculators using the *Reverse Polish Notation* (RPN), in which the operands of operators are kept in a stack, whereas operators pop their operands off the stack and push the results of their work back onto the stack.

As an example of the use of a stack, consider figure 12.5, in which the contents of the stack is shown while the expression $(3 + 4) * 2$ is evaluated. In the RPN this expression becomes $3\ 4\ +\ 2\ *$, and figure 12.5 shows the stack contents after each *token* (i.e., the operands and the operators) is read from the input. Notice that each operand is indeed pushed on the stack, while each operator changes the contents of the stack. The expression is evaluated in five steps. The caret between the tokens in the expressions shown on the first line of figure 12.5 shows what token has just been read. The next line shows the actual stack-contents, and the final line shows the steps for referential purposes. Note that at step 2, two numbers have been pushed on the stack. The first number (3) is now at the bottom of the stack. Next, in step 3, the $+$ operator is read. The operator pops two operands (so that the stack is empty at that moment), calculates their sum, and pushes the resulting value (7) on the stack. Then, in step 4, the number 2 is read, which is dutifully pushed on the stack again. Finally, in step 5 the final operator $*$ is read, which pops the values 2 and 7 from the stack, computes their product, and pushes the result back on the stack. This result (14) could then be popped to be displayed on some medium.

From figure 12.5 we see that a stack has one location (the *top*) where items can be pushed onto and popped off the stack. This top element is the stack's only immediately visible element. It may be




Figure 12.5: The contents of a stack while evaluating $3 \ 4 \ + \ 2 \ *$

accessed and modified directly.

Bearing this model of the stack in mind, let's see what we formally can do with the `stack` container. For the `stack`, the following constructors, operators, and member functions are available:

- Constructors:

- A stack may be constructed empty:

```
stack<string> object;
```

- A stack may be initialized using a copy constructor:

```
extern stack<string> container;  
stack<string> object(container);
```

- Only the basic set of container operators are supported by the stack

- The following member functions are available for stacks:

- ```
- bool empty():
```

this member returns `true` if the stack contains no elements.

- ```
- void push(value):
```

this member places `value` at the top of the stack, hiding the other elements from view.

- ```
- void pop():
```

this member removes the element at the top of the stack. Note that the popped element is *not* returned by this member. Nothing happens if `pop` is used with an empty stack. See section 12.3.3 for a discussion about the reason why `pop` has return type `void`.

- ```
- size_t size():
```

this member returns the number of elements in the stack.

- Type &top():

this member returns a reference to the stack's top (and only visible) element. It is the responsibility of the programmer to use this member only if the stack is not empty.

The stack does not support iterators or a subscript operator. The only elements that can be accessed is its top element. To empty a stack:

- repeatedly remove its front element;
- assign an empty stack to it;
- have its destructor called (e.g., by ending its lifetime).

12.3.11 Hash Tables (C++0x)

The C++0x standard officially adds hash tables to the language.

Before using hash table containers the header file `<unordered_map>` must have been included. Variants are hash-based sets and multi-sets. Before using these hash-based set containers the header file `<unordered_set>` must have been included.

As discussed, the map is a sorted data structure. The keys in maps are sorted using the operator< of the key's data type. Generally, this is not the fastest way to either store or retrieve data. The main benefit of sorting is that a listing of sorted keys appeals more to humans than an unsorted list. However, a by far faster method to store and retrieve data is to use *hashing*.

Hashing uses a function (called the *hash function*) to compute an (unsigned) number from the key, which number is thereupon used as an index in the table in which the keys are stored. Retrieval of a key is as simple as computing the hash value of the provided key, and looking in the table at the computed index location: if the key is present, it is stored in the table, and its value can be returned. If it's not present, the key is not stored.

Collisions occur when a computed index position is already occupied by another element. For these situations the abstract containers have solutions available. A simple solution, adopted by the C++0x standard is to use *linear chaining* which uses a linked list to store colliding table elements in.

In the C++0x standard the term *unordered* is used rather than *hash* to avoid name collisions with hash tables developed before the advent of the C++0x standard. Except where *unordered* is required as part of a type name, the term *hash* will be used here as it is the term commonly encountered.

Four forms of unordered data structures are supported: `unordered_map`, `unordered_multimap`, `unordered_set`, and `unordered_multiset`.

Below the `unordered_map` container is discussed. The other containers using hashing also use hashing but provide functionality corresponding to, respectively, the `multimap`, `set` and `multiset`.

Concentrating on the `unordered_map`, its constructor needs a key type, a value type, an object computing a hash value for the key, and an object comparing two keys for equality. Predefined hash functions are available for `std::string` keys, and for all standard scalar numeric types (`char`, `short`, `int` etc.). If another data type is used, a hash function object and an equality function object must be made available (see also section 10.10). Examples follow below.

The class implementing the hash function could be called `hash`. Its function call operator (`operator()`) returns the (`size_t`) hash value of the key that it received as its argument.

A *generic algorithm* (see chapter 19) exists performing tests of equality (i.e., `equal_to`). These tests can be used if the key's data type supports the equality operator. Alternatively, an overloaded `operator==` or specialized function object could be constructed returning `true` if two keys are equal and `false` otherwise. Examples follow.

The `unordered_map` class implements an associative array in which the elements are stored according to some hashing scheme.

Constructors, operators and member functions available for the map are also available for the `unordered_map`. The map and `unordered_map` support the same set of operators and member functions. However, the *efficiency* of a `unordered_map` in terms of speed should greatly exceed the efficiency of the map. Comparable conclusions may be drawn for the `unordered_set`, `unordered_multimap` and the `unordered_multiset`.

Compared to the map container, the `unordered_map` has an additional constructor:

```
unordered_map<...> hash(n);
```

where `n` is a `size_t` value. It is used to construct a `unordered_map` consisting of an initial number of at least `n` empty slots to put key/value combinations in. This number is automatically extended when needed.

The hashed key type is almost always text. So, a `unordered_map` in which the key's data type is a `std::string` occurs most often. Note that although a `char *` is allowed as key type this is almost always a bad idea since two `char *` variables pointing to equal C-strings stored at different locations will be considered different keys.

The following program defines a `unordered_map` containing the names of the months of the year and the number of days these months (usually) have. Then, using the subscript operator the days in several months are displayed. The equality operator used the generic algorithm `equal_to<string>`, which is the default fourth argument of the `unordered_map` constructor:

```
#include <unordered_map>
#include <iostream>
#include <string>
using namespace std;

int main()
{
    unordered_map<string, int> months;

    months["january"] = 31;
    months["february"] = 28;
    months["march"] = 31;
    months["april"] = 30;
    months["may"] = 31;
    months["june"] = 30;
    months["july"] = 31;
    months["august"] = 31;
    months["september"] = 30;
    months["october"] = 31;
    months["november"] = 30;
    months["december"] = 31;

    cout << "september -> " << months["september"] << '\n' <<
        "april -> " << months["april"] << '\n' <<
        "june -> " << months["june"] << '\n' <<
        "november -> " << months["november"] << '\n';
}
/*
    Generated output:
september -> 30
april -> 30
june -> 30
november -> 30
*/
```

A comparable example, showing the use of explicitly defined hash and equality functions and key-type `char const *`:

```
#include <unordered_map>
#include <iostream>
#include <string>
#include <cstring>
using namespace std;

struct EqualCp
{
    bool operator()(char const *l, char const *r) const
    {
        return strcmp(l, r) == 0;
    }
};
```

```

    }
};
struct HashCp
{
    size_t operator()(char const *str) const
    {
        return hash<std::string const &>()(str);
    }
};
int main()
{
    unordered_map<char const *, int, HashCp, EqualCp> months;

    months["april"] = 30;
    months["november"] = 31;

    string apr("april");    // different pointers, same string

    cout << "april      -> " << months["april"] << '\n' <<
         "april      -> " << months[apr.c_str()] << '\n';
}

```

The `unordered_multimap`, `unordered_set` and `unordered_multiset` containers are used analogously. For these containers the `equal` and `hash` classes must also be defined. The `unordered_multimap` also requires the `unordered_map` header file.

12.3.12 Regular Expressions (C++0x, ?)

The C++0x standard adds handling of regular expressions to the language. Before using regular expressions as offered by the C++ standard the header file `<regex>` must have been included.

Regular expressions were already available in C++ via its C heritage as C has always offered functions like `regcomp` and `regexexec` that are used by, e.g., the `Pattern` class of the Bobcat library¹.

Regular expressions are extensively documented elsewhere (e.g., **regex**(7), Friedl, J.E.F *Mastering Regular Expressions*², O'Reilly) and the reader is referred to these sources for a refresher on the topic of regular expressions.

The C++0x standard adds native object based support for regular expressions by defining several new classes and other facilities. Currently, however, regular expressions are not yet supported by the g++ library and therefore in this section only the basic building blocks the C++0x standard offers to handle regular expressions are mentioned. Once regular expressions actually become available this section will be updated to cover the actually available features.

Eventually, regular expressions will be represented by objects of the class `regex`. Once a `regex` regular expression object has been defined its member `regex_search` can be called to process its regular expression. This function expects arguments representing, respectively, the text against which the regular expression will be matched; an object of the class `cmatch` representing the results of the matching operation and an object of the class `regex` representing the used regular expression. Furthermore, a member `regex_replace` will be available to perform textual replacements based on regular expressions.

Regular expressions using the `regex` class are currently not yet available in the g++ library.

¹<http://bobcat.sourceforge.net>

²<http://oreilly.com/catalog/>

12.4 The 'complex' container

The `complex` container defines the standard operations that can be performed on complex numbers. Before using `complex` containers the header file `<complex>` must have been included.

The complex number's real and imaginary types are specified as the container's data type. Examples:

```
complex<double>
complex<int>
complex<float>
```

Note that the real and imaginary parts of complex numbers have the same datatypes.

When initializing (or assigning) a complex object, the imaginary part may be omitted from the initialization or assignment resulting in its value being 0 (zero). By default, both parts are zero.

Below it is silently assumed that the used `complex` type is `complex<double>`. Given this assumption, complex numbers may be initialized as follows:

- `target`: A default initialization: real and imaginary parts are 0.
- `target(1)`: The real part is 1, imaginary part is 0
- `target(0, 3.5)`: The real part is 0, imaginary part is 3.5
- `target(source)`: `target` is initialized with the values of `source`.

Anonymous complex values may also be used. In the next example two anonymous complex values are pushed on a stack of complex numbers, to be popped again thereafter:

```
#include <iostream>
#include <complex>
#include <stack>

using namespace std;

int main()
{
    stack<complex<double>>
        cstack;

    cstack.push(complex<double>(3.14, 2.71));
    cstack.push(complex<double>(-3.14, -2.71));

    while (cstack.size())
    {
        cout << cstack.top().real() << ", " <<
            cstack.top().imag() << "i" << '\n';
        cstack.pop();
    }
}
/*
    Generated output:
-3.14, -2.71i
3.14, 2.71i
*/
```

The following member functions and operators are defined for complex numbers (below, value may be either a primitive scalar type or a `complex` object):

- Apart from the standard container operators, the following operators are supported from the `complex` container.
 - `complex operator+(value):`
this member returns the sum of the current `complex` container and `value`.
 - `complex operator-(value):`
this member returns the difference between the current `complex` container and `value`.
 - `complex operator*(value):`
this member returns the product of the current `complex` container and `value`.
 - `complex operator/(value):`
this member returns the quotient of the current `complex` container and `value`.
 - `complex operator+=(value):`
this member adds `value` to the current `complex` container, returning the new value.
 - `complex operator-=(value):`
this member subtracts `value` from the current `complex` container, returning the new value.
 - `complex operator*=(value):`
this member multiplies the current `complex` container by `value`, returning the new value
 - `complex operator/=(value):`
this member divides the current `complex` container by `value`, returning the new value.
- `Type real():`
this member returns the real part of a complex number.
- `Type imag():`
this member returns the imaginary part of a complex number.
- Several mathematical functions are available for the `complex` container, such as `abs`, `arg`, `conj`, `cos`, `cosh`, `exp`, `log`, `norm`, `polar`, `pow`, `sin`, `sinh` and `sqrt`. All these functions are free functions, not member functions, accepting complex numbers as their arguments. For example,


```
abs(complex<double>(3, -5));
pow(target, complex<int>(2, 3));
```
- Complex numbers may be extracted from `istream` objects and inserted into `ostream` objects. The insertion results in an ordered pair `(x, y)`, in which `x` represents the real part and `y` the imaginary part of the complex number. The same form may also be used when extracting a complex number from an `istream` object. However, simpler forms are also allowed. E.g., when extracting `1.2345` the imaginary part will be set to 0.

Chapter 13

Inheritance

When programming in **C**, programming problems are commonly approached using a top-down structured approach: functions and actions of the program are defined in terms of sub-functions, which again are defined in sub-sub-functions, etc.. This yields a hierarchy of code: `main` at the top, followed by a level of functions which are called from `main`, etc..

In **C++** the relationship between code and data is also frequently defined in terms of dependencies among *classes*. This looks like *composition* (see section 7.2), where objects of a class contain objects of another class as their data. But the relation described here is of a different kind: a class can be *defined* in terms of an older, pre-existing, class. This produces a new class having all the functionality of the older class, and additionally defining its own specific functionality. Instead of composition, where a given class *contains* another class, we here refer to *derivation*, where a given class *is* or *is-implemented-in-terms-of* another class.

Another term for derivation is *inheritance*: the new class inherits the functionality of an existing class, while the existing class does not appear as a data member in the interface of the new class. When discussing inheritance the existing class is called the *base class*, while the new class is called the *derived class*.

Derivation of classes is often used when the methodology of **C++** program development is fully exploited. In this chapter we will first address the syntactic possibilities offered by **C++** for deriving classes. Following this we will address some of the specific possibilities offered by class derivation (inheritance).

As we have seen in the introductory chapter (see section 2.4), in the object-oriented approach to problem solving classes are identified during the problem analysis. Under this approach objects of the defined classes represent entities that can be observed in the problem at hand. The classes are placed in a hierarchy, with the top-level class containing limited functionality. Each new derivation (and hence descent in the class hierarchy) adds new functionality compared to yet existing classes.

In this chapter we shall use a simple vehicle classification system to build a hierarchy of classes. The first class is `Vehicle`, which implements as its functionality the possibility to set or retrieve the mass of a vehicle. The next level in the object hierarchy are land-, water- and air vehicles.

The initial object hierarchy is illustrated in Figure 13.1.

This chapter mainly focuses on the technicalities of class derivation. The distinction between inheritance used to create derived classes whose objects should be considered objects of the base class and inheritance used to implement derived classes *in-terms-of* their base classes will be postponed until the next chapter (14).




Figure 13.1: Initial object hierarchy of vehicles.

13.1 Related types

The relationship between the proposed classes representing different kinds of vehicles is further investigated here. The figure shows the object hierarchy: an `Auto` is a special case of a `Land` vehicle, which in turn is a special case of a `Vehicle`.

The class `Vehicle` represents the ‘greatest common divisor’ in the classification system. `Vehicle` is given limited functionality: it can store and retrieve a vehicle’s mass:

```

class Vehicle
{
    size_t d_mass;

public:
    Vehicle();
    Vehicle(size_t mass);

    size_t mass() const;
    void setMass(size_t mass);
};
  
```

Using this class, the vehicle’s mass can be defined as soon as the corresponding object has been created. At a later stage the mass can be changed or retrieved.

To represent vehicles travelling over land, a new class `Land` can be defined offering `Vehicle`’s functionality and adding its own specific functionality. Assume we are interested in the speed of land vehicles *and* in their mass. The relationship between `Vehicles` and `Lands` could of course be represented by composition but that would be awkward: composition suggests that a `Land` vehicle *is-implemented-in-terms-of*, i.e., *contains*, a `Vehicle`, while the natural relationship clearly is that the `Land` vehicle *is* a kind of `Vehicle`.

A relationship in terms of composition would also somewhat complicate our `Land` class’s design. Consider the following example showing a class `Land` using composition (only the `setMass` functionality is shown):

```

class Land
{
    Vehicle d_v;          // composed Vehicle
public:
    void setMass(size_t mass);
};
  
```

```
void Land::setMass(size_t mass)
{
    d_v.setMass(mass);
}
```

Using composition, the `Land::setMass` function only passes its argument on to `Vehicle::setMass`. Thus, as far as mass handling is concerned, `Land::setMass` introduces no extra functionality, just extra code. Clearly this code duplication is superfluous: a `Land` object *is* a `Vehicle`; to state that a `Land` object *contains* a `Vehicle` is at least somewhat peculiar.

The intended relationship is represented better by inheritance. A rule of thumb for choosing between inheritance and composition distinguishes between *is-a* and *has-a* relationships. A truck *is* a vehicle, so `Truck` should probably derive from `Vehicle`. On the other hand, a truck *has* an engine; if you need to model engines in your system, you should probably express this by composing an `Engine` class inside the `Truck` class.

Following the above rule of thumb, `Land` is *derived* from the base class `Vehicle`:

```
class Land: public Vehicle
{
    size_t d_speed;
public:
    Land();
    Land(size_t mass, size_t speed);

    void setspeed(size_t speed);
    size_t speed() const;
};
```

To derive a class (e.g., `Land`) from another class (e.g., `Vehicle`) postfix the class name `Land` in its interface by : `public Vehicle`:

```
class Land: public Vehicle
```

The class `Land` now contains all the functionality of its base class `Vehicle` as well as its own features. Here those features are a constructor expecting two arguments and member functions to access the `d_speed` data member. Here is an example showing the possibilities of the derived class `Land`:

```
Land veh(1200, 145);

int main()
{
    cout << "Vehicle weighs " << veh.mass() << ";\n"
         << "its speed is " << veh.speed() << '\n';
}
```

This example illustrates two features of derivation.

- First, `mass` is not mentioned as a member in `Land`'s interface. Nevertheless it is used in `veh.mass`. This member function is an implicit part of the class, inherited from its 'parent' `Vehicle`.
- Second, although the derived class `Land` contains the functionality of `Vehicle`, the `Vehicle`'s private members remain private: they can only be accessed by `Vehicle`'s own member functions. This means that `Land`'s member functions *must* use `Vehicle`'s member functions (like `mass` and `setMass`) to address the `mass` field. Here there's no difference between the access rights granted to `Land` and the access rights granted to other code outside of the class `Vehicle`. The class `Vehicle` *encapsulates* the specific `Vehicle` characteristics, and data hiding is one way to realize encapsulation.

Encapsulation is a core principle of good class design. Encapsulation reduces the dependencies among classes improving the maintainability and testability of classes and allowing us to modify classes without the need to modify depending code. By strictly complying with the principle of data hiding a class's internal data organization may change without requiring depending code to be changed as well. E.g., a class `Lines` originally storing `C`-strings could at some point have its data organization changed. It could abandon its `char **` storage in favor of a `vector<string>` based storage. When `Lines` uses perfect data hiding depending source code may use the new `Lines` class without requiring any modification at all.

As a rule of thumb, derived classes must be fully recompiled (but don't have to be modified) when the *data organization* (i.e., the data members) of their base classes change. Adding new member *functions* to the base class doesn't alter the data organization so no recompilation is needed when new member *functions* are added.

There is one subtle exception to this rule of thumb: if a new member function is added to a base class and that function happens to be the first *virtual* member function of the base class (cf. chapter 14 for a discussion of the virtual member function concept) then that will *also* change the data organization of the base class.

Now that `Land` has been derived from `Vehicle` we're ready for our next class derivation. We'll define a class `Auto` to represent automobiles. Agreeing that an `Auto` object is a `Land` vehicle, and that an `Auto` has a brand name it's easy to design the class `Auto`:

```
class Auto: public Land
{
    std::string d_brandName;

public:
    Auto();
    Auto(size_t mass, size_t speed, std::string const &name);

    std::string const &brandName() const;
};
```

In the above class definition, `Auto` was derived from `Land`, which in turn is derived from `Vehicle`. This is called *nested derivation*: `Land` is called `Auto`'s *direct base class*, while `Vehicle` is called `Auto`'s *indirect base class*.

13.1.1 Inheritance depth: desirable?

Now that `Auto` has been derived from `Land` and `Land` has been derived from `Vehicle` we might easily be seduced into thinking that these class hierarchies are the way to go when designing classes. But maybe we should temper our enthusiasm.

Repeatedly deriving classes from classes quickly results in big, complex class hierarchies that are hard to understand, hard to use and hard to maintain. Hard to understand and use as users of our derived class now also have to learn all its (indirect) base class features as well. Hard to maintain because all those classes are very closely coupled. While it may be true that when data hiding is meticulously adhered to derived classes do not have to be modified when their base classes alter their data organization, it also quickly becomes practically infeasible to change those base classes once more an more (derived) classes depend on their current organization.

What initially looks like a big gain, inheriting the base class's interface, thus becomes a liability. The base class's interface is hardly ever completely required and in the end a class may benefit from explicitly defining its own member functions rather than obtaining them through inheritance.

Often classes can be defined *in-terms-of* existing classes: some of their features are used, but others need to be shielded off. Consider the `stack` container: it is commonly implemented in-terms-of a `deque`, returning `deque::back`'s value as `stack::top`'s value.

When using inheritance to implement an *is-a* relationship make sure to get the ‘direction of use’ right: inheritance aiming at implementing an *is-a* relationship should focus on the base class: the base class facilities aren’t there to be used by the derived class, but the derived class facilities should redefine (reimplement) the base class facilities using polymorphism (which is the topic of the next chapter), allowing code to use the derived class facilities polymorphically through the base class. We’ve seen this approach when studying streams: the base class (e.g., `ostream`) is used time and again. The facilities defined by classes derived from `ostream` (like `ofstream` and `ostringstream`) are then used by code only relying on the facilities offered by the `ostream` class, never using the derived classes directly.

When designing classes always aim at the lowest possible coupling. Big class hierarchies usually indicate poor understanding of robust class design. When a class’s interface is only partially used and if the derived class is implemented in terms of another class consider using composition rather than inheritance and define the appropriate interface members in terms of the members offered by the composed objects.

13.2 The constructor of a derived class

A derived class inherits functionality from its base class (or base classes, as **C++** supports multiple inheritance, cf. section 13.5). When a derived class object is constructed it is built on top of its base class object. As a consequence the base class must have been constructed before the actual derived class elements can be initialized. This results in some requirements that must be observed when defining derived class constructors.

A constructor exists to initialize the object’s data members. A derived class constructor is also responsible for the proper initialization of its base class. Looking at the definition of the class `Land` introduced earlier (section 13.1), its constructor could simply be defined as follows:

```
Land::Land(size_t mass, size_t speed)
{
    setMass(mass);
    setSpeed(speed);
}
```

However, this implementation has several disadvantages.

- When constructing a derived class object a base class constructor will *always* be called before any action is performed on the derived class object itself. By default the base class’s default constructor will be called.
- Using the base class constructor only to reassign new values to its data members in the derived class constructor’s body usually is inefficient, but sometimes sheer impossible as in situations where base class reference or `const` data members must be initialized. In those cases a specialized base class constructor must be used instead of the base class default constructor.

A derived class’s base class may be initialized using a dedicated base class constructor by calling the base class constructor in the derived class constructor’s initializer clause. Calling a base class constructor in a constructor’s initializer clause is called a *base class initializer*. The base class initializer must be called before initializing any of the derived class’s data members and when using the base class initializer none of the derived class data members may be used. When constructing a derived class object the base class is constructed first and only after that construction has successfully completed the derived class data members are available for initialization. `Land`’s constructor may therefore be improved:

```
Land::Land(size_t mass, size_t speed)
:
    Vehicle(mass),
```



```

        d_speed(speed)
    {}

```

Derived class constructors always by default call their base class's default constructor. This is of course not correct for a derived class's copy constructor. Assuming that the class `Land` must be provided with a copy constructor it may use the `Land const &other` to represent the other's base class:

```

Land::Land(Land const &other)    // assume a copy constructor is needed
:
    Vehicle(other),             // copy-construct the base class part.
    d_speed(other.speed)        // copy-construct Land's data members
{}

```

Likewise, a derived class move constructor may have to be defined. A derived class may offer a move constructor for two reasons:

- it supports move construction for its data members
- its base class is move-aware

The design of move constructors moving data members was covered in section 8.6. A move constructor for a derived class whose base class is move-aware must *anonymize* the rvalue reference before passing it to the base class move constructor. The `std::move` function should be used when implementing the move constructor to move the information in base classes or composed objects to their new destination object.

The first example shows the move constructor for the class `Auto`, assuming it has a movable `char *d_brandName` data member and assuming that `Land` is a move-aware class. The second example shows the move constructor for the class `Land`, assuming that it does not itself have movable data members, but that its `Vehicle` base class is move-aware:

```

Auto::Auto(Auto const &&tmp)
:
    Land(std::move(tmp)),        // anonymize 'tmp'
    d_brandName(tmp.d_brandName) // move the char *'s value
{
    const_cast<Auto &>(tmp).d_brandName = 0;
}

Land(Land const &&tmp)
:
    Vehicle(std::move(tmp)),     // move-aware Vehicle
    d_speed(tmp.d_speed)        // plain copying of plain data
{}

```

13.2.1 Merely using base class constructors (C++0x, ?)

The C++0x standard allows derived classes to be constructed without explicitly defining derived class constructors. In those cases the available base class constructors are called.

This feature is either used or not. It is not possible to omit some of the derived class constructors, using the corresponding base class constructors instead. To use this feature for classes that are derived from multiple base classes (cf. section 13.5) all the base class constructors must have different signatures. Considering the complexities that are involved here it's probably best to avoid using base class constructors for classes using multiple inheritance.

The construction of derived class objects can be delegated to base class constructor(s) using the following syntax:


```

class BaseClass
{
    public:
        // BaseClass constructor(s)
};

class DerivedClass: public BaseClass
{
    public:
        using BaseClass::BaseClass; // No DerivedClass constructors
                                    // are defined
};

```

13.3 The destructor of a derived class

Destructors of classes are automatically called when an object is destroyed. This also holds true for objects of classes derived from other classes. Assume we have the following situation:

```

class Base
{
    public:
        ~Base();
};

class Derived: public Base
{
    public:
        ~Derived();
};

int main()
{
    Derived derived;
}

```

At the end of `main`, the derived object ceases to exist. Hence, its destructor (`~Derived`) is called. However, since `derived` is also a `Base` object, the `~Base` destructor is called as well. The base class destructor is never explicitly called from the derived class destructor.

Constructors and destructors are called in a stack-like fashion: when `derived` is constructed, the appropriate base class constructor is called first, then the appropriate derived class constructor is called. When the object `derived` is destroyed, its destructor is called first, automatically followed by the activation of the `Base` class destructor. A derived class destructor is always called before its base class destructor is called.

When the construction of a derived class object did not successfully complete (i.e., the constructor threw an exception) then its destructor is not called. However, the destructors of properly constructed base classes *will* be called if a derived class constructor throws an exception. This, of course, is it should be: a properly constructed object will also be destroyed, eventually. Example:

```

#include <iostream>
struct Base
{
    ~Base()
    {
        std::cout << "Base destructor\n";
    }
}

```

```

};
struct Derived: public Base
{
    Derived()
    {
        throw 1;    // at this time Base has been constructed
    }
};
int main()
{
    try
    {
        Derived d;
    }
    catch(...)
    {}
}
/*
    This program displays 'B destructor'
*/

```

13.4 Redefining member functions

Derived classes may redefine base class members. Let's assume that a vehicle classification system must also cover trucks, consisting of two parts: the front part, the tractor, pulls the rear part, the trailer. Both the tractor and the trailer have their own masses, and the `mass` function should return the combined mass.

The definition of a `Truck` starts with a class definition. Our initial `Truck` class is derived from `Auto` but it is then expanded to hold one more `size_t` field representing the additional mass information. Here we choose to represent the mass of the front part of the truck in the `Auto` class and to store the mass of the trailer in an additional field:

```

class Truck: public Auto
{
    size_t d_trailer_mass;

public:
    Truck();
    Truck(size_t tractor_wt, size_t speed, char const *name,
          size_t trailer_wt);

    void setMass(size_t tractor_wt, size_t trailer_wt);
    size_t mass() const;
};

Truck::Truck(size_t tractor_wt, size_t speed, char const *name,
             size_t trailer_wt)
:
    Auto(tractor_wt, speed, name)
{
    d_trailer_mass = trailer_wt;
}

```

Note that the class `Truck` now contains two functions already present in the base class `Auto`: `setMass` and `mass`.

- The redefinition of `setMass` poses no problems: this function is simply redefined to perform actions which are specific to a `Truck` object.
- The redefinition of `setMass`, however, will *hide* `Auto::setMass`. For a `Truck` only the `setMass` function having two `size_t` arguments can be used.
- The `Vehicle`'s `setMass` function remains available for a `Truck`, but it must now be called *explicitly*, as `Auto::setMass` is hidden from view. This latter function is hidden, even though `Auto::setMass` has only one `size_t` argument. To implement `Truck::setMass` we could write:

```
void Truck::setMass(size_t tractor_wt, size_t trailer_wt)
{
    d_trailer_mass = trailer_wt;
    Auto::setMass(tractor_wt);    // note: Auto:: is required
}
```

- Outside of the class `Auto::setMass` is accessed using the scope resolution operator. So, if a `Truck` `truck` needs to set its `Auto` mass, it must use

```
truck.Auto::setMass(x);
```

- An alternative to using the scope resolution operator is to add a member having the same function prototype as the base class member to the derived class's interface. This derived class member could be implemented inline to call the base class member. E.g., we add the following member to the class `Truck`:

```
// in the interface:
void setMass(size_t tractor_wt);

// below the interface:
inline void Truck::setMass(size_t tractor_wt)
{
    Auto::setMass(tractor_wt);
}
```

Now the single argument `setMass` member function can be used by `Truck` objects without using the scope resolution operator. As the function is defined inline, no overhead of an additional function call is involved.

- To prevent hiding the base class members a using declaration may be added to the derived class interface. The relevant section of `Truck`'s class interface then becomes:

```
class Truck: public Auto
{
    public:
        using Auto::setMass;
        void setMass(size_t tractor_wt, size_t trailer_wt);
};
```

A using declaration imports (all overloaded versions of) the mentioned member function directly into the derived class's interface. If a base class member has a signature that is identical to a derived class member then compilation will fail (a `using Auto::mass` declaration cannot be added to `Truck`'s interface). Now code may use `truck.setMass(5000)` as well as `truck.setMass(5000, 2000)`.

Using declarations obey access rights. To prevent non-class members from using `setMass(5000)` without a scope resolution operator but allowing derived class members to do so the `using Auto::setMass` declaration should be put in the class `Truck`'s private section.

- The function `mass` is also already defined in `Auto`, as it was inherited from `Vehicle`. In this case, the class `Truck` should *redefine* this member function to allow for the extra (trailer) mass in the `Truck`:

```
size_t Truck::mass() const
{
    return
        (
            Auto::mass() +      // sum of:
            d_trailer_mass      // tractor part plus
                               // the trailer
        );
}
```

Example:

```
int main()
{
    Land veh(1200, 145);
    Truck lorry(3000, 120, "Juggernaut", 2500);

    lorry.Vehicle::setMass(4000);

    cout << '\n' << "Truck weighs " <<
        lorry.Vehicle::mass() << '\n' <<
        "Truck + trailer weighs " << lorry.mass() << '\n' <<
        "Speed is " << lorry.speed() << '\n' <<
        "Name is " << lorry.name() << '\n';
}
```

The class `Truck` was derived from `Auto`. However, one might question this class design. Since a truck is conceived of as a combination of an tractor and a trailer it is probably better defined using composition. This changes our point of view from a `Truck` *being* an `Auto` (and some strangely appearing data members) to a `Truck` *consisting of* an `Auto` (the tractor) and a `Vehicle` (the trailer). `Truck`'s interface will be very specific, not requiring users to study `Auto`'s and `Vehicle`'s interfaces and it opens up possibilities for defining 'road trains': tractors towing multiple trailers. Here is an example of such an alternate class setup:

```
class Truck
{
    Auto d_lorry;
    Vehicle d_trailer;      // use vector<Vehicle> for road trains

public:
    Truck();
    Truck(size_t tractor_wt, size_t speed, char const *name,
          size_t trailer_wt);

    void setMass(size_t tractor_wt, size_t trailer_wt);
    void setTractorMass(size_t tractor_wt);
    void setTrailerMass(size_t trailer_wt);
    size_t mass() const;
    size_t tractorMass() const;
    size_t trailerMass() const;
    // consider:
    Auto const &tractor() const;
    Vehicle const &trailer() const;
};
```

13.5 Multiple inheritance

Up to now, a class has always been derived from a single base class. In addition to single inheritance **C++** also supports *multiple inheritance*. In multiple inheritance a class is derived from several base classes and hence inherits functionality from multiple parent classes at the same time.

When using multiple inheritance it should be defensible to consider the newly derived class an instantiation of both base classes. Otherwise, composition is more appropriate. In general, linear derivation (using only one base class) is used much more frequently than multiple derivation. Good class design dictates that a class should have a single, well described responsibility and that principle often conflicts with multiple inheritance where we can state that objects of class `Derived` are *both* `Base1` and `Base2` objects.

But then, consider *the* prototype of an object for which multiple inheritance was used to its extreme: the *Swiss army knife*! This object *is* a knife, *it is* a pair of scissors, *it is* a can-opener, *it is* a corkscrew, *it is*

The ‘Swiss army knife’ is an extreme example of multiple inheritance. In **C++** there *are* some good reasons, not violating the ‘one class, one responsibility’ principle that will be covered in the next chapter. In this section the technical details of constructing classes using multiple inheritance are discussed.

How to construct a ‘Swiss army knife’ in **C++**? First we need (at least) two base classes. For example, let’s assume we are designing a toolkit allowing us to construct an instrument panel of an aircraft’s cockpit. We design all kinds of instruments, like an artificial horizon and an altimeter. One of the components that is often seen in aircraft is a *nav-com set*: a combination of a navigational beacon receiver (the ‘nav’ part) and a radio communication unit (the ‘com’-part). To define the nav-com set, we start by designing the `NavSet` class (assume the existence of the classes `Intercom`, `VHF_Dial` and `Message`):

```
class NavSet
{
    public:
        NavSet(Intercom &intercom, VHF_Dial &dial);

        size_t activeFrequency() const;
        size_t standByFrequency() const;

        void setStandByFrequency(size_t freq);
        size_t toggleActiveStandby();
        void setVolume(size_t level);
        void identEmphasis(bool on_off);
};
```

Next we design the class `ComSet`:

```
class ComSet
{
    public:
        ComSet(Intercom &intercom);

        size_t frequency() const;
        size_t passiveFrequency() const;

        void setPassiveFrequency(size_t freq);
        size_t toggleFrequencies();

        void setAudioLevel(size_t level);
        void powerOn(bool on_off);
        void testState(bool on_off);
};
```

```

        void transmit(Message &message);
    };

```

Using objects of this class we can receive messages, transmitted though the `Intercom`, but we can also *transmit* messages using a `Message` object that's passed to the `ComSet` object using its `transmit` member function.

Now we're ready to construct our `NavComSet` set:

```

class NavComSet: public ComSet, public NavSet
{
    public:
        NavComSet(Intercom &intercom, VHF_Dial &dial);
};

```

Done. Now we have defined a `NavComSet` which is *both* a `NavSet` *and* a `ComSet`: the facilities of both base classes are now available in the derived class using multiple inheritance.

Please note the following:

- The keyword `public` is present before both base class names (`NavSet` and `ComSet`). By default inheritance uses *private derivation* and the keyword `public` must be repeated before each of the base class specifications. Base classes are not required to use the same derivation type. One base class could have `public` derivation and another base class could use `private` derivation.
- The multiply derived class `NavComSet` introduces no additional functionality of its own, but merely combines two existing classes into a new aggregate class. Thus, **C++** offers the possibility to simply sweep multiple simple classes into one more complex class.
- Here is the implementation of The `NavComSet` constructor:

```

NavComSet::NavComSet(Intercom &intercom, VHF_Dial &dial)
:
    ComSet(intercom),
    NavSet(intercom, dial)
{}

```

The constructor requires no extra code: Its purpose is to activate the constructors of its base classes. The order in which the base class initializers are called is *not* dictated by their calling order in the constructor's code, but by the ordering of the base classes in the class interface.

- The `NavComSet` class definition requires no additional data members or member functions: here (and often) the inherited interfaces provide all the required functionality and data for the multiply derived class to operate properly.

Of course, while defining the base classes, we made life easy on ourselves by strictly using different member function names. So, there is a function `setVolume` in the `NavSet` class and a function `setAudioLevel` in the `ComSet` class. A bit cheating, since we could expect that both units in fact have a composed object `Amplifier`, handling the volume setting. A revised class might offer an `Amplifier &lifier() const` member function, and leave it to the application to set up its own interface to the amplifier. Alternatively, a revised class could define members for setting the volume of either the `NavSet` or the `ComSet` parts.

In situations where two base classes offer identically named members special provisions need to be made to prevent ambiguity:

- The intended base class can explicitly be specified using the base class name and scope resolution operator:

```

NavComSet navcom(intercom, dial);

```

```
navcom.NavSet::setVolume(5);    // sets the NavSet volume level
navcom.ComSet::setVolume(5);    // sets the ComSet volume level
```

- The class interface is provided with member functions that can be called unambiguously. These additional members are usually defined inline:

```
class NavComSet: public ComSet, public NavSet
{
    public:
        NavComSet(Intercom &intercom, VHF_Dial &dial);
        void comVolume(size_t volume);
        void navVolume(size_t volume);
};
inline void NavComSet::comVolume(size_t volume)
{
    ComSet::setVolume(volume);
}
inline void NavComSet::navVolume(size_t volume)
{
    NavSet::setVolume(volume);
}
```

- If the NavComSet class is obtained from a third party, and cannot be modified, a disambiguating wrapper class may be used:

```
class MyNavComSet: public NavComSet
{
    public:
        MyNavComSet(Intercom &intercom, VHF_Dial &dial);
        void comVolume(size_t volume);
        void navVolume(size_t volume);
};
inline MyNavComSet::MyNavComSet(Intercom &intercom, VHF_Dial &dial)
:
    NavComSet(intercom, dial);
{}
inline void MyNavComSet::comVolume(size_t volume)
{
    ComSet::setVolume(volume);
}
inline void MyNavComSet::navVolume(size_t volume)
{
    NavSet::setVolume(volume);
}
```

13.6 Public, protected and private derivation

With inheritance public derivation is frequently used. When public derivation is used the access rights of the base class's interface remains unaltered in the derived class. But the type of inheritance may also be defined as *private* or *protected*.

Protected derivation is used when the keyword `protected` is put in front of the derived class's base class:

```
class Derived: protected Base
```

When protected derivation is used all the base class's public and protected members become protected members in the derived class. The derived class may access all the base class's public and protected members. Classes in turn derived from the derived class will view the base class's members as protected, and other code (outside of the inheritance tree) will not be able to access the base class's members.

Private derivation is used when the keyword `private` is put in front of the derived class's base class:

```
class Derived: private Base
```

When private derivation is used all the base class's members turn into private members in the derived class. The derived class members may access all base class public and protected members but base class members cannot be used elsewhere.

Public derivation should be used to define an *is-a* relationship between a derived class and a base class: the derived class object *is-a* base class object allowing the derived class object to be used polymorphically as a base class object in code expecting a base class object. Private inheritance is used in situations where a derived class object is defined in-terms-of the base class where composition cannot be used. There's little documented use for protected inheritance, but one could maybe encounter protected inheritance when defining a base class that is itself a derived class and needs to make its base class members available to classes derived from itself.

Combinations of inheritance types do occur. For example, when designing a stream-class it is usually derived from `std::istream` or `std::ostream`. However, before a stream can be constructed, a `std::streambuf` must be available. Taking advantage of the fact that the inheritance order is defined in the class interface, we use multiple inheritance (see section 13.5) to derive the class from both `std::streambuf` and (then) from `std::ostream`. To the class's users it is a `std::ostream` and not a `std::streambuf`. So private derivation is used for the latter, and public derivation for the former class:

```
class Derived: private std::streambuf, public std::ostream
```

13.6.1 Promoting access rights

When private or protected derivation is used, users of derived class objects are denied access to the base class members. Private derivation denies access to all base class members to users of the derived class, protected derivation does the same, but allows classes that are in turn derived from the derived class to access the base class's public and protected members.

In some situations this scheme is too restrictive. Consider a class `RandStream` derived privately from a class `RandBuf` which is itself derived from `std::streambuf` and also publicly from `istream`:

```
class RandBuf: public std::streambuf
{
    // implements a buffer for random numbers
};
class RandStream: private RandBuf, public std::istream
{
    // implements a stream to extract random values from
};
```

Such a class could be used to extract, e.g., random numbers using the standard `istream` interface.

Although the `RandStream` class is constructed with the functionality of `istream` objects in mind, some of the members of the class `std::streambuf` may be considered useful by themselves. E.g., the function `streambuf::in_avail` returns a lower bound to the number of characters that can be read immediately. The standard way to make this function available is to define a *shadow member* calling the base class's member:


```

class RandStream: private RandBuf, public std::istream
{
    // implements a stream to extract random values from
    public:
        std::streamsize in_avail();
};
inline std::streamsize RandStream::in_avail()
{
    return std::streambuf::in_avail();
}

```

This looks like a lot of work for just making available a member from the protected or private base classes. If the intent is to make available the `in_avail` member *access promotion* can be used. Access promotion allows us to specify which members of private (or protected) base classes become available in the protected (or public) interface of the derived class. Here is the above example, now using access promotion:

```

class RandStream: private RandBuf, public std::istream
{
    // implements a stream to extract random values from
    public:
        using std::streambuf::in_avail;
};

```

It should be noted that access promotion makes available all overloaded versions of the declared base class member. So, if `streambuf` would offer not only `in_avail` but also, e.g., `in_avail(size_t *)` *both* members would become part of the public interface.

13.7 Conversions between base classes and derived classes

When public inheritance is used to define classes, an object of a derived class *is* at the same time an object of the base class. This has important consequences for object assignment and for the situation where pointers or references to such objects are used. Both situations will be discussed now.

13.7.1 Conversions with object assignments

Continuing our discussion of the `NavCom` class, introduced in section 13.5, we now define two objects, a base class and a derived class object:

```

ComSet com(intercom);
NavComSet navcom(intercom2, dial2);

```

The object `navcom` is constructed using an `Intercom` and a `VHF_Dial` object. However, a `NavComSet` is at the same time a `ComSet`, allowing the assignment *from* `navcom` (a derived class object) *to* `com` (a base class object):

```

com = navcom;

```

The effect of this assignment will be that the object `com` will now communicate with `intercom2`. As a `ComSet` does not have a `VHF_Dial`, the `navcom`'s `dial` is ignored by the assignment. When assigning a base class object from a derived class object only the base class data members are assigned, other data members are dropped, a phenomenon called *slicing*. In situations like these slicing probably does not have serious consequences, but when passing derived class objects to functions defining base class

parameters or when returning derived class objects from functions returning base class objects slicing also occurs and might have unwelcome side-effects.

The assignment from a base class object to a derived class object is problematic. In a statement like

```
navcom = com;
```

it isn't clear how to reassign the NavComSet's VHF_Dial data member as they are missing in the ComSet object com. Such an assignment is therefore refused by the compiler. Although derived class objects are also base class objects, the reverse does not hold true: a base class object is not also a derived class object.

The following general rule applies: in assignments in which base class objects and derived class objects are involved, assignments in which data are dropped are legal (called *slicing*). Assignments in which data remain unspecified are *not* allowed. Of course, it is possible to overload an assignment operator to allow the assignment of a derived class object from a base class object. To compile the statement

```
navcom = com;
```

the class NavComSet must have defined an overloaded assignment operator accepting a ComSet object for its argument. In that case it's up to the programmer to decide what the assignment operator will do with the missing data.

13.7.2 Conversions with pointer assignments

We return to our Vehicle classes, and define the following objects and pointer variable:

```
Land land(1200, 130);
Auto auto(500, 75, "Daf");
Truck truck(2600, 120, "Mercedes", 6000);
Vehicle *vp;
```

Now we can assign the addresses of the three objects of the derived classes to the Vehicle pointer:

```
vp = &land;
vp = &auto;
vp = &truck;
```

Each of these assignments is acceptable. However, an implicit conversion of the derived class to the base class Vehicle is used, since vp is defined as a pointer to a Vehicle. Hence, when using vp only the member functions manipulating mass can be called as this is the Vehicle's *only* functionality. As far as the compiler can tell this is the object vp points to.

The same holds true for references to Vehicles. If, e.g., a function is defined having a Vehicle reference parameter, the function may be passed an object of a class derived from Vehicle. Inside the function, the specific Vehicle members remain accessible. This analogy between pointers and references holds true in general. Remember that a reference is nothing but a pointer in disguise: it mimics a plain variable, but actually it is a pointer.

This restricted functionality has an important consequence for the class Truck. Following vp = &truck, vp points to a Truck object. So, vp->mass() will return 2600 instead of 8600 (the combined mass of the cabin and of the trailer: 2600 + 6000), which would have been returned by truck.mass().

When a function is called using a pointer to an object, then the *type of the pointer* (and not the type of the object) determines which member functions are available and will be executed. In other words, C++ implicitly converts the type of an object reached through a pointer to the pointer's type.

If the actual type of the object pointed to by a pointer is known, an explicit type cast can be used to access the full set of member functions that are available for the object:

```
Truck truck;
Vehicle *vp;

vp = &truck;           // vp now points to a truck object

Truck *trp;

trp = reinterpret_cast<Truck *>(vp);
cout << "Make: " << trp->name() << '\n';
```

Here, the second to last statement specifically casts a `Vehicle *` variable to a `Truck *`. As usual (with type casts), this code is not without risk. It will *only* work if `vp` really points to a `Truck`. Otherwise the program may produce unexpected results.

13.8 Using non-default constructors with new[]

An often heard complaint is that operator `new[]` calls the default constructor of a class to initialize the allocated objects. For example, to allocate an array of 10 strings we can do

```
new string[10];
```

but it is not possible to use another constructor. Assuming that we'd want to initialize the strings with the text `hello world`, we can't write something like:

```
new string("hello world")[10];
```

The initialization of a dynamically allocated object usually consists of a two-step process: first the array is allocated (implicitly calling the default constructor); second the array's elements are initialized, as in the following little example:

```
string *sp = new string[10];
fill(sp, sp + 10, string("hello world"));
```

These approaches all suffer from 'double initializations', comparable to not using member initializers in constructors.

One way to avoid double initialization is to use inheritance. Inheritance can profitably be used to call non-default constructors in combination with operator `new[]`. The approach capitalizes on the following:

- A base class pointer may point to a derived class object;
- A derived class without (non-static) data members has the same size as its base class.

The above also suggests a possible approach:

- Derive a simple, member-less class from the class we're interested in;
- Use the appropriate base class initializer in its default constructor;
- Allocate the required number of derived class objects, and assign `new[]`'s return expression to a pointer to base class objects.

Here is a simple example, producing 10 lines containing the text `hello world`:

```
#include <iostream>
#include <string>
#include <algorithm>
#include <iterator>

using namespace std;

struct Xstr: public string
{
    Xstr()
    :
        string("hello world")
    {}
};

int main()
{
    string *sp = new Xstr[10];
    copy(sp, sp + 10, ostream_iterator<string>(cout, "\n"));
}
```

Of course, the above example is fairly unsophisticated, but it's easy to polish the example: the class `Xstr` can be defined in an anonymous namespace, accessible only to a function `getString()` which may be given a `size_t nObjects` parameter, allowing users to specify the number of `hello world`-initialized strings they would like to allocate.

Instead of hard-coding the base class arguments it's also possible to use variables or functions providing the appropriate values for the base class constructor's arguments. In the next example a *local class* `Xstr` is defined inside a function `nStrings(size_t nObjects, char const *fname)`, expecting the number of `string` objects to allocate and the name of a file whose subsequent lines are used to initialize the objects. The local class is invisible outside of the function `nStrings`, so no special namespace safeguards are required.

As discussed in section 7.7, members of local classes cannot access local variables from their surrounding function. However, they can access global and static data defined by the surrounding function.

Using a local class neatly allows us to hide the implementation details within the function `nStrings`, which simply opens the file, allocates the objects, and closes the file again. Since the local class is derived from `string`, it can use any `string` constructor for its base class initializer. In this particular case it calls the `string(char const *)` constructor, providing it with subsequent lines of the just opened stream via its static member function `nextLine()`. This latter function is, as it is a static member function, available to `Xstr` default constructor's member initializers even though no `Xstr` object is available by that time.

```
#include <fstream>
#include <iostream>
#include <string>
#include <algorithm>
#include <iterator>

using namespace std;

string *nStrings(size_t size, char const *fname)
{
    static ifstream in;

    struct Xstr: public string
```

```

{
    Xstr()
    :
        string(nextLine())
    {}
    static char const *nextLine()
    {
        static string line;

        getline(in, line);
        return line.c_str();
    }
};
in.open(fname);
string *sp = new Xstr[10];
in.close();

return sp;
}

int main()
{
    string *sp = nStrings(10, "nstrings.cc");
    copy(sp, sp + 10, ostream_iterator<string>(cout, "\n"));
}

```

When this program is run, it displays the first 10 lines of the file `nstrings.cc`.

Note that the above implementation can't safely be used in a multithreaded environment. In that case a *mutex* should be used to protect the three statements just before the function's return statement.

A completely different way to avoid the double initialization (not using inheritance) is to use placement new (cf. section 8.1.5): simply allocate the required amount of memory followed by the proper in-place allocation of the objects, using the appropriate constructors. The following example can also be used in multithreaded environments. The approach uses a pair of static construct/destroy members to perform the required initialization.

In the program shown below `construct` expects a `istream` that provides the initialization strings for objects of a class `String` simply containing a `std::string` object. `Construct` first allocates enough memory for the `n` `String` objects plus room for an initial `size_t` value. This initial `size_t` value is then initialized with `n`. Next, in a `for` statement, lines are read from the provided stream and the lines are passed to the constructors, using placement new calls. Finally the address of the first `String` object is returned.

The member `destroy` handles the destruction of the objects. It retrieves the number of objects to destroy from the `size_t` it finds just before the location of the address of the first object to destroy. The objects are then destroyed by explicitly calling their destructors. Finally the raw memory, originally allocated by `construct` is returned.

```

#include <fstream>
#include <iostream>
#include <string>
using namespace std;

class String
{
    union Ptrs
    {
        void *vp;
        String *sp;
    }
};

```

```

        size_t *np;
    };

    std::string d_str;

public:
    String(std::string const &txt)
    :
        d_str(txt)
    {}
    ~String()
    {
        cout << "destructor: " << d_str << '\n';
    }
    static String *construct(istream &in, size_t n)
    {
        Ptrs p = {operator new(n * sizeof(String) + sizeof(size_t))};
        *p.np++ = n;

        string line;
        for (size_t idx = 0; idx != n; ++idx)
        {
            getline(in, line);
            new(p.sp + idx) String(line);
        }

        return p.sp;
    }
    static void destroy(String *sp)
    {
        Ptrs p = {sp};
        --p.np;
        for (size_t n = *p.np; n--; )
            sp++->~String();

        operator delete (p.vp);
    }
};

int main()
{
    String *sp = String::construct(cin, 5);

    String::destroy(sp);
}

/*
After providing 5 lines containing, respectively
    alfa, bravo, charlie, delta, echo
the program displays:
    destructor: alfa
    destructor: bravo
    destructor: charlie
    destructor: delta
    destructor: echo
*/

```

Chapter 14

Polymorphism

Using inheritance classes may be derived from other classes, called base classes. In the previous chapter we saw that base class pointers may be used to point to derived class objects. We also saw that when a base class pointer points to an object of a derived class it is the type of the pointer rather than the type of the object it points to what determines which member functions are visible. So when a `Vehicle *vp`, points to an `Auto` object `Auto`'s `speed` or `brandName` members can't be used.

In the previous chapter two fundamental ways classes may be related to each other were discussed: a class may be *implemented-in-terms-of* another class and it can be stated that a derived class *is-a* base class. The former relationship is usually implemented using composition, the latter is usually implemented using a special form of inheritance, called *polymorphism*, the topic of this chapter.

An *is-a* relationship between classes allows us to apply the *Liskov Substitution Principle (LSP)* according to which a derived class object may be passed to and used by code expecting a pointer or reference to a base class object. In the **C++** Annotations so far the LSP has been applied many times. Every time an `ostream`, `ofstream` or `fstream` was passed to functions expecting an `ostream` we've been applying this principle. In this chapter we'll discover how to design our own classes accordingly.

LSP is implemented using a technique called *polymorphism*: although a base class pointer is used it will perform actions defined in the (derived) class of the object it actually points to. So, a `Vehicle *vp` might behave like an `Auto *` when pointing to an `Auto`¹.

Polymorphism is implemented using a feature called *late binding*. It's called that way because the decision *which* function to call (a base class function or a function of a derived class) cannot be made *compile-time*, but is postponed until the program is actually executed: only then it is determined which member function will actually be called.

In **C++** late binding is *not* the default way functions are called. By default *static binding* (or *early binding*) is used. With static binding the functions that are called are determined by the compiler, merely using the class types of objects, object pointers or object references.

Late binding is an inherently different (and slightly slower) process as it is decided run-time, rather than compile-time what function will be called. As **C++** supports *both* late- and early-binding **C++** programmers are offered an option as to what kind of binding to use. Choices can be optimized to the situations at hand. Many other languages offering object oriented facilities (e.g., **Java**) only or by default offer late binding. **C++** programmers should be keenly aware of this. Expecting early binding and getting late binding may easily produce nasty bugs.

Let's look at a simple example to start appreciating the differences between late and early binding. The example merely illustrates. Explanations of *why* things are as shown will shortly be provided.

Consider the following little program:

¹In one of the StarTrek movies, Capt. Kirk was in trouble, as usual. He met an extremely beautiful lady who, however, later on changed into a hideous troll. Kirk was quite surprised, but the lady told him: "Didn't you know I am a polymorph?"

```

#include <iostream>
using namespace std;

class Base
{
    protected:
        void hello()
        {
            cout << "base hello\n";
        }
    public:
        void process()
        {
            hello();
        }
};

class Derived: public Base
{
    protected:
        void hello()
        {
            cout << "derived hello\n";
        }
};

int main()
{
    Derived derived;

    derived.process();
}

```

The important characteristic of the above program is the `Base::process` function, calling `hello`. As `process` is the only member that is defined in the public interface it is the only member that can be called by code not belonging to the two classes. The class `Derived`, derived from `Base` clearly inherits `Base`'s interface and so `process` is also available in `Derived`. So the `Derived` object in `main` is able to call `process`, but not `hello`.

So far, so good. Nothing new, all this was covered in the previous chapter. One may wonder why `Derived` was defined at all. It was presumably defined to create an implementation of `hello` that's appropriate for `Derived` but differing from `Base::hello`'s implementation. `Derived`'s author's reasoning was as follows: `Base`'s implementation of `hello` is not appropriate; a `Derived` class object can remedy that by providing an appropriate implementation. Furthermore our author reasoned:

“since the type of an object determines the interface that is used, `process` must call `Derived::hello` as `hello` is called via `process` from a `Derived` class object”.

Unfortunately our author's reasoning is flawed, due to static binding. When `Base::process` was compiled static binding caused the compiler to fixate the `hello` call to `Base::hello()`.

The author *intended* to create a `Derived` class that is-a `Base` class. That only partially succeeded: `Base`'s interface was inherited, but after that `Derived` has relinquished all control over what happens. Once we're in `process` we're only able to see `Base`'s member implementations. Polymorphism offers a way out, allowing us to redefine (in a derived class) members of a base class allowing these redefined members to be used from the base class's interface.

This is the essence of LSP: public inheritance should not be used to reuse the base class members (in derived classes) but to be reused (by the base class, polymorphically using derived class members reimplementing base class members).

Take a second to appreciate the implications of the above little program. The `hello` and `process` mem-

bers aren't too impressive, but the implications of the example are. The `process` member could implement directory travel, `hello` could define the action to perform when encountering a file. `Base::hello` might simply show the name of a file, but `Derived::hello` might delete the file; might only list its name if it's younger than a certain age; might list its name if it contains a certain text; etc., etc.. Up to now `Derived` would have to implement `process`'s actions itself; Up to now code expecting a `Base` class reference or pointer could only perform `Base`'s actions. Polymorphism allows us to reimplement members of base classes and to use those reimplemented members in code expecting base class references or pointers. Using polymorphism existing code may be reused by derived classes reimplementing the appropriate members of their base classes. It's about time to uncover how this magic can be realized.

Polymorphism, which is not the default in **C++**, solves the problem and allows the author of the classes to reach its goal. For the curious reader: prefix `void hello()` in the `Base` class with the keyword `virtual` and recompile. Running the modified program produces the intended and expected derived `hello`. Why this happens is explained next.

14.1 Virtual functions

By default the behavior of a member function called via a pointer or reference is determined by the implementation of that function in the pointer's or reference's class. E.g., a `Vehicle *` will activate `Vehicle`'s member functions, even when pointing to an object of a derived class. This is known as *early* or *static* binding: the function to call is determined compile-time. In **C++** *late* or *dynamic* binding is realized using *virtual member functions*.

A member function becomes a virtual member function when its declaration starts with the keyword `virtual`. It is stressed once again that in **C++**, different from several other object oriented languages, this is *not* the default situation. By default *static* binding is used.

Once a function is declared `virtual` in a base class, it remains virtual in all derived classes; even when the keyword `virtual` is not repeated in derived classes.

In the vehicle classification system (see section 13.1) the two member functions `mass` and `setMass` might be declared `virtual`. Concentrating on `mass` The relevant sections of the class definitions of the class `Vehicle` and `Truck` are shown below. Also, we show the implementations of the member function `mass`:

```
class Vehicle
{
    public:
        virtual int mass() const;
};
class Truck: // inherited from Vehicle through Auto and Land
{
    // not altered
};
int Vehicle::mass() const
{
    return d_mass;
}

int Truck::mass() const
{
    return Auto::mass() + d_trailer_wt;
}
```

The keyword `virtual` *only* appears in the (`Vehicle`) base class. There is no need (but there is also no penalty) to repeat it in derived classes. Once a class member has been declared `virtual` it will be virtual in all derived classes. A member function may be declared `virtual` *anywhere* in a class hierarchy. The compiler will be perfectly happy if `mass` is declared `virtual` in `Auto`, rather than in

Vehicle. The specific characteristics of virtual member functions would then only be available for Auto objects and for objects of classes derived from Auto. For a Vehicle pointer static binding would remain to be used. The effect of late binding is illustrated below:

```
Vehicle v(1200);           // vehicle with mass 1200
Truck t(6000, 115,        // truck with cabin mass 6000, speed 115,
    "Scania", 15000);     // make Scania, trailer mass 15000
Vehicle *vp;              // generic vehicle pointer

int main()
{
    vp = &v;               // see (1) below
    cout << vp->mass() << '\n';

    vp = &t;               // see (2) below
    cout << vp->mass() << '\n';

    cout << vp->speed() << '\n';    // see (3) below
}
```

Now that mass is defined virtual, late binding will be used:

- at (1), `Vehicle::mass` is called.
- at (2) `Truck::mass` is called.
- at (3) a syntax error is generated. The member `speed` is no member of `Vehicle`, and hence not callable via a `Vehicle*`.

The example illustrates that when a pointer to a class is used *only the members of that class can be called*. These functions may or may not be virtual. A member's virtual characteristic only influences the type of binding (early vs. late), not the set of member functions that is visible to the pointer.

Through virtual members derived classes may redefine the behavior performed by functions called from base class members or from pointers or references to base class objects. This redefinition of base class members by derived classes is called *overriding members*.

14.2 Virtual destructors

When an object ceases to exist the object's destructor is called. Now consider the following code fragment (cf. section 13.1):

```
Vehicle *vp = new Land(1000, 120);

delete vp;           // object destroyed
```

Here `delete` is applied to a base class pointer. As the base class defines the available interface `delete vp` calls `~Vehicle` and `~Land` remains out of sight. Assuming that `Land` allocates memory a memory leak results. Freeing memory is not the only action destructors can perform. In general they may perform any action that's necessary when an object ceases to exist. But here none of the actions defined by `~Land` will be performed. Bad news....

In C++ this problem is solved by *virtual destructors*. A destructor can be declared virtual. When a base class destructor is declared virtual the destructor of the actual class pointed to by a base class

pointer `bp` will be called when executing `delete bp`. Thus, late binding is realized for destructors even though the destructors of derived classes have unique names. Example:

```
class Vehicle
{
    public:
        virtual ~Vehicle();    // all derived class destructors are
                                // now virtual as well.
};
```

By declaring a virtual destructor, the above `delete` operation (`delete vp`) will correctly call `Land`'s destructor, rather than `Vehicle`'s destructor.

Once a destructor is called it will perform as usual, whether or not it is a virtual destructor. So, `~Land` will first execute its own statements and will then call `~Vehicle`. Thus, the above `delete vp` statement will use late binding to call `~Vehicle` and from this point on the object destruction proceeds as usual.

Destructors should always be defined `virtual` in classes designed as a base class from which other classes are going to be derived. Often those destructors themselves have no tasks to perform. In these cases the virtual destructor is given an empty body. For example, the definition of `Vehicle::~~Vehicle()` may be as simple as:

```
Vehicle::~~Vehicle()
{ }
```

Resist the temptation to define destructors (even empty destructors) inline as this will complicate class maintenance. Section 14.9 discusses the reason behind this rule of thumb.

14.3 Pure virtual functions

The base class `Vehicle` is provided with its own concrete implementations of its virtual members (`mass` and `setMass`). However, virtual member functions not necessarily *have* to be implemented in base classes.

When the implementations of virtual members are omitted from base classes the class imposes requirements upon derived classes. The derived classes are required to provide the 'missing implementations'

This approach, in some languages (like **C#**, **Delphi** and **Java**) known as an *interface*, defines a *protocol*. Derived classes *must* obey the protocol by implementing the as yet not implemented members. If a class contains at least one member whose implementation is missing no objects of that class can be defined.

Such incompletely defined classes are always base classes. They enforce a protocol by merely declaring names, return values and arguments of some of their members. These classes are called *abstract classes* or *abstract base classes*. Derived classes become non-abstract classes by implementing the as yet not implemented members.

Abstract base classes are the foundation of many *design patterns* (cf. *Gamma et al.* (1995)), allowing the programmer to create highly *reusable software*. Some of these design patterns are covered by the **C++** Annotations (e.g, the *Template Method* in section 23.3), but for a thorough discussion of design patterns the reader is referred to *Gamma et al.*'s book.

Members that are merely declared in base classes are called *pure virtual functions*. A virtual member becomes a pure virtual member by postfixing `= 0` to its declaration (i.e., by replacing the semicolon ending its declaration by `= 0;`). Example:

```
#include <iosfwd>
class Base
```

```

{
    public:
        virtual ~Base();
        virtual std::ostream &insertInto(std::ostream &out) const = 0;
};
inline std::ostream &operator<<(std::ostream &out, Base const &base)
{
    return base.insertInto(out);
}

```

All classes derived from `Object` *must* implement the `insertInto` member function, or their objects cannot be constructed. This is neat: all objects derived from `Object` can now always be inserted into `ostream` objects.

Could the virtual destructor of a base class ever be a pure virtual function? The answer to this question is no. First of all, there is no need to enforce the availability of destructors in derived classes as destructors are provided by default (unless a destructor is declared with the `= delete` attribute using the new C++0x standard). Second, if it is a pure virtual member its implementation does not exist, but derived class destructors will eventually call their base class destructors. How could they call base class destructors if their implementations are lacking? More about this in the next section.

Often, but not necessarily, pure virtual member functions are `const` member functions. This allows the construction of constant derived class objects. In other situations this might not be necessary (or realistic), and non-constant member functions might be required. The general rule for `const` member functions also applies to pure virtual functions: if the member function alters the object's data members, it cannot be a `const` member function.

Abstract base classes frequently don't have data members. However, once a base class declares a pure virtual member it *must* be declared identically in derived classes. If the implementation of a pure virtual function in a derived class alters the derived class object's data, then *that* function cannot be declared as a `const` member. Therefore, the author of an abstract base class should carefully consider whether a pure virtual member function should be a `const` member function or not.

14.3.1 Implementing pure virtual functions

Pure virtual member functions may be implemented. To implement a pure virtual member function: pure virtual implementation member function, provide it with its normal `= 0;` specification, but implement it as well. Since the `= 0;` ends in a semicolon, the pure virtual member is always at most a declaration in its class, but an implementation may either be provided outside from its interface (maybe using `inline`).

Pure virtual member functions may be called from derived class objects or from its class or derived class members by specifying the base class and scope resolution operator together with the member to be called. Example:

```

#include <iostream>

class Base
{
    public:
        virtual ~Base();
        virtual void pureimp() = 0;
};
Base::~~Base()
{}
void Base::pureimp()
{
    std::cout << "Base::pureimp() called\n";
}

```

```

}
class Derived: public Base
{
    public:
        virtual void pureimp();
};
inline void Derived::pureimp()
{
    Base::pureimp();
    std::cout << "Derived::pureimp() called\n";
}
int main()
{
    Derived derived;

    derived.pureimp();
    derived.Base::pureimp();

    Derived *dp = &derived;

    dp->pureimp();
    dp->Base::pureimp();
}
// Output:
//      Base::pureimp() called
//      Derived::pureimp() called
//      Base::pureimp() called
//      Base::pureimp() called
//      Derived::pureimp() called
//      Base::pureimp() called

```

Implementing a pure virtual member has limited use. One could argue that the pure virtual member function's implementation may be used to perform tasks that can already be performed at the base class level. However, there is no guarantee that the base class virtual member function will actually be called. Therefore a base class specific tasks could as well be offered by a separate member, without blurring the distinction between a member doing some work and a pure virtual member enforcing a protocol.

14.4 Virtual functions and multiple inheritance

In chapter 6 we encountered the class `fstream`, one class offering features of `ifstream` and `ofstream`. In chapter 13 we learned that a class may be derived from multiple base classes. Such a derived class inherits the properties of all its base classes. Polymorphism can also be used in combination with multiple inheritance.

Consider what would happen if more than one 'path' leads from the derived class up to its (base) classes. This is illustrated in the next (fictitious) example where a class `Derived` is doubly derived from `Base`:

```

class Base
{
    int d_field;
    public:
        void setfield(int val);
        int field() const;
};
inline void Base::setfield(int val)
{

```




Figure 14.1: Duplication of a base class in multiple derivation.

```

    d_field = val;
}
inline int Base::field() const
{
    return d_field;
}

class Derived: public Base, public Base
{
};

```

Due to the double derivation, `Base`'s functionality now occurs twice in `Derived`. This results in ambiguity: when the function `setfield()` is called for a `Derived` class object, which function will that be as there are two of them? The scope resolution operator won't come to the rescue and so the **C++** compiler will not be able to compile the above example and will (correctly) identify an error.

The above code clearly duplicates its base class in the derivation, which can of course easily be avoided by not doubly deriving from `Base` (or by using composition (!)). But duplication of a base class can also occur through nested inheritance, where an object is derived from, e.g., an `Auto` and from an `Air` (cf. section 13.1). Such a class would be needed to represent, e.g., a flying car². An `AirAuto` would ultimately contain two `Vehicles`, and hence two mass fields, two `setMass()` functions and two `mass()` functions. Is this what we want?

14.4.1 Ambiguity in multiple inheritance

Let's investigate closer why an `AirAuto` introduces ambiguity, when derived from `Auto` and `Air`.

- An `AirAuto` is an `Auto`, hence a `Land`, and hence a `Vehicle`.
- However, an `AirAuto` is also an `Air`, and hence a `Vehicle`.

The duplication of `Vehicle` data is further illustrated in Figure 14.1. The internal organization of an `AirAuto` is shown in Figure 14.2. The **C++** compiler detects the ambiguity in an `AirAuto` object, and will therefore not compile statements like:

```

AirAuto jBond;
cout << jBond.mass() << '\n';

```

Which member function `mass` to call cannot be determined by the compiler but the programmer has two possibilities to resolve the ambiguity for the compiler:

²such as the one in James Bond vs. the Man with the Golden Gun...




Figure 14.2: Internal organization of an AirAuto object.

- First, the function call where the ambiguity originates can be modified. The ambiguity is resolved using the scope resolution operator:

```
// let's hope that the mass is kept in the Auto
// part of the object..
cout << jBond.Auto::mass() << '\n';
```

The scope resolution operator and the class name are put right before the name of the member function.

- Second, a dedicated function `mass` could be created for the class `AirAuto`:

```
int AirAuto::mass() const
{
    return Auto::mass();
}
```

The second possibility is preferred as it does not require the compiler to flag an error; nor does it require the programmer using the class `AirAuto` to take special precautions.

However, there exists a more elegant solution, discussed in the next section.

14.4.2 Virtual base classes

As illustrated in Figure 14.2, an `AirAuto` represents *two* Vehicles. This not only results in an ambiguity about which function to use to access the `mass` data, but it also defines two `mass` fields in an `AirAuto`. This is slightly redundant, since we can assume that an `AirAuto` has but one `mass`.

It is, however, possible to define an `AirAuto` as a class consisting of but one `Vehicle` and yet using multiple derivation. This is realized by defining the base classes that are multiply mentioned in a derived class's inheritance tree as a *virtual base class*.

For the class `AirAuto` this implies a small change when deriving an `AirAuto` from `Land` and `Air` classes:

```
class Land: virtual public Vehicle
{
    // etc
};
class Auto: public Land
{
    // etc
};
class Air: virtual public Vehicle
```




Figure 14.3: Internal organization of an AirAuto object when the base classes are virtual.

```

{
    // etc
};
class AirAuto: public Auto, public Air
{
};

```

Virtual derivation ensures that a Vehicle is only added once to a derived class. This means that the route along which a Vehicle is added to an AirAuto is no longer depending on its direct base classes; we can only state that an AirAuto is a Vehicle. The internal organization of an AirAuto after virtual derivation is shown in Figure 14.3.

When a class Third inherits from a base class Second which in turn inherits from a base class First then the First class constructor called by the Second class constructor is also used when this Second constructor is used when constructing a Third object. Example:

```

class First
{
public:
    First(int x);
};
class Second: public First
{
public:
    Second(int x)
    :
        First(x)
    {}
};
class Third: public Second
{
public:
    Third(int x)
    :
        Second(x)           // calls First(x)
    {}
};

```

The above no longer holds true when Second uses virtual derivation. When Second uses virtual derivation its base class constructor is *ignored* when Second's constructor is called from Third. Instead Second will by default call First's default constructor. This is illustrated by the next example:

```

class First
{

```



```

    public:
        First()
        {
            cout << "First()\n";
        }
        First(int x);
};
class Second: public virtual First      // note: virtual
{
    public:
        Second(int x)
        :
            First(x)
        {}
};
class Third: public Second
{
    public:
        Third(int x)
        :
            Second(x)
        {}
};
int main()
{
    Third third(3);      // displays 'First()'
}

```

When constructing `Third` `First`'s default constructor is used by default. `Third`'s constructor, however, may overrule this default behavior by explicitly specifying the constructor to use. Since the `First` object must be available before `Second` can be constructed it must be specified first. To call `First(int)` when constructing `Third(int)` the latter constructor can be defined as follows:

```

class Third: public Second
{
    public:
        Third(int x)
        :
            First(x),          // now First(int) is called.
            Second(x)
        {}
};

```

This behavior may seem puzzling when simple linear inheritance is used but it makes sense when multiple inheritance is used with base classes using virtual inheritance. Consider `AirAuto`: when `Air` and `Auto` both virtually inherit from `Vehicle` will `Air` and (`Auto`) both initialize the common `Vehicle` object? If so, which one will be called first? What if `Air` and `Auto` use different `Vehicle` constructors? All these questions can be avoided by passing the responsibility for the initialization of a common base class to the class eventually using the common base class object. In the above example `Third`. Hence `Third` is provided an opportunity to specify the constructor to use when initializing `First`.

Multiple inheritance may also be used to inherit from classes that do not all use virtual inheritance. Assume we have two classes, `Derived1` and `Derived2`, both (possibly virtually) derived from `Base`.

We will address the question which constructors will be called when calling a constructor of the class `Final: public Derived1, public Derived2`.

To distinguish the involved constructors `Base1` indicates the `Base` class constructor called as base class initializer for `Derived1` (and analogously: `Base2` called from `Derived2`). A plain `Base` indicates `Base`'s default constructor.

Derived1 and Derived2 indicate the base class initializers used when constructing a Final object.

Now we're ready to distinguish the various cases when constructing an object of the class Final:
 public Derived1, public Derived2:

- classes:

```
Derived1: public Base
Derived2: public Base
```

This is normal, non virtual multiple derivation. The following constructors are called in the order shown:

```
Base1,
Derived1,
Base2,
Derived2
```

- classes:

```
Derived1: public Base
Derived2: virtual public Base
```

Only Derived2 uses virtual derivation. Derived2's base class constructor is ignored. Instead, Base will be called and it will be called prior to any other constructor:

```
Base,
Base1,
Derived1,
Derived2
```

As only one class uses virtual derivation, there will still be *two* Base class objects in the eventual Final class.

- classes:

```
Derived1: virtual public Base
Derived2: public Base
```

Only Derived1 uses virtual derivation. Derived1's base class constructor is ignored. Instead, Base will be called and it will be called prior to any other constructor. Different from the first (non-virtual) case Base is now called, rather than Base1:

```
Base,
Derived1,
Base2,
Derived2
```

- classes:

```
Derived1: virtual public Base
Derived2: virtual public Base
```

Both base classes use virtual derivation and so only *one* Base class object will be present in the Final class object. The following constructors are called in the order shown:

```
Base,
Derived1,
Derived2
```

Virtual derivation is, in contrast to virtual functions, a pure compile-time issue. Virtual inheritance merely defines how the compiler defines a class's data organization and construction process.

14.4.3 When virtual derivation is not appropriate

Virtual inheritance can be used to merge multiply occurring base classes. However, situations may be encountered where multiple occurrences of base classes is appropriate. Consider the definition of a Truck (cf. section 13.4):

```
class Truck: public Auto
{
    int d_trailer_mass;

public:
    Truck();
    Truck(int engine_wt, int sp, char const *nm,
          int trailer_wt);

    void setMass(int engine_wt, int trailer_wt);
    int mass() const;
};

Truck::Truck(int engine_wt, int sp, char const *nm,
             int trailer_wt)
:
    Auto(engine_wt, sp, nm)
{
    d_trailer_mass = trailer_wt;
}

int Truck::mass() const
{
    return
        Auto::mass() +    // sum of:
        trailer_wt;       // engine part plus
                          // the trailer
}
```

This definition shows how a Truck object is constructed to contain two mass fields: one via its derivation from Auto and one via its own int d_trailer_mass data member. Such a definition is of course valid, but it could also be rewritten. We could derive a Truck from an Auto *and* from a Vehicle, thereby explicitly requesting the double presence of a Vehicle; one for the mass of the engine and cabin, and one for the mass of the trailer. A slight complication is that a class organization like

```
class Truck: public Auto, public Vehicle
```

is not accepted by the C++ compiler. As a Vehicle is already part of an Auto, it is therefore not needed once again. This organization may, however be forced using a small trick. By creating an additional class inheriting from Vehicle and deriving Truck from that additional class rather than directly from Vehicle the problem is solved. Simply derive a class TrailerVeh from Vehicle, and then Truck from Auto and TrailerVeh:

```
class TrailerVeh: public Vehicle
{
public:
    TrailerVeh(int wt)
    :
        Vehicle(wt)
    {}
};

class Truck: public Auto, public TrailerVeh
{
public:
```

```

    Truck();
    Truck(int engine_wt, int sp, char const *nm, int trailer_wt);
    void setMass(int engine_wt, int trailer_wt);
    int mass() const;
};
inline Truck::Truck(int engine_wt, int sp, char const *nm,
                    int trailer_wt)
:
    Auto(engine_wt, sp, nm),
    TrailerVeh(trailer_wt)
{}
inline int Truck::mass() const
{
    return
        Auto::mass() +           // sum of:
        TrailerVeh::mass();      // engine part plus
                                // the trailer
}

```

14.5 Run-time type identification

C++ offers two ways to (run-time) retrieve the type of objects and expressions. The possibilities of **C++**'s run-time type identification are limited compared to languages like **Java**. Usually static type checking and static type identification is used in **C++**. Static type checking is possibly safer and certainly more efficient than run-time type identification and should therefore be preferred over run-time type identification. But situations exist where run-time type identification is appropriate. **C++** offers run-time type identification through the *dynamic cast* and *typeid* operators.

- A `dynamic_cast` is used to convert a base class pointer or reference to a derived class pointer or reference. This is also known as *down-casting*.
- The `typeid` operator returns the actual type of an expression.

These operators can be used with objects of classes having at least one virtual member function.

14.5.1 The `dynamic_cast` operator

The `dynamic_cast<>` operator is used to convert a base class pointer or reference to, respectively, a derived class pointer or reference. This is also called *down-casting* the the direction of the cast is *down* the inheritance tree.

A dynamic cast is performed run-time. A prerequisite for using a dynamic cast is the existence of at least one virtual member function in the base class.

In the following example a pointer to the class `Derived` is obtained from the `Base` class pointer `bp`:

```

class Base
{
    public:
        virtual ~Base();
};
class Derived: public Base
{
    public:
        char const *toString();
};
inline char const *Derived::toString()

```

```

{
    return "Derived object";
}
int main()
{
    Base *bp;
    Derived *dp,
    Derived d;

    bp = &d;

    dp = dynamic_cast<Derived *>(bp);

    if (dp)
        cout << dp->toString() << '\n';
    else
        cout << "dynamic cast conversion failed\n";
}

```

In the condition of the above if statement the success of the dynamic cast is verified. This verification must be performed *run-time*, as the actual class of the objects to which the pointer points is only known then. If a base class pointer is provided, the dynamic cast operator returns 0 on failure and a pointer to the requested derived class on success.

Assume a `vector<Base *>` is used. Such a vector's pointers may point to objects of various classes, all derived from Base. A dynamic cast returns a pointer to the specified class if the base class pointer indeed points to an object of the specified class and returns 0 otherwise. So we could determine the actual class of an object a pointer points to by performing a series of checks to find the actual derived class to which a base class pointer points. Example:

```

class Base
{
public:
    virtual ~Base();
};
class Derived1: public Base;
class Derived2: public Base;

int main()
{
    vector<Base *> vb(initializeBase());

    Base *bp = vb.front();

    if (dynamic_cast<Derived1 *>(bp))
        cout << "bp points to a Derived1 class object\n";
    else if (dynamic_cast<Derived2 *>(bp))
        cout << "bp points to a Derived2 class object\n";
}

```

Alternatively, a reference to a base class object may be available. In this case the `dynamic_cast` operator will throw an exception if the down casting fails. Example:

```

#include <iostream>

class Base
{
public:

```

```

        virtual ~Base();
        virtual char const *toString();
};
inline char const *Base::toString()
{
    return "Base::toString() called";
}
class Derived1: public Base
{};
class Derived2: public Base
{};

Base::~~Base()
{}
void process(Base &b)
{
    try
    {
        std::cout << dynamic_cast<Derived1 &>(b).toString() << '\n';
    }
    catch (std::bad_cast)
    {}
    try
    {
        std::cout << dynamic_cast<Derived2 &>(b).toString() << '\n';
    }
    catch (std::bad_cast)
    {
        std::cout << "Bad cast to Derived2\n";
    }
}
int main()
{
    Derived1 d;
    process(d);
}
/*
    Generated output:

    Base::toString() called
    Bad cast to Derived2
*/

```

In this example the value `std::bad_cast` is used. A `std::bad_cast` exception is thrown if the dynamic cast of a reference to a derived class object fails.

Note the form of the catch clause: `bad_cast` is the name of a type. Section [17.4.1](#) describes how such a type can be defined.

The dynamic cast operator is a useful tool when an existing base class cannot or should not be modified (e.g., when the sources are not available), and a derived class may be modified instead. Code receiving a base class pointer or reference may then perform a dynamic cast to the derived class to access the derived class's functionality.

One may wonder what the difference is between a `dynamic_cast` and a `reinterpret_cast`. One of the differences is of course that the `dynamic_cast` can operate on references while the `reinterpret_cast` can only operate on pointers. But is there a difference when both arguments are pointers?

When the `reinterpret_cast` is used, we tell the compiler that it literally should re-interpret a block of memory as something else. A `reinterpret` cast could be used to access the individual bytes of an `int`.

An `int` consists of `sizeof(int)` bytes, and these bytes can be accessed by reinterpreting the location of the `int` value as a `char *`. When using a `reinterpret_cast` the compiler can no longer offer safeguards against stupidity. The compiler will happily `reinterpret_cast` an `int *` to a `double *`, but the resulting dereference will produce at the very least a questionable value.

The `dynamic_cast` also reinterprets a block of memory, but here a run-time safeguard is provided. The dynamic cast fails when the requested type doesn't match the actual type of the object we're pointing at. The `dynamic_cast`'s purpose is also much more restricted than the `reinterpret_cast`'s purpose, as it can only be used for downcasting to derived classes having virtual members.

In the end a dynamic cast is a cast, and casts should be avoided. When the need for dynamic casting arises ask yourself whether the base class has appropriately been designed. In situations where code expects a base class reference or pointer the base class interface should be all that is required and using a dynamic cast should not be necessary. Maybe the base class's virtual interface can be modified so as to prevent the use of dynamic casts. Start frowning when encountering code using dynamic casts. When using dynamic casts in your own code always properly document why the dynamic cast was appropriately used and could not have been avoided.

14.5.2 The 'typeid' operator

As with the `dynamic_cast` operator, `typeid` is usually applied to references to base class objects that refer to derived class objects. `Typeid` should only be used with base classes offering virtual members. Before using `typeid` the `<typeinfo>` header file must have been included.

The `typeid` operator returns an object of type `type_info`. Different compilers may offer different implementations of the class `type_info`, but at the very least `typeid` must offer the following interface:

```
class type_info
{
public:
    virtual ~type_info();
    int operator==(type_info const &other) const;
    int operator!=(type_info const &other) const;
    bool before(type_info const &rhs) const;
    char const *name() const;
private:
    type_info(type_info const &other);
    type_info &operator=(type_info const &other);
};
```

Note that this class has a private copy constructor and a private overloaded assignment operator. This prevents code from constructing `type_info` objects and prevents code from assigning `type_info` objects to each other. Instead, `type_info` objects are constructed and returned by the `typeid` operator.

If the `typeid` operator is passed a base class reference it is able to return the actual name of the type the reference refers to. Example:

```
class Base;
class Derived: public Base;

Derived d;
Base    &br = d;

cout << typeid(br).name() << '\n';
```

In this example the `typeid` operator is given a base class reference. It prints the text "Derived", being the class name of the class `br` actually refers to. If `Base` does not contain virtual functions, the text "Base" is printed.

The `typeid` operator can be used to determine the name of the actual type of expressions, not just of class type objects. For example:

```
cout << typeid(12).name() << '\n';    // prints:  int
cout << typeid(12.23).name() << '\n';  // prints:  double
```

Note, however, that the above example is suggestive at most. It *may* print `int` and `double`, but this is not necessarily the case. If portability is required, make sure no tests against these static, built-in text-strings are required. Check out what your compiler produces in case of doubt.

In situations where the `typeid` operator is applied to determine the type of a derived class, a base class *reference* should be used as the argument of the `typeid` operator. Consider the following example:

```
class Base;      // contains at least one virtual function
class Derived: public Base;

Base *bp = new Derived;    // base class pointer to derived object

if (typeid(bp) == typeid(Derived *))    // 1: false
    ...
if (typeid(bp) == typeid(Base *))       // 2: true
    ...
if (typeid(bp) == typeid(Derived))      // 3: false
    ...
if (typeid(bp) == typeid(Base))         // 4: false
    ...
if (typeid(*bp) == typeid(Derived))     // 5: true
    ...
if (typeid(*bp) == typeid(Base))        // 6: false
    ...

Base &br = *bp;

if (typeid(br) == typeid(Derived))      // 7: true
    ...
if (typeid(br) == typeid(Base))         // 8: false
    ...
```

Here, (1) returns false as a `Base *` is not a `Derived *`. (2) returns true, as the two pointer types are the same, (3) and (4) return false as pointers to objects are not the objects themselves.

On the other hand, if `*bp` is used in the above expressions, then (1) and (2) return false as an object (or reference to an object) is not a pointer to an object, whereas (5) now returns true: `*bp` actually refers to a `Derived` class object, and `typeid(*bp)` will return `typeid(Derived)`. A similar result is obtained if a base class reference is used: 7 returning true and 8 returning false.

The `type_info::before(type_info const &rhs)` member is used to determine the *collating order* of classes. This is useful when comparing two *types* for equality. The function returns a nonzero value if `*this` precedes `rhs` in the hierarchy or collating order of the used types. When a derived class is compared to its base class the comparison returns 0, otherwise a non-zero value. E.g.:

```
cout << typeid(istream).before(typeid(istream)) << '\n' << // not 0
      typeid(istream).before(typeid(istream)) << '\n';    // 0
```

With built-in types the implementor may implement that non-0 is returned when a ‘wider’ type is compared to a ‘smaller’ type and 0 otherwise:

```
cout << typeid(double).before(typeid(int)) << '\n' <<    // not 0
      typeid(int).before(typeid(double)) << '\n';        // 0
```


When two equal types are compared, 0 is returned:

```
cout << typeid(istream).before(typeid(istream)) << '\n';    // 0
```

When a 0-pointer is passed to the operator `typeid` a `bad_typeid` exception is thrown.

14.6 Inheritance: when to use to achieve what?

Inheritance should not be applied automatically and thoughtlessly. Often composition can be used instead, improving on a class's design by reducing coupling. When inheritance is used *public* inheritance should not automatically be used but the type of inheritance that is selected should match the programmer's intent.

We've seen that polymorphic classes on the one hand offer interface members defining the functionality that can be requested of base classes and on the other hand offer virtual members that can be overridden. One of the signs of good class design is that member functions are designed according to the principle of 'one function, one task'. In the current context: a class member should either be a member of the class's public or protected interface or it should be available as a virtual member for reimplementation by derived classes. Often this boils down to virtual members that are defined in the base class's *private* section. Those functions shouldn't be called by code using the base class, but they exist to be overridden by derived classes using polymorphism to redefine the base class's behavior.

The underlying principle was mentioned before in the introductory paragraph of this chapter: according to the *Liskov Substitution Principle (LSP)* an *is-a* relationship between classes (indicating that a derived class object *is a* base class object) implies that a derived class object may be used in code expecting a base class object.

In this case inheritance is used *not* to let the derived class use the facilities already implemented by the base class but to reuse the base class polymorphically by reimplementing the base class's virtual members in the derived class.

In this section we'll discuss the reasons for using inheritance. Why should inheritance (not) be used? If it is used what do we try to accomplish by it?

Inheritance often competes with composition. Consider the following two alternative class designs:

```
class Derived: // derived from Base
{ ... };

class Composed
{
    Base d_base;
    ...
};
```

Why and when prefer `Derived` over `Composed` and vice versa? What kind of inheritance should be used when designing the class `Derived`?

- Since `Composed` and `Derived` are offered as alternatives we are looking at the design of a class (`Derived` or `Composed`) that *is-implemented-in-terms-of* another class.
- Since `Composed` does itself not make `Base`'s interface available, `Derived` shouldn't do so either. The underlying principle is that *private inheritance* should be used when deriving from `Base` when `Derived` is-implemented-in-terms-of.
- Should we use inheritance or composition? Here are some arguments:
 - In general terms composition results in looser coupling and should therefore be preferred over inheritance.

- Composition allows us to define classes having multiple members of the same type (think about a class having multiple `std::string` members) which can not be realized using inheritance.
- Composition allows us to separate the class's interface from its implementation. This allows us to modify the class's data organization without the need to recompile code using our class. This is also known as the *bridge design pattern* or the *compiler firewall* or *pimpl* (pointer to the implementation) idiom.
- If Base offers members in its *protected* interface that must be used when implementing Derived inheritance must also be used. Again: since we're implementing-in-terms-of the inheritance type should be *private*.
- Protected inheritance may be considered when the derived class (D) itself is intended as a base class that should only make the members of its own base class (B) available to classes that are derived from it (i.e., D).

Private inheritance should also be used when a derived class is-a certain type of base class, but in order to initialize that base class an object of another class type must be available. Example: a new `istream` class-type (say: a stream `IRandStream` from which random numbers can be extracted) will be derived from `std::istream`. Although an `istream` can be constructed empty, receiving its `streambuf` later using its `rdbuf` member it is clearly preferable to initialize the `istream` base class right away.

Assuming that a `Randbuffer: public std::streambuf` has been created for generating random numbers then `IRandStream` can be derived from `Randbuffer` and `std::ostream`. That way the `ostream` base class can be initialized using the `Randbuffer` base class.

As a `RandStream` is definitely not a `Randbuffer` *public* inheritance is *not* appropriate. In this case `IRandStream` is-implemented-in-terms-of a `Randbuffer` and so *private* inheritance should be used.

`IRandStream`'s class interface should therefore start like this:

```
class IRandStream: private Randbuffer, public std::istream
{
    public:
        IRandStream(int lowest, int highest)    // defines the range
        :
            Randbuffer(lowest, highest),
            std::istream(this)                  // passes &Randbuffer
        {}
        ...
};
```

Public inheritance should be reserved for classes for which the LSP holds true. In those cases the derived classes can always be used instead of the base class from which they derive by code merely using base class references, pointers or members (I.e., conceptually the derived class *is-a* base class). This most often applies to classes derived from base classes offering virtual members. To separate the user interface from the redefinable interface the base class's public interface should *not* contain virtual members (except for the virtual destructor) and the virtual members should all be in the base class's private section. Such virtual members can still be overridden by derived classes (this should not come as a surprise, considering how polymorphism is implemented) and this design offers the base class full control over the context in which the redefined members are used. Often the public interface merely calls a virtual member, but those members can always be redefined to perform additional duties.

The prototypical form of a base class therefore looks like this:

```
class Base
{
    public:
        virtual ~Base()
        void process();           // calls a virtual member
};
```

```
private:
    virtual void processImp(); // overridden by derived classes
};
```

Alternatively a base class may offer a non-virtual destructor, which should then be protected. It shouldn't be public to prevent deleting objects through their base class pointers (in which case virtual destructors should be used). It should be protected to allow derived class destructors to call their base class destructors. Such base classes should, for the same reasons, have non-public constructors and overloaded assignment operators.

14.7 The ‘streambuf’ class

The class `std::streambuf` receives the character sequences processed by streams and defines the interface between the stream objects and the devices (like a file on disk). A `streambuf` object is usually not directly constructed, but usually it is used as base class of some derived class implementing the communication with some concrete device.

The primary reason for existence of the class `streambuf` is to decouple the stream classes from the devices they operate upon. The rationale here is to add an extra layer between the classes allowing us to communicate with devices and the devices themselves. This implements a *chain of command* which is seen regularly in software design.

The *chain of command* is considered a generic pattern when designing reusable software, encountered also in, e.g., the TCP/IP stack.

A `streambuf` can be considered yet another example of the chain of command pattern. Here the program talks to stream objects, which in turn forward their requests to `streambuf` objects, which in turn communicate with the devices. Thus, as we will see shortly, we are able to do in user-software what had to be done via (expensive) system calls before.

The class `streambuf` has no public constructor, but does make available several public member functions. In addition to these public member functions, several member functions are only available to classes derived from `streambuf`. In section 14.7.2 a predefined specialization of the class `streambuf` is introduced. All public members of `streambuf` discussed here are *also* available in `filebuf`.

The next section shows the `streambuf` members that may be overridden when deriving classes from `streambuf`. Chapter 23 offers concrete examples of classes derived from `streambuf`.

The class `streambuf` is used by streams performing input operations and by streams performing output operations and their member functions can be ordered likewise. The type `std::streamsize` used below may, for all practical purposes, be considered equal to the type `size_t`.

Public members for input operations

- `std::streamsize in_avail():`

This member function returns a lower bound on the number of characters that can be read immediately.

- `int sbumpc():`

The next available character or EOF is returned. The returned character is removed from the `streambuf` object. If no input is available, `sbumpc` will call the (protected) member `uflow` (see section 14.7.1 below) to make new characters available. EOF is returned if no more characters are available.

- `int sgetc():`

The next available character or EOF is returned. The character is *not* removed from the `streambuf` object.

- `int sgetn(char *buffer, std::streamsize n):`

At most `n` characters are retrieved from the input buffer, and stored in `buffer`. The actual number of characters read is returned. The (protected) member `xsgetn` (see section 14.7.1 below) is called to obtain the requested number of characters.

- `int snextc():`

The current character is removed from the input buffer and returned as the next available character or EOF is returned. The character is *not* removed from the `streambuf` object.

- `int sputback(char c):`

Inserts `c` into the `streambuf`'s buffer to be returned as the next character to read from the `streambuf` object. Caution should be exercised when using this function: often there is a maximum of just one character that can be put back.

- `int sungetc():`

Returns the last character read to the input buffer, to be read again at the next input operation. Caution should be exercised when using this function: often there is a maximum of just one character that can be put back.

Public members for output operations

- `int pubsync():`

Synchronizes (i.e., flush) the buffer by writing any information currently available in the `streambuf`'s buffer to the device. Normally only used by classes derived from `streambuf`.

- `int sputc(char c):`

Character `c` is inserted into the `streambuf` object. If, after writing the character, the buffer is full, the function calls the (protected) member function `overflow` to flush the buffer to the device (see section 14.7.1 below).

- `int sputn(char const *buffer, std::streamsize n):`

At most `n` characters from `buffer` are inserted into the `streambuf` object. The actual number of characters inserted is returned. This member function calls the (protected) member `xspun` (see section 14.7.1 below) to insert the requested number of characters.

Public members for miscellaneous operations

The next three members are normally only used by classes derived from `streambuf`.

- `ios::pos_type pubseekoff(ios::off_type offset, ios::seekdir way, ios::openmode mode = ios::in | ios::out):`

Sets the offset of the next character to be read or written to `offset`, relative to the standard `ios::seekdir` values indicating the direction of the seeking operation.

- `ios::pos_type pubseekpos(ios::pos_type offset, ios::openmode mode = ios::in | ios::out):`

Sets the absolute position of the next character to be read or written to `pos`.

- `streambuf *pubsetbuf(char* buffer, std::streamsize n):`

The `streambuf` object will use the buffer accomodating at least `n` characters.

14.7.1 Protected 'streambuf' members

The *protected* members of the class `streambuf` are important for understanding and using `streambuf` objects. Although there are both protected data members and protected member functions defined in the class `streambuf` the protected *data* members are not mentioned here as using them would violate the principle of *data hiding*. As `streambuf`'s set of member functions is quite extensive directly using its data members is probably hardly ever necessary. This section not even lists all protected member functions but lists only those that are useful for constructing specializations.

`Streambuf` objects control a buffer, used for input and/or output, for which begin-, actual- and end-pointers have been defined, as depicted in figure 14.4.

`Streambuf` offers one protected constructor:

- `streambuf::streambuf()`:

Default (protected) constructor of the class `streambuf`.

Several protected member functions are available for input operations. The member functions marked `virtual` may or course be redefined in derived classes:

- `char *eback()`:

`Streambuf` maintains three pointers controlling its input buffer: `eback` points to the 'end of the putback' area: characters can safely be put back up to this position. See also figure 14.4. `Eback` points to the *beginning* of the input buffer.

- `char *egptr()`:

`Egptr` points just beyond the last character that can be retrieved from the input buffer. See also figure 14.4. If `gptr` equals `egptr` the buffer must be refilled. This should be implemented by calling `underflow`, see below.

- `void gbump(int n)`:

The object's `gptr` (see below) is advanced over `n` positions.

- `char *gptr()`:

`Gptr` points to the next character to be retrieved from the object's input buffer. See also figure 14.4.

- `virtual int pbackfail(int c)`:

This member function may be overridden by derived classes to do something intelligent when putting back character `c` fails. One might consider restoring the old read pointer when input buffer's begin has been reached. This member function is called when ungetting or putting back a character fails. In particular, it is called when


- `gptr() == 0`: no buffering used,
- `gptr() == eback()`: no more room to push back,
- `*gptr() != c`: a different character than the next character to be read must be pushed back.

If `c == endOfFile()` then the input device must be reset by one character position. Otherwise `c` must be prepended to the characters to be read. The function should return `EOF` on failure. Otherwise 0 can be returned.

- `void setg(char *beg, char *next, char *beyond)`:

This member function initializes an input buffer. `beg` points to the beginning of the input area, `next` points to the next character to be retrieved, and `beyond` points to the location just beyond the input buffer's last character. Usually `next` is at least `beg + 1`, to allow for a put back operation. No input buffering is used when this member is called as `setg(0, 0, 0)`. See also the member `uflow`, below.

Input



Output




Figure 14.4: Input- and output buffer pointers of the class ‘streambuf’

- `virtual streamsize showmanyc():`

(Pronounce: s-how-many-c) This member function may be overridden by derived classes. It must return a guaranteed lower bound on the number of characters that can be read from the device before `uflow` or `underflow` returns `EOF`. By default 0 is returned (meaning no or some characters will be returned before the latter two functions return `EOF`). When a positive value is returned then the next call of `u(nder)flow` will not return `EOF`.

- `virtual int uflow():`

This member function may be overridden by derived classes to reload an input buffer with fresh characters. Its default implementation is to call `underflow` (see below). If `underflow()` fails, `EOF` is returned. Otherwise, the next character available character is returned as `*gptr()` following a `gbump(-1)`. `Uflow` also moves the pending character that is returned to the backup sequence. This is different from `underflow()`, which merely returns the next available character, but does not alter the input pointer positions.

When *no* input buffering is required this function, rather than `underflow`, can be overridden to produce the next available character from the device to read from.

- `virtual int underflow():`

This member function may be overridden by derived classes to read another character from the device. The default implementation is to return `EOF`.

It is called when

- there is no input buffer (`eback() == 0`)
- `gptr() >= egptr()`: the input buffer is exhausted.

Often, when buffering is used, the complete buffer is not refreshed as this would make it impossible to put back characters immediately following a reload. Instead, buffers are often refreshed in halves. This system is called a *split buffer*.

Classes derived from `streambuf` for reading normally at least override `underflow`. The prototypical example of an overridden `underflow` function looks like this:

```
int underflow()
{
    if (not refillTheBuffer()) // assume a member d_buffer is available
        return EOF;

                                // reset the input buffer pointers
    setg(d_buffer, d_buffer, d_buffer + d_nCharsRead);

                                // return the next available character
                                // (the cast is used to prevent
                                // misinterpretations of 0xff characters
                                // as EOF)
    return static_cast<unsigned char>(*gptr());
}
```

- `virtual streamsize xsgetn(char *buffer, streamsize n):`

This member function may be overridden by derived classes to retrieve at once `n` characters from the input device. The default implementation is to call `sbumpc` for every single character meaning that by default this member (eventually) calls `underflow` for every single character. The function returns the actual number of characters read or `eofOffFile()`. If `EOF` is returned the `streambuf` will stop reading the device.

The following protected members are available for output operations. Again, some members may be overridden by derived classes:

- `virtual int overflow(int c):`

This member function may be overridden by derived classes to flush the characters currently stored in the output buffer to the output device, and then to reset the output buffer pointers so as to represent an empty buffer. Its parameter `c` is initialized to the next character to be processed. If no output buffering is used `overflow` is called for every single character that is written to the `streambuf` object. No output buffering is accomplished by setting the buffer pointers (using, `setp`, see below) to 0. The default implementation returns `EOF`, indicating that no characters can be written to the device. Classes derived from `streambuf` for writing normally at least override `overflow`. The prototypical example of an overridden `overflow` function looks like this:

```
int OFdStreambuf::overflow(int c)
{
    sync();                // flush the buffer
    if (c != EOF)           // write a character?
    {
        *pptr() = static_cast<char>(c); // put it into the buffer
        pbump(1);              // advance the buffer's pointer
    }
    return c;
}
```

- `char *pbase():`

`Streambuf` maintains three pointers controlling its output buffer: `pbase` points to the beginning of the output buffer area. See also figure 14.4.

- `char *epptr():`

`Streambuf` maintains three pointers controlling its output buffer: `epptr` points just beyond the output buffer's last available location. See also figure 14.4. If `pptr` (see below) equals `epptr` the buffer must be flushed. This is implemented by calling `overflow`, see before.

- `void pbump(int n):`

The location returned by `pptr` (see below) is advanced by `n`. The next character to write will be entered at that location.

- `char *pptr():`

`Streambuf` maintains three pointers controlling its output buffer: `pptr` points to the location in the output buffer where the next available character should be written. See also figure 14.4.

- `void setp(char *beg, char *beyond):`

`Streambuf`'s output buffer is initialized to the locations passed to `setp`. `Beg` points to the beginning of the output buffer and `beyond` points just beyond the last available location of the output buffer. Use `setp(0, 0)` to indicate that `i`(no buffering) should be used. In that case `tt(overflow)` is called for every single character to write to the device.

`streamsize xsputn(char const *buffer, streamsize n):`

This member function may be overridden by derived classes to write a series of at most `n` characters to the output buffer. The actual number of inserted characters is returned. If `EOF` is returned writing to the device stops. The default implementation calls `sputc` for each individual character, so redefining this member is only necessary if a more efficient implementation is required.

Several protected members are related to buffer management and positioning:

- `virtual streambuf *setbuf(char *buffer, streamsize n):`

This member function may be overridden by derived classes to install a buffer. The default implementation is to do nothing. It is called by `pubsetbuf`.

- virtual pos_type seekoff(off_type offset, ios::seekdir way, ios::openmode mode = ios::in | ios::out)

This member function may be overridden by derived classes to reset the next pointer for input or output to a new relative position (using `ios::beg`, `ios::cur` or `ios::end`). The default implementation indicates failure by returning -1. The function is called when `tellg` or `tellp` are called. When derived class supports seeking, then it should also define this function to handle repositioning requests. It is called by `pubseekoff`. The new position or an invalid position (i.e., -1) is returned.

- virtual pos_type seekpos(pos_type offset, ios::openmode mode = ios::in | ios::out):

This member function may be overridden by derived classes to reset the next pointer for input or output to a new absolute position (i.e, relative to `ios::beg`). The default implementation indicates failure by returning -1.

- virtual int sync():

This member function may be overridden by derived classes to flush the output buffer to the output device or to reset the input device just beyond the position of the character that was returned last. It returns 0 on success, -1 on failure. The default implementation (not using a buffer) is to return 0, indicating successful syncing. This member is used to ensure that any characters that are still buffered are written to the device or to put unconsumed characters back to the device when the `streambuf` object ceases to exist.

When classes are derived from `streambuf` at least `underflow` should be overridden by classes intending to read information from devices, and `overflow` should be overridden by classes intending to write information to devices. Several examples of classes derived from `streambuf` are provided in chapter 23.

`Fstream` class type objects use a combined input/output buffer. This is a result from that `istream` and `ostream` being virtually derived from `ios`, which class contains the `streambuf`. To construct a class supporting both input and output using separate buffers, the `streambuf` itself may define two buffers. When `seekoff` is called for reading, a mode parameter can be set to `ios::in`, otherwise to `ios::out`. Thus the derived class knows whether it should access the read buffer or the write buffer. Of course, `underflow` and `overflow` do not have to inspect the mode flag as they by implication know on which buffer they should operate.

14.7.2 The class ‘filebuf’

The class `filebuf` is a specialization of `streambuf` used by the file stream classes. Before using a `filebuf` the header file `<fstream>` must have been included.

In addition to the (public) members that are available through the class `streambuf`, `filebuf` offers the following (public) members:

- `filebuf()`:

`Filebuf` offers a public constructor. It initializes a plain `filebuf` object that is not yet connected to a stream.

- `bool is_open()`:

`True` is returned if the `filebuf` is actually connected to an open file, `false` otherwise. See the `open` member, below.

- `filebuf *open(char const *name, ios::openmode mode):`

This member function associates the `filebuf` object with a file whose name is provided. The file is opened according to the provided `openmode`.

- `filebuf *close()`:

This member function closes the association between the `filebuf` object and its file. The association is automatically closed when the `filebuf` object ceases to exist.

14.8 A polymorphic exception class

Earlier in the **C++ Annotations** (section 9.3.1) we hinted at the possibility of designing a class `Exception` whose `process` member would behave differently, depending on the kind of exception that was thrown. Now that we've introduced polymorphism we can further develop this example.

It will probably not come as a surprise that our class `Exception` should be a polymorphic base class from which special exception handling classes can be derived. In section 9.3.1 a member `severity` was used offering functionality that may be replaced by members of the `Exception` base class.

The base class `Exception` may be designed as follows:

```
#ifndef INCLUDED_EXCEPTION_H_
#define INCLUDED_EXCEPTION_H_
#include <iostream>
#include <string>

class Exception
{
    std::string d_reason;

public:
    Exception(std::string const &reason);
    virtual ~Exception();

    std::ostream &insertInto(std::ostream &out) const;
    void handle() const;

private:
    virtual void action() const;
};

inline void Exception::action() const
{
    throw;
}
inline Exception::Exception(std::string const &reason)
:
    d_reason(reason)
{}
inline void Exception::handle() const
{
    action();
}
inline std::ostream &Exception::insertInto(std::ostream &out) const
{
    return out << d_reason;
}

inline std::ostream &operator<<(std::ostream &out, Exception const &e)
{
    return e.insertInto(out);
}
```

```
#endif
```

Objects of this class may be inserted into ostreams but the core element of this class is the virtual member function `action`, by default rethrowing an exception.

A derived class `Warning` simply prefixes the thrown warning text by the text `Warning:`, but a derived class `Fatal` overrides `Exception::action` by calling `std::terminate`, forcefully terminating the program.

Here are the classes `Warning` and `Fatal`

```
#ifndef WARNINGEXCEPTION_H_
#define WARNINGEXCEPTION_H_

#include "exception.h"

class Warning: public Exception
{
public:
    Warning(std::string const &reason)
    :
        Exception("Warning: " + reason)
    {}
};
#endif

#ifndef FATAL_H_
#define FATAL_H_

#include "exception.h"

class Fatal: public Exception
{
public:
    Fatal(std::string const &reason);
private:
    virtual void action() const;
};

inline Fatal::Fatal(std::string const &reason)
:
    Exception(reason)
{}

inline void Fatal::action() const
{
    std::cout << "Fatal::action() terminates" << '\n';
    std::terminate();
}

#endif
```

When the example program is started without arguments it will throw a `Fatal` exception, otherwise it will throw a `Warning` exception. Of course, additional exception types could also easily be defined:

```
#include "warning.h"
#include "fatal.h"
```

```

Exception::~Exception()
{}

using namespace std;

int main(int argc, char **argv)
try
{
    try
    {
        if (argc == 1)
            throw Fatal("Missing Argument") ;
        else
            throw Warning("the argument is ignored");
    }
    catch (Exception const &e)
    {
        cout << e << '\n';
        e.handle();
    }
}
catch(...)
{
    cout << "caught rethrown exception\n";
}

//
//
// void initialExceptionHandler(Exception const *e)
// {
//     cout << *e << '\n';           // show the plain-text information
//
//     if
//     (
//         !dynamic_cast<MessageException const *>(e)
//         &&
//         !dynamic_cast<WarningException const *>(e)
//     )
//         throw;                     // Pass on other types of Exceptions
//
//     e->process();                   // Process a message or a warning
//     delete e;
// }

```

14.9 How polymorphism is implemented

This section briefly describes how polymorphism is implemented in **C++**. It is not necessary to understand how polymorphism is implemented if you just want to *use* polymorphism. However, we think it's nice to know how polymorphism is possible. Also, knowing how polymorphism is implemented clarifies why there is a (small) penalty to using polymorphism in terms of memory usage and efficiency.

The fundamental idea behind polymorphism is that the compiler does not know which function to call compile-time. The appropriate function will be selected run-time. That means that the address of the function must be available somewhere, to be looked up prior to the actual call. This 'somewhere' place must be accessible to the object in question. So when a `Vehicle *vp` points to a `Truck` object, then `vp->mass()` calls `Truck`'s member function. the address of this function is obtained through the actual




Figure 14.5: Internal organization objects when virtual functions are defined.

object to which `vp` points.

Polymorphism is commonly implemented as follows: an object containing virtual member functions also contains, usually as its first data member a hidden data member, pointing to an array containing the addresses of the class's virtual member functions. The hidden data member is usually called the *vpointer*, the array of virtual member function addresses the *vtable*.

The class's *vtable* is shared by all objects of that class. The overhead of polymorphism in terms of memory consumption is therefore:

- one *vpointer* data member per object pointing to:
- one *vtable* per class.

Consequently, a statement like `vp->mass` first inspects the hidden data member of the object pointed to by `vp`. In the case of the vehicle classification system, this data member points to a table containing two addresses: one pointer to the function `mass` and one pointer to the function `setMass` (three pointers if the class also defines (as it should) a virtual destructor). The actually called function is determined from this table.

The internal organization of the objects having virtual functions is illustrated in figures Figure 14.5 and Figure 14.6 (originals provided by Guillaume Caumon³).

As shown by figures Figure 14.5 and Figure 14.6, objects potentially using virtual member functions must have one (hidden) data member to address a table of function pointers. The objects of the classes `Vehicle` and `Auto` both address the same table. The class `Truck`, however, overrides `mass`. Consequently, `Truck` needs its own *vtable*.

A small complication arises when a class is derived from multiple base classes, each defining virtual functions. Consider the following example:

```
class Base1
{
public:
    virtual ~Base1();
    void fun1();           // calls vOne and vTwo
private:
    virtual void vOne();
    virtual void vTwo();
};
class Base2
{

```

³<mailto:Guillaume.Caumon@ensg.inpl-nancy.fr>




Figure 14.6: Complementary figure, provided by Guillaume Caumon

```

public:
    virtual ~Base2();
    void fun2();          // calls vThree
private:
    virtual void vThree();
};
class Derived: public Base1, public Base2
{
public:
    virtual ~Derived();
private:
    virtual ~vOne();
    virtual ~vThree();
};

```

In the example `Derived` is multiply derived from `Base1` and `Base2`, each supporting virtual functions. Because of this, `Derived` also has virtual functions, and so `Derived` has a `vtable` allowing a base class pointer or reference to access the proper virtual member.

When `Derived::fun1` is called (or a `Base1` pointer pointing to `fun1` calls `fun1`) `fun1` will call `Derived::vOne` and `Base1::vTwo`. Likewise, when `Derived::fun2` is called `Derived::vThree` will be called.

The complication occurs with `Derived`'s `vtable`. When `fun1` is called its class type determines the `vtable` to use and hence which virtual member to call. So when `vOne` is called from `fun1`, it is presumably the second entry in `Derived`'s `vtable`, as it must match the second entry in `Base1`'s `vtable`. However, when `fun2` calls `vThree` it apparently is also the second entry in `Derived`'s `vtable` as it must match the second entry in `Base2`'s `vtable`.

Of course this cannot be realized by a single `vtable`. Therefore, when multiple inheritance is used (each base class defining virtual members) another approach is followed to determine which virtual function to call. In this situation (cf. figure Figure 14.7) the class `Derived` receives *two* `vtables`, one for each of its base classes and each `Derived` class object harbors *two* hidden `vpointers`, each one pointing to its corresponding `vtable`.

Since base class pointers, base class references, or base class interface members unambiguously refer to one of the base classes the compiler can determine which `vpointer` to use.

The following therefore holds true for classes multiply derived from base classes offering virtual member functions:




Figure 14.7: Vtables and vpointers with multiple base classes

- the derived class defines a vtable for each of its base classes offering virtual members;
- Each derived class object contains as many hidden vpointers as it has vtables.
- Each of a derived class object's vpointers points to a unique vtable and the vpointer to use is determined by the class type of the base class pointer, the base class reference, or the base class interface function that is used.

14.10 Undefined reference to vtable ...

Occasionally, the linker will generate an error like the following:

```
In function 'Derived::Derived()':
: undefined reference to 'vtable for Derived'
```

This error is generated when a virtual function's implementation is missing in a derived class, but the function is mentioned in the derived class's interface.

Such a situation is easily encountered:

- Construct a (complete) base class defining a virtual member function;
- Construct a Derived class mentioning the virtual function in its interface;
- The Derived class's virtual function is not implemented. Of course, the compiler doesn't know that the derived class's function is not implemented and will, when asked, generate code to create a derived class object;
- Eventually, the linker is unable to find the derived class's virtual member function. Therefore, it is unable to construct the derived class's vtable;
- The linker complains with the message:

```
undefined reference to 'vtable for Derived'
```

Here is an example producing the error:

```
class Base
{
    virtual void member();
};
inline void Base::member()
{}
class Derived: public Base
{
    virtual void member();           // only declared
};
int main()
{
    Derived d; // Will compile, since all members were declared.
              // Linking will fail, since we don't have the
              // implementation of Derived::member()
}
```

It's of course easy to correct the error: implement the derived class's missing virtual member function.

14.11 Virtual constructors

In section 14.2 we learned that C++ supports *virtual destructors*. Like many other object oriented languages (e.g., **Java**), however, the notion of a *virtual constructor* is not supported. Not having virtual constructors becomes a liability when only base class references or pointers are available, and a copy of a derived class object is required. *Gamma et al.* (1995) discuss the *Prototype design pattern* to deal with this situation.

According to the *Prototype Design Pattern* each derived class is given the responsibility of implementing a member function returning a pointer to a copy of the object for which the member is called. The usual name for this function is `clone`. Separating the user interface from the reimplementation interface `clone` is made part of the interface and `newCopy` is defined in the reimplementation interface. A base class supporting ‘cloning’ defines a virtual destructor, `clone`, returning `newCopy`’s return value and the *virtual copy constructor*, a pure virtual function, having the prototype `virtual Base *newCopy() const = 0`. As `newCopy` is a pure virtual function all derived classes must now implement their own ‘virtual constructor’.

This setup suffices in most situations where we have a pointer or reference to a base class, but it will fail when used with abstract containers. We can’t create a `vector<Base>`, with `Base` featuring the pure virtual `copy` member in its interface, as `Base` is called to initialize new elements of such a vector. This is impossible as `newCopy` is a pure virtual function, so a `Base` object can’t be constructed.

The intuitive solution, providing `newCopy` with a default implementation, defining it as an ordinary virtual function, fails too as the container calls `Base(Base const &other)`, which would have to call `newCopy` to copy `other`. At this point it is unclear what to do with that copy, as the new `Base` object already exists, and contains no `Base` pointer or reference data member to assign `newCopy`’s return value to.

Alternatively (and preferred) the original `Base` class (defined as an abstract base class) is kept as-is and a wrapper class `Clonable` is used to manage the `Base` class pointers returned by `newCopy`. In chapter 17 ways to merge `Base` and `Clonable` into one class are discussed, but for now we’ll define `Base` and `Clonable` as separate classes.

The class `Clonable` is a very standard class. It contains a pointer member so it needs a copy constructor, destructor, and overloaded assignment operator. It’s given at least one non-standard member: `Base &base() const`, returning a reference to the derived object to which `Clonable`’s `Base *` data member refers. It is also provided with an additional constructor to initialize its `Base *` data member.

Any non-abstract class derived from `Base` must implement `Base *newCopy()`, returning a pointer to a newly created (allocated) copy of the object for which `newCopy` is called.

Once we have defined a derived class (e.g., `Derived1`), we can put our `Clonable` and `Base` facilities to good use. In the next example we see `main` defining a `vector<Clonable>`. An anonymous `Derived1` object is then inserted into the vector using the following steps:

- A new anonymous `Derived1` object is created;
- It initializes a `Clonable` using `Clonable(Base *bp)`;
- The just created `Clonable` object is inserted into the vector, using `Clonable`’s move constructor. There are only temporary `Derived` and `Clonable` objects at this point, so no copy construction is required.

In this sequence, only the `Clonable` object containing the `Derived1 *` is used. No additional copies need to be made (or destroyed).

Next, the base member is used in combination with `typeid` to show the actual type of the `Base &` object: a `Derived1` object.

`Main` then contains the interesting definition `vector<Clonable> v2(bv)`. Here a copy of `bv` is created. This copy construction observes the actual types of the `Base` references, making sure that the appropriate types appear in the vector’s copy.

At the end of the program, we have created two `Derived1` objects, which are correctly deleted by the vector's destructors. Here is the full program, illustrating the 'virtual constructor' concept⁴:

```
#include <iostream>
#include <vector>
#include <algorithm>
#include <typeinfo>

// Base and its inline member:
class Base
{
public:
    virtual ~Base();
    Base *clone() const;
private:
    virtual Base *newCopy() const = 0;
};
inline Base *Base::clone() const
{
    return newCopy();
}

// Clonable and its inline members:
class Clonable
{
    Base *d_bp;

public:
    Clonable();
    explicit Clonable(Base *base);
    ~Clonable();
    Clonable(Clonable const &other);
    Clonable(Clonable const &&tmp);
    Clonable &operator=(Clonable const &other);
    Clonable &operator=(Clonable const &&tmp);

    Base &base() const;
};
inline Clonable::Clonable()
:
    d_bp(0)
{}
inline Clonable::Clonable(Base *bp)
:
    d_bp(bp)
{}
inline Clonable::Clonable(Clonable const &other)
:
    d_bp(other.d_bp->clone())
{}
inline Clonable::Clonable(Clonable const &&tmp)
:
    d_bp(tmp.d_bp)
{
    const_cast<Clonable &>(tmp).d_bp = 0;
}
inline Clonable::~~Clonable()
```

⁴ Jesse van den Kieboom created an alternative implementation of a class `Clonable`, implemented as a class template. His implementation is found here⁵.

```

    {
        delete d_bp;
    }
    inline Base &Clonable::base() const
    {
        return *d_bp;
    }

// Derived and its inline member:
class Derived1: public Base
{
    public:
        ~Derived1();
    private:
        virtual Base *newCopy() const;
};
inline Base *Derived1::newCopy() const
{
    return new Derived1(*this);
}

// Members not implemented inline:
Base::~~Base()
{}
Clonable &Clonable::operator=(Clonable const &other)
{
    Clonable tmp(other);
    std::swap(d_bp, tmp.d_bp);
    return *this;
}
Clonable &Clonable::operator=(Clonable const &&tmp)
{
    std::swap(d_bp, const_cast<Clonable &>(tmp).d_bp);
    return *this;
}
Derived1::~~Derived1()
{
    std::cout << "~Derived1() called\n";
}

// The main function:
using namespace std;

int main()
{
    vector<Clonable> bv;

    bv.push_back(Clonable(new Derived1()));
    cout << "bv[0].name: " << typeid(bv[0].base()).name() << '\n';

    vector<Clonable> v2(bv);
    cout << "v2[0].name: " << typeid(v2[0].base()).name() << '\n';
}
/*
Output:
    bv[0].name: 8Derived1
    v2[0].name: 8Derived1
    ~Derived1() called
    ~Derived1() called
*/

```

* /

Chapter 15

Friends

In all examples discussed up to now, we've seen that `private` members are only accessible by the members of their class. This is *good*, as it enforces encapsulation and data hiding: By encapsulating functionality in classes we prevent that classes have multiple responsibilities; by hiding its data from external code we promote a class's data integrity and we prevent that external code becomes implementation dependent on the data in a class.

In this (very) short chapter we introduce the `friend` keyword and the principles that underly its use. The bottom line being that by using the `friend` keyword functions are granted access to a class's `private` members. As will be discussed this does not automatically imply that we abandon the principle of data hiding when the `friend` keyword is used.

In this chapter the topic of friendship among classes is not discussed. Situations in which it is natural to use friendship among classes are discussed in chapters 17 and 20 and are a natural extension of the way friendship is handled for functions.

There should be a well-defined conceptual reason for declaring friendship (i.e., using the `friend` keyword). The traditionally offered definition of the class concept usually looks something like this:

A class is a set of data together with the functions that operate on that set of data.

As we've seen in chapter 10 some functions have to be defined outside of a class interface. They are defined outside of the class interface to allow promotions for their operands or to extend the facilities of existing classes not directly under our control. According to the above traditional definition of the class concept those functions that cannot be defined in the class interface itself should nevertheless be considered functions belonging to the class. Stated otherwise: if permitted by the language's syntax they would certainly have been defined inside the class interface. There are two ways to implement such functions. One way consists of implementing those functions using available public member functions. This approach was used, e.g., in section 10.2. Another approach applies the definition of the class concept to those functions. By stating that those functions in fact belong to the class they should be given direct access to the data members of objects. This is accomplished by the `friend` keyword.

As a general principle we state that all functions operating on the data of objects of a class that are declared in the same file as the class interface itself belong to that class and may be granted direct access to the class's data members.

15.1 Friend functions

In section 10.2 the insertion operator of the class `Person` (cf. section 8.3) was implemented like this:

```
ostream &operator<<(ostream &out, Person const &person)
```

```

{
    return
        out <<
            "Name:      " << person.name() << " , "
            "Address:  " << person.address() << " , "
            "Phone:    " << person.phone();
}

```

Person objects can now be inserted into streams.

However, this implementation required three member functions to be called, which may be considered a source of inefficiency. An improvement would be reached by defining a member `Person::insertInto` and let `operator<<` call that function. These two functions could be defined as follows:

```

std::ostream &operator<<(std::ostream &out, Person const &person)
{
    return person.insertInto(out);
}
std::ostream &Person::insertInto(std::ostream &out)
{
    return
        cout << "Name:      " << d_name << " , "
            "Address:  " << d_address << " , "
            "Phone:    " << d_phone;
}

```

As `insertInto` is a member function it has direct access to the object's data members so no additional member functions must be called when inserting person into `out`.

The next step consists of realizing that `insertInto` is only defined for the benefit of `operator<<`, and that `operator<<`, as it is declared in the header file containing `Person`'s class interface should be considered a function belonging to the class `Person`. The member `insertInto` can therefore be omitted when `operator<<` is declared as a friend.

Friend functions must be declared as friends in the class interface. These *friend declarations* are not *member* functions, and so they are independent of the class's `private`, `protected` and `public` sections. Friend declaration may be placed anywhere in the class interface. Convention dictates that friend declarations are listed directly at the top of the class interface. The class `Person`, using friend declaration for its extraction and insertion operators starts like this:

```

class Person
{
    friend std::ostream &operator<<(std::ostream &out, Person &pd);
    friend std::istream &operator>>(std::istream &in, Person &pd);

    // previously shown interface (data and functions)
};

```

The insertion operator may now directly access a `Person` object's data members:

```

std::ostream &operator<<(std::ostream &out, Person const &person)
{
    return
        cout << "Name:      " << person.d_name << " , "
            "Address:  " << person.d_address << " , "
            "Phone:    " << person.d_phone;
}

```

Friend declarations are true declarations. Once a class contains friend declarations these friend functions do not have to be declared again below the class's interface. This also clearly indicates the class designer's intent: the friend functions are declared by the class, and can thus be considered functions belonging to the class.

Chapter 16

Classes Having Pointers To Members

Classes having pointer data members have been discussed in detail in chapter 8. Classes defining pointer data-members deserve some special attention, as they usually require the definitions of copy constructors, overloaded assignment operators and destructors

Situations exist where we do not need a pointer to an object but rather a pointer to members of a class. Pointers to members can profitably be used to configure the behavior of objects of classes. Depending on which member a pointer to a member points to objects will show certain behavior.

Although pointers to members have their use, polymorphism can frequently be used to realize comparable behavior. Consider a class having a member `process` performing one of a series of alternate behaviors. Instead of selecting the behavior of choice at object construction time the class could use the interface of some (abstract) base class, passing an object of some derived class to its constructor and could thus configure its behavior. This allows for easy, extensible and flexible configuration, but access to the class's data members would be less flexible and would possibly require the use of 'friend' declarations. In such cases pointers to members may actually be preferred as this allows for (somewhat less flexible) configuration as well as direct access to a class's data members.

So the choice apparently is between on the one hand ease of configuration and on the other hand ease of access to a class's data members. In this chapter we'll concentrate on pointers to members, investigating what these pointers have to offer.

16.1 Pointers to members: an example

Knowing how pointers to variables and objects are used does not intuitively lead to the concept of *pointers to members*. Even if the return types and parameter types of member functions are taken into account, surprises can easily be encountered. For example, consider the following class:

```
class String
{
    char const *(*d_sp)() const;

public:
    char const *get() const;
};
```

For this class, it is not possible to let `char const *(*d_sp)() const` point to the `String::get` member function as `d_sp` cannot be given the address of the member function `get`.

One of the reasons why this doesn't work is that the variable `d_sp` has global scope (it is a pointer to a function, not a pointer to a function within `String`), while the member function `get` is defined within the `String` class, and thus has class scope. The fact that `d_sp` is a data member of the class `String` is irrelevant here. According to `d_sp`'s definition, it points to a function living somewhere *outside* of the class.

Consequently, to define a pointer to a member (either data or function, but usually a function) of a class, the scope of the pointer must indicate class scope. Doing so, a pointer to the member `String::get` is defined like this:

```
char const *(String::*d_sp)() const;
```

So, by prefixing the `*d_sp` pointer data member by `String::`, it is defined as a pointer in the context of the class `String`. According to its definition it is *a pointer to a function in the class `String`, not expecting arguments, not modifying its object's data, and returning a pointer to constant characters.*

16.2 Defining pointers to members

Pointers to members are defined by prefixing the normal pointer notation with the appropriate class plus scope resolution operator. Therefore, in the previous section, we used `char const * (String::*d_sp)() const` to indicate that `d_sp`

- is a pointer (`*d_sp`);
- points to something in the class `String` (`String::*d_sp`);
- is a pointer to a `const` function, returning a `char const *` (`char const * (String::*d_sp)() const`).

The prototype of a matching function is therefore:

```
char const *String::somefun() const;
```

which is any `const` parameterless function in the class `String`, returning a `char const *`.

When defining pointers to members the standard procedure for constructing pointers to functions can still be applied:

- put parentheses around the fully qualified function name (i.e., the function's header, including the function's class name):

```
char const * ( String::somefun ) () const
```

- Put a pointer (a star `*`) character immediately before the function name itself:

```
char const * ( String:: * somefun ) () const
```

- Replace the function name with the name of the pointer variable:

```
char const * (String::*d_sp)() const
```

Here is another example, defining a pointer to a data member. Assume the class `String` contains a `string d_text` member. How to construct a pointer to this member? Again we follow standard procedure:

- put parentheses around the fully qualified variable name:

```
std::string (String::d_text)
```

- Put a pointer (a star (*)) character immediately before the variable-name itself:

```
std::string (String::d_text)
```

- Replace the variable name with the name of the pointer variable:

```
std::string (String::*tp)
```

In this case, the parentheses are superfluous and may be omitted:

```
string String::*tp
```

Alternatively, a very simple rule of thumb is

- Define a normal (i.e., global) pointer variable,
- Prefix the class name to the pointer character, once you point to something inside a class

For example, the following pointer to a global function

```
char const * (*sp)() const;
```

becomes a pointer to a member function after prefixing the class-scope:

```
char const * (String::*sp)() const;
```

Nothing forces us to define pointers to members in their target (`String`) classes. Pointers to members *may* be defined in its target class (so it becomes a data member), or in another class, or as a local variable or as a global variable. In all these cases the pointer to member variable can be given the address of the kind of member it points to. The important part is that a pointer to member can be initialized or assigned without requiring the existence an object of the pointer's target class.

Initializing or assigning an address to such a pointer merely indicates to which member the pointer points. This can be considered some kind of *relative address*; relative to the object for which the function is called. No object is required when pointers to members are initialized or assigned. While it is allowed to initialize or assign a pointer to member, it is (of course) not possible to *call* those members without specifying an object of the correct type.

In the following example initialization of and assignment to pointers to members is illustrated (for illustration purposes all members of the class `PointerDemo` are defined `public`). In the example itself the `&`-operator is used to determine the addresses of the members. These operators as well as the class-scopes are required. Even when used inside member implementations:

```
class PointerDemo
{
public:
    size_t d_value;
    size_t get() const;
};

inline size_t PointerDemo::get() const
{
    return d_value;
}

int main()
{
    // initialization
    size_t (PointerDemo::*getPtr)() const = &PointerDemo::get;
```

```

size_t PointerDemo::*valuePtr          = &PointerDemo::d_value;

getPtr    = &PointerDemo::get;          // assignment
valuePtr  = &PointerDemo::d_value;
}

```

This involves nothing special. The difference with pointers at global scope is that we're now restricting ourselves to the scope of the `PointerDemo` class. Because of this restriction, all *pointer* definitions and all variables whose addresses are used must be given the `PointerDemo` class scope.

Pointers to members can also be used with virtual member functions. No special syntax is required when pointing to virtual members. Pointer construction, initialization and assignment is done identically to the way it is done with non-virtual members.

16.3 Using pointers to members

Using pointers to members to call a member function requires the existence of an object of the class of the members to which the pointer to member refers to. With pointers operating at global scope, the dereferencing operator `*` is used. With pointers to objects the field selector operator operating on pointers (`->`) or the field selector operating on objects (`.`) can be used to select appropriate members.

To use a pointer to member in combination with an object the pointer to member field selector (`.*`) must be specified. To use a pointer to a member via a pointer to an object the 'pointer to member field selector through a pointer to an object' (`->*`) must be specified. These two operators combine the notions of a field selection (the `.` and `->` parts) to reach the appropriate field in an object and of dereferencing: a dereference operation is used to reach the function or variable the pointer to member points to.

Using the example from the previous section, let's see how we can use pointers to members function and pointers to data members:

```

#include <iostream>

class PointerDemo
{
public:
    size_t d_value;
    size_t get() const;
};

inline size_t PointerDemo::get() const
{
    return d_value;
}

using namespace std;

int main()
{
    // initialization
    size_t (PointerDemo::*getPtr)() const = &PointerDemo::get;
    size_t PointerDemo::*valuePtr        = &PointerDemo::d_value;

    PointerDemo object;                // (1) (see text)
    PointerDemo *ptr = &object;

    object.*valuePtr = 12345;           // (2)
    cout << object.*valuePtr << '\n' <<

```

```

        object.d_value << '\n';

    ptr->*valuePtr = 54321;                // (3)
    cout << object.d_value << '\n' <<
        (object.*getPtr)() << '\n' <<    // (4)
        (ptr->*getPtr)() << '\n';
}

```

We note:

- At (1) a `PointerDemo` object and a pointer to such an object is defined.
- At (2) we specify an object (and hence the `.*` operator) to reach the member `valuePtr` points to. This member is given a value.
- At (3) the same member is assigned another value, but this time using the pointer to a `PointerDemo` object. Hence we use the `->*` operator.
- At (4) the `.*` and `->*` are used once again, this time to call a function through a pointer to member. As the function argument list has a higher priority than the pointer to member field selector operator, the latter *must* be protected by parentheses.

Pointers to members can be used profitably in situations where a class has a member that behaves differently depending on a configuration setting. Consider once again the class `Person` from section 8.3. `Person` defines data members holding a person's name, address and phone number. Assume we want to construct a `Person` database of employees. The employee database can be queried, but depending on the kind of person querying the database either the name, the name and phone number or all stored information about the person is made available. This implies that a member function like `address` must return something like '<not available>' in cases where the person querying the database is not allowed to see the person's address, and the actual address in other cases.

The employee database is opened specifying an argument reflecting the status of the employee who wants to make some queries. The status could reflect his or her position in the organization, like `BOARD`, `SUPERVISOR`, `SALESPERSON`, or `CLERK`. The first two categories are allowed to see all information about the employees, a `SALESPERSON` is allowed to see the employee's phone numbers, while the `CLERK` is only allowed to verify whether a person is actually a member of the organization.

We now construct a member string `personInfo(char const *name)` in the database class. A standard implementation of this class could be:

```

string PersonData::personInfo(char const *name)
{
    Person *p = lookup(name);    // see if 'name' exists

    if (!p)
        return "not found";

    switch (d_category)
    {
        case BOARD:
        case SUPERVISOR:
            return allInfo(p);
        case SALESPERSON:
            return noPhone(p);
        case CLERK:
            return nameOnly(p);
    }
}

```

Although it doesn't take much time, the `switch` must nonetheless be evaluated every time `personInfo()` is called. Instead of using a `switch`, we could define a member `d_infoPtr` as a pointer to a member function of the class `PersonData` returning a string and expecting a `Person` reference as its argument.

Instead of evaluating the `switch` this pointer can be used to point to `allInfo`, `noPhone` or `nameOnly`. Furthermore, the member function the pointer points to will be known by the time the `PersonData` object is constructed and so its value needs to be determined only once (at the `PersonData` object's construction time).

Having initialized `d_infoPtr` `personInfo()` member function is now implemented simply as:

```
string PersonData::personInfo(char const *name)
{
    Person *p = lookup(name);          // see if 'name' exists

    return p ? (this->*d_infoPtr)(p) : "not found";
}
```

The member `d_infoPtr` is defined as follows (within the class `PersonData`, omitting other members):

```
class PersonData
{
    string (PersonData::*d_infoPtr)(Person *p);
};
```

Finally, the constructor initializes `d_infoPtr`. This could be realized using a simple `switch`:

```
PersonData::PersonData(PersonData::EmployeeCategory cat)
:
{
    switch (cat)
    {
        case BOARD:
        case SUPERVISOR:
            d_infoPtr = &PersonData::allInfo;
            break;
        case SALESPERSON:
            d_infoPtr = &PersonData::noPhone;
            break;
        case CLERK:
            d_infoPtr = &PersonData::nameOnly;
            break;
    }
}
```

Note how addresses of member functions are determined. The class `PersonData` scope *must* be specified, even though we're already inside a member function of the class `PersonData`.

An example using pointers to data members is provided in section [19.1.60](#), in the context of the `stable_sort` generic algorithm.

16.4 Pointers to static members

Static members of a class can be used without having available an object of their class. Public static members can be called like free functions, albeit that their class names must be specified when they are called.

Assume a class `String` has a public static member function `count`, returning the number of string objects created so far. Then, without using any `String` object the function `String::count` may be called:

```
void fun()
{
    cout << String::count() << '\n';
}
```

Public static members can be called like free functions (but see also section [11.2.1](#)). *Private* static members can only be called within the context of their class, by their class's member or friend functions.

Since static members have no associated objects their addresses can be stored in ordinary function pointer variables, operating at the global level. Pointers to members cannot be used to store addresses of static members. Example:

```
void fun()
{
    size_t (*pf)() = String::count;
    // initialize pf with the address of a static member function

    cout << (*pf)() << '\n';
    // displays the value returned by String::count()
}
```

16.5 Pointer sizes

An interesting characteristic of pointers to members is that their sizes differ from those of 'normal' pointers. Consider the following little program:

```
#include <string>
#include <iostream>

class X
{
public:
    void fun();
    std::string d_str;
};
inline void X::fun()
{
    std::cout << "hello\n";
}

using namespace std;
int main()
{
    cout <<
        "size of pointer to data-member:      " << sizeof(&X::d_str) << "\n"
        "size of pointer to member function:  " << sizeof(&X::fun) << "\n"
        "size of pointer to non-member data:   " << sizeof(char *) << "\n"
        "size of pointer to free function:     " << sizeof(&printf) << '\n';
}

/*
generated output:
```

```

size of pointer to data-member:      4
size of pointer to member function:  8
size of pointer to non-member data:  4
size of pointer to free function:     4
*/

```

On a 32-bit architecture a pointer to a member function requires eight bytes, whereas other kind of pointers require four bytes (Using Gnu's g++ compiler).

Pointer sizes are hardly ever explicitly used, but their sizes may cause confusion in statements like:

```
printf("%p", &X::fun);
```

Of course, `printf` is likely not the right tool to produce the value of these **C++** specific pointers. The values of these pointers can be inserted into streams when a union, reinterpreting the 8-byte pointers as a series of `size_t` char values, is used:

```

#include <string>
#include <iostream>
#include <iomanip>

class X
{
public:
    void fun();
    std::string d_str;
};
inline void X::fun()
{
    std::cout << "hello\n";
}

using namespace std;
int main()
{
    union
    {
        void (X::*f)();
        unsigned char *cp;
    }
    u = { &X::fun };

    cout.fill('0');
    cout << hex;
    for (unsigned idx = sizeof(void (X::*))(); idx-- > 0; )
        cout << setw(2) << static_cast<unsigned>(u.cp[idx]);
    cout << '\n';
}

```


Chapter 17

Nested Classes

Classes can be defined inside other classes. Classes that are defined inside other classes are called *nested classes*. Nested classes are used in situations where the nested class has a close conceptual relationship to its surrounding class. For example, with the class `string` a type `string::iterator` is available which will provide all characters that are stored in the `string`. This `string::iterator` type could be defined as an object `iterator`, defined as nested class in the class `string`.

A class can be nested in every part of the surrounding class: in the `public`, `protected` or `private` section. Such a nested class can be considered a member of the surrounding class. The normal access and rules in classes apply to nested classes. If a class is nested in the `public` section of a class, it is visible outside the surrounding class. If it is nested in the `protected` section it is visible in subclasses, derived from the surrounding class, if it is nested in the `private` section, it is only visible for the members of the surrounding class.

The surrounding class has no special privileges towards the nested class. The nested class has full control over the accessibility of its members by the surrounding class. For example, consider the following class definition:

```
class Surround
{
    public:
        class FirstWithin
        {
            int d_variable;

            public:
                FirstWithin();
                int var() const;
        };
    private:
        class SecondWithin
        {
            int d_variable;

            public:
                SecondWithin();
                int var() const;
        };
};
inline int Surround::FirstWithin::var() const
{
    return d_variable;
}
inline int Surround::SecondWithin::var() const
```

```

{
    return d_variable;
}

```

Here access to the members is defined as follows:

- The class `FirstWithin` is visible outside and inside `Surround`. The class `FirstWithin` this has global visibility.
- `FirstWithin`'s constructor and its member function `var` are also globally visible.
- The data member `d_variable` is only visible to the members of the class `FirstWithin`. Neither the members of `Surround` nor the members of `SecondWithin` can directly access `FirstWithin::d_variable`.
- The class `SecondWithin` is only visible inside `Surround`. The public members of the class `SecondWithin` can also be used by the members of the class `FirstWithin`, as nested classes can be considered members of their surrounding class.
- `SecondWithin`'s constructor and its member function `var` also can only be reached by the members of `Surround` (and by the members of its nested classes).
- `SecondWithin::d_variable` is only visible to `SecondWithin`'s members. Neither the members of `Surround` nor the members of `FirstWithin` can access `d_variable` of the class `SecondWithin` directly.
- As always, an object of the class type is required before its members can be called. This also holds true for nested classes.

To grant the surrounding class access rights to the private members of its nested classes or to grant nested classes access rights to the private members of the surrounding class, the classes can be defined as friend classes (see section 17.3).

Nested classes can be considered members of the surrounding class, but members of nested classes are *not* members of the surrounding class. So, a member of the class `Surround` may not access `FirstWithin::var` directly. This is understandable considering that a `Surround` object is not also a `FirstWithin` or `SecondWithin` object. In fact, nested classes are just typenames. It is not implied that objects of such classes automatically exist in the surrounding class. If a member of the surrounding class should use a (non-static) member of a nested class then the surrounding class must define a nested class object, which can thereupon be used by the members of the surrounding class to use members of the nested class.

For example, in the following class definition there is a surrounding class `Outer` and a nested class `Inner`. The class `Outer` contains a member function `caller`. The member function `caller` uses the inner object that is composed within `Outer` to call `Inner::infunction`:

```

class Outer
{
    public:
        void caller();

    private:
        class Inner
        {
            public:
                void infunction();
        };
        Inner d_inner;           // class Inner must be known
};
void Outer::caller()
{
    d_inner.infunction();
}

```

`Inner::infunction` can be called as part of the inline definition of `Outer::caller`, even though the definition of the class `Inner` is yet to be seen by the compiler. On the other hand, the compiler must have seen the definition of the class `Inner` before a data member of that class can be defined.

17.1 Defining nested class members

Member functions of nested classes may be defined as inline functions. Inline member functions can be defined as if they were defined outside of the class definition. To define the member function `Outer::caller` outside of the class `Outer`, the function's fully qualified name (starting from the outermost class scope (`Outer`)) must be provided to the compiler. Inline and in-class functions can be defined accordingly. They can be defined and they can use any nested class. Even if the nested class's definition appears later in the outer class's interface.

When (nested) member functions are defined inline, their definitions should be put below their class interface. Static nested data members are also usually defined outside of their classes. If the class `FirstWithin` would have a static `size_t` data member `epoch`, it could be initialized as follows:

```
size_t Surround::FirstWithin::epoch = 1970;
```

Furthermore, multiple scope resolution operators are needed to refer to public static members in code outside of the surrounding class:

```
void showEpoch()
{
    cout << Surround::FirstWithin::epoch = 1970;
}
```

Within the class `Surround` only the `FirstWithin::` scope must be used; within the class `FirstWithin` there is no need to refer explicitly to the scope.

What about the members of the class `SecondWithin`? The classes `FirstWithin` and `SecondWithin` are both nested within `Surround`, and can be considered members of the surrounding class. Since members of a class may directly refer to each other, members of the class `SecondWithin` can refer to (public) members of the class `FirstWithin`. Consequently, members of the class `SecondWithin` could refer to the `epoch` member of `FirstWithin` as `FirstWithin::epoch`.

17.2 Declaring nested classes

Nested classes may be declared before they are actually defined in a surrounding class. Such forward declarations are required if a class contains multiple nested classes, and the nested classes contain pointers, references, parameters or return values to objects of the other nested classes.

For example, the following class `Outer` contains two nested classes `Inner1` and `Inner2`. The class `Inner1` contains a pointer to `Inner2` objects, and `Inner2` contains a pointer to `Inner1` objects. Cross references require forward declarations. Forward declarations must be given an access specification that is identical to the access specification of their definitions. In the following example the `Inner2` forward declaration must be given in a `private` section, as its definition is also part of the class `Outer`'s private interface:

```
class Outer
{
    private:
        class Inner2;           // forward declaration
```

```

class Inner1
{
    Inner2 *pi2;    // points to Inner2 objects
};
class Inner2
{
    Inner1 *pil;    // points to Inner1 objects
};
};

```

17.3 Accessing private members in nested classes

To grant nested classes access rights to the private members of their surrounding class, to grant access to the private members of other nested classes, or to grant a surrounding class access to the private members of its nested classes the `friend` keyword must be used.

Consider the following situation where a class `Surround` has two nested classes `FirstWithin` and `SecondWithin`. Each of the three classes has a static data member `int s_variable`:

```

class Surround
{
    static int s_variable;
public:
    class FirstWithin
    {
        static int s_variable;
        public:
            int value();
    };
    int value();
private:
    class SecondWithin
    {
        static int s_variable;
        public:
            int value();
    };
};

```

If the class `Surround` should be able to access `FirstWithin` and `SecondWithin`'s private members, these latter two classes must declare `Surround` to be their friend. The function `Surround::value` can thereupon access the private members of its nested classes. For example (note the `friend` declarations in the two nested classes):

```

class Surround
{
    static int s_variable;
public:
    class FirstWithin
    {
        friend class Surround;
        static int s_variable;
        public:
            int value();
    };
    int value();
};

```

```

private:
    class SecondWithin
    {
        friend class Surround;
        static int s_variable;
    public:
        int value();
    };
};
inline int Surround::FirstWithin::value()
{
    FirstWithin::s_variable = SecondWithin::s_variable;
    return (s_variable);
}

```

To allow the nested classes access to the private members of their surrounding class, the class Surround must declare its nested classes as friends. As the friend keyword may only be used when the class that is to become a friend is already known as a class by the compiler, either a forward declaration of the nested classes is required (to be followed by the friend declaration), or the friend declaration follows the definition of the nested classes. The forward declaration followed by the friend declaration looks like this:

```

class Surround
{
    public:
        class FirstWithin;
        class SecondWithin;
        friend class FirstWithin;
        friend class SecondWithin;
        class FirstWithin
        { ... };
        ...
};

```

Alternatively, the friend declaration may follow the definition of the classes. A class can be declared a friend following its definition, with in-class code already using the fact that it will be declared a friend of the outer class. Furthermore, in-class defined nested class members may already use members of the surrounding class that have not yet been seen by the compiler. Finally note that 's_variable' which is defined in the class Surround may be accessed by the nested classes as Surround::s_variable:

```

class Surround
{
    static int s_variable;
    public:
        class FirstWithin
        {
            friend class Surround;
            static int s_variable;
        public:
            int value();
        };
        friend class FirstWithin;
        int value();

    private:
        class SecondWithin
        {
            friend class Surround;

```

```

        static int s_variable;
    public:
        int value();
};
static void classMember();

    friend class SecondWithin;
};
inline int Surround::value()
{
    FirstWithin::s_variable = SecondWithin::s_variable;
    return s_variable;
}
inline int Surround::FirstWithin::value()
{
    Surround::s_variable = 4;
    Surround::classMember();
    return s_variable;
}
inline int Surround::SecondWithin::value()
{
    Surround::s_variable = 40;
    return s_variable;
}

```

Finally, friend declarations must be applied to grant the nested classes access to each other's private members. To grant `FirstWithin` access to `SecondWithin`'s private members nothing but a friend declaration in `SecondWithin` is required. However, to grant `SecondWithin` access to `FirstWithin`'s private members the class `FirstWithin` cannot simply use `friend class SecondWithin`, as `SecondWithin`'s definition is as yet unknown. A forward declaration of `SecondWithin` is required and this forward declaration must be provided by the class `Surround`, rather than by the class `FirstWithin`.

Clearly, a forward declaration like `'class SecondWithin'` makes no sense in the class `FirstWithin` itself, as this would refer to an external (global) class `SecondWithin`. Likewise, the forward declaration of the nested class `SecondWithin` cannot be provided inside `FirstWithin` as `class Surround::SecondWithin`. Doing so would generate the following error message:

`'Surround' does not have a nested type named 'SecondWithin'`

Here the class `SecondWithin` must be declared by the class `Surround`, before the class `FirstWithin` has been defined. This way `SecondWithin`'s friend declaration is accepted inside `FirstWithin`.

The following example shows the classes having full access to all private members of all classes:

```

class Surround
{
    class SecondWithin;
    static int s_variable;
    public:
        class FirstWithin
        {
            friend class Surround;
            friend class SecondWithin;
            static int s_variable;
            public:
                int value();
        };
    friend class FirstWithin;
    int value();
}

```

```

private:
    class SecondWithin
    {
        friend class Surround;
        friend class FirstWithin;
        static int s_variable;
    public:
        int value();
    };
    friend class SecondWithin;
};
inline int Surround::value()
{
    FirstWithin::s_variable = SecondWithin::s_variable;
    return s_variable;
}
inline int Surround::FirstWithin::value()
{
    Surround::s_variable = SecondWithin::s_variable;
    return s_variable;
}
inline int Surround::SecondWithin::value()
{
    Surround::s_variable = FirstWithin::s_variable;
    return s_variable;
}

```

17.4 Nesting enumerations

Enumerations may also be nested in classes. Nesting enumerations is a good way to show the close connection between the enumeration and its class. Nested enumerations have the same controlled visibility as other class members. They may be defined in the private, protected or public sections of classes and are inherited by derived classes. In the class `ios` we've seen values like `ios::beg` and `ios::cur`. In the current Gnu C++ implementation these values are defined as values of the `seek_dir` enumeration:

```

class ios: public _ios_fields
{
    public:
        enum seek_dir
        {
            beg,
            cur,
            end
        };
};

```

As an illustration assume that a class `DataStructure` represents a data structure that may be traversed in a forward or backward direction. Such a class can define an enumeration `Traversal` having the values `FORWARD` and `BACKWARD`. Furthermore, a member function `setTraversal` can be defined requiring a `Traversal` type of argument. The class can be defined as follows:

```

class DataStructure
{
    public:
        enum Traversal

```

```

        {
            FORWARD,
            BACKWARD
        };
        setTraversal(Traversal mode);
private:
    Traversal
        d_mode;
};

```

Within the class `DataStructure` the values of the `Traversal` enumeration can be used directly. For example:

```

void DataStructure::setTraversal(Traversal mode)
{
    d_mode = mode;
    switch (d_mode)
    {
        FORWARD:
            break;

        BACKWARD:
            break;
    }
}

```

Outside of the class `DataStructure` the name of the enumeration type is not used to refer to the values of the enumeration. Here the classname is sufficient. Only if a variable of the enumeration type is required the name of the enumeration type is needed, as illustrated by the following piece of code:

```

void fun()
{
    DataStructure::Traversal                // enum typename required
        localMode = DataStructure::FORWARD; // enum typename not required

    DataStructure ds;

    ds.setTraversal(DataStructure::BACKWARD); // enum typename not required
}

```

Only if `DataStructure` defines a nested class `Nested`, in turn defining the enumeration `Traversal`, the two class scopes are required. In that case the latter example should have been coded as follows:

```

void fun()
{
    DataStructure::Nested::Traversal
        localMode = DataStructure::Nested::FORWARD;

    DataStructure ds;

    ds.setTraversal(DataStructure::Nested::BACKWARD);
}

```

17.4.1 Empty enumerations

Enum types usually define symbolic values. However, this is not required. In section [14.5.1](#) the `std::bad_cast` type was introduced. A `bad_cast` is thrown by the `dynamic_cast<>` operator when

a reference to a base class object cannot be cast to a derived class reference. The `bad_cast` could be caught as type, irrespective of any value it might represent.

Types may be defined without any associated values. An *empty enum* can be defined which is an enum not defining any values. The empty enum's type name may thereupon be used as a legitimate type in, e.g. a catch clause.

The example shows how an empty enum is defined (often, but not necessarily within a class) and how it may be thrown (and caught) as exceptions:

```
#include <iostream>

enum EmptyEnum
{};

int main()
try
{
    throw EmptyEnum();
}
catch (EmptyEnum)
{
    std::cout << "Caught empty enum\n";
}
```

17.5 Revisiting virtual constructors

In section 14.11 the notion of virtual constructors was introduced. In that section a class `Base` was defined as an abstract base class. A class `Clonable` was defined to manage `Base` class pointers in containers like vectors.

As the class `Base` is a minute class, hardly requiring any implementation, it can very well be defined as a nested class in `Clonable`. This emphasizes the close relationship between `Clonable` and `Base`. Nesting `Base` under `Clonable` changes

```
class Derived: public Base
```

into:

```
class Derived: public Clonable::Base
```

Apart from defining `Base` as a nested class and deriving from `Clonable::Base` rather than from `Base` (and providing `Base` members with the proper `Clonable::` prefix to complete their fully qualified names), no further modifications are required. Here are the modified parts of the program shown earlier (cf. section 14.11), now using `Base` nested under `Clonable`:

```
// Clonable and nested Base, including their inline members:
class Clonable
{
public:
    class Base;
private:
    Base *d_bp;
public:
    class Base
    {
```

```

        public:
            virtual ~Base();
            Base *clone() const;
        private:
            virtual Base *newCopy() const = 0;
    };
    Clonable();
    explicit Clonable(Base *base);
    ~Clonable();
    Clonable(Clonable const &other);
    Clonable(Clonable const &&tmp);
    Clonable &operator=(Clonable const &other);
    Clonable &operator=(Clonable const &&tmp);

    Base &base() const;
};
inline Clonable::Base *Clonable::Base::clone() const
{
    return newCopy();
}
inline Clonable::Base &Clonable::base() const
{
    return *d_bp;
}

// Derived and its inline member:
class Derived1: public Clonable::Base
{
    public:
        ~Derived1();
    private:
        virtual Clonable::Base *newCopy() const;
};
inline Clonable::Base *Derived1::newCopy() const
{
    return new Derived1(*this);
}

// Members not implemented inline:
Clonable::Base::~~Base()
{
}

```

Chapter 18

The Standard Template Library

The Standard Template Library (STL) is a general purpose library consisting of containers, generic algorithms, iterators, function objects, allocators, adaptors and data structures. The data structures used by the algorithms are *abstract* in the sense that the algorithms can be used with (practically) any data type.

The algorithms can process these abstract data types because they are *template* based. This chapter does not cover template *construction* (but see chapter 20 for that). Rather, it focuses on the *use* of the algorithms.

Several elements also used by the standard template library have already been discussed in the C++ Annotations. In chapter 12 abstract containers were discussed, and in section 10.10 function objects were introduced. Also, *iterators* were mentioned at several places in this document.

The main components of the STL will be covered in this and the next chapter. Iterators, adaptors, smart pointers, multi threading and other features of the STL will be discussed in coming sections. Generic algorithms are covered in the next chapter (19).

Allocators take care of the memory allocation within the STL. The default allocator class suffices for most applications, and is not further discussed in the C++ Annotations.

All elements of the STL are defined in the standard namespace. Therefore, a `using namespace std` or a comparable directive is required unless it is preferred to specify the required namespace explicitly. In header files the `std` namespace should explicitly be used (cf. section 7.9.1).

In this chapter the empty angle bracket notation is frequently used. In code a typename must be supplied between the angle brackets. E.g., `plus<>` is used in the C++ Annotations, but in code `plus<string>` may be encountered.

18.1 Predefined function objects

Before using the predefined function objects presented in this section the `<functional>` header file must have been included.

Function objects play important roles in generic algorithms. For example, there exists a generic algorithm `sort` expecting two iterators defining the range of objects that should be sorted, as well as a function object calling the appropriate comparison operator for two objects. Let's take a quick look at this situation. Assume strings are stored in a vector, and we want to sort the vector in descending order. In that case, sorting the vector `stringVec` is as simple as:

```
sort(stringVec.begin(), stringVec.end(), greater<string>());
```

The last argument is recognized as a *constructor*: it is an *instantiation* of the `greater<>` class template,

applied to strings. This object is called as a function object by the `sort` generic algorithm. The generic algorithm calls the function object's `operator()` member to compare two string objects. The function object's `operator()` will, in turn, call `operator<` of the string data type. Eventually, when `sort` returns, the first element of the vector will contain the string having the greatest string value of all.

The function object's `operator()` itself is *not* visible at this point. Don't confuse the parentheses in the '`greater<string>()`' argument with calling `operator()`. When `operator()` is actually used inside `sort`, it receives two arguments: two strings to compare for 'greaterness'. Since `greater<string>::operator()` is defined inline, the call itself is not actually present in the above `sort` call. Instead `sort` calls `string::operator<` through `greater<string>::operator()`.

Now that we know that a constructor is passed as argument to (many) generic algorithms, we can design our own function objects. Assume we want to sort our vector case-insensitively. How do we proceed? First we note that the default `string::operator<` (for an incremental sort) is not appropriate, as it does case sensitive comparisons. So, we provide our own `CaseInsensitive` class, which compares two strings case insensitively. Using the standard C function `strcasecmp`, the following program performs the trick. It case-insensitively sorts its command-line arguments in ascending alphabetic order:

```
#include <iostream>
#include <string>
#include <cstring>
#include <algorithm>
using namespace std;

class CaseInsensitive
{
public:
    bool operator()(string const &left, string const &right) const
    {
        return strcasecmp(left.c_str(), right.c_str()) < 0;
    }
};

int main(int argc, char **argv)
{
    sort(argv, argv + argc, CaseInsensitive());
    for (int idx = 0; idx < argc; ++idx)
        cout << argv[idx] << " ";
    cout << '\n';
}
```

The default constructor of the class `CaseInsensitive` is used to provide `sort` with its final argument. So the only member function that must be defined is `CaseInsensitive::operator()`. Since we know it's called with string arguments, we define it to expect two string arguments, which are used when calling `strcasecmp`. Furthermore, `operator()` function is defined inline, so that it does not produce overhead when called by the `sort` function. The `sort` function calls the function object with various combinations of strings. If the compiler grants our inline requests, it will in fact call `strcasecmp`, skipping two extra function calls.

The comparison function object is often a *eme*(predefined function object), which are available for many commonly used operations. In the following sections the available predefined function objects are presented, together with some examples showing their use. Near the end of the section about function objects *function adaptors* are introduced.

Predefined function objects are used predominantly with generic algorithms. Predefined function objects exists for arithmetic, relational, and logical operations. In section 23.4 predefined function objects are developed performing bitwise operations.

18.1.1 Arithmetic function objects

The arithmetic function objects support the standard arithmetic operations: addition, subtraction, multiplication, division, modulo and negation. These function objects invoke the corresponding operators of the data types for which they are instantiated. For example, for addition the function object `plus<Type>` is available. If we replace `Type` by `size_t` then the addition operator for `size_t` values is used, if we replace `Type` by `string`, the addition operator for strings is used. For example:

```
#include <iostream>
#include <string>
#include <functional>
using namespace std;

int main(int argc, char **argv)
{
    plus<size_t> uAdd;                // function object to add size_ts

    cout << "3 + 5 = " << uAdd(3, 5) << '\n';

    plus<string> sAdd;                // function object to add strings

    cout << "argv[0] + argv[1] = " << sAdd(argv[0], argv[1]) << '\n';
}
/*
Output when called as: a.out going

3 + 5 = 8
argv[0] + argv[1] = a.outgoing
*/
```

Why is this useful? Note that the function object can be used with all kinds of data types (not only with the predefined datatypes) supporting the operator called by the function object.

Suppose we want to perform an operation on a left hand side operand which is always the same variable and a right hand side argument for which, in turn, all elements of an array should be used. E.g., we want to compute the sum of all elements in an array; or we want to concatenate all the strings in a text-array. In situations like these function objects come in handy.

As stated, function objects are heavily used in the context of the generic algorithms, so let's take a quick look ahead at yet another one.

The generic algorithm `accumulate` visits all elements specified by an iterator-range, and performs a requested binary operation on a common element and each of the elements in the range, returning the accumulated result after visiting all elements specified by the iterator range. It's easy to use this algorithm. The next program accumulates all command line arguments and prints the final string:

```
#include <iostream>
#include <string>
#include <functional>
#include <numeric>
using namespace std;

int main(int argc, char **argv)
{
    string result =
        accumulate(argv, argv + argc, string(), plus<string>());

    cout << "All concatenated arguments: " << result << '\n';
}
```

The first two arguments define the (iterator) range of elements to visit, the third argument is `string`. This anonymous `string` object provides an initial value. We could also have used

```
string("All concatenated arguments: ")
```

in which case the `cout` statement could simply have been `cout << result << '\n'`. The string-addition operation is used, called from `plus<string>`. The final concatenated string is returned.

Now we define a class `Time`, overloading `operator+`. Again, we can apply the predefined function object `plus`, now tailored to our newly defined datatype, to add times:

```
#include <iostream>
#include <string>
#include <vector>
#include <functional>
#include <numeric>
using namespace std;

class Time
{
    friend ostream &operator<<(ostream &str, Time const &time);
    size_t d_days;
    size_t d_hours;
    size_t d_minutes;
    size_t d_seconds;
public:
    Time(size_t hours, size_t minutes, size_t seconds);
    Time &operator+=(Time const &rValue);
};

Time const operator+(Time const &lValue, Time const &rValue)
{
    Time ret(lValue);
    ret += rValue;
    return ret;
}

Time::Time(size_t hours, size_t minutes, size_t seconds)
:
    d_days(0),
    d_hours(hours),
    d_minutes(minutes),
    d_seconds(seconds)
{}

Time &Time::operator+=(Time const &rValue)
{
    d_seconds += rValue.d_seconds;
    d_minutes += rValue.d_minutes + d_seconds / 60;
    d_hours += rValue.d_hours + d_minutes / 60;
    d_days += rValue.d_days + d_hours / 24;
    d_seconds %= 60;
    d_minutes %= 60;
    d_hours %= 24;
    return *this;
}

ostream &operator<<(ostream &str, Time const &time)
{
    return cout << time.d_days << " days, " << time.d_hours <<
        " hours, " <<
        time.d_minutes << " minutes and " <<
        time.d_seconds << " seconds.";
```

```

}
int main(int argc, char **argv)
{
    vector<Time> tvector;

    tvector.push_back(Time( 1, 10, 20));
    tvector.push_back(Time(10, 30, 40));
    tvector.push_back(Time(20, 50,  0));
    tvector.push_back(Time(30, 20, 30));

    cout <<
        accumulate
        (
            tvector.begin(), tvector.end(), Time(0, 0, 0), plus<Time>()
        ) <<
        '\n';
}
// Displays: 2 days, 14 hours, 51 minutes and 30 seconds.

```

The design of the above program is fairly straightforward. `Time` defines a constructor, it defines an insertion operator and it defines its own `operator+`, adding two time objects. In `main` four `Time` objects are stored in a `vector<Time>` object. Then, `accumulate` is used to compute the accumulated time. It returns a `Time` object, which is inserted into `cout`.

While the first example did show the use of a *named* function object, the last two examples showed the use of *anonymous* objects that were passed to the `(accumulate)` function.

The STL supports the following set of arithmetic function objects:

- `plus<>`: as shown, this object's `operator()` member calls the binary `operator+`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `minus<>`: this object's `operator()` member calls the binary `operator-`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `multiplies<>`: this object's `operator()` member calls the binary `operator*`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `divides<>`: this object's `operator()` member calls `operator/`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `modulus<>`: this object's `operator()` member calls `operator%`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `negate<>`: this object's `operator()` member calls the unary `operator-`, passing the latter operator its parameter and returning the latter operator's return value.

In the next example the `transform` generic algorithm is used to toggle the signs of all elements of an array. `Transform` expects two iterators, defining the range of objects to be transformed; an iterator defining the begin of the destination range (which may be the same iterator as the first argument); and a function object defining a unary operation for the indicated data type.

```

#include <iostream>
#include <string>
#include <functional>
#include <algorithm>
using namespace std;

int main(int argc, char **argv)
{

```

```

int iArr[] = { 1, -2, 3, -4, 5, -6 };

transform(iArr, iArr + 6, iArr, negate<int>());

for (int idx = 0; idx < 6; ++idx)
    cout << iArr[idx] << ", ";
cout << '\n';
}
// Displays:  -1, 2, -3, 4, -5, 6,

```

18.1.2 Relational function objects

The relational operators are called by the relational function objects. All standard relational operators are supported: `==`, `!=`, `>`, `>=`, `<` and `<=`.

The STL supports the following set of relational function objects:

- `equal_to<>`: this object's `operator()` member calls `operator==`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `not_equal_to<>`: this object's `operator()` member calls `operator!=`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `greater<>`: this object's `operator()` member calls `operator>`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `greater_equal<>`: this object's `operator()` member calls `operator>=`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `less<>`: this object's `operator()` member calls `operator<`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `less_equal<>`: this object's `operator()` member calls `operator<=`, passing the latter operator its two parameter values and returning the latter operator's return value.

An example using the relational function objects in combination with `sort` is:

```

#include <iostream>
#include <string>
#include <functional>
#include <algorithm>
using namespace std;

int main(int argc, char **argv)
{
    sort(argv, argv + argc, greater_equal<string>());

    for (int idx = 0; idx < argc; ++idx)
        cout << argv[idx] << " ";
    cout << '\n';

    sort(argv, argv + argc, less<string>());

    for (int idx = 0; idx < argc; ++idx)
        cout << argv[idx] << " ";
    cout << '\n';
}

```


The example illustrates how strings may be alphabetically and reversed alphabetically sorted. By passing `greater_equal<string>` the strings are sorted in *decreasing* order (the first word will be the 'greatest'), by passing `less<string>` the strings are sorted in *increasing* order (the first word will be the 'smallest').

Note that `argv` contains `char *` values, and that the relational function object expects a `string`. The promotion from `char const *` to `string` is silently performed.

18.1.3 Logical function objects

The logical operators are called by the logical function objects. The standard logical operators are supported: `and`, `or`, and `not`.

The STL supports the following set of logical function objects:

- `logical_and<>`: this object's `operator()` member calls `operator&&`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `logical_or<>`: this object's `operator()` member calls `operator||`, passing the latter operator its two parameter values and returning the latter operator's return value.
- `logical_not<>`: this object's `operator()` member calls `operator!`, passing the latter operator its parameter and returning the latter operator's return value.

An example using `operator!` is provided in the following trivial program, using `transform` to transform the logical values stored in an array:

```
#include <iostream>
#include <string>
#include <functional>
#include <algorithm>
using namespace std;

int main(int argc, char **argv)
{
    bool bArr[] = {true, true, true, false, false, false};
    size_t const bArrSize = sizeof(bArr) / sizeof(bool);

    for (size_t idx = 0; idx < bArrSize; ++idx)
        cout << bArr[idx] << " ";
    cout << '\n';

    transform(bArr, bArr + bArrSize, bArr, logical_not<bool>());

    for (size_t idx = 0; idx < bArrSize; ++idx)
        cout << bArr[idx] << " ";
    cout << '\n';
}
/*
Displays:

1 1 1 0 0 0
0 0 0 1 1 1
*/
```

18.1.4 Function adaptors

Function adaptors modify the working of existing function objects. There are two kinds of function adaptors:

- *Binders* are function adaptors converting binary function objects to unary function objects. They do so by *binding* one parameter of a binary function object to a constant value. For example, the first parameter of the `minus<int>` function object may be bound to 100, meaning that the resulting value will always be 100 minus the value of the function object's second argument.

Either the first or the second parameter may be bound to a specific value. To bind the constant value to the function object's first parameter the function adaptor `bind1st` is used. To bind the constant value to the function object's second parameter the function adaptor `bind2nd` is used. As an example, assume we want to count all elements of a vector of `string` objects that occur later in the alphabetical ordering than some reference string.

The `count_if` generic algorithm is the algorithm of choice for solving these kinds of problems. It expects the usual iterator range and a function object. However, instead of providing it with a function object it is provided with the `bind2nd` adaptor which in turn is initialized with a relational function object (`greater<string>`) and a reference string against which all strings in the iterator range are compared. Here is the required `bind2nd` specification:

```
bind2nd(greater<string>(), referenceString)
```

Here is what this binder will do:

- To begin with, an adaptor (and so a binder) is a function object, so it defines `operator()`. In this case the binder function object is a *unary* function object.
- The binder's `operator()` receives each of the strings referred to by the iterator range in turn.
- Next it passes these strings and the binder's second argument (the reference object) to the (binary) `operator()` defined by the function object that is passed as the binder's first argument.
- It returns the return value of that latter function object

Although binders are defined as templates, it is illustrative to have a look at their implementations, assuming they were ordinary classes. Here is such a pseudo-implementation of the `bind2nd` function adaptor:

```
class bind2nd
{
    FunctionObject d_object;
    Operand const &d_operand;
public:
    bind2nd(FunctionObject const &object, Operand const &operand);
    ReturnType operator()(Operand const &lvalue);
};
inline bind2nd::bind2nd(FunctionObject const &object,
                        Operand const &operand)
:
    d_object(object),
    d_operand(operand)
{}
inline ReturnType bind2nd::operator()(Operand const &lvalue)
{
    return d_object(lvalue, d_rvalue);
}
```

The binder's `operator()` merely calls the function object's `operator()`, providing it with two arguments. It uses its parameter as the (latter) `operator()`'s first argument and it uses `d_operand`

as `operator()`'s second argument. The adaptor's members are typically very small so they are usually implemented inline.

The above application of the `bind2nd` adaptor has another important characteristic. Its return type is identical to the return type of the function object that it receives as its first argument, which is `bool`. Functions returning `bool` values are also called *predicate functions*. In the above application the `bind2nd` adaptor therefore becomes a predicate function itself.

The `count_if` generic algorithm visits all the elements in an iterator range, returning the number of times the predicate specified as its final argument returns `true`. Each of the elements of the iterator range is passed to this predicate, which is therefore a unary predicate. Through the binder the binary function object `greater<>` is adapted to a unary function object, that now compares each of the elements referred to by the iterator range to the reference string. Eventually, the `count_if` function is called like this:

```
count_if(stringVector.begin(), stringVector.end(),
         bind2nd(greater<string>(), referenceString));
```

- *Negators* are function adaptors converting the values returned by predicate function. Since there are unary and binary predicate functions, two negator function adaptors were predefined: `not1` is the negator to use with unary predicates, `not2` is the negator to with binary function objects.

Example: to count the number of persons in a `vector<string>` vector ordered alphabetically before (i.e., *not* exceeding) a certain reference text one of the following alternatives could be used:

- a binary predicate that directly offers the required comparison:

```
count_if(stringVector.begin(), stringVector.end(),
         bind2nd(less_equal<string>(), referenceText))
```

- `not2` in combination with the `greater<>` predicate:

```
count_if(stringVector.begin(), stringVector.end(),
         bind2nd(not2(greater<string>()), referenceText))
```

Here `not2` is used as it negates the truth value of a binary operator(), in this case the `greater<string>::operator()` member function.

- `not1` in combination with the `bind2nd` predicate:

```
count_if(stringVector.begin(), stringVector.end(),
         not1(bind2nd(greater<string>(), referenceText)))
```

Here `not1` is used as it negates the truth value of a unary operator(), in this case the `bind2nd` function adaptor.

The use of negators is illustrated by the following program:

```
#include <iostream>
#include <functional>
#include <algorithm>
#include <vector>
using namespace std;

int main(int argc, char **argv)
{
    int iArr[] = { 1, 2, 3, 4, 5, 6, 7, 8, 9, 10};

    cout << count_if(iArr, iArr + 10, bind2nd(less_equal<int>(), 6)) <<
        ' ';
```

```

    cout << count_if(iArr, iArr + 10, bind2nd(not2(greater<int>()), 6)) <<
        ' ';
    cout << count_if(iArr, iArr + 10, not1(bind2nd(greater<int>()), 6)) <<
        '\n';
}
// Displays: 6 6 6

```

One may wonder which of these alternative approaches is fastest. Using the first approach, in which a directly available function object was used, two actions must be performed for each iteration by `count_if`:

- The binder's `operator()` is called;
- The operation `<=` is performed.

When the compiler uses `inline` as requested, only the second step is actually performed.

Using the second approach, using the `not2` negator to negate the truth value of the complementary logical function adaptor, three actions must be performed for each iteration by `count_if`:

- The binder's `operator()` is called;
- The negator's `operator()` is called;
- The operation `>` is performed.

When the compiler uses `inline` as requested, only the third step is actually performed.

Using the third approach, using `not1` negator to negate the truth value of the binder, three actions must be performed for each iteration by `count_if`:

- The negator's `operator()` is called;
- The binder's `operator()` is called;
- The operation `>` is performed.

When the compiler uses `inline` as requested, only the third step is actually performed.

With a commonly used optimization flag like `-O2` the compiler will try to grant `inline` requests. However, if the compiler ignores the `inline` requests the first variant will be fastest.

18.2 Iterators

In addition to the conceptual iterator types presented in this section the STL defines several adaptors allowing objects to be passed as iterators. These adaptors are presented in the upcoming sections. Before those adaptors can be used the `<iterator>` header file must have been included.

Iterators are objects acting like pointers. Iterators have the following general characteristics:

- Two iterators may be compared for (in)equality using the `==` and `!=` operators. The *ordering* operators (e.g., `>`, `<`) can usually not be used.
- Given an iterator `iter`, `*iter` represents the object the iterator points to (alternatively, `iter->` can be used to reach the members of the object the iterator points to).
- `++iter` or `iter++` advances the iterator to the next element. The notion of advancing an iterator to the next element is consequently applied: several containers support *reversed_iterator* types, in which the `++iter` operation actually reaches a previous element in a sequence.

- *Pointer arithmetic* may be used with iterators of containers storing their elements consecutively in memory like vector and deque. For such containers `iter + 2` points to the second element beyond the one to which `iter` points.
- Merely defining an iterator is comparable to having a 0-pointer. Example:

```
#include <vector>
#include <iostream>
using namespace std;

int main()
{
    vector<int>::iterator vi;

    cout << &*vi;        // prints 0
}
```

STL containers usually define members offering iterators (i.e., they define their own type iterator). These members are commonly called `begin` and `end` and (for reversed iterators (type `reverse_iterator`)) `rbegin` and `rend`.

Standard practice requires iterator ranges to be *left inclusive*. The notation `[left, right)` indicates that `left` is an iterator pointing to the first element, while `right` is an iterator pointing just *beyond* the last element. The iterator range is *empty* when `left == right`.

The following example shows how all elements of a vector of strings can be inserted into `cout` using its iterator ranges `[begin(), end())`, and `[rbegin(), rend())`. Note that the for-loops for both ranges are identical. Furthermore it nicely illustrates how the `auto` keyword can be used to define the type of the loop control variable instead of using a much more verbose variable definition like `vector<string>::iterator` (see also section 3.3.6):

```
#include <iostream>
#include <vector>
#include <string>
using namespace std;

int main(int argc, char **argv)
{
    vector<string> args(argv, argv + argc);

    for (auto iter = args.begin(); iter != args.end(); ++iter)
        cout << *iter << " ";
    cout << '\n';

    for (auto iter = args.rbegin(); iter != args.rend(); ++iter)
        cout << *iter << " ";
    cout << '\n';
}
```

Furthermore, the STL defines *const_iterator* types that must be used when visiting a series of elements in a constant container. Whereas the elements of the vector in the previous example could have been altered, the elements of the vector in the next example are immutable, and *const_iterators* are required:

```
#include <iostream>
#include <vector>
#include <string>
using namespace std;
```

```

int main(int argc, char **argv)
{
    vector<string> const args(argv, argv + argc);

    for
    (
        vector<string>::const_iterator iter = args.begin();
        iter != args.end();
        ++iter
    )
        cout << *iter << " ";
    cout << '\n';

    for
    (
        vector<string>::const_reverse_iterator iter = args.rbegin();
        iter != args.rend();
        ++iter
    )
        cout << *iter << " ";
    cout << '\n';

    return 0;
}

```

The examples also illustrates that plain pointers can be used as iterators. The initialization `vector<string> args(argv, argv + argc)` provides the `args` vector with a pair of pointer-based iterators: `argv` points to the first element to initialize `sarg` with, `argv + argc` points just beyond the last element to be used, `++argv` reaches the next command line argument. This is a general pointer characteristic, which is why they too can be used in situations where iterators are expected.

The STL defines five types of iterators. These iterator types are expected by generic algorithms, and in order to create a particular type of iterator yourself it is important to know their characteristics. In general, iterators must define:

- `operator==`, testing two iterators for equality,
- `operator++`, incrementing the iterator, as prefix operator,
- `operator*`, to access the element the iterator refers to,

The following types of iterators are used when describing generic algorithms in chapter 19:

- **InputIterators:**

`InputIterators` are used to read from a container. The dereference operator is guaranteed to work as `rvalue` in expressions. Instead of an `InputIterator` it is also possible to use (see below) `Forward-`, `Bidirectional-` or `RandomAccessIterators`. Notations like `InputIterator1` and `InputIterator2` may be used as well. In these cases, numbers are used to indicate which iterators ‘belong together’. E.g., the generic algorithm `inner_product` has the following prototype:

```

Type inner_product(InputIterator1 first1, InputIterator1 last1,
                  InputIterator2 first2, Type init);

```

`InputIterator1 first1` and `InputIterator1 last1` define a pair of input iterators on one range, while `InputIterator2 first2` defines the beginning of another range. Analogous notations may be used with other iterator types.

- **OutputIterators:**

OutputIterators can be used to write to a container. The dereference operator is guaranteed to work as an lvalue in expressions, but not necessarily as rvalue. Instead of an OutputIterator it is also possible to use (see below) Forward-, Bidirectional- or RandomAccessIterators.

- **ForwardIterators:**

ForwardIterators combine InputIterators and OutputIterators. They can be used to traverse containers in one direction, for reading and/or writing. Instead of a ForwardIterator it is also possible to use (see below) Bidirectional- or RandomAccessIterators.

- **BidirectionalIterators:**

BidirectionalIterators can be used to traverse containers in both directions, for reading and writing. Instead of a BidirectionalIterator it is also possible to use (see below) a RandomAccessIterator.

- **RandomAccessIterators:**

RandomAccessIterators provide random access to container elements. An algorithm like `sort` requires a RandomAccessIterator, and can therefore *not* be used to sort the elements of lists or maps, which only provide BidirectionalIterators.

The example given with the RandomAccessIterator illustrates how to relate iterators and generic algorithms: look for the iterator that's required by the (generic) algorithm, and then see whether the datastructure supports the required type of iterator. If not, the algorithm cannot be used with the particular datastructure.

18.2.1 Insert iterators

Generic algorithms often require a target container into which the results of the algorithm are deposited. For example, the `copy` generic algorithm has three parameters. The first two define the range of visited elements, the third defines the first position where the results of the copy operation should be stored.

With the `copy` algorithm the number of elements to copy is usually available beforehand, since that number can usually be provided by pointer arithmetic. However, situations exist where pointer arithmetic cannot be used. Analogously, the number of resulting elements sometimes differs from the number of elements in the initial range. The generic algorithm `unique_copy` is a case in point. Here the number of elements that are copied to the destination container is normally not known beforehand.

In situations like these an *inserter* adaptor function can often be used to create elements in the destination container. There are three types of inserter adaptors:

- `back_inserter`: calls the container's `push_back` member to add new elements at the end of the container. E.g., to copy all elements of source in reversed order to the back of destination, using the `copy` generic algorithm:

```
copy(source.rbegin(), source.rend(), back_inserter(destination));
```

- `front_inserter` calls the container's `push_front` member, adding new elements at the beginning of the container. E.g., to copy all elements of source to the front of the destination container (thereby also reversing the order of the elements):

```
copy(source.begin(), source.end(), front_inserter(destination));
```

- `inserter` calls the container's `insert` member adding new elements starting at a specified starting point. E.g., to copy all elements of `source` to the destination container, starting at the beginning of destination, shifting up existing elements to beyond the newly inserted elements:

```
copy(source.begin(), source.end(), inserter(destination,
destination.begin()));
```

The `inserter` adaptors require the existence of two typedefs:

- `typedef Data value_type`, where `Data` is the data type stored in the class offering `push_back`, `push_front` or `insert` members (Example: `typedef std::string value_type`);
- `typedef value_type const &const_reference`

Concentrating on `back_inserter`, this iterator expects the name of a container supporting a member `push_back`. The `inserter`'s `operator()` member calls the container's `push_back` member. Objects of any class supporting a `push_back` member can be passed as arguments to `back_inserter` provided the class adds

```
typedef DataType const &const_reference;
```

to its interface (where `DataType const &` is the type of the parameter of the class's member `push_back`). Example:

```
#include <algorithm>
#include <iterator>
using namespace std;

class Insertable
{
public:
    typedef int const &const_reference;

    void push_back(int const &)
    {}
};

int main()
{
    int arr[] = {1};
    Insertable insertable;

    copy(arr, arr + 1, back_inserter(insertable));
}
```

18.2.2 Iterators for 'istream' objects

The `istream_iterator<Type>` can be used to define a set of iterators for `istream` objects. The general form of the `istream_iterator` iterator is:

```
istream_iterator<Type> identifier(istream &in)
```

Here, `Type` is the type of the data elements read from the `istream` stream. It is used as the 'begin' iterator in an iterator range. `Type` may be any type for which `operator>>` is defined in combination with `istream` objects.

The default constructor is used as the end-iterator and corresponds to the end-of-stream. For example,

```
istream_iterator<string> endOfStream;
```

The *stream* object that was specified when defining the begin-iterator is *not* mentioned with the default constructor.

Using `back_inserter` and `istream_iterator` adaptors, all strings from a stream can easily be stored in a container. Example (using anonymous `istream_iterator` adaptors):

```
#include <iostream>
#include <iterator>
#include <string>
#include <vector>
#include <algorithm>
using namespace std;

int main()
{
    vector<string> vs;

    copy(istream_iterator<string>(cin), istream_iterator<string>(),
        back_inserter(vs));

    for
    (
        vector<string>::const_iterator begin = vs.begin(), end = vs.end();
        begin != end; ++begin
    )
        cout << *begin << ' ';
    cout << '\n';
}
```

18.2.3 Iterators for ‘istreambuf’ objects

Input iterators are also available for `streambuf` objects.

To read from `streambuf` objects supporting input operations `istreambuf_iterators` can be used, supporting the operations that are also available for `istream_iterator`. Different from the latter iterator type `istreambuf_iterators` support three constructors:

- `istreambuf_iterator<Type>:`

The end iterator of an iterator range is created using the default `istreambuf_iterator` constructor. It represents the end-of-stream condition when extracting values of type `Type` from the `streambuf`.

- `istreambuf_iterator<Type>(streambuf *):`

A pointer to a `streambuf` may be used when defining an `istreambuf_iterator`. It represents the begin iterator of an iterator range.

- `istreambuf_iterator<Type>(istream):`

An *istream* may be also used when defining an `istreambuf_iterator`. It accesses the *istream*’s `streambuf` and it also represents the begin iterator of an iterator range.

In section [18.2.4.1](#) an example is given using both `istreambuf_iterators` and `ostreambuf_iterators`.

18.2.4 Iterators for ‘ostream’ objects

An `ostream_iterator<Type>` adaptor can be used to pass an `ostream` to algorithms expecting an `OutputIterator`. Two constructors are available for defining `ostream_iterators`:

```
ostream_iterator<Type> identifier(ostream &outStream);
ostream_iterator<Type> identifier(ostream &outStream, char const *delim);
```

`Type` is the type of the data elements that should be inserted into an `ostream`. It may be any type for which `operator<<` is defined in combinations with `ostream` objects. The latter constructor can be used to separate the individual `Type` data elements by delimiter strings. The former constructor does not use any delimiters.

The example shows how `istream_iterators` and an `ostream_iterator` may be used to copy information of a file to another file. A subtlety is use of `in.unsetf(ios::skipws)`. It is used to clear the `ios::skipws` flag. As a consequence white space characters are simply returned by the operator, and the file is copied character by character. Here is the program:

```
#include <iostream>
#include <algorithm>
#include <iterator>
using namespace std;

int main()
{
    cin.unsetf(ios::skipws);
    copy(istream_iterator<char>(cin), istream_iterator<char>(),
         ostream_iterator<char>(cout));
}
```

18.2.4.1 Iterators for ‘ostreambuf’ objects

Output iterators are also available for `streambuf` objects.

To read from `streambuf` objects supporting input operations `ostreambuf_iterators` can be used, supporting the operations that are also available for `ostream_iterator`. `Ostreambuf_iterators` support two constructors:

- `ostreambuf_iterator<Type>(streambuf *)`:

A pointer to a `streambuf` may be used when defining an `ostreambuf_iterator`. It can be used as an `OutputIterator`.

- `ostreambuf_iterator<Type>(ostream)`:

An *ostream* may be also used when defining an `ostreambuf_iterator`. It accesses the `ostream`’s `streambuf` and it can also be used as an `OutputIterator`.

The next example illustrates the use of both `istreambuf_iterators` and `ostreambuf_iterators` by copying a stream in yet another way. Since the stream’s `streambufs` are directly accessed the streams and stream flags are bypassed. Consequently there is no need to clear `ios::skipws` as in the previous section, while the next program’s efficiency will likely also exceed the efficiency of the program shown in the previous section.

```
#include <iostream>
#include <algorithm>
#include <iterator>
```

```
using namespace std;

int main()
{
    istreambuf_iterator<char> in(cin.rdbuf());
    istreambuf_iterator<char> eof;
    ostreambuf_iterator<char> out(cout.rdbuf());

    copy(in, eof, out);

    return 0;
}
```

18.3 The class 'unique_ptr' (C++0x, 4.4)

Before using the `unique_ptr` class presented in this section the `<memory>` header file must have been included.

When pointers are used to access dynamically allocated memory strict bookkeeping is required to prevent memory leaks from happening. When a pointer variable referring to dynamically allocated memory goes out of scope, the dynamically allocated memory becomes inaccessible and the program suffers from a memory leak.

To prevent such memory leaks strict bookkeeping is required: the programmer has to make sure that the dynamically allocated memory is returned to the common pool just before the pointer variable goes out of scope.

When a pointer variable points to a dynamically allocated single value or object, bookkeeping requirements are greatly simplified when the pointer variable is defined as a `std::unique_ptr` object.

`Unique_ptrs` are *objects* masquerading as pointers. Since they are objects, their destructors are called when they go out of scope. Their destructors automatically delete the dynamically allocated memory.

`Unique_ptrs` have some special characteristics:

- when assigning a `unique_ptr` to another *move semantics* is used. If move semantics are not available compilation will fail. On the other hand, if compilation succeeds then the used containers or generic algorithms support the use of `unique_ptrs`. Here is an example:

```
std::unique_ptr<int> up1(new int);
std::unique_ptr<int> up2(up1);           // compilation error
```

The second definition fails to compile as `unique_ptr`'s copy constructor is private (the same holds true for the assignment operator). But the `unique_ptr` class *does* offer facilities to initialize and assign from *rvalue references*:

```
class unique_ptr                                // interface partially shown
{
public:
    unique_ptr(unique_ptr &&other); // rvalues bind here
private:
    unique_ptr(const unique_ptr &other);
};
```

In the next example move semantics is used and so it compiles correctly:

```
unique_ptr<int> cp(unique_ptr<int>(new int));
```

- a `unique_ptr` object should only point to memory that was made available dynamically, as only dynamically allocated memory can be deleted.
- multiple `unique_ptr` objects should not be allowed to point to the same block of dynamically allocated memory. The `unique_ptr`'s interface was designed to prevent this from happening. Once a `unique_ptr` object goes out of scope, it deletes the memory it points to, immediately changing any other object also pointing to the allocated memory into a wild pointer.

The class `unique_ptr` offers several member functions to access the pointer itself or to have a `unique_ptr` point to another block of memory. These member functions (and `unique_ptr` constructors) are introduced in the next few sections.

A `unique_ptr` (as well as a `shared_ptr`, see section 18.4) can be used as a safe alternative to the now deprecated `auto_ptr`. `Unique_ptr` also augments `auto_ptr` as it can be used with containers and (generic) algorithms as it adds customizable deleters arrays can also be handled by `unique_ptr`s.

18.3.1 Defining ‘`unique_ptr`’ objects (C++0x, 4.4)

There are three ways to define `unique_ptr` objects. Each definition contains the usual `<type>` specifier between angle brackets:

- The default constructor simply creates a `unique_ptr` object that does not point to a particular block of memory. Its pointer is initialized to 0 (zero):

```
unique_ptr<type> identifier;
```

This form is discussed in section 18.3.2.

- The *move constructor* initializes an `unique_ptr` object. Following the use of the move constructor its `unique_ptr` argument no longer points to the dynamically allocated memory and its pointer data member is turned into a zero-pointer:

```
unique_ptr<type> identifier(another unique_ptr for type);
```

This form is discussed in section 18.3.3.

- The form that is used most often initializes a `unique_ptr` object to the block of dynamically allocated memory that is passed to the object's constructor. Optionally deleter can be provided. A (free) function (or function object) receiving the `unique_ptr`'s pointer as its argument can be passed as deleter. It is supposed to return the dynamically allocated memory to the common pool (doing nothing if the pointer equals zero).

```
unique_ptr<type> identifier (new-expression [, deleter]);
```

This form is discussed in section 18.3.4.

18.3.2 Creating a plain ‘`unique_ptr`’ (C++0x, 4.4)

`Unique_ptr`'s default constructor defines a `unique_ptr` not pointing to a particular block of memory:

```
unique_ptr<type> identifier;
```

The pointer controlled by the `unique_ptr` object is initialized to 0 (zero). Although the `unique_ptr` object itself is not the pointer, its value *can* be compared to 0. Example:

```
unique_ptr<int> ip;

if (!ip)
    cout << "0-pointer with a unique_ptr object\n";
```

Alternatively, the member `get` can be used (cf. section 18.3.5).

18.3.3 Moving another 'unique_ptr' (C++0x, 4.4)

A `unique_ptr` may be initialized using an rvalue reference to a `unique_ptr` object for the same type:

```
unique_ptr<type> identifier(other unique_ptr object);
```

The move constructor is used, e.g., in the following example:

```
void mover(unique_ptr<string> &&param)
{
    unique_ptr<string> tmp(move(param));
}
```

Analogously, the assignment operator can be used. A `unique_ptr` object may be assigned to a temporary `unique_ptr` object of the same type (again move-semantics is used). For example:

```
#include <iostream>
#include <memory>
#include <string>

using namespace std;

int main()
{
    unique_ptr<string> hello1(new string("Hello world"));
    unique_ptr<string> hello2(move(hello1));
    unique_ptr<string> hello3;

    hello3 = move(hello2);
    cout << // *hello1 << /\n' <<    // would have segfaulted
           // *hello2 << '\n' <<    // same
           *hello3 << '\n';
}
// Displays:    Hello world
```

The example illustrates that

- `hello1` is initialized by a pointer to a dynamically allocated string (see the next section).
- The `unique_ptr` `hello2` grabs the pointer controlled by `hello1` using a move constructor. This effectively changes `hello1` into a 0-pointer.
- Then `hello3` is defined as a default `unique_ptr<string>`. But then it grabs its value using move-assignment from `hello2` (which, as a consequence, is changed into a 0-pointer as well)

If `hello1` or `hello2` would have been inserted into `cout` a *segmentation fault* would have resulted. The reason for this should now be clear: it is caused by dereferencing 0-pointers. In the end, only `hello3` actually points to the originally allocated string.

18.3.4 Pointing to a newly allocated object (C++0x, 4.4)

A `unique_ptr` is most often initialized using a pointer to dynamically allocated memory. The generic form is:

```
unique_ptr<type [, deleter_type]> identifier(new-expression
[, deleter = deleter_type()]);
```

The second (template) argument (`deleter(_type)`) is optional and may refer to a free function or function object handling the destruction of the allocated memory. A deleter is used, e.g., in situations where a double pointer is allocated and the destruction must visit each nested pointer to destroy the allocated memory (see below for an illustration).

Here is an example initializing an `unique_ptr` pointing to a string object:

```
unique_ptr<string> strPtr(new string("Hello world"));
```

The argument that is passed to the constructor is the pointer returned by operator `new`. Note that `type` does *not* mention the pointer. The type that is used in the `unique_ptr` construction is the same as the type that is used in `new` expressions.

Here is an example showing how an explicitly defined deleter may be used to delete a dynamically allocated array of pointers to strings:

```
#include <iostream>
#include <string>
#include <memory>
using namespace std;

struct Deleter
{
    size_t d_size;
    Deleter(size_t size = 0)
    :
        d_size(size)
    {}
    void operator()(string **ptr) const
    {
        for (size_t idx = 0; idx < d_size; ++idx)
            delete ptr[idx];
        delete[] ptr;
    }
};

int main()
{
    unique_ptr<string *, Deleter> sp2(new string *[10], Deleter(10));

    Deleter &obj = sp2.get_deleter();
}
```

A `unique_ptr` can be used to reach the member functions that are available for objects allocated by the `new` expression. These members can be reached as if the `unique_ptr` was a plain pointer to the dynamically allocated object. For example, in the following program the text ‘C++’ is inserted behind the word ‘hello’:

```
#include <iostream>
#include <memory>
#include <cstring>
using namespace std;

int main()
{
    unique_ptr<string> sp(new string("Hello world"));
```

```

    cout << *sp << '\n';
    sp->insert(strlen("Hello "), "C++ ");
    cout << *sp << '\n';
}
/*
    Displays:
        Hello world
        Hello C++ world
*/

```

18.3.5 Operators and members (C++0x, 4.4)

The class `unique_ptr` offers the following operators:

- `unique_ptr<Type> &unique_ptr<Type>operator=(unique_ptr<Type> &&tmp):`

This operator transfers the memory pointed to by the rvalue `unique_ptr` object to the lvalue `unique_ptr` object using *move semantics*. So, the rvalue object *loses* the memory it pointed at and turns into a 0-pointer. An existing `unique_ptr` may be assigned to another `unique_ptr` by converting it to an rvalue reference first using `std::move`. Example:

```

    unique_ptr<int> ip1(unique_ptr<int>(new int));
    unique_ptr<int> ip2;

    ip2 = std::move(ip1);

```

- `operator bool() const:`

This operator returns `false` if the `unique_ptr` does not point to memory (i.e., its `get` member, see below, returns 0). Otherwise, `true` is returned.

- `Type &operator*():`

This operator returns a reference to the information stored in the `unique_ptr` object. It acts like a normal pointer dereference operator.

- `Type *operator->():`

This operator returns a pointer to the information stored in the `unique_ptr` object. Through this operator members of a stored object can be selected. Example:

```

    unique_ptr<string> sp(new string("hello"));
    cout << sp->c_str();

```

The class `unique_ptr` supports the following member functions:

- `Type *get():`

A pointer to the information controlled by the `unique_ptr` object is returned. It acts like `operator->`. The returned pointer can be inspected. If it is zero the `unique_ptr` object does not point to any memory.

- `Deleter &unique_ptr<Type>::get_deleter():`

A reference to the deleter object used by the `unique_ptr` is returned.

- `Type *release():`

A pointer to the information stored in the `unique_ptr` object is returned. At the same time the object itself becomes a 0-pointer (i.e., its pointer data member is turned

into a 0-pointer). This member can be used to transfer the information stored in the `unique_ptr` object to a plain `Type` pointer. Having called this member the proper destruction of the dynamically allocated memory has become the responsibility of the programmer.

- `void reset(Type *):`

The dynamically allocated memory controlled by the `unique_ptr` object to the common pool and it is reassigned to the argument that is passed to the function. It can also be called without argument, turning the object into a 0-pointer. This member function can be used to assign a new block of dynamically allocated memory to a `unique_ptr` object.

- `void swap(unique_ptr<Type> &):`

Two identically typed `unique_ptr`s are swapped.

18.3.6 Using ‘`unique_ptr`’ objects for arrays (C++0x, 4.4)

When a `unique_ptr` is used to store arrays the dereferencing operator makes little sense but with arrays `unique_ptr` objects benefit from index operators. The distinction between a single object `unique_ptr` and a `unique_ptr` referring to a dynamically allocated array of objects is realized through a template specialization.

With dynamically allocated arrays the following syntax is available:

- the index (`tt[]`) notation is used to specify that the the smart pointer controls a dynamically allocated *array*. Example:

```
unique_ptr<int[]> intArr(new int[3]);
```

- the index operator can be used to access the array’s elements. Example:

```
intArr[2] = intArr[0];
```

In these cases the smart pointer’s destructors call `delete[]` rather than `delete`.

18.3.7 The legacy class ‘`auto_ptr`’ (deprecated)

The (now deprecated by the C++0x standard) smart pointer class `std::auto_ptr<Type>` has traditionally been offered by C++. This class does not support *move semantics*, but when an `auto_ptr` object is assigned to another, the right-hand object loses its information.

The class `unique_ptr` does not have `auto_ptr`’s drawbacks and consequently using `auto_ptr` is now deprecated. `Auto_ptr`s suffer from the following drawbacks:

- they do not support *move semantics*;
- they should not be used to point to arrays;
- they cannot be used as data types of abstract containers.

Because of its drawbacks and available replacements the `auto_ptr` class is longer covered by the C++ Annotations. Existing software should be modified to use smart pointers (`unique_ptr`s or `shared_ptr`s) and new software should, where applicable, directly be implemented in terms of these new smart pointer types.

18.4 The class 'shared_ptr' (C++0x)

In addition to `unique_ptr` the C++0x standard offers `std::shared_ptr<Type>` which is a reference counting smart pointer. Before using `shared_ptr`s the `<memory>` header file must have been included.

The shared pointer automatically destroys its contents once its reference count has decayed to zero.

`Shared_ptr`s support copy and move constructors as well as standard and move overloaded assignment operators.

Like `unique_ptr`s, `shared_ptr`s may refer to dynamically allocated arrays.

18.4.1 Defining 'shared_ptr' objects (C++0x)

There are four ways to define `shared_ptr` objects. Each definition contains the usual `<type>` specifier between angle brackets:

- The default constructor simply creates a `shared_ptr` object that does not point to a particular block of memory. Its pointer is initialized to 0 (zero):

```
shared_ptr<type> identifier;
```

This form is discussed in section [18.4.2](#).

- The copy constructor initializes a `shared_ptr` so that both objects share the memory pointed at by the existing object. The copy constructor also increments the `shared_ptr`'s reference count. Example:

```
shared_ptr<string> org(new string("hi there"));
shared_ptr<string> copy(org);    // reference count now 2
```

- The move constructor initializes a `shared_ptr` with the pointer and reference count of a temporary `shared_ptr`. The temporary `shared_ptr` is changed into a 0-pointer. An existing `shared_ptr` may have its data moved to a newly defined `shared_ptr` (turning the existing `shared_ptr` into a 0-pointer as well) by applying `std::move`. Example:

```
shared_ptr<string> grabber(shared_ptr<string>(new string("hi there")));
```

- The form that is used most often initializes a `shared_ptr` object to the block of dynamically allocated memory that is passed to the object's constructor. Optionally deleter can be provided. A (free) function (or function object) receiving the `shared_ptr`'s pointer as its argument can be passed as deleter. It is supposed to return the dynamically allocated memory to the common pool (doing nothing if the pointer equals zero).

```
shared_ptr<type> identifier (new-expression [, deleter]);
```

This form is discussed in section [18.4.3](#).

18.4.2 Creating a plain 'shared_ptr' (C++0x)

`Shared_ptr`'s default constructor defines a `shared_ptr` not pointing to a particular block of memory:

```
shared_ptr<type> identifier;
```

The pointer controlled by the `shared_ptr` object is initialized to 0 (zero). Although the `shared_ptr` object itself is not the pointer, its value *can* be compared to 0. Example:

```
shared_ptr<int> ip;

if (!ip)
    cout << "0-pointer with a shared_ptr object\n";
```

Alternatively, the member `get` can be used (cf. section 18.4.4).

18.4.3 Pointing to a newly allocated object (C++0x)

Most often a `shared_ptr` is initialized by a dynamically allocated block of memory. The generic form is:

```
shared_ptr<type [, deleter_type]> identifier(new-expression
[, deleter = deleter_type()]);
```

The second (template) argument (`deleter(_type)`) is optional and may refer to a free function or function object handling the destruction of the allocated memory. A deleter is used, e.g., in situations where a double pointer is allocated and the destruction must visit each nested pointer to destroy the allocated memory (see below for an illustration). It is used in situations comparable to those encountered with `unique_ptr` (cf. section 18.3.4).

Here is an example initializing an `shared_ptr` pointing to a string object:

```
shared_ptr<string> strPtr(new string("Hello world"));
```

The argument that is passed to the constructor is the pointer returned by operator `new`. Note that `type` does *not* mention the pointer. The type that is used in the `shared_ptr` construction is the same as the type that is used in `new` expressions.

The example illustrates that two `shared_ptr`s indeed share their information. After modifying the information controlled by one of the objects the information controlled by the other object is modified as well:

```
#include <iostream>
#include <memory>
#include <cstring>
using namespace std;

int main()
{
    shared_ptr<string> sp(new string("Hello world"));
    shared_ptr<string> sp2(sp);

    sp->insert(strlen("Hello "), "C++ ");
    cout << *sp << '\n' <<
         *sp2 << '\n';
}
/*
Displays:
    Hello C++ world
    Hello C++ world
*/
```

18.4.4 Operators and members (C++0x)

The class `shared_ptr` offers the following operators:

- `shared_ptr &operator=(shared_ptr<Type> const &other):`

Copy assignment: the reference count of the operator's left hand side operand is reduced. If the reference count decays to zero the dynamically allocated memory controlled by the left hand side operand is deleted. Next it will share the information with the operator's right hand side operand, incrementing the information's reference count.

- `shared_ptr &operator=(shared_ptr<Type> &&tmp):`

Move assignment: the reference count of the operator's left hand side operand is reduced. If the reference count decays to zero the dynamically allocated memory controlled by the left hand side operand is deleted. Next it will grab the information controlled by the operator's right hand side operand which is turned into a 0-pointer.

- `operator bool() const:`

If the `shared_ptr` actually points to memory `true` is returned, otherwise, `false` is returned.

- `Type &operator*():`

A reference to the information stored in the `shared_ptr` object is returned. It acts like a normal pointer.

- `Type *operator->():`

A pointer to the information controlled by the `shared_ptr` object is returned. Example:

```
shared_ptr<string> sp(new string("hello"));
cout << sp->c_str() << '\n';
```

The following member function member functions are supported:

- `Type *get():`

A pointer to the information controlled by the `shared_ptr` object is returned. It acts like `operator->`. The returned pointer can be inspected. If it is zero the `shared_ptr` object does not point to any memory.

- `Deleter &get_deleter():`

A reference to the `shared_ptr`'s deleter (function or function object) is returned.

- `void reset(Type *):`

The reference count of the information controlled by the `shared_ptr` object is reduced and if it decays to zero it is deleted. Then the object's information will refer to the argument that is passed to the function, setting its shared count to 1. It can also be called without argument, turning the object into a 0-pointer. This member function can be used to assign a new block of dynamically allocated memory to a `shared_ptr` object.

- `void shared_ptr<Type>::swap(shared_ptr<Type> &&):`

Two identically typed `shared_ptr`s are swapped.

- `bool unique() const:`

If the current object is the only object referring to the memory controlled by the object `true` is returned otherwise (including the situation where the object is a 0-pointer) `false` is returned.

- `size_t use_count() const:`

The number of objects sharing the memory controlled by the object is returned.

18.4.5 Casting shared pointers (C++0x)

Shared pointers cannot simply be cast using the standard C++ style casts. Consider the following two classes:

```
struct Base
{
};
struct Derived: public Base
{
};
```

A `shared_ptr<Derived>` can easily be defined. Since a `Derived` is also a `Base` a pointer to a `Derived` can be cast to a pointer to a `Base` using a static cast:

```
Derived d;
static_cast<Base *>(&d);
```

However, a plain `static_cast` cannot be used when initializing a shared pointer to a `Base` using the object pointer of a shared pointer to a `Derived` object. I.e., the following statement will eventually result in an attempt to delete the dynamically allocated `Base` object twice:

```
shared_ptr<Derived> sd(new Derived);
shared_ptr<Base> sb(static_cast<Base *>(sd.get()));
```

Since `sd` and `sb` point at the same object `~Base` will be called for the same object when `sb` goes out of scope and when `sd` goes out of scope, resulting in premature termination of the program due to a *double free* error.

These errors can be prevented using casts that were specifically designed for being used with `shared_ptr`s. These casts use specialized constructors that create a `shared_ptr` pointing to memory but shares ownership (i.e., a reference count) with an existing `shared_ptr`. These special casts are:

- `std::static_pointer_cast<Base>(std::shared_ptr<Derived> ptr):`

A `shared_ptr` to a `Base` class object is returned. The returned `shared_ptr` refers to the base class portion of the `Derived` class to which the `shared_ptr<Derived> ptr` refers. Example:

```
shared_ptr<Derived> dp(new Derived());
shared_ptr<Base> bp = static_pointer_cast<Base>(dp);
```

- `std::const_pointer_cast<Class>(std::shared_ptr<Class const> ptr):`

A `shared_ptr` to a `Class` class object is returned. The returned `shared_ptr` refers to a non-const `Class` object whereas the `ptr` argument refers to a `Derived const` object. Example:

```
shared_ptr<Derived const> cp(new Derived());
shared_ptr<Derived> ncp = const_pointer_cast<Derived>(cp);
```

- `std::dynamic_pointer_cast<Derived>(std::shared_ptr<Base> ptr):`

A `shared_ptr` to a `Derived` class object is returned. The `Base` class must have at least one virtual member function, and the class `Derived`, inheriting from `Base` may have overridden `Base`'s virtual member(s). The returned `shared_ptr` refers to a `Derived` class object if the dynamic cast from `Base *` to `Derived *` succeeded. If the dynamic cast did not succeed the `shared_ptr`'s `get` member returns 0. Example (assume `Derived1` and `Derived2` were derived from `Base`):

```
shared_ptr<Base> bp(new Derived());
cout << dynamic_pointer_cast<Derived>(bp).get() << ' ' <<
      dynamic_pointer_cast<Derived2>(bp).get() << '\n';
```

The first `get` returns a non-0 pointer value, the second `get` returns 0.

18.4.6 Using 'shared_ptr' objects for arrays (C++0x)

Different from the `unique_ptr` class no specialization exists for the `shared_ptr` class to handle dynamically allocated arrays of objects.

But like `unique_ptr`s, with `shared_ptr`s referring to arrays the dereferencing operator makes little sense while in these circumstances `shared_ptr` objects would benefit from index operators.

It is not difficult to create a class `shared_array` offering such facilities. The class template `shared_array`, derived from `shared_ptr` merely should provide an appropriate *deleter* to make sure that the array and its elements are properly destroyed. In addition it should define the index operator and optionally can declare the dereferences operators using `delete`.

Here is an example showing how `shared_array` can be defined and used:

```
struct X
{
    ~X()
    {
        cout << "destr\n"; // show the object's destruction
    }
};

template <typename Type>
class shared_array: public shared_ptr<Type>
{
    struct Deleter          // Deleter receives the pointer
    {
        // and calls delete[]
        void operator()(Type* ptr)
        {
            delete[] ptr;
        }
    };

public:
    shared_array(Type *p)          // other constructors
    :                               // not shown here
      shared_ptr<Type>(p, Deleter())
    {}
    Type &operator[](size_t idx)    // index operators
    {
        return shared_ptr<Type>::get()[idx];
    }
    Type const &operator[](size_t idx) const
    {
        return shared_ptr<Type>::get()[idx];
    }
    Type &operator*() = delete;     // delete pointless members
    Type const &operator*() const = delete;
    Type *operator->() = delete;
    Type const *operator->() const = delete;
};

int main()
{
    shared_array<X> sp(new X[3]);
    sp[0] = sp[1];
}
```

18.5 Classes having pointer data members (C++0x)

Classes having pointer data members require special attention. In particular at construction time one must be careful to prevent wild pointers and/or memory leaks. Consider the following class defining two pointer data members:

```
class Filter
{
    istream *d_in;
    output  *d_out;
public:
    Filter(char const *in, char const *out);
};
```

Assume that `Filter` objects filter information read from `*d_in` and write the filtered information to `*d_out`. Using pointers to streams allows us to have them point at any kind of stream like `istreams`, `ifstreams`, `fstreams` or `istringstreams`. The shown constructor could be implemented like this:

```
Filter::Filter(char const *in, char const *out)
:
    d_in(new ifstream(in)),
    d_out(new ofstream(out))
{
    if (!*d_in || !*d_out)
        throw string("Input and/or output stream not available");
}
```

Of course, the construction could fail. `new` could throw an exception, the stream constructors could throw an exception or the streams could not be opened in which case an exception is thrown from the constructor's body. Using a function try block helps, but if `d_in`'s initialization throws then `d_out` is still a wild pointer. Consequently the pointers would first have to be initialized to 0 and only then the initialization can be performed:

```
Filter::Filter(char const *in, char const *out)
try
:
    d_in(0),
    d_out(0)
{
    d_in = new ifstream(in);
    d_out = new ofstream(out);

    if (!*d_in || !*d_out)
        throw string("Input and/or output stream not available");
}
catch (...)
{
    delete d_out;
    delete d_in;
}
```

This may easily get complicated, though. If `filter` harbors yet another data member of a class whose constructor needs two streams then that data cannot be constructed or it must itself be converted into a pointer:

```
Filter::Filter(char const *in, char const *out)
```

```

try
:
    d_in(0),
    d_out(0)
    d_filterImp(*d_in, *d_out)    // won't work
{ ... }

// instead:

Filter::Filter(char const *in, char const *out)
try
:
    d_in(0),
    d_out(0),
    d_filterImp(0)
{
    d_in = new ifstream(in);
    d_out = new ofstream(out);
    d_filterImp = new FilterImp(*d_in, *d_out);
    ...
}
catch (...)
{
    delete d_filterImp;
    delete d_out;
    delete d_in;
}

```

Although the latter alternative works, it quickly gets hairy. In situations like this smart pointers should be used to prevent this hairiness. By defining the stream pointers as (smart pointer) objects they will, once constructed, properly be destroyed even if the rest of the constructor's code throws exceptions. Using a `FilterImp` and two `unique_ptr` data members `Filter`'s setup and its constructor becomes:

```

class Filter
{
    std::unique_ptr<std::ifstream> d_in;
    std::unique_ptr<std::ofstream> d_out;
    FilterImp d_filterImp;
    ...
};

Filter::Filter(char const *in, char const *out)
try
:
    d_in(new ifstream(in)),
    d_out(new ofstream(out)),
    d_filterImp(*d_in, *d_out)
{
    if (!*d_in || !*d_out)
        throw string("Input and/or output stream not available");
}

```

We're back at the original implementation but this time without having to worry about wild pointers and memory leaks. If one of the member initializers throws the destructors of previously constructed data members (which are now objects) are always called.

As a rule of thumb: when classes need to define pointer data members they should define those pointer data members as smart pointers if there's any chance that their constructors throw exceptions.

18.6 Multi Threading (C++0x, 4.4)

The C++0x standard adds multi threading to C++ through the C++ standard library.

The C++ Annotations don't discuss the concepts behind multi threading. It is a topic by itself and many good reference sources exist (cf. Nichols, B, *et al.*'s *Pthreads Programming*¹, O'Reilly for some good introductions to multi-threading).

Multi threading facilities are offered through the class `std::thread`. Its constructor and assignment operator accept a function or function object that will handle the thread created by the thread object.

Thread synchronization is handled by objects of the class `std::mutex` and condition variables are implemented by the class `std::condition_variable`.

In order to use multi threading in C++ programs the Gnu g++ compiler requires the use of the `-pthread` flag. E.g., to compile a multi-threaded program defined in a source file `multi.cc` the compiler must be called as follows:

```
g++ --std=c++0x -pthread -Wall multi.cc
```

Threads in C++ are very much under development. It is likely that in the near future features will be added and possibly redefined. The next sections should therefore be read with this in mind.

18.6.1 The class 'std::thread' (C++0x, 4.4)

The `std::thread` class implements a (new) thread. Before using Thread objects the `<thread>` header file must have been included.

Thread objects can be constructed empty (in which case no new thread is started yet) but it may also be given a function or function object, in which case the thread is started immediately.

Alternatively, a function or function object may be *assigned* to an existing thread object causing a new thread to be launched using that function (object).

There are several ways to end a launched thread. Currently a thread ends when the function called from the thread object ends. Since the thread object not only accepts functions but also function objects as its argument, a *local context* may be passed on to the thread. Here are two examples of how a thread may be started: in the first example a function is passed on to the thread, in the second example a function object. The example uses the thread member `join`, discussed below:

```
#include <iostream>
#include <thread>
#include <cstdlib>
using namespace std;

void hello()
{
    cout << "hello world\n";
}

class Zero
{
    int *d_data;
    size_t d_size;
    int d_value;
public:
    Zero(int *data, size_t size, int value)
```

¹<http://oreilly.com/catalog/>


```

        :
        d_data(data),
        d_size(size),
        d_value(value)
    {}
    void operator()()
    {
        for (int *ptr = d_data + d_size; ptr-- != d_data; )
            *ptr = d_value;
    }
};

int main()
{
    int data[30];
    Zero zero(data, 30, 0);
    thread t1(zero);
    thread t2(hello);
    t1.join();
    t2.join();
};

```

Thread objects do not implement a copy constructor but a move constructor is provided. Threads may be swapped as well, even if they're actually running a thread. E.g.,

```

std::thread t1(Thread());
std::thread t2(Thread());
t1.swap(t2);

```

According to the current specifications of the `thread` class its constructor should also be able to accept additional arguments (in addition to the function (object) handled by the thread object), but currently that facility does not appear to be available. Any object passed to the function call operator could of course also be passed using separate members or using the object's constructors. This is probably an acceptable makeshift solution until multiple arguments can be passed to the thread constructor itself (using perfect forwarding, cf. section 21.5.2).

The thread's overloaded assignment operator can also be used to start a thread. If the current thread object actually runs a thread it is stopped, and the function (object) assigned to the thread object becomes the new running thread. E.g.,

```

std::thread thr;    // no thread runs from thr yet
thr = Thread();    // a thread is launched

```

Threads (among which the thread represented by `main`) may be forced to wait for another thread's completion by calling the other thread's `join` member. E.g., in the following example `main` launches two threads and waits for the completion of both:

```

int main()
{
    std::thread t1(Thread());
    std::thread t2(Thread());

    t1.join();    // wait for t1 to complete
    t2.join();    // same, t2
}

```

The thread's member `detach` can be called to disassociate the current thread from its starting thread. Currently ending a thread other than by ending the activities of the function defining the thread's activities appears to be very well implemented.

18.6.2 Synchronization (mutexes) (C++0x, 4.4)

The C++0x standard offers a series of mutex classes to protect shared data. Before using mutexes the `<mutex>` header file must have been included.

Apart from the `std::mutex` class `std::recursive_mutex` is offered. When a `recursive_mutex` is called multiple times by the same thread it will increase its lock-count. Before other threads may access the protected data the recursive mutex must be unlocked again that number of times. In addition the classes `std::timed_mutex` and `std::recursive_timed_mutex` are available. Their locks will (also) expire after a preset amount of time.

In many situations locks will be released at the end of some action block. To simplify locking additional template classes `std::unique_lock<>` and `std::lock_guard<>` are provided. As their constructors lock the data and their destructors unlock the data they can be defined as local variables, unlocking their data once their scope terminates. Here is a simple example showing the use of a `lock_guard`. Once `safeProcess` ends `guard` is destroyed, thereby releasing the lock on data:

```
std::mutex dataMutex;
Data data;

void safeProcess()
{
    std::lock_guard<std::mutex> guard(dataMutex);
    process(data);
}
```

`Unique_lock` is used similarly, but is used when timeouts must be considered as well:

```
std::timed_mutex dataMutex;
Data data;

void safeProcess()
{
    std::unique_lock<std::timed_mutex>
        guard(dataMutex, std::chrono::milliseconds(3));
    if (guard)
        process(data);
}
```

In the above example `guard` tries to obtain the lock during three milliseconds. If `guard`'s operator `bool` returns `true` the lock was obtained and data can be processed safely.

Deadlocks are commonly encountered in multi threaded programs. If a deadlock occurs when two locks are required to process data, but one thread obtains the first lock and another thread obtains the second lock. The C++0x standard defines a generic `std::lock` function that can be used to prevent problems like these. The `std::lock` function can be used to lock multiple mutexes in one atomic action. Here is an example:

```
struct SafeString
{
    std::mutex d_mutex;
    std::string d_text;
};

void calledByThread(SafeString &first, SafeString &second)
{
    std::unique_lock<std::mutex>                // 1
        lock_first(first.d_mutex, std::defer_lock);
```

```

std::unique_lock<std::mutex>                // 2
    lock_second(second.d_mutex, std::defer_lock);

std::lock(lock_first, lock_second);        // 3

safeProcess(first.d_text, second.d_text);
}

```

At 1 and 2 `unique_locks` are created. Locking is deferred until calling `std::lock` at 3. Having obtained the lock, the two `SafeString` text members can both be safely processed by `calledByThread`.

Another problematic issue with threads involves initialization. If multiple threads are running and only the first thread encountering the initialization code should perform the initialization then this problem should not be solved using mutexes. Although proper synchronization is realized, the synchronization will also be performed time and again for every thread. The C++0x standard offers several ways to perform a proper initialization:

- First, a *constexpr constructor* may be defined. *Constexpr* constructors are currently not yet supported by the g++ compiler and they are not yet discussed in the C++ Annotations.
- Second, a static variable defined within a compound statement may be used (e.g., a static local variable within a function body). In C++ static variables defined within a compound statement are initialized the first time the function is called at the point in the code where the static variable is defined as illustrated by the following example:

```

#include <iostream>

struct Cons
{
    Cons()
    {
        std::cout << "Cons called\n";
    }
};

void called(char const *time)
{
    std::cout << time << "time called() activated\n";
    static Cons cons;
}

int main()
{
    std::cout << "Pre-1\n";
    called("first");
    called("second");
    std::cout << "Pre-2\n";
    Cons cons;
}

/*
Displays:
Pre-1
firsttime called() activated
Cons called
secondtime called() activated
Pre-2
Cons called
*/

```

This feature causes a thread to wait automatically if another thread is still initializing the static

data (note that *non-static* data never cause problems, as each non-static local variables have lives that are completely restricted to their own threads).

- If the above two approaches can't be used. The combined use of `std::call_once` and `std::once_flag` result in one-time execution of a specified function as illustrated by the next example:

```
std::string *global;
std::once_flag globalFlag;

void initializeGlobal()
{
    global = new std::string("Hello world (why not?)");
}
void safeUse()
{
    std::call_once(globalFlag, initializeGlobal);
    process(*global);
}
```

18.6.3 Event handling (condition variables) (C++0x)

Consider a classic producer-consumer case: the producer generates items to be consumed by a consumer. The producer can only produce so many items before its storage capacity has filled up and the client cannot consume more items than the producer has produced.

At some point the producer will therefore have to wait until the client has consumed enough so there's again space available in the producer's storage. Similarly, the client will have to wait until the producer has produced at least some items.

Locking and polling the amount of available items/storage at fixed time intervals usually isn't a good option as it is in essence a wasteful scheme: threads continue to wait during the full interval even though the condition to continue may already have been met; reducing the interval, on the other hand, isn't an attractive option either as it results in a relative increase of the overhead associated with handling the associated mutexes.

Condition variables may be used to solve these kinds of problems. A thread simply sleeps until it is notified by another thread. Generally this may be accomplished as follows:

```
producer loop:
- produce the next item
- wait until there's room to store the item,
  then reduce the available room
- store the item
- increment the number of items in store

consumer loop:
- wait until there's an item in store,
  then reduce the number of items in store
- remove the item from the store
- increment the number of available storage locations
- do something with the retrieved item
```

It is important that the two storage administrative tasks (registering the number of available items and available storage locations) are either performed by the client or by the producer. 'Waiting' in this case means:

- Get a lock on the variable containing the actual count

- As long as the count is zero: wait, release the lock until another thread has increased the count, re-acquire the lock.
- Reduce the count
- Release the lock.

To implement this scheme a `condition_variable` is used. The variable containing the actual count is called a semaphore and it can be protected using a mutex `sem_mutex`. In addition a `condition_variable` condition is defined. The waiting process is defined in the following function down implemented as follows:

```
void down()
{
    unique_lock<mutex> lock(sem_mutex);    // get the lock
    while (semaphore == 0)
        condition.wait(lock);             // see 1, below.
    --semaphore;                           // dec. semaphore count
}
```

At 1 the condition variable's `wait` member internally releases the lock, wait for a notification to continue, and re-acquires the lock just before returning. Consequently, `down`'s code always has complete and unique control over `semaphore`.

What about notifying the condition variable? This is handled by the 'increment the number ...' parts in the abovementioned producer and consumer loops. These parts are defined by the following `up` function:

```
void up()
{
    lock_guard<std::mutex> lock(sem_mutex); // get the lock
    if (semaphore++ == 0)
        condition.notify_one();           // see 2, below
}
```

At 2 `semaphore` is always incremented. However, by using a postfix increment it can be tested for being zero at the same time and if it was zero initially then `semaphore` is now one. Consequently, the thread waiting for `semaphore` being unequal to zero may now continue. `Condition.notify_one` will notify a waiting thread (see `down`'s implementation above). In situations where multiple threads are waiting 'notify_all' can be used.

Handling semaphore can very well be encapsulated in a class `Semaphore`, offering members `down` and `up`. For a more extensive discussion of semaphores see Tanenbaum, A.S. (2006) *Structured Computer Organization*, Pearson Prentice-Hall.

Using the semaphore facilities of the class `Semaphore` whose constructor expects an initial value of its semaphore data member, the classic producer and consumer case can now easily be implemented in the following multi-threaded program²:

```
Semaphore available(10);
Semaphore filled(0);
std::queue itemQueue;

void producer()
{
    size_t item = 0;
```

²A more elaborate example of the producer-consumer program is found in the `yo/stl/examples/events.cc` file in the C++ Annotations's source archive

```

while (true)
{
    ++item;
    available.down();
    itemQueue.push(item);
    filled.up();
}
}
void client()
{
    while (true)
    {
        filled.down();
        size_t item = itemQueue.front();
        itemQueue.pop();
        available.up();
        process(item);        // not implemented here
    }
}

int main()
{
    thread produce(producer);
    thread consume(consumer);

    produce.join();
    return 0;
}

```

To use `condition_variable` objects the header file `condition_variable` must be included.

18.7 Lambda functions (C++0x, 4.5)

The C++0x standard has added *lambda function* *lambda functions* to **C++**. As we've seen generic algorithms often accept an argument that can either be a function object or a plain function. Examples are the `sort` and `find_if` generic algorithms. When the function called by the generic algorithm must remember its state a function object is appropriate, otherwise a plain function will do.

The function or function object is usually not readily available. Often it must be defined in or near the location where the generic algorithm is used. Often the software engineer will resort to anonymous namespaces in which a class or function is defined that is thereupon used by the function calling the generic algorithm. If that function is itself a member function the need may be felt to allow the function called by the generic algorithm access to other members of its class. Often this results in a significant amount of code (defining the class); in complex code (to make available software elements that aren't native to the called function (object)); and -at the level of the source file- code that is irrelevant at the current level of specification. Nested classes don't solve these problems and nested classes can't be used in templates.

A lambda function is an anonymous function. Such a function may be defined on the spot and exists only during the lifetime of the statement of which it is a part.

Here is an example of a lambda function:

```

[](int x, int y)
{
    return x * y;
}

```

This particular function expects two `int` arguments and returns their product. It could be used e.g., in combination with the `accumulate` generic algorithm to compute the product of a series of `int` values stored in a vector:

```
cout << accumulate(vi.begin(), vi.end(), 1,
    [](int x, int y) { return x * y; });
```

The above lambda function will use the implicit return type (return type: `implicit`) type `decltype(x * y)`. An implicit return type can only be used if the lambda function has a single statement of the form `return expression;`.

Alternatively, the return type can be explicitly specified using a late-specified return type, (cf. section 3.3.6):

```
[](int x, int y) -> int
{
    int z = x + y;
    return z + x;
}
```

There is no need to specify a return type for lambda functions that do not return values (i.e., a void lambda function).

Variables having the same scope as the lambda function can be accessed from the lambda function using references, declared in between the lambda function's square brackets. This allows passing the local context to lambda functions. Such variables are called a *closure*. Here is an example:

```
void showSum(vector<int> &vi)
{
    int total = 0;
    for_each(
        vi.begin(), vi.end(),
        [&total](int x)
        {
            total += x;
        }
    );
    std::cout << total;
}
```

The variable `int total` is passed to the lambda function as a reference (`[&total]`) and can directly be accessed by the function. Its parameter list merely defines an `int x`, which is initialized in sequence by each of the values stored in `vi`. Once the generic algorithm has completed `showSum`'s variable `total` has received a value that is equal to the sum of all the vector's values. It has outlived the lambda function and its value is displayed.

If a closure variable is defined without the reference symbol (`&`) it is interpreted as a value parameter of the lambda function that is initialized by the local variable when the lambda function is passed to the generic algorithm. Usually closure variables are passed by reference. If *all* local variables are to be passed by reference a mere `[&]` can be used (to pass the full closure by value `[=]` should be used):

```
void show(vector<int> &vi)
{
    int sum = 0;
    int prod = 1;
    for_each(
        vi.begin(), vi.end(),
        [&](int x)
```

```

        {
            sum += x;
            prod *= x;
        }
    );
    std::cout << sum << ' ' << prod;
}

```

It is also possible to pass some variables to lambda function by value and other variables by reference. In that case the default is specified using `&` or `=`. This default specifying symbol is then followed by a list of variables passed differently. Example:

```

[&, value](int x)
{
    total += x * value;
};

```

Here `total` will be passed by reference, `value` by value.

Class members may also define lambda functions. Such lambda functions have full access to all the class's members. In other words, they are automatically defined as friends of the class. Example:

```

class Data
{
    std::vector<std::string> d_names;
public:
    void show() const
    {
        int count = 0;
        std::for_each(d_names.begin(), d_end(),
            [this, &count](std::string const &name)
            {
                std::cout << ++count <<
                    this->capitalized(name) << '\n';
            }
        )
    }
private:
    std::string capitalized(std::string const &name);
}

```

Note the use of the `this` pointer: inside the lambda function it must explicitly be used (so, `this->capitalized(name)` is used rather than `capitalized(name)`). In addition, in situations like these `this` will automatically be available when either `[&]` or `[=]` is used. So, the above lambda function could also have been defined as:

```

[&](std::string const &name)
{
    std::cout << ++count <<
        this->capitalized(name) << '\n';
}

```

Lambda functions may be assigned to variables. An example of such an assignment (using `auto` to define the variable's type) is:

```

auto lambdaFun = [this]()
{

```



```

        this->member();
    };

```

The lifetime of such lambda functions is equal to the lifetime of the variable receiving the lambda function as its value.

18.8 Polymorphous wrappers for function objects (C++0x, ?)

In C++ pointers to (member) function have fairly strict rvalues. They may only point to functions matching their types. This becomes a problem when defining templates where type of a function pointer may vary from instantiation to instantiation.

To improve handling of these situations the C++0x standard introduces *polymorphous (function object) wrappers*. Polymorphous wrappers can refer to function pointers, member functions or functors, as long as they match in type and number of their parameters.

18.9 Randomization and Mathematical Distributions (C++0x)

The C++0x standard introduces several standard mathematical (statistical) distributions into the STL. These distributions allow programmers to obtain randomly selected values from a specified distribution.

Using these distributions is based on new random number generator functions, differing from the traditional rand function provided by the C standard library. These random number generators are used to produce pseudo-random numbers, which are then filtered through a particular distribution to obtain values that are randomly selected from the specified distribution.

Currently not all mathematical distributions have been implemented.

18.9.1 Random Number Generators (C++0x)

The following generators are available:

Class template	Integral/Floating point	Quality	Speed	Size of state
linear_congruential	Integral	Medium	Medium	1
subtract_with_carry	Both	Medium	Fast	25
mersenne_twister	Integral	Good	Fast	624

The linear_congruential random number generator computes

$$\text{value}_{i+1} = a * \text{value}_i + c \% m$$

It expects template arguments for, respectively, the data type to contain the generated random values; the multiplier a; the additive constant c; and the modulo value m. Example:

```
linear_congruential<int, 10, 3, 13> lincon;
```

The linear_congruential generator may be seeded by providing its constructor with a seeding-argument. E.g., lincon(time(0)).

The subtract_with_carry random number generator computes

$$\text{value}_i = \text{value}_{i-s} - \text{value}_{i-r} - \text{carry}_{i-1} \% m$$

It expects template arguments for, respectively, are the data type to contain the generated random values; the modulo value `m`; the subtractive constants `s` and `r`. Example:

```
subtract_with_carry<int, 13, 3, 13> subcar;
```

The `subtract_with_carry` generator may be seeded by providing its constructor with a seeding-argument. E.g., `subcar(time(0))`.

The predefined `mersenne_twister` `mt19937` (predefined using a `typedef` defined by the `<random>` header file) is used in the examples below. It can be constructed using `'mt19937 mt'` or it can be seeded by providing its constructor with an argument (e.g., `mt19937 mt(time(0))`). Other ways to initialize the `mersenne_twister` are beyond the scope of the C++ Annotations (but see Lewis *et al.*³ (1969)).

The random number generators may also be seeded by calling their members `seed` accepting unsigned long values or generator functions (as in `lc.seed(time(0))`, `lc.seed(mt)`).

The random number generators offer members `min` and `max` returning, respectively, their minimum and maximum values (inclusive). If a reduced range is required the generators can be nested in a function or class adapting the range.

18.9.2 Mathematical distributions (C++0x)

The following standard distributions are currently available (an example showing their use is provided at the end of this section). For information about the distributions mentioned below can be found at web-locations like http://en.wikipedia.org/wiki/Bernoulli_distribution.

Before using the mathematical distributions the `<random>` header file must have been included.

All distributions offer the following members (*result_type* refers to the type name of the values returned by the distribution; *name_distribution* refers to the type name of the mathematical distribution, e.g., `bernoulli_distribution`):

- `result_type operator()(RandomNumberGenerator)`: The next randomly generated value is returned.
- `std::istream &operator<<(std::istream &in, distribution-name &object)`: The parameters of the distribution are extracted from an `std::istream`;
- `std::ostream &operator<<(std::ostream &out, bernoulli_distribution const &bd)`: The parameters of the distribution are inserted into an `std::ostream`

Distributions:

- `bernoulli_distribution`
Logical true values are generated with a certain probability `p`.
Constructor:
 - `bernoulli_distribution(double p = 0.5)`
- `binomial_distribution<IntType = int, RealType = double>`
`IntType`: the type of the generated random value (by default `int`).
`RealType`: the probability parameter of the binomial distribution.
Random integral values are generated according to the specified binomial distribution
Constructor:
 - `binomial_distribution<IntType, RealType>(IntType t, RealType p = RealType(0.5))`

³ Lewis, P.A.W., Goodman, A.S., and Miller, J.M. (1969), A pseudorandom number generator for the System/360, IBM Systems Journal, 8, 136-146.

- `gamma_distribution<Type = double>`
 Type: the parameter of the gamma distribution.
 Random values are generated according to the specified gamma distribution.
 Constructor:

```
- gamma_distribution<IntType, Type>(Type alpha = Type(1))
```
- `geometric_distribution<IntType = int, RealType = double>`
 IntType: the type of the generated random value (by default int).
 RealType: the probability parameter of the geometric distribution.
 Random integral values are generated according to the specified geometric distribution
 Constructor:

```
- geometric_distribution<IntType, RealType>(RealType p = RealType(0.5))
```
- `exponential_distribution<Type = double>`
 Type: the parameter of the exponential distribution.
 Random integral values are generated according to the specified exponential distribution
 Constructor:

```
- exponential_distribution<IntType, Type>(Type lambda = Type(1))
```
- `normal_distribution<Type = double>`
 Type: the type of the generated random value (by default double).
 Constructor:

```
- normal_distribution<Type>(RealType mean = Type(0), Type sigma = Type(1))
```
- `poisson_distribution<IntType = int, RealType = double>`
 IntType: the type of the generated random value (by default int).
 RealType: the type of the parameter of the distribution (by default double).
 Random integral values are generated that are distributed according to a poisson distribution
 with parameter mean. Constructor:

```
- poisson_distribution<IntType, RealType>(RealType mean = RealType(1))
```
- `uniform_int<Type = int>`
 Type: the type of the generated random value (by default int).
 Random integral values are generated that are uniformly distributed over a certain range.
 Constructor:

```
- uniform_int<Type>(Type min = 0, Type max = 9)
```

Additional member:

- `Type operator()(RandomNumberGenerator), Type upper`
 Random numbers are generated in the range `[0)(upper)` (half-inclusive).
- `uniform_real<Type = real>`
 Type: the type of the generated random value (by default real).
 Random real values are generated that are uniformly distributed over a certain range.
 Constructor:

```
- uniform_real<Type>(Type min = Type(0), Type max = Type(1))
```

Note: the current implementation generates

$$\text{GRN} * (\text{max} - \text{min}) + \text{min}$$

which might not be what you'd expect.

Some of the distributions mentioned below appear not yet to be fully operational in the STL. This appears to be the case for the `binomial_distribution`, the `gamma_distribution`, the `normal_distribution`, and the `poisson_distribution`. These distributions will likely become fully operational in the near future.

Here is an example showing the outcome of a statistical experiment consisting of throwing an honest coin 20 times:

```
#include <iostream>
#include <random>
#include <ctime>
using namespace std;

int main()
{
    std::mt19937 mt(time(0));
    bernoulli_distribution bd;

    for (int idx = 0; idx < 20; ++idx)
        cout << (bd(mt) ? "heads" : "tail") << (idx + 1 == 10 ? '\n' : ' ');
    cout << '\n';
}
```

Chapter 19

The STL Generic Algorithms

19.1 The Generic Algorithms

Before using the generic algorithms presented in this chapter, except for those in the Operators category (defined below), the `<algorithm>` header file must have been included. Before using a generic algorithm in the Operators category the `<numeric>` header file must have been included.

In the previous chapter the Standard Template Library (STL) was introduced. An important element of the STL, the *generic algorithms*, was not covered in that chapter as they form a fairly extensive part of the STL. Over time the STL has grown considerably, mainly as a result of a growing importance and appreciation of *templates*. Covering generic algorithm in the STL chapter itself would turn that chapter into an unwieldy one and so the generic algorithms were moved to a chapter of their own.

Generic algorithms perform an amazing task. Due to the strength of templates algorithms could be developed that can be applied to a wide range of different data types while maintaining type safety. The prototypical example of this is the `sort` generic algorithm. To contrast: while **C** requires programmers to write callback functions in which type-unsafe `void const *` parameters have to be used, internally forcing the programmer to resort to casts, STL's `sort` frequently allows the programmer merely to state something akin to

```
sort(first-element, last-element)
```

Generic algorithms should be used wherever possible. Avoid the urge to design your own code for commonly encountered algorithms. Make it a habit to *first* thoroughly search the generic algorithms for an available candidate. The generic algorithms should become your *weapon of choice* when writing code: acquire full familiarity with them and turn their use into your 'second nature'.

This chapter's sections cover the STL's generic algorithms in alphabetical order. For each algorithm the following information is provided:

- The required header file;
- The function prototype;
- A short description;
- A short example.

In the prototypes of the algorithms `Type` is used to specify a generic data type. Also, the particular type of iterator (see section 18.2) that is required is mentioned as well as other generic types that might be required (e.g., performing `BinaryOperations`, like `plus<Type>`).

Almost every generic algorithm expects an iterator range `[first, last)`, defining the range of elements on which the algorithm operates. The iterators point to objects or values. When an iterator

points to a `Type` value or object, function objects used by the algorithms usually receive `Type const` & objects or values. Usually function objects cannot modify the objects they receive as their arguments. This does not hold true for *modifying generic algorithms*, which *are* of course able to modify the objects they operate upon.

Generic algorithms may be categorized. The **C++ Annotations** distinguishes the following categories of generic algorithms:

- Comparators: comparing (ranges of) elements:
`equal`; `includes`; `lexicographical_compare`; `max`; `min`; `mismatch`;
- Copiers: performing copy operations:
`copy`; `copy_backward`; `partial_sort_copy`; `remove_copy`; `remove_copy_if`; `replace_copy`; `replace_copy_if`; `reverse_copy`; `rotate_copy`; `unique_copy`;
- Counters: performing count operations:
`count`; `count_if`;
- Heap operators: manipulating a max-heap:
`make_heap`; `pop_heap`; `push_heap`; `sort_heap`;
- Initializers: initializing data:
`fill`; `fill_n`; `generate`; `generate_n`;
- Operators: performing arithmetic operations of some sort:
`accumulate`; `adjacent_difference`; `inner_product`; `partial_sum`;
- Searchers: performing search (and find) operations:
`adjacent_find`; `binary_search`; `equal_range`; `find`; `find_end`; `find_first_of`; `find_if`; `lower_bound`; `max_element`; `min_element`; `search`; `search_n`; `set_difference`; `set_intersection`; `set_symmetric_difference`; `set_union`; `upper_bound`;
- Shufflers: performing reordering operations (sorting, merging, permuting, shuffling, swapping):
`inplace_merge`; `iter_swap`; `merge`; `next_permutation`; `nth_element`; `partial_sort`; `partial_sort_copy`; `partition`; `prev_permutation`; `random_shuffle`; `remove`; `remove_copy`; `remove_copy_if`; `remove_if`; `reverse`; `reverse_copy`; `rotate`; `rotate_copy`; `sort`; `stable_partition`; `stable_sort`; `swap`; `unique`;
- Visitors: visiting elements in a range:
`for_each`; `replace`; `replace_copy`; `replace_copy_if`; `replace_if`; `transform`; `unique_copy`;

19.1.1 accumulate

- Header file: `<numeric>`
- Function prototypes:
 - `Type accumulate(InputIterator first, InputIterator last, Type init);`
 - `Type accumulate(InputIterator first, InputIterator last, Type init, BinaryOperation op);`
- Description:
 - The first prototype: `operator+` is applied to all elements implied by the iterator range and to the initial value `init`. The resulting value is returned.

- The second prototype: the binary operator `op` is applied to all elements implied by the iterator range and to the initial value `init`, and the resulting value is returned.

- Example:

```
#include <numeric>
#include <vector>
#include <iostream>
using namespace std;

int main()
{
    int          ia[] = {1, 2, 3, 4};
    vector<int> iv(ia, ia + 4);

    cout <<
        "Sum of values: " << accumulate(iv.begin(), iv.end(), int()) <<
        "\n"
        "Product of values: " << accumulate(iv.begin(), iv.end(), int(1),
                                           multiplies<int>()) << '\n';
}
/*
    Displays:
        Sum of values: 10
        Product of values: 24
*/
```

19.1.2 adjacent_difference

- Header file: `<numeric>`

- Function prototypes:

- `OutputIterator adjacent_difference(InputIterator first, InputIterator last, OutputIterator result);`
- `OutputIterator adjacent_difference(InputIterator first, InputIterator last, OutputIterator result, BinaryOperation op);`

- Description: All operations are performed on the original values, all computed values are returned values.

- The first prototype: the first returned element is equal to the first element of the input range. The remaining returned elements are equal to the difference of the corresponding element in the input range and its previous element.
- The second prototype: the first returned element is equal to the first element of the input range. The remaining returned elements are equal to the result of the binary operator `op` applied to the corresponding element in the input range (left operand) and its previous element (right operand).

- Example:

```
#include <numeric>
#include <vector>
#include <iterator>
#include <iostream>
using namespace std;

int main()
{
```

```

    int          ia[] = {1, 2, 5, 10};
    vector<int>   iv(ia, ia + 4);
    vector<int>   ov(iv.size());

    adjacent_difference(iv.begin(), iv.end(), ov.begin());

    copy(ov.begin(), ov.end(), ostream_iterator<int>(cout, " "));
    cout << '\n';

    adjacent_difference(iv.begin(), iv.end(), ov.begin(), minus<int>());

    copy(ov.begin(), ov.end(), ostream_iterator<int>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        1 1 3 5
        1 1 3 5
*/

```

19.1.3 adjacent_find

- Header file: <algorithm>
- Function prototypes:
 - ForwardIterator adjacent_find(ForwardIterator first, ForwardIterator last);
 - OutputIterator adjacent_find(ForwardIterator first, ForwardIterator last, Predicate pred);
- Description:
 - The first prototype: the iterator pointing to the first element of the first pair of two adjacent equal elements is returned. If no such element exists, last is returned.
 - The second prototype: the iterator pointing to the first element of the first pair of two adjacent elements for which the binary predicate pred returns true is returned. If no such element exists, last is returned.
- Example:

```

#include <algorithm>
#include <string>
#include <iostream>
using namespace std;

class SquaresDiff
{
    size_t d_minimum;
public:
    SquaresDiff(size_t minimum)
    :
        d_minimum(minimum)
    {}
    bool operator()(size_t first, size_t second)
    {
        return second * second - first * first >= d_minimum;
    }
};

int main()

```



```

{
    string sarr[] =
    {
        "Alpha", "bravo", "charley", "delta", "echo", "echo",
        "foxtrot", "golf"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);
    string *result = adjacent_find(sarr, last);

    cout << *result << '\n';
    result = adjacent_find(++result, last);

    cout << "Second time, starting from the next position:\n" <<
        (
            result == last ?
                "** No more adjacent equal elements **"
            :
                "*result"
        ) << '\n';

    size_t iv[] = {1, 2, 3, 4, 5, 6, 7, 8, 9, 10};
    size_t *ilast = iv + sizeof(iv) / sizeof(size_t);
    size_t *ires = adjacent_find(iv, ilast, SquaresDiff(10));

    cout <<
        "The first numbers for which the squares differ at least 10: "
        << *ires << " and " << *(ires + 1) << '\n';
}
/*
Displays:
echo
Second time, starting from the next position:
** No more adjacent equal elements **
The first numbers for which the squares differ at least 10: 5 and 6
*/

```

19.1.4 binary_search

- Header file: <algorithm>

- Function prototypes:

```

- bool binary_search(ForwardIterator first, ForwardIterator last,
    Type const &value);

- bool binary_search(ForwardIterator first, ForwardIterator last,
    Type const &value, Comparator comp);

```

- Description:

- The first prototype: value is looked up using binary search in the range of elements implied by the iterator range [first, last). The elements in the range must have been sorted by the `Type::operator<` function. True is returned if the element was found, false otherwise.
- The second prototype: value is looked up using binary search in the range of elements implied by the iterator range [first, last). The elements in the range must have been sorted by the `Comparator` function object. True is returned if the element was found, false otherwise.

- Example:

```
#include <algorithm>
#include <string>
#include <iostream>
#include <functional>
using namespace std;

int main()
{
    string sarr[] =
    {
        "alpha", "bravo", "charley", "delta", "echo",
        "foxtrot", "golf", "hotel"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);
    bool result = binary_search(sarr, last, "foxtrot");

    cout << (result ? "found " : "didn't find ") << "foxtrot" << '\n';

    reverse(sarr, last);                // reverse the order of elements
                                        // binary search now fails:
    result = binary_search(sarr, last, "foxtrot");
    cout << (result ? "found " : "didn't find ") << "foxtrot" << '\n';
                                        // ok when using appropriate
                                        // comparator:
    result = binary_search(sarr, last, "foxtrot", greater<string>());
    cout << (result ? "found " : "didn't find ") << "foxtrot" << '\n';

    return 0;
}
/*
    Displays:
        found foxtrot
        didn't find foxtrot
        found foxtrot
*/
```

19.1.5 copy

- Header file: `<algorithm>`
- Function prototype:
 - `OutputIterator copy(InputIterator first, InputIterator last, OutputIterator destination);`
- Description:
 - The range of elements implied by the iterator range `[first, last)` is copied to an output range, starting at `destination` using the assignment operator of the underlying data type. The return value is the `OutputIterator` pointing just beyond the last element that was copied to the destination range (so, 'last' in the destination range is returned).
- Example:

Note the second call to `copy`. It uses an `ostream_iterator` for string objects. This iterator will write the string values to the specified `ostream` (i.e., `cout`), separating the values by the specified separation string (i.e., " ").

```
#include <algorithm>
```

```

#include <string>
#include <iostream>
#include <iterator>
using namespace std;

int main()
{
    string sarr[] =
    {
        "alpha", "bravo", "charley", "delta", "echo",
        "foxtrot", "golf", "hotel"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);

    copy(sarr + 2, last, sarr); // move all elements two positions left

                                // copy to cout using an ostream_iterator
                                // for strings,
    copy(sarr, last, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
// Displays: charley delta echo foxtrot golf hotel golf hotel

```

- See also: `unique_copy`

19.1.6 `copy_backward`

- Header file: `<algorithm>`
- Function prototype:

```

- BidirectionalIterator copy_backward(InputIterator first,
    InputIterator last, BidirectionalIterator last2);

```

- Description:

- The range of elements implied by the iterator range `[first, last)` are copied from the element at position `last - 1` until (and including) the element at position `first` to the element range, *ending* at position `last2 - 1` using the assignment operator of the underlying data type. The destination range is therefore `[last2 - (last - first), last2)`.

The return value is the `BidirectionalIterator` pointing to the last element that was copied to the destination range (so, 'first' in the destination range, pointed to by `last2 - (last - first)`, is returned).

- Example:

```

#include <algorithm>
#include <string>
#include <iostream>
#include <iterator>
using namespace std;

int main()
{
    string sarr[] =
    {
        "alpha", "bravo", "charley", "delta", "echo",
        "foxtrot", "golf", "hotel"
    };
}

```

```

    string *last = sarr + sizeof(sarr) / sizeof(string);

    copy
    (
        copy_backward(sarr + 3, last, last - 3),
        last,
        ostream_iterator<string>(cout, " ")
    );
    cout << '\n';
}
// Displays:    golf hotel foxtrot golf hotel foxtrot golf hotel

```

19.1.7 count

- Header file: <algorithm>
- Function prototype:
 - `size_t count(InputIterator first, InputIterator last, Type const &value);`
- Description:
 - The number of times value occurs in the iterator range [first, last) is returned. Uses `Type::operator==` to determine whether value is equal to an element in the iterator range.
- Example:

```

#include <algorithm>
#include <iostream>
using namespace std;

int main()
{
    int ia[] = {1, 2, 3, 4, 3, 4, 2, 1, 3};

    cout << "Number of times the value 3 is available: " <<
        count(ia, ia + sizeof(ia) / sizeof(int), 3) <<
        '\n';
}
// Displays:    Number of times the value 3 is available: 3

```

19.1.8 count_if

- Header file: <algorithm>
- Function prototype:
 - `size_t count_if(InputIterator first, InputIterator last, Predicate predicate);`
- Description:
 - The number of times unary predicate 'predicate' returns true when applied to the elements implied by the iterator range [first, last) is returned.
- Example:

```

#include <algorithm>
#include <iostream>

```

```

using namespace std;

class Odd
{
public:
    bool operator()(int value) const
    {
        return value & 1;
    }
};

int main()
{
    int    ia[] = {1, 2, 3, 4, 3, 4, 2, 1, 3};

    cout << "The number of odd values in the array is: " <<
        count_if(ia, ia + sizeof(ia) / sizeof(int), Odd()) << '\n';
}
// Displays:      The number of odd values in the array is: 5

```

19.1.9 equal

- Header file: <algorithm>
- Function prototypes:
 - `bool equal(InputIterator first, InputIterator last, InputIterator otherFirst);`
 - `bool equal(InputIterator first, InputIterator last, InputIterator otherFirst, BinaryPredicate pred);`
- Description:
 - The first prototype: the elements in the range `[first, last)` are compared to a range of equal length starting at `otherFirst`. The function returns `true` if the visited elements in both ranges are equal pairwise. The ranges need not be of equal length, only the elements in the indicated range are considered (and must be available).
 - The second prototype: the elements in the range `[first, last)` are compared to a range of equal length starting at `otherFirst`. The function returns `true` if the binary predicate, applied to all corresponding elements in both ranges returns `true` for every pair of corresponding elements. The ranges need not be of equal length, only the elements in the indicated range are considered (and must be available).
- Example:

```

#include <algorithm>
#include <string>
#include <cstring>
#include <iostream>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first,
                    string const &second) const
    {
        return !strcasecmp(first.c_str(), second.c_str());
    }
};

```

```

int main()
{
    string first[] =
    {
        "Alpha", "bravo", "Charley", "delta", "Echo",
        "foxtrot", "Golf", "hotel"
    };
    string second[] =
    {
        "alpha", "bravo", "charley", "delta", "echo",
        "foxtrot", "golf", "hotel"
    };
    string *last = first + sizeof(first) / sizeof(string);

    cout << "The elements of 'first' and 'second' are pairwise " <<
        (equal(first, last, second) ? "equal" : "not equal") <<
        '\n' <<
        "compared case-insensitively, they are " <<
        (
            equal(first, last, second, CaseString()) ?
            "equal" : "not equal"
        ) << '\n';
}
/*
    Displays:
    The elements of 'first' and 'second' are pairwise not equal
    compared case-insensitively, they are equal
*/

```

19.1.10 equal_range

- Header file: `<algorithm>`
- Function prototypes:
 - `pair<ForwardIterator, ForwardIterator> equal_range(ForwardIterator first, ForwardIterator last, Type const &value);`
 - `pair<ForwardIterator, ForwardIterator> equal_range(ForwardIterator first, ForwardIterator last, Type const &value, Compare comp);`
- Description (see also identically named member functions of, e.g., the `map` (section 12.3.6) and `multimap` (section 12.3.7)):
 - The first prototype: starting from a sorted sequence (where the `operator<` of the data type to which the iterators point was used to sort the elements in the provided range), a pair of iterators is returned representing the return value of, respectively, `lower_bound` (returning the first element that is not smaller than the provided reference value, see section 19.1.25) and `upper_bound` (returning the first element beyond the provided reference value, see section 19.1.66).
 - The second prototype: starting from a sorted sequence (where the `comp` function object was used to sort the elements in the provided range), a pair of iterators is returned representing the return values of, respectively, the functions `lower_bound` (section 19.1.25) and `upper_bound` (section 19.1.66).
- Example:

```

#include <algorithm>
#include <functional>
#include <iterator>

```

```

#include <iostream>
using namespace std;

int main()
{
    int                range[] = {1, 3, 5, 7, 7, 9, 9, 9};
    size_t const       size = sizeof(range) / sizeof(int);

    pair<int *, int *> pi;

    pi = equal_range(range, range + size, 6);

    cout << "Lower bound for 6: " << *pi.first << '\n';
    cout << "Upper bound for 6: " << *pi.second << '\n';

    pi = equal_range(range, range + size, 7);

    cout << "Lower bound for 7: ";
    copy(pi.first, range + size, ostream_iterator<int>(cout, " "));
    cout << '\n';

    cout << "Upper bound for 7: ";
    copy(pi.second, range + size, ostream_iterator<int>(cout, " "));
    cout << '\n';

    sort(range, range + size, greater<int>());

    cout << "Sorted in descending order\n";

    copy(range, range + size, ostream_iterator<int>(cout, " "));
    cout << '\n';

    pi = equal_range(range, range + size, 7, greater<int>());

    cout << "Lower bound for 7: ";
    copy(pi.first, range + size, ostream_iterator<int>(cout, " "));
    cout << '\n';

    cout << "Upper bound for 7: ";
    copy(pi.second, range + size, ostream_iterator<int>(cout, " "));
    cout << '\n';

    return 0;
}
/*
Displays:
    Lower bound for 6: 7
    Upper bound for 6: 7
    Lower bound for 7: 7 7 9 9 9
    Upper bound for 7: 9 9 9
    Sorted in descending order
    9 9 9 7 7 5 3 1
    Lower bound for 7: 7 7 5 3 1
    Upper bound for 7: 5 3 1
*/

```

19.1.11 fill

- Header file: `<algorithm>`
- Function prototype:
 - `void fill(ForwardIterator first, ForwardIterator last, Type const &value);`
- Description:
 - all the elements implied by the iterator range `[first, last)` are initialized to `value`, overwriting the previous stored values.
- Example:

```
#include <algorithm>
#include <vector>
#include <iterator>
#include <iostream>
using namespace std;

int main()
{
    vector<int>      iv(8);

    fill(iv.begin(), iv.end(), 8);

    copy(iv.begin(), iv.end(), ostream_iterator<int>(cout, " "));
    cout << '\n';
}
// Displays:      8 8 8 8 8 8 8 8
```

19.1.12 fill_n

- Header file: `<algorithm>`
- Function prototype:
 - `void fill_n(ForwardIterator first, Size n, Type const &value);`
- Description:
 - `n` elements starting at the element pointed to by `first` are initialized to `value`, overwriting the previous stored values.
- Example:

```
#include <algorithm>
#include <vector>
#include <iterator>
#include <iostream>
using namespace std;

int main()
{
    vector<int>      iv(8);

    fill_n(iv.begin() + 2, 4, 8);

    copy(iv.begin(), iv.end(), ostream_iterator<int>(cout, " "));
    cout << '\n';
}
// Displays:      0 0 8 8 8 8 0 0
```


19.1.13 find

- Header file: `<algorithm>`
- Function prototype:
 - `InputIterator find(InputIterator first, InputIterator last, Type const &value);`
- Description:
 - Element value is searched for in the range of the elements implied by the iterator range `[first, last)`. An iterator pointing to the first element found is returned. If the element was not found, `last` is returned. The operator `==` of the underlying data type is used to compare the elements.
- Example:

```
#include <algorithm>
#include <string>
#include <iterator>
#include <iostream>
using namespace std;

int main()
{
    string sarr[] =
    {
        "alpha", "bravo", "charley", "delta", "echo"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);

    copy
    (
        find(sarr, last, "delta"), last,
        ostream_iterator<string>(cout, " ")
    );
    cout << '\n';

    if (find(sarr, last, "india") == last)
    {
        cout << "'india' was not found in the range\n";
        copy(sarr, last, ostream_iterator<string>(cout, " "));
        cout << '\n';
    }
}
/*
Displays:
delta echo
'india' was not found in the range
alpha bravo charley delta echo
*/
```

19.1.14 find_end

- Header file: `<algorithm>`
- Function prototypes:
 - `ForwardIterator1 find_end(ForwardIterator1 first1, ForwardIterator1 last1, ForwardIterator2 first2, ForwardIterator2 last2)`

```
- ForwardIterator1 find_end(ForwardIterator1 first1, ForwardIterator1 last1,
    ForwardIterator2 first2, ForwardIterator2 last2, BinaryPredicate pred)
```

- Description:

- The first prototype: the sequence of elements implied by [first1, last1) is searched for the last occurrence of the sequence of elements implied by [first2, last2). If the sequence [first2, last2) is not found, last1 is returned, otherwise an iterator pointing to the first element of the matching sequence is returned. The operator== of the underlying data type is used to compare the elements in the two sequences.
- The second prototype: the sequence of elements implied by [first1, last1) is searched for the last occurrence of the sequence of elements implied by [first2, last2). If the sequence [first2, last2) is not found, last1 is returned, otherwise an iterator pointing to the first element of the matching sequence is returned. The provided binary predicate is used to compare the elements in the two sequences.

- Example:

```
#include <algorithm>
#include <string>
#include <iterator>
#include <iostream>
using namespace std;

class Twice
{
public:
    bool operator()(size_t first, size_t second) const
    {
        return first == (second << 1);
    }
};

int main()
{
    string sarr[] =
    {
        "alpha", "bravo", "charley", "delta", "echo",
        "foxtrot", "golf", "hotel",
        "foxtrot", "golf", "hotel",
        "india", "juliet", "kilo"
    };
    string search[] =
    {
        "foxtrot",
        "golf",
        "hotel"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);

    copy
    (
        find_end(sarr, last, search, search + 3),    // sequence starting
        last, ostream_iterator<string>(cout, " ")    // at 2nd 'foxtrot'
    );
    cout << '\n';

    size_t range[] = {2, 4, 6, 8, 10, 4, 6, 8, 10};
    size_t nrs[]    = {2, 3, 4};

    copy                                     // sequence of values starting at last sequence
```

```

        ( // of range[] that are twice the values in nrs[]
          find_end(range, range + 9, nrs, nrs + 3, Twice()),
          range + 9, ostream_iterator<size_t>(cout, " ")
        );
    cout << '\n';
}
/*
    Displays:
        foxtrot golf hotel india juliet kilo
        4 6 8 10
*/

```

19.1.15 find_first_of

- Header file: <algorithm>

- Function prototypes:

```

- ForwardIterator1 find_first_of(ForwardIterator1 first1, ForwardIterator1
  last1, ForwardIterator2 first2, ForwardIterator2 last2)
- ForwardIterator1 find_first_of(ForwardIterator1 first1, ForwardIterator1
  last1, ForwardIterator2 first2, ForwardIterator2 last2, BinaryPredicate
  pred)

```

- Description:

- The first prototype: the sequence of elements implied by [first1, last1) is searched for the first occurrence of an element in the sequence of elements implied by [first2, last2). If no element in the sequence [first2, last2) is found, last1 is returned, otherwise an iterator pointing to the first element in [first1, last1) that is equal to an element in [first2, last2) is returned. The operator== of the underlying data type is used to compare the elements in the two sequences.
- The second prototype: the sequence of elements implied by [first1, first1) is searched for the first occurrence of an element in the sequence of elements implied by [first2, last2). Each element in the range [first1, last1) is compared to each element in the range [first2, last2), and an iterator to the first element in [first1, last1) for which the binary predicate pred (receiving an the element out of the range [first1, last1) and an element from the range [first2, last2)) returns true is returned. Otherwise, last1 is returned.

- Example:

```

#include <algorithm>
#include <string>
#include <iterator>
#include <iostream>
using namespace std;

class Twice
{
public:
    bool operator()(size_t first, size_t second) const
    {
        return first == (second << 1);
    }
};

int main()
{
    string sarr[] =

```

```

    {
        "alpha", "bravo", "charley", "delta", "echo",
        "foxtrot", "golf", "hotel",
        "foxtrot", "golf", "hotel",
        "india", "juliet", "kilo"
    };
    string search[] =
    {
        "foxtrot",
        "golf",
        "hotel"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);

    copy
    (
        // sequence starting
        find_first_of(sarr, last, search, search + 3), // at 1st 'foxtrot'
        last, ostream_iterator<string>(cout, " ")
    );
    cout << '\n';

    size_t range[] = {2, 4, 6, 8, 10, 4, 6, 8, 10};
    size_t nrs[] = {2, 3, 4};

    copy // sequence of values starting at first sequence
    ( // of range[] that are twice the values in nrs[]
        find_first_of(range, range + 9, nrs, nrs + 3, Twice()),
        range + 9, ostream_iterator<size_t>(cout, " ")
    );
    cout << '\n';
}
/*
    Displays:
        foxtrot golf hotel foxtrot golf hotel india juliet kilo
        4 6 8 10 4 6 8 10
*/

```

19.1.16 find_if

- Header file: <algorithm>
- Function prototype:
 - InputIterator find_if(InputIterator first, InputIterator last, Predicate pred);
- Description:
 - An iterator pointing to the first element in the range implied by the iterator range [first, last) for which the (unary) predicate pred returns true is returned. If the element was not found, last is returned.
- Example:

```

#include <algorithm>
#include <string>
#include <cstring>
#include <iterator>
#include <iostream>
using namespace std;

```

```

class CaseName
{
    std::string d_string;

public:
    CaseName(char const *str): d_string(str)
    {}
    bool operator()(std::string const &element) const
    {
        return strcasecmp(element.c_str(), d_string.c_str()) == 0;
    }
};

int main()
{
    string sarr[] =
    {
        "Alpha", "Bravo", "Charley", "Delta", "Echo"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);

    copy
    (
        find_if(sarr, last, CaseName("charley")),
        last, ostream_iterator<string>(cout, " ")
    );
    cout << '\n';

    if (find_if(sarr, last, CaseName("india")) == last)
    {
        cout << "'india' was not found in the range\n";
        copy(sarr, last, ostream_iterator<string>(cout, " "));
        cout << '\n';
    }
}
/*
Displays:
Charley Delta Echo
'india' was not found in the range
Alpha Bravo Charley Delta Echo
*/

```

19.1.17 for_each

- Header file: `<algorithm>`
- Function prototype:
 - Function `for_each(ForwardIterator first, ForwardIterator last, Function func);`
- Description:
 - Each of the elements implied by the iterator range `[first, last)` is passed in turn as a reference to the function (or function object) `func`. The function may modify the elements it receives (as the used iterator is a forward iterator). Alternatively, if the elements should be transformed, `transform` (see section [19.1.63](#)) can be used. The function itself or a copy of the provided function object is returned: see the example below, in which an extra argument list is added to the `for_each` call, which argument is eventually also passed to the function

given to `for_each`. Within `for_each` the return value of the function that is passed to it is ignored.

- Example:

```
#include <algorithm>
#include <string>
#include <cstring>
#include <iostream>
#include <cctype>
using namespace std;

void lowerCase(char &c)                                // 'c' *is* modified
{
    c = tolower(static_cast<unsigned char>(c));
}
void capitalizedOutput(string const &str)              // 'str' is *not* modified
{
    char    *tmp = strcpy(new char[str.size() + 1], str.c_str());

    for_each(tmp + 1, tmp + str.size(), lowerCase);

    tmp[0] = toupper(*tmp);
    cout << tmp << " ";
    delete tmp;
};
int main()
{
    string sarr[] =
    {
        "alpha", "BRAVO", "charley", "DELTA", "echo",
        "FOXTROT", "golf", "HOTEL"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);

    for_each(sarr, last, capitalizedOutput)("that's all, folks");
    cout << '\n';
}
/*
Displays:
Alpha Bravo Charley Delta Echo Foxtrot Golf Hotel That's all, folks
*/
```

- Here is another example using a function object:

```
#include <algorithm>
#include <string>
#include <iostream>
#include <cctype>
using namespace std;

void lowerCase(char &c)
{
    c = tolower(static_cast<unsigned char>(c));
}
class Show
{
    int d_count;

    public:
```

```

    Show()
    :
        d_count(0)
    {}
    void operator()(std::string &str)
    {
        std::for_each(str.begin(), str.end(), lowerCase);
        str[0] = toupper(str[0]); // here assuming str.length()
        std::cout << ++d_count << " " << str << "; ";
    }
    int count() const
    {
        return d_count;
    }
};
int main()
{
    string sarr[] =
    {
        "alpha", "BRAVO", "charley", "DELTA", "echo",
        "FOXTROT", "golf", "HOTEL"
    };
    string *last = sarr + sizeof(sarr) / sizeof(string);

    cout << for_each(sarr, last, Show()).count() << '\n';
}
/*
    Displays (all on one line):
        1 Alpha; 2 Bravo; 3 Charley; 4 Delta; 5 Echo; 6 Foxtrot;
                                           7 Golf; 8 Hotel; 8
*/

```

The example also shows that the `for_each` algorithm may be used with functions defining `const` and `non-const` parameters. Also, see section [19.1.63](#) for differences between the `for_each` and `transform` generic algorithms.

The `for_each` algorithm cannot directly be used (i.e., by passing `*this` as the function object argument) inside a member function to modify its own object as the `for_each` algorithm first creates its own copy of the passed function object. A *lambda function* or a *wrapper class* whose constructor accepts a pointer or reference to the current object and possibly to one of its member functions solves this problem.

19.1.18 generate

- Header file: `<algorithm>`

- Function prototype:

```

- void generate(ForwardIterator first, ForwardIterator last,
    Generator generator);

```

- Description:

- All elements implied by the iterator range `[first, last)` are initialized by the return value of `generator`, which can be a function or function object. `Generator::operator()` does not receive any arguments. The example uses a well-known fact from algebra: in order to obtain the square of $n + 1$, add $1 + 2 * n$ to $n * n$.

- Example:

```
#include <algorithm>
#include <vector>
#include <iterator>
#include <iostream>
using namespace std;

class NaturalSquares
{
    size_t d_newsqr;
    size_t d_last;

public:
    NaturalSquares(): d_newsqr(0), d_last(0)
    {}
    size_t operator()()
    {
        // using: (a + 1)^2 == a^2 + 2*a + 1
        return d_newsqr += (d_last++ << 1) + 1;
    }
};

int main()
{
    vector<size_t>    uv(10);

    generate(uv.begin(), uv.end(), NaturalSquares());

    copy(uv.begin(), uv.end(), ostream_iterator<int>(cout, " "));
    cout << '\n';
}
// Displays:    1 4 9 16 25 36 49 64 81 100
```

19.1.19 generate_n

- Header file: <algorithm>

- Function prototypes:

```
- void generate_n(ForwardIterator first, Size n, Generator generator);
```

- Description:

- n elements starting at the element pointed to by iterator `first` are initialized by the return value of `generator`, which can be a function or function object.

- Example:

```
#include <algorithm>
#include <vector>
#include <iterator>
#include <iostream>
using namespace std;

class NaturalSquares
{
    size_t d_newsqr;
    size_t d_last;

public:
    NaturalSquares(): d_newsqr(0), d_last(0)
```



```

    {}
    size_t operator()()
    {
        // using: (a + 1)^2 == a^2 + 2*a + 1
        return d_newsqr += (d_last++ << 1) + 1;
    }
};
int main()
{
    vector<size_t>    uv(10);

    generate_n(uv.begin(), 5, NaturalSquares());

    copy(uv.begin(), uv.end(), ostream_iterator<int>(cout, " "));
    cout << '\n';
}
// Displays:    1 4 9 16 25 0 0 0 0 0

```

19.1.20 includes

- Header file: <algorithm>
- Function prototypes:
 - `bool includes(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2);`
 - `bool includes(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, Compare comp);`
- Description:
 - The first prototype: both sequences of elements implied by the ranges `[first1, last1)` and `[first2, last2)` should have been sorted using the `operator<` of the data type to which the iterators point. The function returns `true` if every element in the second sequence `[first2, second2)` is contained in the first sequence `[first1, second1)` (the second range is a subset of the first range).
 - The second prototype: both sequences of elements implied by the ranges `[first1, last1)` and `[first2, last2)` should have been sorted using the `comp` function object. The function returns `true` if every element in the second sequence `[first2, second2)` is contained in the first sequence `[first1, second1)` (the second range is a subset of the first range).
- Example:

```

#include <algorithm>
#include <string>
#include <cstring>
#include <iostream>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first,
                    string const &second) const
    {
        return !strcasecmp(first.c_str(), second.c_str());
    }
};
int main()
{

```

```

string first1[] =
{
    "alpha", "bravo", "charley", "delta", "echo",
    "foxtrot", "golf", "hotel"
};
string first2[] =
{
    "Alpha", "bravo", "Charley", "delta", "Echo",
    "foxtrot", "Golf", "hotel"
};
string second[] =
{
    "charley", "foxtrot", "hotel"
};
size_t n = sizeof(first1) / sizeof(string);

cout << "The elements of 'second' are " <<
    (includes(first1, first1 + n, second, second + 3) ? "" : "not")
    << " contained in the first sequence:\n"
    << "second is a subset of first1\n";

cout << "The elements of 'first1' are " <<
    (includes(second, second + 3, first1, first1 + n) ? "" : "not")
    << " contained in the second sequence\n";

cout << "The elements of 'second' are " <<
    (includes(first2, first2 + n, second, second + 3) ? "" : "not")
    << " contained in the first2 sequence\n";

cout << "Using case-insensitive comparison,\n"
    "the elements of 'second' are "
    <<
    (includes(first2, first2 + n, second, second + 3, CaseString()) ?
        "" : "not")
    << " contained in the first2 sequence\n";
}
/*
Displays:
The elements of 'second' are contained in the first sequence:
second is a subset of first1
The elements of 'first1' are not contained in the second sequence
The elements of 'second' are not contained in the first2 sequence
Using case-insensitive comparison,
the elements of 'second' are contained in the first2 sequence
*/

```

19.1.21 inner_product

- Header file: <numeric>
- Function prototypes:
 - Type `inner_product(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, Type init);`
 - Type `inner_product(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, Type init, BinaryOperator1 op1, BinaryOperator2 op2);`
- Description:

- The first prototype: the sum of all pairwise products of the elements implied by the range `[first1, last1)` and the same number of elements starting at the element pointed to by `first2` are added to `init`, and this sum is returned. The function uses the operator`+` and operator`*` of the data type to which the iterators point.
- The second prototype: binary operator `op1` instead of the default addition operator, and binary operator `op2` instead of the default multiplication operator are applied to all pairwise elements implied by the range `[first1, last1)` and the same number of elements starting at the element pointed to by `first2`. The final result is returned.

• Example:

```
#include <numeric>
#include <algorithm>
#include <iterator>
#include <iostream>
#include <string>
using namespace std;

class Cat
{
    std::string d_sep;
public:
    Cat(string const &sep)
    :
        d_sep(sep)
    {}
    string operator()
        (string const &s1, string const &s2) const
    {
        return s1 + d_sep + s2;
    }
};

int main()
{
    size_t ial[] = {1, 2, 3, 4, 5, 6, 7};
    size_t ia2[] = {7, 6, 5, 4, 3, 2, 1};
    size_t init = 0;

    cout << "The sum of all squares in ";
    copy(ial, ial + 7, ostream_iterator<size_t>(cout, " "));
    cout << "is " <<
        inner_product(ial, ial + 7, ial, init) << '\n';

    cout << "The sum of all cross-products in ";
    copy(ial, ial + 7, ostream_iterator<size_t>(cout, " "));
    cout << "and ";
    copy(ia2, ia2 + 7, ostream_iterator<size_t>(cout, " "));
    cout << "is " <<
        inner_product(ial, ial + 7, ia2, init) << '\n';

    string names1[] = {"Frank", "Karel", "Piet"};
    string names2[] = {"Brokken", "Kubat", "Plomp"};

    cout << "A list of all combined names in ";
    copy(names1, names1 + 3, ostream_iterator<string>(cout, " "));
    cout << "and\n";
    copy(names2, names2 + 3, ostream_iterator<string>(cout, " "));
    cout << "is:" <<
        inner_product(names1, names1 + 3, names2, string("\t"),
```

```

        Cat("\n\t"), Cat(" ")) <<
        '\n';
    }
    /*
    Displays:
    The sum of all squares in 1 2 3 4 5 6 7 is 140
    The sum of all cross-products in 1 2 3 4 5 6 7 and 7 6 5 4 3 2 1 is 84
    A list of all combined names in Frank Karel Piet and
    Brokken Kubat Plomp is:
        Frank Brokken
        Karel Kubat
        Piet Plomp
    */

```

19.1.22 inplace_merge

- Header file: `<algorithm>`
- Function prototypes:
 - `void inplace_merge(BidirectionalIterator first, BidirectionalIterator middle, BidirectionalIterator last);`
 - `void inplace_merge(BidirectionalIterator first, BidirectionalIterator middle, BidirectionalIterator last, Compare comp);`
- Description:
 - The first prototype: the two (sorted) ranges `[first, middle)` and `[middle, last)` are merged, keeping a sorted list (using the operator`<` of the data type to which the iterators point). The final series is stored in the range `[first, last)`.
 - The second prototype: the two (sorted) ranges `[first, middle)` and `[middle, last)` are merged, keeping a sorted list (using the boolean result of the binary comparison operator `comp`). The final series is stored in the range `[first, last)`.
- Example:

```

#include <algorithm>
#include <string>
#include <cstring>
#include <iterator>
#include <iostream>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first, string const &second) const
    {
        return strcasecmp(first.c_str(), second.c_str()) < 0;
    }
};

int main()
{
    string range[] =
    {
        "alpha", "charley", "echo", "golf",
        "bravo", "delta", "foxtrot",
    };
}

```

```

    inplace_merge(range, range + 4, range + 7);
    copy(range, range + 7, ostream_iterator<string>(cout, " "));
    cout << '\n';

    string range2[] =
    {
        "ALFA", "CHARLEY", "DELTA", "foxtrot", "hotel",
        "bravo", "ECHO", "GOLF"
    };

    inplace_merge(range2, range2 + 5, range2 + 8, CaseString());
    copy(range2, range2 + 8, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        alpha bravo charley delta echo foxtrot golf
        ALFA bravo CHARLEY DELTA ECHO foxtrot GOLF hotel
*/

```

19.1.23 iter_swap

- Header file: <algorithm>

- Function prototype:

```
- void iter_swap(ForwardIterator1 iter1, ForwardIterator2 iter2);
```

- Description:

```
- The elements pointed to by iter1 and iter2 are swapped.
```

- Example:

```

#include <algorithm>
#include <iterator>
#include <iostream>
#include <string>
using namespace std;

int main()
{
    string first[] = {"alpha", "bravo", "charley"};
    string second[] = {"echo", "foxtrot", "golf"};
    size_t const n = sizeof(first) / sizeof(string);

    cout << "Before:\n";
    copy(first, first + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
    copy(second, second + n, ostream_iterator<string>(cout, " "));
    cout << '\n';

    for (size_t idx = 0; idx < n; ++idx)
        iter_swap(first + idx, second + idx);

    cout << "After:\n";
    copy(first, first + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
    copy(second, second + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
}

```

```

}
/*
    Displays:
        Before:
        alpha bravo charley
        echo foxtrot golf
        After:
        echo foxtrot golf
        alpha bravo charley
*/

```

19.1.24 lexicographical_compare

- Header file: `<algorithm>`
- Function prototypes:
 - `bool lexicographical_compare(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2);`
 - `bool lexicographical_compare(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, Compare comp);`
- Description:
 - The first prototype: the corresponding pairs of elements in the ranges pointed to by `[first1, last1)` and `[first2, last2)` are compared. The function returns `true`
 - * at the first element in the first range which is less than the corresponding element in the second range (using `operator<` of the underlying data type),
 - * if `last1` is reached, but `last2` isn't reached yet.

False is returned in the other cases, which indicates that the first sequence is not lexicographically less than the second sequence. So, `false` is returned:

 - * at the first element in the first range which is greater than the corresponding element in the second range (using `operator<` of the data type to which the iterators point, reversing the operands),
 - * if `last2` is reached, but `last1` isn't reached yet,
 - * if `last1` and `last2` are reached.
 - The second prototype: with this function the binary comparison operation as defined by `comp` is used instead of `operator<` of the data type to which the iterators point.
- Example:

```

#include <algorithm>
#include <iterator>
#include <iostream>
#include <string>
#include <cstring>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first,
                    string const &second) const
    {
        return strcasecmp(first.c_str(), second.c_str()) < 0;
    }
};

```

```

int main()
{
    string word1 = "hello";
    string word2 = "help";

    cout << word1 << " is " <<
        (
            lexicographical_compare(word1.begin(), word1.end(),
                                   word2.begin(), word2.end()) ?
            "before "
            :
            "beyond or at "
        ) <<
        word2 << " in the alphabet\n";

    cout << word1 << " is " <<
        (
            lexicographical_compare(word1.begin(), word1.end(),
                                   word1.begin(), word1.end()) ?
            "before "
            :
            "beyond or at "
        ) <<
        word1 << " in the alphabet\n";

    cout << word2 << " is " <<
        (
            lexicographical_compare(word2.begin(), word2.end(),
                                   word1.begin(), word1.end()) ?
            "before "
            :
            "beyond or at "
        ) <<
        word1 << " in the alphabet\n";

    string one[] = {"alpha", "bravo", "charley"};
    string two[] = {"ALPHA", "BRAVO", "DELTA"};

    copy(one, one + 3, ostream_iterator<string>(cout, " "));
    cout << " is ordered " <<
        (
            lexicographical_compare(one, one + 3,
                                   two, two + 3, CaseString()) ?
            "before "
            :
            "beyond or at "
        );
    copy(two, two + 3, ostream_iterator<string>(cout, " "));
    cout << "\n"
        "using case-insensitive comparisons.\n";
}
/*
Displays:
hello is before help in the alphabet
hello is beyond or at hello in the alphabet
help is beyond or at hello in the alphabet
alpha bravo charley is ordered before ALPHA BRAVO DELTA
using case-insensitive comparisons.
*/

```

19.1.25 lower_bound

- Header file: <algorithm>
- Function prototypes:
 - ForwardIterator lower_bound(ForwardIterator first, ForwardIterator last, const Type &value);
 - ForwardIterator lower_bound(ForwardIterator first, ForwardIterator last, const Type &value, Compare comp);
- Description:
 - The first prototype: the sorted elements indicated by the iterator range [first, last) are searched for the first element that is not less than (i.e., greater than or equal to) value. The returned iterator marks the location in the sequence where value can be inserted without breaking the sorted order of the elements. The operator< of the data type to which the iterators point is used. If no such element is found, last is returned.
 - The second prototype: the elements indicated by the iterator range [first, last) must have been sorted using the comp function (-object). Each element in the range is compared to value using the comp function. An iterator to the first element for which the binary predicate comp, applied to the elements of the range and value, returns false is returned. If no such element is found, last is returned.
- Example:

```
#include <algorithm>
#include <iostream>
#include <iterator>
#include <functional>
using namespace std;

int main()
{
    int    ia[] = {10, 20, 30};

    cout << "Sequence: ";
    copy(ia, ia + 3, ostream_iterator<int>(cout, " "));
    cout << '\n';

    cout << "15 can be inserted before " <<
        *lower_bound(ia, ia + 3, 15) << '\n';
    cout << "35 can be inserted after " <<
        (lower_bound(ia, ia + 3, 35) == ia + 3 ?
         "the last element" : "???") << '\n';

    iter_swap(ia, ia + 2);

    cout << "Sequence: ";
    copy(ia, ia + 3, ostream_iterator<int>(cout, " "));
    cout << '\n';

    cout << "15 can be inserted before " <<
        *lower_bound(ia, ia + 3, 15, greater<int>()) << '\n';
    cout << "35 can be inserted before " <<
        (lower_bound(ia, ia + 3, 35, greater<int>()) == ia ?
         "the first element " : "???") << '\n';
}
/*
Displays:
```



```

Sequence: 10 20 30
15 can be inserted before 20
35 can be inserted after the last element
Sequence: 30 20 10
15 can be inserted before 10
35 can be inserted before the first element
*/

```

19.1.26 max

- Header file: `<algorithm>`
- Function prototypes:
 - `Type const &max(Type const &one, Type const &two);`
 - `Type const &max(Type const &one, Type const &two, Comparator comp);`
- Description:
 - The first prototype: the larger of the two elements `one` and `two` is returned using the operator `>` of the data type to which the iterators point.
 - The second prototype: `one` is returned if the binary predicate `comp(one, two)` returns true, otherwise `two` is returned.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <cstring>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first, string const &second) const
    {
        return strcasecmp(second.c_str(), first.c_str()) > 0;
    }
};

int main()
{
    cout << "Word '" << max(string("first"), string("second")) <<
        "' is lexicographically last\n";

    cout << "Word '" << max(string("first"), string("SECOND")) <<
        "' is lexicographically last\n";

    cout << "Word '" << max(string("first"), string("SECOND"),
        CaseString()) << "' is lexicographically last\n";
}
/*
Displays:
Word 'second' is lexicographically last
Word 'first' is lexicographically last
Word 'SECOND' is lexicographically last
*/

```

19.1.27 max_element

- Header file: `<algorithm>`
- Function prototypes:
 - `ForwardIterator max_element(ForwardIterator first, ForwardIterator last);`
 - `ForwardIterator max_element(ForwardIterator first, ForwardIterator last, Comparator comp);`
- Description:
 - The first prototype: an iterator pointing to the largest element in the range implied by `[first, last)` is returned. The operator`<` of the data type to which the iterators point is used.
 - The second prototype: rather than using operator`<`, the binary predicate `comp` is used to make the comparisons between the elements implied by the iterator range `[first, last)`. The element for which `comp` returns most often true, compared with other elements, is returned.
- Example:

```
#include <algorithm>
#include <iostream>
using namespace std;

class AbsValue
{
public:
    bool operator()(int first, int second) const
    {
        return abs(first) < abs(second);
    }
};

int main()
{
    int    ia[] = {-4, 7, -2, 10, -12};

    cout << "The max. int value is " << *max_element(ia, ia + 5) << '\n';
    cout << "The max. absolute int value is " <<
        *max_element(ia, ia + 5, AbsValue()) << '\n';
}
/*
Displays:
    The max. int value is 10
    The max. absolute int value is -12
*/
```

19.1.28 merge

- Header file: `<algorithm>`
- Function prototypes:
 - `OutputIterator merge(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, OutputIterator result);`
 - `OutputIterator merge(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, OutputIterator result, Compare comp);`

- Description:

- The first prototype: the two (sorted) ranges `[first1, last1)` and `[first2, last2)` are merged, keeping a sorted list (using the `operator<` of the data type to which the iterators point). The final series is stored in the range starting at `result` and ending just before the `OutputIterator` returned by the function.
- The second prototype: the two (sorted) ranges `[first1, last1)` and `[first2, last2)` are merged, keeping a sorted list (using the boolean result of the binary comparison operator `comp`). The final series is stored in the range starting at `result` and ending just before the `OutputIterator` returned by the function.

- Example:

```
#include <algorithm>
#include <string>
#include <cstring>
#include <iterator>
#include <iostream>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first, string const &second) const
    {
        return strcasecmp(first.c_str(), second.c_str()) < 0;
    }
};

int main()
{
    string range1[] =
    {
        // 5 elements
        "alpha", "bravo", "foxtrot", "hotel", "zulu"
    };
    string range2[] =
    {
        // 4 elements
        "echo", "delta", "golf", "romeo"
    };
    string result[5 + 4];

    copy(result,
        merge(range1, range1 + 5, range2, range2 + 4, result),
        ostream_iterator<string>(cout, " "));
    cout << '\n';

    string range3[] =
    {
        "ALPHA", "bravo", "foxtrot", "HOTEL", "ZULU"
    };
    string range4[] =
    {
        "delta", "ECHO", "GOLF", "romeo"
    };

    copy(result,
        merge(range3, range3 + 5, range4, range4 + 4, result,
            CaseString()),
        ostream_iterator<string>(cout, " "));
    cout << '\n';
}
```

```

/*
    Displays:
        alpha bravo echo delta foxtrot golf hotel romeo zulu
        ALPHA bravo delta ECHO foxtrot GOLF HOTEL romeo ZULU
*/

```

19.1.29 min

- Header file: <algorithm>
- Function prototypes:
 - `Type const &min(Type const &one, Type const &two);`
 - `Type const &min(Type const &one, Type const &two, Comparator comp);`
- Description:
 - The first prototype: the smaller of the two elements one and two is returned using the operator< of the data type to which the iterators point.
 - The second prototype: one is returned if the binary predicate `comp(one, two)` returns false, otherwise two is returned.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <cstring>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first, string const &second) const
    {
        return strcasecmp(second.c_str(), first.c_str()) > 0;
    }
};

int main()
{
    cout << "Word '" << min(string("first"), string("second")) <<
        "' is lexicographically first\n";

    cout << "Word '" << min(string("first"), string("SECOND")) <<
        "' is lexicographically first\n";

    cout << "Word '" << min(string("first"), string("SECOND"),
        CaseString()) << "' is lexicographically first\n";
}
/*
    Displays:
        Word 'first' is lexicographically first
        Word 'SECOND' is lexicographically first
        Word 'first' is lexicographically first
*/

```

19.1.30 min_element

- Header file: `<algorithm>`
- Function prototypes:
 - `ForwardIterator min_element(ForwardIterator first, ForwardIterator last);`
 - `ForwardIterator min_element(ForwardIterator first, ForwardIterator last, Comparator comp);`
- Description:
 - The first prototype: an iterator pointing to the smallest element in the range implied by `[first, last)` is returned using `operator<` of the data type to which the iterators point.
 - The second prototype: rather than using `operator<`, the binary predicate `comp` is used to make the comparisons between the elements implied by the iterator range `[first, last)`. The element for which `comp` returns false most often is returned.
- Example:

```
#include <algorithm>
#include <iostream>
using namespace std;

class AbsValue
{
    public:
        bool operator()(int first, int second) const
        {
            return abs(first) < abs(second);
        }
};

int main()
{
    int    ia[] = {-4, 7, -2, 10, -12};

    cout << "The minimum int value is " << *min_element(ia, ia + 5) <<
        '\n';
    cout << "The minimum absolute int value is " <<
        *min_element(ia, ia + 5, AbsValue()) << '\n';
}
/*
    Displays:
        The minimum int value is -12
        The minimum absolute int value is -2
*/
```

19.1.31 mismatch

- Header file: `<algorithm>`
- Function prototypes:
 - `pair<InputIterator1, InputIterator2> mismatch(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2);`
 - `pair<InputIterator1, InputIterator2> mismatch(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, Compare comp);`

- Description:

- The first prototype: the two sequences of elements starting at `first1` and `first2` are compared using the equality operator of the data type to which the iterators point. Comparison stops if the compared elements differ (i.e., `operator==` returns false) or `last1` is reached. A pair containing iterators pointing to the final positions is returned. The second sequence may contain more elements than the first sequence. The behavior of the algorithm is undefined if the second sequence contains fewer elements than the first sequence.
- The second prototype: the two sequences of elements starting at `first1` and `first2` are compared using the binary comparison operation as defined by `comp`, instead of `operator==`. Comparison stops if the `comp` function returns false or `last1` is reached. A pair containing iterators pointing to the final positions is returned. The second sequence may contain more elements than the first sequence. The behavior of the algorithm is undefined if the second sequence contains fewer elements than the first sequence.

- Example:

```
#include <algorithm>
#include <string>
#include <cstring>
#include <iostream>
#include <utility>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first, string const &second) const
    {
        return strcasecmp(first.c_str(), second.c_str()) == 0;
    }
};

int main()
{
    string range1[] =
    {
        "alpha", "bravo", "foxtrot", "hotel", "zulu"
    };
    string range2[] =
    {
        "alpha", "bravo", "foxtrot", "Hotel", "zulu"
    };
    pair<string *, string *> pss = mismatch(range1, range1 + 5, range2);

    cout << "The elements " << *pss.first << " and " << *pss.second <<
        " at offset " << (pss.first - range1) << " differ\n";
    if
    (
        mismatch(range1, range1 + 5, range2, CaseString()).first
        ==
        range1 + 5
    )
        cout << "When compared case-insensitively they match\n";
}
/*
Displays:
The elements hotel and Hotel at offset 3 differ
When compared case-insensitively they match
*/
```

19.1.32 next_permutation

- Header file: `<algorithm>`
- Function prototypes:
 - `bool next_permutation(BidirectionalIterator first, BidirectionalIterator last);`
 - `bool next_permutation(BidirectionalIterator first, BidirectionalIterator last, Comp comp);`

- Description:

- The first prototype: the next permutation, given the sequence of elements in the range `[first, last)`, is determined. For example, if the elements 1, 2 and 3 are the range for which `next_permutation` is called, then subsequent calls of `next_permutation` reorders the following series:

```

1 2 3
1 3 2
2 1 3
2 3 1
3 1 2
3 2 1

```

This example shows that the elements are reordered such that each new permutation represents the next bigger value (132 is bigger than 123, 213 is bigger than 132, etc.) using `operator<` of the data type to which the iterators point. The value `true` is returned if a reordering took place, the value `false` is returned if no reordering took place, which is the case if the sequence represents the last (biggest) value. In that case, the sequence is also sorted using `operator<`.

- The second prototype: the next permutation given the sequence of elements in the range `[first, last)` is determined. The elements in the range are reordered. The value `true` is returned if a reordering took place, the value `false` is returned if no reordering took place, which is the case if the resulting sequence would have been ordered using the binary predicate `comp` to compare elements.
- Example:

```

#include <algorithm>
#include <iterator>
#include <iostream>
#include <string>
#include <cstring>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first, string const &second) const
    {
        return strcasecmp(first.c_str(), second.c_str()) < 0;
    }
};

int main()
{
    string saints[] = {"Oh", "when", "the", "saints"};

    cout << "All permutations of 'Oh when the saints':\n";
    cout << "Sequences:\n";
    do
    {

```

```

        copy(saints, saints + 4, ostream_iterator<string>(cout, " "));
        cout << '\n';
    }
    while (next_permutation(saints, saints + 4, CaseString()));

    cout << "After first sorting the sequence:\n";
    sort(saints, saints + 4, CaseString());
    cout << "Sequences:\n";
    do
    {
        copy(saints, saints + 4, ostream_iterator<string>(cout, " "));
        cout << '\n';
    }
    while (next_permutation(saints, saints + 4, CaseString()));
}
/*
Displays (partially):
    All permutations of 'Oh when the saints':
    Sequences:
    Oh when the saints
    saints Oh the when
    saints Oh when the
    saints the Oh when
    ...
    After first sorting the sequence:
    Sequences:
    Oh saints the when
    Oh saints when the
    Oh the saints when
    Oh the when saints
    ...
*/

```

19.1.33 nth_element

- Header file: <algorithm>
- Function prototypes:
 - void nth_element(RandomAccessIterator first, RandomAccessIterator nth, RandomAccessIterator last);
 - void nth_element(RandomAccessIterator first, RandomAccessIterator nth, RandomAccessIterator last, Compare comp);
- Description:
 - The first prototype: all elements in the range [first, last) are sorted relative to the element pointed to by nth: all elements in the range [left, nth) are smaller than the element pointed to by nth, and alle elements in the range [nth + 1, last) are greater than the element pointed to by nth. The two subsets themselves are not sorted. The operator< of the data type to which the iterators point is used to compare the elements.
 - The second prototype: all elements in the range [first, last) are sorted relative to the element pointed to by nth: all elements in the range [left, nth) are smaller than the element pointed to by nth, and alle elements in the range [nth + 1, last) are greater than the element pointed to by nth. The two subsets themselves are not sorted. The comp function object is used to compare the elements.
- Example:


```
#include <algorithm>
```



```

#include <iostream>
#include <iterator>
#include <functional>
using namespace std;

int main()
{
    int ia[] = {1, 3, 5, 7, 9, 2, 4, 6, 8, 10};

    nth_element(ia, ia + 3, ia + 10);

    cout << "sorting with respect to " << ia[3] << '\n';
    copy(ia, ia + 10, ostream_iterator<int>(cout, " "));
    cout << '\n';

    nth_element(ia, ia + 5, ia + 10, greater<int>());

    cout << "sorting with respect to " << ia[5] << '\n';
    copy(ia, ia + 10, ostream_iterator<int>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        sorting with respect to 4
        1 2 3 4 9 7 5 6 8 10
        sorting with respect to 5
        10 8 7 9 6 5 3 4 2 1
*/

```

19.1.34 partial_sort

- Header file: <algorithm>
- Function prototypes:
 - void partial_sort(RandomAccessIterator first, RandomAccessIterator middle, RandomAccessIterator last);
 - void partial_sort(RandomAccessIterator first, RandomAccessIterator middle, RandomAccessIterator last, Compare comp);
- Description:
 - The first prototype: the middle - first smallest elements are sorted and stored in the [first, middle) using the operator< of the data type to which the iterators point. The remaining elements of the series remain unsorted, and are stored in [middle, last).
 - The second prototype: the middle - first smallest elements (according to the provided binary predicate comp) are sorted and stored in the [first, middle). The remaining elements of the series remain unsorted.
- Example:

```

#include <algorithm>
#include <iostream>
#include <functional>
#include <iterator>
using namespace std;

int main()
{

```

```

int ia[] = {1, 3, 5, 7, 9, 2, 4, 6, 8, 10};

partial_sort(ia, ia + 3, ia + 10);

cout << "find the 3 smallest elements:\n";
copy(ia, ia + 10, ostream_iterator<int>(cout, " "));
cout << '\n';

cout << "find the 5 biggest elements:\n";
partial_sort(ia, ia + 5, ia + 10, greater<int>());
copy(ia, ia + 10, ostream_iterator<int>(cout, " "));
cout << '\n';
}
/*
Displays:
    find the 3 smallest elements:
    1 2 3 7 9 5 4 6 8 10
    find the 5 biggest elements:
    10 9 8 7 6 1 2 3 4 5
*/

```

19.1.35 partial_sort_copy

- Header file: `<algorithm>`
- Function prototypes:
 - `void partial_sort_copy(InputIterator first, InputIterator last, RandomAccessIterator dest_first, RandomAccessIterator dest_last);`
 - `void partial_sort_copy(InputIterator first, InputIterator last, RandomAccessIterator dest_first, RandomAccessIterator dest_last, Compare comp);`
- Description:
 - The first prototype: the smallest elements in the range `[first, last)` are copied to the range `[dest_first, dest_last)`, using the operator`<` of the data type to which the iterators point. Only the number of elements in the smaller range are copied to the second range.
 - The second prototype: the elements in the range `[first, last)` are sorted by the binary predicate `comp`. The elements for which the predicate returns most often true are copied to the range `[dest_first, dest_last)`. Only the number of elements in the smaller range are copied to the second range.
- Example:

```

#include <algorithm>
#include <iostream>
#include <functional>
#include <iterator>
using namespace std;

int main()
{
    int ia[] = {1, 10, 3, 8, 5, 6, 7, 4, 9, 2};
    int ia2[6];

    partial_sort_copy(ia, ia + 10, ia2, ia2 + 6);
}

```

```

    copy(ia, ia + 10, ostream_iterator<int>(cout, " "));
    cout << '\n';
    cout << "the 6 smallest elements: ";
    copy(ia2, ia2 + 6, ostream_iterator<int>(cout, " "));
    cout << '\n';

    cout << "the 4 smallest elements to a larger range:\n";
    partial_sort_copy(ia, ia + 4, ia2, ia2 + 6);
    copy(ia2, ia2 + 6, ostream_iterator<int>(cout, " "));
    cout << '\n';

    cout << "the 4 biggest elements to a larger range:\n";
    partial_sort_copy(ia, ia + 4, ia2, ia2 + 6, greater<int>());
    copy(ia2, ia2 + 6, ostream_iterator<int>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        1 10 3 8 5 6 7 4 9 2
        the 6 smallest elements: 1 2 3 4 5 6
        the 4 smallest elements to a larger range:
        1 3 8 10 5 6
        the 4 biggest elements to a larger range:
        10 8 3 1 5 6
*/

```

19.1.36 partial_sum

- Header file: `<numeric>`
- Function prototypes:
 - `OutputIterator partial_sum(InputIterator first, InputIterator last, OutputIterator result);`
 - `OutputIterator partial_sum(InputIterator first, InputIterator last, OutputIterator result, BinaryOperation op);`
- Description:
 - The first prototype: each element in the range `[result, <returned OutputIterator>)` receives a value which is obtained by adding the elements in the corresponding range of the range `[first, last)`. The first element in the resulting range will be equal to the element pointed to by `first`.
 - The second prototype: the value of each element in the range `[result, <returned OutputIterator>)` is obtained by applying the binary operator `op` to the previous element in the resulting range and the corresponding element in the range `[first, last)`. The first element in the resulting range will be equal to the element pointed to by `first`.
- Example:

```

#include <numeric>
#include <algorithm>
#include <iostream>
#include <functional>
#include <iterator>
using namespace std;

int main()
{

```

```

int ia[] = {1, 2, 3, 4, 5};
int ia2[5];

copy(ia2,
     partial_sum(ia, ia + 5, ia2),
     ostream_iterator<int>(cout, " "));
cout << '\n';

copy(ia2,
     partial_sum(ia, ia + 5, ia2, multiplies<int>()),
     ostream_iterator<int>(cout, " "));
cout << '\n';
}
/*
Displays:
    1 3 6 10 15
    1 2 6 24 120
*/

```

19.1.37 partition

- Header file: <algorithm>
- Function prototype:
 - BidirectionalIterator partition(BidirectionalIterator first, BidirectionalIterator last, UnaryPredicate pred);
- Description:
 - All elements in the range [first, last) for which the unary predicate pred evaluates as true are placed before the elements which evaluate as false. The return value points just beyond the last element in the partitioned range for which pred evaluates as true.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

class LessThan
{
    int d_x;
public:
    LessThan(int x)
    :
        d_x(x)
    {}
    bool operator()(int value) const
    {
        return value <= d_x;
    }
};

int main()
{
    int ia[] = {1, 3, 5, 7, 9, 10, 2, 8, 6, 4};
    int *split;

```

```

        split = partition(ia, ia + 10, LessThan(ia[9]));
        cout << "Last element <= 4 is ia[" << split - ia - 1 << "]\n";

        copy(ia, ia + 10, ostream_iterator<int>(cout, " "));
        cout << '\n';
    }
    /*
    Displays:
        Last element <= 4 is ia[3]
        1 3 4 2 9 10 7 8 6 5
    */

```

19.1.38 prev_permutation

- Header file: <algorithm>
- Function prototypes:
 - `bool prev_permutation(BidirectionalIterator first, BidirectionalIterator last);`
 - `bool prev_permutation(BidirectionalIterator first, BidirectionalIterator last, Comp comp);`
- Description:
 - The first prototype: the previous permutation given the sequence of elements in the range `[first, last)` is determined. The elements in the range are reordered such that the first ordering is obtained representing a ‘smaller’ value (see `next_permutation` (section [19.1.32](#)) for an example involving the opposite ordering). The value `true` is returned if a reordering took place, the value `false` is returned if no reordering took place, which is the case if the provided sequence was already ordered, according to the `operator<` of the data type to which the iterators point.
 - The second prototype: the previous permutation given the sequence of elements in the range `[first, last)` is determined. The elements in the range are reordered. The value `true` is returned if a reordering took place, the value `false` is returned if no reordering took place, which is the case if the original sequence was already ordered, using the binary predicate `comp` to compare two elements.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <cstring>
#include <iterator>
using namespace std;

class CaseString
{
public:
    bool operator()(string const &first, string const &second) const
    {
        return strcasecmp(first.c_str(), second.c_str()) < 0;
    }
};

int main()
{
    string saints[] = {"Oh", "when", "the", "saints"};

```

```

cout << "All previous permutations of 'Oh when the saints':\n";
cout << "Sequences:\n";
do
{
    copy(saints, saints + 4, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
while (prev_permutation(saints, saints + 4, CaseString()));

cout << "After first sorting the sequence:\n";
sort(saints, saints + 4, CaseString());
cout << "Sequences:\n";
while (prev_permutation(saints, saints + 4, CaseString()))
{
    copy(saints, saints + 4, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
cout << "No (more) previous permutations\n";
}
/*
Displays:
    All previous permutations of 'Oh when the saints':
    Sequences:
    Oh when the saints
    Oh when saints the
    Oh the when saints
    Oh the saints when
    Oh saints when the
    Oh saints the when
    After first sorting the sequence:
    Sequences:
    No (more) previous permutations
*/

```

19.1.39 random_shuffle

- Header file: `<algorithm>`
- Function prototypes:
 - `void random_shuffle(RandomAccessIterator first, RandomAccessIterator last);`
 - `void random_shuffle(RandomAccessIterator first, RandomAccessIterator last, RandomNumberGenerator rand);`
- Description:
 - The first prototype: the elements in the range `[first, last)` are randomly reordered.
 - The second prototype: The elements in the range `[first, last)` are randomly reordered using the `rand` random number generator, which should return an `int` in the range `[0, remaining)`, where `remaining` is passed as argument to the `operator()` of the `rand` function object. Alternatively, the random number generator may be a function expecting an `int` `remaining` parameter and returning an `int` `randomvalue` in the range `[0, remaining)`. Note that when a function object is used, it cannot be an anonymous object. The function in the example uses a procedure outlined in *Press et al. (1992) Numerical Recipes in C: The Art of Scientific Computing* (New York: Cambridge University Press, (2nd ed., p. 277)).
- Example:


```
#include <algorithm>
```

```

#include <iostream>
#include <string>
#include <time.h>
#include <iterator>
using namespace std;

int randomValue(int remaining)
{
    return rand() % remaining;
}
class RandomGenerator
{
public:
    RandomGenerator()
    {
        srand(time(0));
    }
    int operator()(int remaining) const
    {
        return randomValue(remaining);
    }
};

void show(string *begin, string *end)
{
    copy(begin, end, ostream_iterator<string>(cout, " "));
    cout << "\n\n";
}

int main()
{
    string words[] =
        { "kilo", "lima", "mike", "november", "oscar", "papa" };
    size_t const size = sizeof(words) / sizeof(string);

    cout << "Using Default Shuffle:\n";
    random_shuffle(words, words + size);
    show(words, words + size);

    cout << "Using RandomGenerator:\n";
    RandomGenerator rg;
    random_shuffle(words, words + size, rg);
    show(words, words + size);

    srand(time(0) << 1);
    cout << "Using the randomValue() function:\n";
    random_shuffle(words, words + size, randomValue);
    show(words, words + size);
}
/*
Displays (for example):
    Using Default Shuffle:
    lima oscar mike november papa kilo

    Using RandomGenerator:
    kilo lima papa oscar mike november

    Using the randomValue() function:
    mike papa november kilo oscar lima
*/

```

19.1.40 remove

- Header file: `<algorithm>`
- Function prototype:
 - `ForwardIterator remove(ForwardIterator first, ForwardIterator last, Type const &value);`
- Description:
 - The elements in the range pointed to by `[first, last)` are reordered such that all values unequal to `value` are placed at the beginning of the range. The returned forward iterator points to the first element that can be removed after reordering. The range `[returnvalue, last)` is called the *leftover* of the algorithm. Note that the leftover may contain elements different from `value`, but these elements can be removed safely, as such elements will also be present in the range `[first, return value)`. Such duplication is the result of the fact that the algorithm *copies*, rather than *moves* elements into new locations. The function uses `operator==` of the data type to which the iterators point to determine which elements to remove.
- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

int main()
{
    string words[] =
        { "kilo", "alpha", "lima", "mike", "alpha", "november", "alpha",
          "alpha", "alpha", "papa", "quebec" };
    string *removed;
    size_t const size = sizeof(words) / sizeof(string);

    cout << "Removing all \"alpha\"s:\n";
    removed = remove(words, words + size, "alpha");
    copy(words, removed, ostream_iterator<string>(cout, " "));
    cout << '\n'
         << "Leftover elements are:\n";
    copy(removed, words + size, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
Displays:
Removing all "alpha"s:
kilo lima mike november oscar papa quebec
Trailing elements are:
oscar alpha alpha papa quebec
*/
```

19.1.41 remove_copy

- Header file: `<algorithm>`
- Function prototypes:
 - `OutputIterator remove_copy(InputIterator first, InputIterator last, OutputIterator result, Type const &value);`

- Description:

- The elements in the range pointed to by `[first, last)` not matching value are copied to the range `[result, returnvalue)`, where `returnvalue` is the value returned by the function. The range `[first, last)` is not modified. The function uses `operator==` of the data type to which the iterators point to determine which elements not to copy.

- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
#include <functional>
#include <iterator>
using namespace std;

int main()
{
    string words[] =
        { "kilo", "alpha", "lima", "mike", "alpha", "november", "alpha",
          "oscar", "alpha", "alpha", "papa", "quebec" };
    size_t const size = sizeof(words) / sizeof(string);
    string remaining
        [
            size -
            count_if
            (
                words, words + size,
                bind2nd(equal_to<string>(), string("alpha"))
            )
        ];
    string *returnvalue =
        remove_copy(words, words + size, remaining, "alpha");

    cout << "Removing all \"alpha\"s:\n";
    copy(remaining, returnvalue, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        Removing all "alpha"s:
        kilo lima mike november oscar papa quebec
*/
```

19.1.42 remove_copy_if

- Header file: `<algorithm>`

- Function prototype:

- `OutputIterator remove_copy_if(InputIterator first, InputIterator last, OutputIterator result, UnaryPredicate pred);`

- Description:

- The elements in the range pointed to by `[first, last)` for which the unary predicate `pred` returns true are copied to the range `[result, returnvalue)`, where `returnvalue` is the value returned by the function. The range `[first, last)` is not modified.

- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
#include <functional>
#include <iterator>
using namespace std;

int main()
{
    string words[] =
        { "kilo", "alpha", "lima", "mike", "alpha", "november", "alpha",
          "oscar", "alpha", "alpha", "papa", "quebec" };
    size_t const size = sizeof(words) / sizeof(string);
    string remaining[
        size -
        count_if
        (
            words, words + size,
            bind2nd(equal_to<string>(), "alpha")
        )
    ];
    string *returnvalue =
        remove_copy_if
        (
            words, words + size, remaining,
            bind2nd(equal_to<string>(), "alpha")
        );

    cout << "Removing all \"alpha\"s:\n";
    copy(remaining, returnvalue, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
Displays:
Removing all "alpha"s:
kilo lima mike november oscar papa quebec
*/
```

19.1.43 remove_if

- Header file: <algorithm>

- Function prototype:

```
- ForwardIterator remove_if(ForwardIterator first, ForwardIterator last,
    UnaryPredicate pred);
```

- Description:

- The elements in the range pointed to by [first, last) are reordered such that all values for which the unary predicate `pred` evaluates as false are placed at the beginning of the range. The returned forward iterator points to the first element, after reordering, for which `pred` returns true. The range [returnvalue, last) is called the *leftover* of the algorithm. The leftover may contain elements for which the predicate `pred` returns false, but these can safely be removed, as such elements will also be present in the range [first, returnvalue). Such duplication is the result of the fact that the algorithm *copies*, rather than *moves* elements into new locations.

- Example:

```
#include <functional>
#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

int main()
{
    string words[] =
        { "kilo", "alpha", "lima", "mike", "alpha", "november", "alpha",
          "oscar", "alpha", "alpha", "papa", "quebec" };
    size_t const size = sizeof(words) / sizeof(string);

    cout << "Removing all \"alpha\"s:\n";

    string *removed = remove_if(words, words + size,
                                bind2nd(equal_to<string>(), string("alpha")));

    copy(words, removed, ostream_iterator<string>(cout, " "));
    cout << '\n'
         << "Trailing elements are:\n";
    copy(removed, words + size, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
Displays:
    Removing all "alpha"s:
    kilo lima mike november oscar papa quebec
    Trailing elements are:
    oscar alpha alpha papa quebec
*/
```

19.1.44 replace

- Header file: <algorithm>

- Function prototype:

```
- ForwardIterator replace(ForwardIterator first, ForwardIterator last,
    Type const &oldvalue, Type const &newvalue);
```

- Description:

```
- All elements equal to oldvalue in the range pointed to by [first, last) are replaced by
  a copy of newvalue. The algorithm uses operator== of the data type to which the iterators
  point.
```

- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

int main()
{
```

```

string words[] =
    { "kilo", "alpha", "lima", "mike", "alpha", "november", "alpha",
      "oscar", "alpha", "alpha", "papa" };
size_t const size = sizeof(words) / sizeof(string);

replace(words, words + size, string("alpha"), string("ALPHA"));
copy(words, words + size, ostream_iterator<string>(cout, " "));
cout << '\n';
}
/*
    Displays
    kilo ALPHA lima mike ALPHA november ALPHA oscar ALPHA ALPHA papa
*/

```

19.1.45 replace_copy

- Header file: `<algorithm>`
- Function prototype:
 - `OutputIterator replace_copy(InputIterator first, InputIterator last, OutputIterator result, Type const &oldvalue, Type const &newvalue);`
- Description:
 - All elements equal to `oldvalue` in the range pointed to by `[first, last)` are replaced by a copy of `newvalue` in a new range `[result, returnvalue)`, where `returnvalue` is the return value of the function. The algorithm uses `operator==` of the data type to which the iterators point.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

int main()
{
    string words[] =
        { "kilo", "alpha", "lima", "mike", "alpha", "november", "alpha",
          "oscar", "alpha", "alpha", "papa" };
    size_t const size = sizeof(words) / sizeof(string);
    string remaining[size];

    copy
    (
        remaining,
        replace_copy(words, words + size, remaining, string("alpha"),
                     string("ALPHA")),
        ostream_iterator<string>(cout, " ")
    );
    cout << '\n';
}
/*
    Displays:
    kilo ALPHA lima mike ALPHA november ALPHA oscar ALPHA ALPHA papa
*/

```

19.1.46 replace_copy_if

- Header file: `<algorithm>`
- Function prototypes:
 - `OutputIterator replace_copy_if(ForwardIterator first, ForwardIterator last, OutputIterator result, UnaryPredicate pred, Type const &value);`
- Description:
 - The elements in the range pointed to by `[first, last)` are copied to the range `[result, returnvalue)`, where `returnvalue` is the value returned by the function. The elements for which the unary predicate `pred` returns `true` are replaced by `newvalue`. The range `[first, last)` is not modified.
- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
#include <functional>
#include <iterator>
using namespace std;

int main()
{
    string words[] =
        { "kilo", "alpha", "lima", "mike", "alpha", "november",
          "alpha", "oscar", "alpha", "alpha", "papa" };
    size_t const size = sizeof(words) / sizeof(string);
    string result[size];

    replace_copy_if(words, words + size, result,
                    bind1st(greater<string>(), string("mike")),
                        string("ALPHA"));
    copy (result, result + size, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        ALPHA ALPHA ALPHA mike ALPHA november ALPHA oscar ALPHA ALPHA papa
*/
```

19.1.47 replace_if

- Header file: `<algorithm>`
- Function prototype:
 - `ForwardIterator replace_if(ForwardIterator first, ForwardIterator last, UnaryPredicate pred, Type const &value);`
- Description:
 - The elements in the range pointed to by `[first, last)` for which the unary predicate `pred` evaluates as `true` are replaced by `newvalue`.

Example:

```
#include <algorithm>
```

```

#include <iostream>
#include <string>
#include <functional>
#include <iterator>
using namespace std;

int main()
{
    string words[] =
        { "kilo", "alpha", "lima", "mike", "alpha", "november", "alpha",
          "oscar", "alpha", "alpha", "papa", "quebec" };
    size_t const size = sizeof(words) / sizeof(string);

    replace_if(words, words + size,
               bind1st(equal_to<string>(), string("alpha")),
               string("ALPHA"));
    copy(words, words + size, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        kilo ALPHA lima mike ALPHA november ALPHA oscar ALPHA ALPHA papa
*/

```

19.1.48 reverse

- Header file: <algorithm>
- Function prototype:
 - void reverse(BidirectionalIterator first, BidirectionalIterator last);
- Description:
 - The elements in the range pointed to by [first, last) are reversed.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
using namespace std;

int main()
{
    string line;

    while (getline(cin, line))
    {
        reverse(line.begin(), line.end());
        cout << line << '\n';
    }
}

```

19.1.49 reverse_copy

- Header file: <algorithm>

- Function prototype:
 - `OutputIterator reverse_copy(BidirectionalIterator first, BidirectionalIterator last, OutputIterator result);`
- Description:
 - The elements in the range pointed to by `[first, last)` are copied to the range `[result, returnvalue)` in reversed order. The value `returnvalue` is the value that is returned by the function.
- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
using namespace std;

int main()
{
    string line;

    while (getline(cin, line))
    {
        size_t    size = line.size();
        char      copy[size + 1];

        cout << "line: " << line << '\n' <<
            "reversed: ";
        reverse_copy(line.begin(), line.end(), copy);
        copy[size] = 0;      // 0 is not part of the reversed
                           // line !
        cout << copy << '\n';
    }
}
```

19.1.50 rotate

- Header file: `<algorithm>`
- Function prototype:
 - `void rotate(ForwardIterator first, ForwardIterator middle, ForwardIterator last);`
- Description:
 - The elements implied by the range `[first, middle)` are moved to the end of the container, the elements implied by the range `[middle, last)` are moved to the beginning of the container, keeping the order of the elements in the two subsets intact.
- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

int main()
{
```

```

string words[] =
    { "kilo", "lima", "mike", "november", "oscar",
      "foxtrot", "golf", "hotel", "india", "juliet" };
size_t const size = sizeof(words) / sizeof(string);
size_t const midsize = size / 2;

rotate(words, words + midsize, words + size);

copy(words, words + size, ostream_iterator<string>(cout, " "));
cout << '\n';
}
/*
    Displays:
        foxtrot golf hotel india juliet kilo lima mike november oscar
*/

```

19.1.51 rotate_copy

- Header file: <algorithm>
- Function prototypes:
 - `OutputIterator rotate_copy(ForwardIterator first, ForwardIterator middle, ForwardIterator last, OutputIterator result);`
- Description:
 - The elements implied by the range `[middle, last)` and then the elements implied by the range `[first, middle)` are copied to the destination container having range `[result, returnvalue)`, where `returnvalue` is the iterator returned by the function. The original order of the elements in the two subsets is not altered.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

int main()
{
    string words[] =
        { "kilo", "lima", "mike", "november", "oscar",
          "foxtrot", "golf", "hotel", "india", "juliet" };
    size_t const size = sizeof(words) / sizeof(string);
    size_t const midsize = size / 2;
    string out[size];

    copy(out,
        rotate_copy(words, words + midsize, words + size, out),
        ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        foxtrot golf hotel india juliet kilo lima mike november oscar
*/

```


19.1.52 search

- Header file: <algorithm>
- Function prototypes:
 - `ForwardIterator1 search(ForwardIterator1 first1, ForwardIterator1 last1, ForwardIterator2 first2, ForwardIterator2 last2);`
 - `ForwardIterator1 search(ForwardIterator1 first1, ForwardIterator1 last1, ForwardIterator2 first2, ForwardIterator2 last2, BinaryPredicate pred);`
- Description:
 - The first prototype: an iterator into the first range `[first1, last1)` is returned where the elements in the range `[first2, last2)` are found using `operator==` operator of the data type to which the iterators point. If no such location exists, `last1` is returned.
 - The second prototype: an iterator into the first range `[first1, last1)` is returned where the elements in the range `[first2, last2)` are found using the provided binary predicate `pred` to compare the elements in the two ranges. If no such location exists, `last1` is returned.
- Example:

```
#include <algorithm>
#include <iostream>
#include <iterator>
using namespace std;

class absInt
{
public:
    bool operator()(int i1, int i2) const
    {
        return abs(i1) == abs(i2);
    }
};

int main()
{
    int range1[] = {-2, -4, -6, -8, 2, 4, 6, 8};
    int range2[] = {6, 8};

    copy
    (
        search(range1, range1 + 8, range2, range2 + 2),
        range1 + 8,
        ostream_iterator<int>(cout, " ")
    );
    cout << '\n';

    copy
    (
        search(range1, range1 + 8, range2, range2 + 2, absInt()),
        range1 + 8,
        ostream_iterator<int>(cout, " ")
    );
    cout << '\n';
}
/*
Displays:
    6 8
   -6 -8 2 4 6 8
*/
```

19.1.53 search_n

- Header file: <algorithm>
- Function prototypes:
 - `ForwardIterator1 search_n(ForwardIterator1 first1, ForwardIterator1 last1, Size count, Type const &value);`
 - `ForwardIterator1 search_n(ForwardIterator1 first1, ForwardIterator1 last1, Size count, Type const &value, BinaryPredicate pred);`
- Description:
 - The first prototype: an iterator into the first range `[first1, last1)` is returned where `n` consecutive elements having value `value` are found using operator`==` of the data type to which the iterators point to compare the elements. If no such location exists, `last1` is returned.
 - The second prototype: an iterator into the first range `[first1, last1)` is returned where `n` consecutive elements having value `value` are found using the provided binary predicate `pred` to compare the elements. If no such location exists, `last1` is returned.
- Example:

```
#include <algorithm>
#include <iostream>
#include <iterator>
using namespace std;

bool eqInt(int i1, int i2)
{
    return abs(i1) == abs(i2);
}

int main()
{
    int range1[] = {-2, -4, -4, -6, -8, 2, 4, 4, 6, 8};
    int range2[] = {6, 8};

    copy
    (
        search_n(range1, range1 + 8, 2, 4),
        range1 + 8,
        ostream_iterator<int>(cout, " ")
    );
    cout << '\n';

    copy
    (
        search_n(range1, range1 + 8, 2, 4, eqInt),
        range1 + 8,
        ostream_iterator<int>(cout, " ")
    );
    cout << '\n';
}
/*
Displays:
  4 4
-4 -4 -6 -8 2 4 4
*/
```

19.1.54 set_difference

- Header file: <algorithm>
- Function prototypes:
 - `OutputIterator set_difference(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, OutputIterator result);`
 - `OutputIterator set_difference(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, OutputIterator result, Compare comp);`
- Description:
 - The first prototype: a sorted sequence of the elements pointed to by the range `[first1, last1)` that are not present in the range `[first2, last2)` is returned, starting at `result`, and ending at the `OutputIterator` returned by the function. The elements in the two ranges must have been sorted using `operator<` of the data type to which the iterators point.
 - The second prototype: a sorted sequence of the elements pointed to by the range `[first1, last1)` that are not present in the range `[first2, last2)` is returned, starting at `result`, and ending at the `OutputIterator` returned by the function. The elements in the two ranges must have been sorted using the `comp` function object.
- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
#include <cstring>
#include <iterator>
using namespace std;

bool caseless(string const &left, string const &right)
{
    return strcasecmp(left.c_str(), right.c_str()) < 0;
}

int main()
{
    string set1[] = { "kilo", "lima", "mike", "november",
                     "oscar", "papa", "quebec" };
    string set2[] = { "papa", "quebec", "romeo" };
    string result[7];
    string *returned;

    copy(result,
          set_difference(set1, set1 + 7, set2, set2 + 3, result),
          ostream_iterator<string>(cout, " "));
    cout << '\n';

    string set3[] = { "PAPA", "QUEBEC", "ROMEO" };

    copy(result,
          set_difference(set1, set1 + 7, set3, set3 + 3, result,
                        caseless),
          ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
Displays:
    kilo lima mike november oscar
```

```

        kilo lima mike november oscar
    */

```

19.1.55 set_intersection

- Header file: <algorithm>
- Function prototypes:
 - `OutputIterator set_intersection(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, OutputIterator result);`
 - `OutputIterator set_intersection(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, OutputIterator result, Compare comp);`
- Description:
 - The first prototype: a sorted sequence of the elements pointed to by the range `[first1, last1)` that are also present in the range `[first2, last2)` is returned, starting at `result`, and ending at the `OutputIterator` returned by the function. The elements in the two ranges must have been sorted using `operator<` of the data type to which the iterators point.
 - The second prototype: a sorted sequence of the elements pointed to by the range `[first1, last1)` that are also present in the range `[first2, last2)` is returned, starting at `result`, and ending at the `OutputIterator` returned by the function. The elements in the two ranges must have been sorted using the `comp` function object.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <cstring>
#include <iterator>
using namespace std;

bool caseless(string const &left, string const &right)
{
    return strcasecmp(left.c_str(), right.c_str()) < 0;
}

int main()
{
    string set1[] = { "kilo", "lima", "mike", "november",
                     "oscar", "papa", "quebec" };
    string set2[] = { "papa", "quebec", "romeo" };
    string result[7];
    string *returned;

    copy(result,
          set_intersection(set1, set1 + 7, set2, set2 + 3, result),
          ostream_iterator<string>(cout, " "));
    cout << '\n';

    string set3[] = { "PAPA", "QUEBEC", "ROMEO" };

    copy(result,
          set_intersection(set1, set1 + 7, set3, set3 + 3, result,
                           caseless),
          ostream_iterator<string>(cout, " "));

```

```

        cout << '\n';
    }
    /*
        Displays:
            papa quebec
            papa quebec
    */

```

19.1.56 set_symmetric_difference

- Header file: `<algorithm>`

- Function prototypes:

```

- OutputIterator set_symmetric_difference( InputIterator1 first1,
    InputIterator1 last1, InputIterator2 first2,
    InputIterator2 last2, OutputIterator result);

- OutputIterator set_symmetric_difference( InputIterator1 first1,
    InputIterator1 last1, InputIterator2 first2,
    InputIterator2 last2, OutputIterator result,
    Compare comp);

```

- Description:

- The first prototype: a sorted sequence of the elements pointed to by the range `[first1, last1)` that are not present in the range `[first2, last2)` and those in the range `[first2, last2)` that are not present in the range `[first1, last1)` is returned, starting at `result`, and ending at the `OutputIterator` returned by the function. The elements in the two ranges must have been sorted using `operator<` of the data type to which the iterators point.
- The second prototype: a sorted sequence of the elements pointed to by the range `[first1, last1)` that are not present in the range `[first2, last2)` and those in the range `[first2, last2)` that are not present in the range `[first1, last1)` is returned, starting at `result`, and ending at the `OutputIterator` returned by the function. The elements in the two ranges must have been sorted using the `comp` function object.

- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <cstring>
#include <iterator>
using namespace std;

bool caseless(string const &left, string const &right)
{
    return strcasecmp(left.c_str(), right.c_str()) < 0;
}

int main()
{
    string set1[] = { "kilo", "lima", "mike", "november",
                     "oscar", "papa", "quebec" };
    string set2[] = { "papa", "quebec", "romeo" };
    string result[7];
    string *returned;

    copy(result,
        set_symmetric_difference(set1, set1 + 7, set2, set2 + 3,
                                result),

```

```

        ostream_iterator<string>(cout, " ");
    cout << '\n';

    string set3[] = { "PAPA", "QUEBEC", "ROMEO" };

    copy(result,
        set_symmetric_difference(set1, set1 + 7, set3, set3 + 3,
                                result, caseless),
        ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        kilo lima mike november oscar romeo
        kilo lima mike november oscar ROMEO
*/

```

19.1.57 set_union

- Header file: <algorithm>
- Function prototypes:
 - OutputIterator set_union(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, OutputIterator result);
 - OutputIterator set_union(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, InputIterator2 last2, OutputIterator result, Compare comp);
- Description:
 - The first prototype: a sorted sequence of the elements that are present in either the range [first1, last1) or the range [first2, last2) or in both ranges is returned, starting at result, and ending at the OutputIterator returned by the function. The elements in the two ranges must have been sorted using operator< of the data type to which the iterators point. Note that in the final range each element will appear only once.
 - The second prototype: a sorted sequence of the elements that are present in either the range [first1, last1) or the range [first2, last2) or in both ranges is returned, starting at result, and ending at the OutputIterator returned by the function. The elements in the two ranges must have been sorted using comp function object. Note that in the final range each element will appear only once.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <cstring>
#include <iterator>
using namespace std;

bool caseless(string const &left, string const &right)
{
    return strcasecmp(left.c_str(), right.c_str()) < 0;
}

int main()
{
    string set1[] = { "kilo", "lima", "mike", "november",
                     "oscar", "papa", "quebec" };

```

```

    string set2[] = { "papa", "quebec", "romeo"};
    string result[7];
    string *returned;

    copy(result,
        set_union(set1, set1 + 7, set2, set2 + 3, result),
        ostream_iterator<string>(cout, " "));
    cout << '\n';

    string set3[] = { "PAPA", "QUEBEC", "ROMEO"};

    copy(result,
        set_union(set1, set1 + 7, set3, set3 + 3, result, caseless),
        ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        kilo lima mike november oscar papa quebec romeo
        kilo lima mike november oscar papa quebec ROMEO
*/

```

19.1.58 sort

- Header file: `<algorithm>`
- Function prototypes:
 - `void sort(RandomAccessIterator first, RandomAccessIterator last);`
 - `void sort(RandomAccessIterator first, RandomAccessIterator last, Compare comp);`
- Description:
 - The first prototype: the elements in the range `[first, last)` are sorted in ascending order using `operator<` of the data type to which the iterators point.
 - The second prototype: the elements in the range `[first, last)` are sorted in ascending order using the `comp` function object to compare the elements. The binary predicate `comp` should return `true` if its first argument should be placed earlier in the sorted sequence than its second argument.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <functional>
#include <iterator>
using namespace std;

int main()
{
    string words[] = {"november", "kilo", "mike", "lima",
                     "oscar", "quebec", "papa"};

    sort(words, words + 7);
    copy(words, words + 7, ostream_iterator<string>(cout, " "));
    cout << '\n';
}

```

```

    sort(words, words + 7, greater<string>());
    copy(words, words + 7, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        kilo lima mike november oscar papa quebec
        quebec papa oscar november mike lima kilo
*/

```

19.1.59 stable_partition

- Header file: `<algorithm>`
- Function prototype:
 - `BidirectionalIterator stable_partition(BidirectionalIterator first, BidirectionalIterator last, UnaryPredicate pred);`
- Description:
 - All elements in the range `[first, last)` for which the unary predicate `pred` evaluates as `true` are placed before the elements which evaluate as `false`. Apart from this reordering, the relative order of all elements for which the predicate evaluates to `false` and the relative order of all elements for which the predicate evaluates to `true` is kept. The return value points just beyond the last element in the partitioned range for which `pred` evaluates as `true`.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <functional>
#include <iterator>
using namespace std;

int main()
{
    int org[] = {1, 3, 5, 7, 9, 10, 2, 8, 6, 4};
    int ia[10];
    int *split;

    copy(org, org + 10, ia);
    split = partition(ia, ia + 10, bind2nd(less_equal<int>(), ia[9]));
    cout << "Last element <= 4 is ia[" << split - ia - 1 << "]\n";

    copy(ia, ia + 10, ostream_iterator<int>(cout, " "));
    cout << '\n';

    copy(org, org + 10, ia);
    split = stable_partition(ia, ia + 10,
                             bind2nd(less_equal<int>(), ia[9]));
    cout << "Last element <= 4 is ia[" << split - ia - 1 << "]\n";

    copy(ia, ia + 10, ostream_iterator<int>(cout, " "));
    cout << '\n';
}
/*
    Displays:

```



```

        Last element <= 4 is ia[3]
        1 3 4 2 9 10 7 8 6 5
        Last element <= 4 is ia[3]
        1 3 2 4 5 7 9 10 8 6
    */

```

19.1.60 `stable_sort`

- Header file: `<algorithm>`
- Function prototypes:
 - `void stable_sort(RandomAccessIterator first, RandomAccessIterator last);`
 - `void stable_sort(RandomAccessIterator first, RandomAccessIterator last, Compare comp);`
- Description:
 - The first prototype: the elements in the range `[first, last)` are stable-sorted in ascending order using `operator<` of the data type to which the iterators point: the relative order of equal elements is kept.
 - The second prototype: the elements in the range `[first, last)` are stable-sorted in ascending order using the `comp` binary predicate to compare the elements. This predicate should return `true` if its first argument should be placed before its second argument in the sorted set of element.
- Example (annotated below):

```

#include <algorithm>
#include <iostream>
#include <string>
#include <vector>
#include <iterator>
using namespace std;

struct Pss: public pair<string, string> // 1
{
    Pss(string const &s1, string const &s2)
    :
        pair<string, string>(s1, s2)
    {}
};

ostream &operator<<(ostream &out, Pss const &p) // 2
{
    return out << "      " << p.first << " " << p.second << '\n';
}

class Sortby
{
    string Pss::*d_field;
public:
    Sortby(string Pss::*field) // 3
    :
        d_field(field)
    {}
    bool operator()(Pss const &p1, Pss const &p2) const // 4
    {
        return p1.*d_field < p2.*d_field;
    }
};

```

```

int main()
{
    vector<Pss> namecity;                                     // 5

    namecity.push_back(Pss("Hampson", "Godalming"));
    namecity.push_back(Pss("Moran", "Eugene"));
    namecity.push_back(Pss("Goldberg", "Eugene"));
    namecity.push_back(Pss("Moran", "Godalming"));
    namecity.push_back(Pss("Goldberg", "Chicago"));
    namecity.push_back(Pss("Hampson", "Eugene"));

    sort(namecity.begin(), namecity.end(), Sortby(&Pss::first)); // 6

    cout << "sorted by names:\n";
    copy(namecity.begin(), namecity.end(), ostream_iterator<Pss>(cout));

                                                                    // 7
    stable_sort(namecity.begin(), namecity.end(), Sortby(&Pss::second));

    cout << "sorted by names within sorted cities:\n";
    copy(namecity.begin(), namecity.end(), ostream_iterator<Pss>(cout));
}
/*
Displays:
    sorted by names:
        Goldberg Eugene
        Goldberg Chicago
        Hampson Godalming
        Hampson Eugene
        Moran Eugene
        Moran Godalming
    sorted by names within sorted cities:
        Goldberg Chicago
        Goldberg Eugene
        Hampson Eugene
        Moran Eugene
        Hampson Godalming
        Moran Godalming
*/

```

Note that the example implements a solution to an often occurring problem: how to sort using multiple hierarchal criteria. The example deserves some additional attention:

- First, at // 1 a wrapper struct `Pss` is created around `std::pair<std::string, std::string>`. Once the C++0x standard supports the direct use of base class constructors in derived classes (cf. section 13.2.1) it becomes even simpler to create this struct. The intent here is to define a type that is a wrapper around a class that is defined in the `std` namespace for which no insertion operation has been defined. This struct design conflicts with the principles outlined in section 14.6 inheritance is nonetheless defensible here as the intention is not to add ‘missing features’ and as `pair` itself is in essence just Plain Old Data.
- Next (// 2), `operator<<` is overloaded for `Pss` objects. Although the compiler wouldn’t have complained if this operator would have been defined in the `std` namespace for the `pair<string, string>` type, this would also be bad style as the `std` namespace is *off limits* for ordinary programs. By defining a wrapper type around `pair<string, string>` bad style can be prevented.
- Then (// 3), a class `Sortby` is defined, allowing us to construct an anonymous object receiving a pointer to one of the `Pss` data members that are used for sorting. In this case, as both members are `string` objects, its constructor can easily be defined. It expects a pointer to a `string` member of the class `Pss`.

- `Sortby's operator()` member (// 4) receives two references to `Pss` objects and uses its pointer to member to compare the appropriate fields of the `Pss` objects.
- In `main` some data is stored in a vector (// 5).
- Then (// 6) the first sort takes place. The least important criterion must be sorted first and for this a simple sort suffices. Since we want the names to be sorted within cities, the names represent the least important criterion, so we sort by names: `Sortby(&Pss::first)`.
- The next important criterion, the cities, are sorted next (// 7). Since the relative ordering of the *names* will not be altered anymore by `stable_sort`, the ties that are observed when cities are sorted are solved in such a way that the existing relative ordering will not be broken. So, we end up getting Goldberg in Eugene before Hampson in Eugene, before Moran in Eugene. To sort by cities, we use another anonymous `Sortby` object: `Sortby(&Pss::second)`.

19.1.61 swap

- Header file: `<algorithm>`
- Function prototype:
 - `void swap(Type &object1, Type &object2);`
- Description:
 - The elements `object1` and `object2` exchange their values. They do so by either cyclic copy assignment or cyclic move assignment (if available).
- Example:

```
#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

int main()
{
    string first[] = {"alpha", "bravo", "charley"};
    string second[] = {"echo", "foxtrot", "golf"};
    size_t const n = sizeof(first) / sizeof(string);

    cout << "Before:\n";
    copy(first, first + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
    copy(second, second + n, ostream_iterator<string>(cout, " "));
    cout << '\n';

    for (size_t idx = 0; idx < n; ++idx)
        swap(first[idx], second[idx]);

    cout << "After:\n";
    copy(first, first + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
    copy(second, second + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
```

Displays:

Before:

alpha bravo charley

```

        echo foxtrot golf
    After:
        echo foxtrot golf
        alpha bravo charley
*/

```

19.1.62 swap_ranges

- Header file: <algorithm>

- Function prototype:

```

- ForwardIterator2 swap_ranges(ForwardIterator1 first1, ForwardIterator1
  last1, ForwardIterator2 result);

```

- Description:

- The elements in the range pointed to by [first1, last1) are swapped with the elements in the range [result, returnvalue), where returnvalue is the value returned by the function. The two ranges must be disjoint.

- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <iterator>
using namespace std;

int main()
{
    string first[] = {"alpha", "bravo", "charley"};
    string second[] = {"echo", "foxtrot", "golf"};
    size_t const n = sizeof(first) / sizeof(string);

    cout << "Before:\n";
    copy(first, first + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
    copy(second, second + n, ostream_iterator<string>(cout, " "));
    cout << '\n';

    swap_ranges(first, first + n, second);

    cout << "After:\n";
    copy(first, first + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
    copy(second, second + n, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
Displays:
    Before:
    alpha bravo charley
    echo foxtrot golf
    After:
    echo foxtrot golf
    alpha bravo charley
*/

```

19.1.63 transform

- Header file:

```
#include <algorithm>
```

- Function prototypes:

- `OutputIterator transform(InputIterator first, InputIterator last, OutputIterator result, UnaryOperator op);`
- `OutputIterator transform(InputIterator1 first1, InputIterator1 last1, InputIterator2 first2, OutputIterator result, BinaryOperator op);`

- Description:

- The first prototype: the unary operator `op` is applied to each of the elements in the range `[first, last)`, and the resulting values are stored in the range starting at `result`. The return value points just beyond the last generated element.
- The second prototype: the binary operator `op` is applied to each of the elements in the range `[first1, last1)` and the corresponding element in the second range starting at `first2`. The resulting values are stored in the range starting at `result`. The return value points just beyond the last generated element.

- Example:

```
#include <functional>
#include <vector>
#include <algorithm>
#include <iostream>
#include <string>
#include <cctype>
#include <iterator>
using namespace std;

string caps(string const &src)
{
    string tmp;
    tmp.resize(src.length());

    transform(src.begin(), src.end(), tmp.begin(), ::toupper);
    return tmp;
}

int main()
{
    string words[] = {"alpha", "bravo", "charley"};

    copy(words, transform(words, words + 3, words, caps),
          ostream_iterator<string>(cout, " "));
    cout << '\n';

    int values[] = {1, 2, 3, 4, 5};
    vector<int> squares;

    transform(values, values + 5, values,
              back_inserter(squares), multiplies<int>());

    copy(squares.begin(), squares.end(),
          ostream_iterator<int>(cout, " "));
    cout << '\n';
}
```

```

/*
    Displays:
        ALPHA BRAVO CHARLEY
        1 4 9 16 25
*/

```

the following differences between the `for_each` (section 19.1.17) and transform generic algorithms should be noted:

- With transform the *return value* of the function object's `operator()` member is used; the argument that is passed to the `operator()` member itself is not changed.
- With `for_each` the function object's `operator()` receives a reference to an argument, which itself may be changed by the function object's `operator()`.

19.1.64 unique

- Header file: `<algorithm>`
- Function prototypes:
 - `ForwardIterator unique(ForwardIterator first, ForwardIterator last);`
 - `ForwardIterator unique(ForwardIterator first, ForwardIterator last, BinaryPredicate pred);`
- Description:
 - The first prototype: using `operator==`, all but the first of consecutively equal elements of the data type to which the iterators point in the range pointed to by `[first, last)` are relocated to the end of the range. The returned forward iterator marks the beginning of the *leftover*. All elements in the range `[first, return-value)` are unique, all elements in the range `[return-value, last)` are equal to elements in the range `[first, return-value)`.
 - The second prototype: all but the first of consecutive elements in the range pointed to by `[first, last)` for which the binary predicate `pred` (expecting two arguments of the data type to which the iterators point) returns `true`, are relocated to the end of the range. The returned forward iterator marks the beginning of the *leftover*. For all pairs of elements in the range `[first, return-value)` `pred` returns `false` (i.e., are *unique*), while `pred` returns `true` for a combination of, as its first operand, an element in the range `[return-value, last)` and, as its second operand, an element in the range `[first, return-value)`.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <cstring>
#include <iterator>
using namespace std;

bool casestring(string const &first, string const &second)
{
    return strcasecmp(first.c_str(), second.c_str()) == 0;
}

int main()
{
    string words[] = {"alpha", "alpha", "Alpha", "papa", "quebec" };
    size_t const size = sizeof(words) / sizeof(string);

```

```

    string *removed = unique(words, words + size);
    copy(words, removed, ostream_iterator<string>(cout, " "));
    cout << '\n'
         << "Trailing elements are:\n";
    copy(removed, words + size, ostream_iterator<string>(cout, " "));
    cout << '\n';

    removed = unique(words, words + size, casestring);
    copy(words, removed, ostream_iterator<string>(cout, " "));
    cout << '\n'
         << "Trailing elements are:\n";
    copy(removed, words + size, ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        alpha Alpha papa quebec
        Trailing elements are:
        quebec
        alpha papa quebec
        Trailing elements are:
        quebec quebec
*/

```

19.1.65 unique_copy

- Header file: <algorithm>
- Function prototypes:
 - OutputIterator unique_copy(InputIterator first, InputIterator last, OutputIterator result);
 - OutputIterator unique_copy(InputIterator first, InputIterator last, OutputIterator Result, BinaryPredicate pred);
- Description:
 - The first prototype: the elements in the range [first, last) are copied to the resulting container, starting at result. Consecutively equal elements (using operator== of the data type to which the iterators point) are copied only once. The returned output iterator points just beyond the last copied element.
 - The second prototype: the elements in the range [first, last) are copied to the resulting container, starting at result. Consecutive elements in the range pointed to by [first, last) for which the binary predicate pred returns true are copied only once. The returned output iterator points just beyond the last copied element.
- Example:

```

#include <algorithm>
#include <iostream>
#include <string>
#include <vector>
#include <iterator>
#include <cstring>
using namespace std;

bool casestring(string const &first, string const &second)
{

```

```

    return strcasecmp(first.c_str(), second.c_str()) == 0;
}
int main()
{
    string words[] = {"oscar", "Alpha", "alpha", "alpha",
                     "papa", "quebec" };
    size_t const size = sizeof(words) / sizeof(string);
    vector<string> remaining;

    unique_copy(words, words + size, back_inserter(remaining));

    copy(remaining.begin(), remaining.end(),
         ostream_iterator<string>(cout, " "));
    cout << '\n';

    vector<string> remaining2;

    unique_copy(words, words + size,
                 back_inserter(remaining2), casestring);

    copy(remaining2.begin(), remaining2.end(),
         ostream_iterator<string>(cout, " "));
    cout << '\n';
}
/*
    Displays:
        oscar Alpha alpha papa quebec
        oscar Alpha papa quebec
*/

```

19.1.66 upper_bound

- Header file: <algorithm>
- Function prototypes:
 - ForwardIterator upper_bound(ForwardIterator first, ForwardIterator last, Type const &value);
 - ForwardIterator upper_bound(ForwardIterator first, ForwardIterator last, Type const &value, Compare comp);
- Description:
 - The first prototype: the sorted elements stored in the iterator range [first, last) are searched for the first element that is greater than value. The returned iterator marks the first location in the sequence where value can be inserted without breaking the sorted order of the elements using operator< of the data type to which the iterators point. If no such element is found, last is returned.
 - The second prototype: the elements implied by the iterator range [first, last) must have been sorted using the comp function or function object. Each element in the range is compared to value using the comp function. An iterator to the first element for which the binary predicate comp, applied to the elements of the range and value, returns true is returned. If no such element is found, last is returned.
- Example:

```

#include <algorithm>
#include <iostream>
#include <functional>

```



```

#include <iterator>
using namespace std;

int main()
{
    int          ia[] = {10, 15, 15, 20, 30};
    size_t      n = sizeof(ia) / sizeof(int);

    cout << "Sequence: ";
    copy(ia, ia + n, ostream_iterator<int>(cout, " "));
    cout << '\n';

    cout << "15 can be inserted before " <<
        *upper_bound(ia, ia + n, 15) << '\n';
    cout << "35 can be inserted after " <<
        (upper_bound(ia, ia + n, 35) == ia + n ?
         "the last element" : "???") << '\n';

    sort(ia, ia + n, greater<int>());

    cout << "Sequence: ";
    copy(ia, ia + n, ostream_iterator<int>(cout, " "));
    cout << '\n';

    cout << "15 can be inserted before " <<
        *upper_bound(ia, ia + n, 15, greater<int>()) << '\n';
    cout << "35 can be inserted before " <<
        (upper_bound(ia, ia + n, 35, greater<int>()) == ia ?
         "the first element " : "???") << '\n';
}
/*
Displays:
Sequence: 10 15 15 20 30
15 can be inserted before 20
35 can be inserted after the last element
Sequence: 30 20 15 15 10
15 can be inserted before 10
35 can be inserted before the first element
*/

```

19.1.67 Heap algorithms

A heap is a kind of binary tree which can be represented by an array. In the standard heap, the key of an element is not smaller than the key of its children. This kind of heap is called a *max heap*. A tree in which numbers are keys could be organized as shown in figure 19.1. Such a tree may also be organized in an array:

12, 11, 10, 8, 9, 7, 6, 1, 2, 4, 3, 5

In the following description, keep two pointers into this array in mind: a pointer `node` indicates the location of the next node of the tree, a pointer `child` points to the next element which is a child of the node `pointer`. Initially, `node` points to the first element, and `child` points to the second element.

- `*node++` (`== 12`). 12 is the top node. its children are `*child++` (11) and `*child++` (10), both less than 12.
- The next node (`*node++` (`== 11`)), in turn, has `*child++` (8) and `*child++` (9) as its children.




Figure 19.1: A binary tree representation of a heap

- The next node (`*node++` (`== 10`)) has `*child++` (7) and `*child++` (6) as its children.
- The next node (`*node++` (`== 8`)) has `*child++` (1) and `*child++` (2) as its children.
- Then, node (`*node++` (`== 9`)) has children `*child++` (4) and `*child++` (3).
- Finally (as far as children are concerned) (`*node++` (`== 7`)) has one child `*child++` (5)

Since `child` now points beyond the array, the remaining nodes have no children. So, nodes 6, 1, 2, 4, 3 and 5 don't have children.

Note that the left and right branches are not ordered: 8 is less than 9, but 7 is larger than 6.

A heap is created by traversing a binary tree level-wise, starting from the top node. The top node is 12, at the zeroth level. At the first level we find 11 and 10. At the second level 6, 7, 8 and 9 are found, etc.

Heaps can be constructed in containers supporting random access. So, a list is not an appropriate data structure for a heap. Heaps can be constructed from an (unsorted) array (using `make_heap`). The top-element can be pruned from a heap, followed by reordering the heap (using `pop_heap`), a new element can be added to the heap, followed by reordering the heap (using `push_heap`), and the elements in a heap can be sorted (using `sort_heap`, which (of course) invalidates the heap).

19.1.67.1 The 'make_heap' function

- Header file: `<algorithm>`
- Function prototypes:
 - `void make_heap(RandomAccessIterator first, RandomAccessIterator last);`
 - `void make_heap(RandomAccessIterator first, RandomAccessIterator last, Compare comp);`
- Description:
 - The first prototype: the elements in the range `[first, last)` are reordered to form a max-heap using `operator<` of the data type to which the iterators point.
 - The second prototype: the elements in the range `[first, last)` are reordered to form a max-heap using the binary comparison function object `comp` to compare elements.

19.1.67.2 The 'pop_heap' function

- Header file: `<algorithm>`

- Function prototypes:

- `void pop_heap(RandomAccessIterator first, RandomAccessIterator last);`
- `void pop_heap(RandomAccessIterator first, RandomAccessIterator last, Compare comp);`

- Description:

- The first prototype: the first element in the range `[first, last)` is moved to `last - 1`. Then, the elements in the range `[first, last - 1)` are reordered to form a max-heap using the operator`<` of the data type to which the iterators point.
- The second prototype: the first element in the range `[first, last)` is moved to `last - 1`. Then, the elements in the range `[first, last - 1)` are reordered to form a max-heap using the binary comparison function object `comp` to compare elements.

19.1.67.3 The ‘push_heap’ function

- Header file: `<algorithm>`

- Function prototypes:

- `void push_heap(RandomAccessIterator first, RandomAccessIterator last);`
- `void push_heap(RandomAccessIterator first, RandomAccessIterator last, Compare comp);`

- Description:

- The first prototype: assuming that the range `[first, last - 2)` contains a valid heap, and the element at `last - 1` contains an element to be added to the heap, the elements in the range `[first, last - 1)` are reordered to form a max-heap using the operator`<` of the data type to which the iterators point.
- The second prototype: assuming that the range `[first, last - 2)` contains a valid heap, and the element at `last - 1` contains an element to be added to the heap, the elements in the range `[first, last - 1)` are reordered to form a max-heap using the binary comparison function object `comp` to compare elements.

19.1.67.4 The ‘sort_heap’ function

- Header file: `<algorithm>`

- Function prototypes:

- `void sort_heap(RandomAccessIterator first, RandomAccessIterator last);`
- `void sort_heap(RandomAccessIterator first, RandomAccessIterator last, Compare comp);`

- Description:

- The first prototype: assuming the elements in the range `[first, last)` form a valid max-heap, the elements in the range `[first, last)` are sorted using operator`<` of the data type to which the iterators point.
- The second prototype: assuming the elements in the range `[first, last)` form a valid heap, the elements in the range `[first, last)` are sorted using the binary comparison function object `comp` to compare elements.

19.1.67.5 An example using the heap functions

Here is an example showing the various generic algorithms manipulating heaps:

```
#include <algorithm>
#include <iostream>
#include <functional>
#include <iterator>
using namespace std;

void show(int *ia, char const *header)
{
    cout << header << ":\n";
    copy(ia, ia + 20, ostream_iterator<int>(cout, " "));
    cout << '\n';
}

int main()
{
    int ia[] = {1, 2, 3, 4, 5, 6, 7, 8, 9, 10,
                11, 12, 13, 14, 15, 16, 17, 18, 19, 20};

    make_heap(ia, ia + 20);
    show(ia, "The values 1-20 in a max-heap");

    pop_heap(ia, ia + 20);
    show(ia, "Removing the first element (now at the end)");

    push_heap(ia, ia + 20);
    show(ia, "Adding 20 (at the end) to the heap again");

    sort_heap(ia, ia + 20);
    show(ia, "Sorting the elements in the heap");

    make_heap(ia, ia + 20, greater<int>());
    show(ia, "The values 1-20 in a heap, using > (and beyond too)");

    pop_heap(ia, ia + 20, greater<int>());
    show(ia, "Removing the first element (now at the end)");

    push_heap(ia, ia + 20, greater<int>());
    show(ia, "Re-adding the removed element");

    sort_heap(ia, ia + 20, greater<int>());
    show(ia, "Sorting the elements in the heap");
}
/*
```

Displays:

```
The values 1-20 in a max-heap:
20 19 15 18 11 13 14 17 9 10 2 12 6 3 7 16 8 4 1 5
Removing the first element (now at the end):
19 18 15 17 11 13 14 16 9 10 2 12 6 3 7 5 8 4 1 20
Adding 20 (at the end) to the heap again:
20 19 15 17 18 13 14 16 9 11 2 12 6 3 7 5 8 4 1 10
Sorting the elements in the heap:
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20
The values 1-20 in a heap, using > (and beyond too):
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20
Removing the first element (now at the end):
```

```
2 4 3 8 5 6 7 16 9 10 11 12 13 14 15 20 17 18 19 1
Re-adding the removed element:
1 2 3 8 4 6 7 16 9 5 11 12 13 14 15 20 17 18 19 10
Sorting the elements in the heap:
20 19 18 17 16 15 14 13 12 11 10 9 8 7 6 5 4 3 2 1
```

```
*/
```


Chapter 20

Function Templates

C++ supports syntactic constructs allowing programmers to define and use completely general (or abstract) functions or classes, based on generic types and/or (possibly inferred) constant values. In the chapters on abstract containers (chapter 12) and the STL (chapter 18) we've already used these constructs, commonly known as the *template mechanism*.

The template mechanism allows us to specify classes and algorithms, fairly independently of the actual types for which the templates will eventually be used. Whenever the template is used, the compiler generates code that is tailored to the particular data type(s) used with the template. This code is generated compile-time from the template's definition. The piece of generated code is called an *instantiation* of the template.

In this chapter the syntactic peculiarities of templates are covered. The notions of *template type parameter*, *template non-type parameter*, and *function template* are introduced and several examples of templates are provided (both in this chapter and in chapter 23). Template *classes* are covered in chapter 21.

Templates offered standard by the language include the abstract containers (cf. chapter 12); the `string` (cf. chapter 5); streams (cf. chapter 6); and the generic algorithms (cf. chapter 19). So, templates play a central role in present-day **C++**, and should not be considered an esoteric feature of the language.

Templates should be approached somewhat similarly as generic algorithms: they're a *way of life*; a **C++** software engineer should actively look for opportunities to use them. Initially, templates may appear to be rather complex and you might be tempted to turn your back on them. However, over time their strengths and benefits are more and more appreciated. Eventually you'll be able to recognize opportunities for using templates. That's the time where your efforts should no longer focus on constructing ordinary functions and classes (i.e., functions or classes that are not templates), but on constructing templates.

This chapter starts by introducing *function templates*. The emphasis is on the required syntax. This chapter lays the foundation upon which the other chapter about templates are built.

20.1 Defining function templates

A function template's definition is very similar to the definition of a normal function. A function template has a function head, a function body, a return type, possibly overloaded definitions, etc.. However, different from ordinary functions, function templates always use one or more *formal types*: types for which almost any existing (class or primitive) type could be used. Let's have a look at a simple example. The following function `add` expects two `Type` arguments and returns their sum:

```
Type add(Type const &lvalue, Type const &rvalue)
```

```

{
    return lvalue + rvalue;
}

```

Note how closely the above function's definition follows its description: it gets two arguments, and returns its sum. Now consider what would happen if we would have defined this function for, e.g., `int` values. We would have written:

```

int add(int const &lvalue, int const &rvalue)
{
    return lvalue + rvalue;
}

```

So far, so good. However, were we to add two doubles, we would have overloaded this function:

```

double add(double const &lvalue, double const &rvalue)
{
    return lvalue + rvalue;
}

```

There is no end to the number of overloaded versions we might be forced to construct: an overloaded version for `string`, for `size_t`, for In general, we would need an overloaded version for every type supporting `operator+` and a copy constructor. All these overloaded versions of basically the same function are required because of the strongly typed nature of **C++**. Because of this, a truly generic function cannot be constructed without resorting to the template mechanism.

Fortunately, we've already seen a large part of a template function. Our initial function `add` actually is an implementation of such a function although it isn't a full template definition yet. If we would give the first `add` function to the compiler, it would produce an error message like:

```

error: 'Type' was not declared in this scope
error: parse error before 'const'

```

And rightly so, as we failed to define `Type`. The error is prevented when we change `add` into a full template definition. To do this, we look at the function's implementation and decide that `Type` is actually a *formal* typename. Comparing it to the alternate implementations, it will be clear that we could have changed `Type` into `int` to get the first implementation, and into `double` to get the second.

The full template definition allows for this formal character of the `Type` typename. Using the keyword `template`, we prefix one line to our initial definition, obtaining the following function template definition:

```

template <typename Type>
Type add(Type const &lvalue, Type const &rvalue)
{
    return lvalue + rvalue;
}

```

In this definition we distinguish:

- The keyword `template`, starting a template definition or declaration.
- The angle bracket enclosed list following `template`. This is a list containing one or more comma-separated elements. This angle bracket enclosed list is called the *template parameter list*. Template parameter lists using multiple elements could look like this:

```

typename Type1, typename Type2

```


- Inside the template parameter list we find the *formal type* name `Type`. It is a formal type name, comparable to a formal parameter name in a function's definition. Up to now we've only encountered formal variable names with functions. The *types* of the parameters were always known by the time the function was defined. Templates escalate the notion of formal names one step further up the ladder. Templates allow type names to be formalized, rather than just the variable names themselves. The fact that `Type` is a formal type name is indicated by the keyword `typename`, prefixed to `Type` in the template parameter list. A formal type name like `Type` is also called a *template type parameter*. Template non-type parameters also exist, and are shortly introduced.

Other texts on C++ sometimes use the keyword `class` where we use `typename`. So, in other texts template definitions might start with a line like:

```
template <class Type>
```

In the C++ Annotations the use of `typename` over `class` is preferred, reasoning that a template type parameter is, after all, a type name (some authors prefer `class` over `typename`; in the end it's a matter of taste).

- The `template` keyword and the template parameter list is called the .
- The function head: it is like a normal function head, albeit that the template's type parameters must be used in its parameter list. When the function is eventually called using actual arguments having actual types, these actual types are used by the compiler to infer which version (i.e., overload to fit the actual argument types) of the function template must be used. At the point where the function is called the compiler will create the function that is called, a process called *instantiation*. The function head may also use a formal type to specify its return value. This feature was actually used in the `add` template's definition.
- The function parameters are specified as `Type const &` parameters. This has the usual meaning: the parameters are references to `Type` objects or values that will not be modified by the function.
- The function body is like a normal function body. In the body the formal type names may be used to define or declare variables, which may then be used as any other local variable. But some restrictions apply. Looking at `add`'s body, it is clear that `operator+` is used, as well as a copy constructor, as the function returns a value. This allows us to formulate the following restrictions for the formal type `Type` as used by our `add` function template:

- `Type` should support `operator+`
- `Type` should support a copy constructor

Consequently, while `Type` could be a `string`, it could never be an `ostream`, as neither `operator+` nor the copy constructor are available for streams.

Normal scope rules and identifier visibility rules apply to templates. Within the template definition's scope formal type names overrule identically named identifiers of broader scopes.

Look again at the `add`'s parameters. By specifying `Type const &` rather than `Type` superfluous copying is prevented, at the same time allowing values of primitive types to be passed as arguments to the function. So, when `add(3, 4)` is called, `int(4)` will be assigned to `Type const &rvalue`. In general, function parameters should be defined as `Type const &` to prevent unnecessary copying. The compiler is smart enough to handle 'references to references' in this case, which is something the language normally does not support. For example, consider the following `main` function (here and in the following simple examples it is assumed that the template and the required headers and namespace declarations have been provided):

```
int main()
{
    size_t const &var = size_t(4);
    cout << add(var, var) << '\n';
}
```

Here `var` is a reference to a constant `size_t`. It is passed as argument to `add`, thereby initializing `lvalue` and `rvalue` as `Type const &` to `size_t const &` values. The compiler interpreting `Type` as `size_t`. Alternatively, the parameters might have been specified using `Type &`, rather than `Type const &`. The disadvantage of this (non-const) specification being that temporary values cannot be passed to the function anymore. The following therefore fails to compile:

```
int main()
{
    cout << add(string("a"), string("b")) << '\n';
}
```

Here, a `string const &` cannot be used to initialize a `string &`. If `add` would define `Type &&` parameters the above program *would* compile just fine. In addition the following will compile as the compiler decides that `Type` apparently is a `string const`:

```
int main()
{
    string const &s = string("a");
    cout << add(s, s) << '\n';
}
```

What can we deduce from these examples?

- In general, function parameters should be specified as `Type const &` parameters to prevent unnecessary copying.
- The template mechanism is fairly flexible. It will interpret formal types as plain types, const types, pointer types, etc., depending on the actually provided types. The rule of thumb is that the formal type is used as a generic mask for the actual type, with the formal type name covering whatever part of the actual type must be covered. Some examples, assuming the parameter is defined as `Type const &`:

argument type	Type ==
<code>size_t const</code>	<code>size_t</code>
<code>size_t</code>	<code>size_t</code>
<code>size_t *</code>	<code>size_t *</code>
<code>size_t const *</code>	<code>size_t const *</code>

As a second example of a function template, consider the following function template:

```
template <typename Type, size_t Size>
Type sum(Type const (&array)[Size])
{
    Type tp = Type();

    for (size_t idx = 0; idx < Size; idx++)
        tp += array[idx];

    return tp;
}
```

This template definition introduces the following new concepts and features:

- The *template parameter list*. This template parameter list has two elements. The first element is a well-known template type parameter, but the second element has a very specific type: a `size_t`. Template parameters of specific (i.e., non-formal) types used in template parameter lists are called *template non-type parameters*. A template non-type parameter defines the type of a constant expression, which must be known by the time the template is instantiated and which is specified in terms of existing types, such as a `size_t`.

- Looking at the function's head, we see one parameter:

```
Type const (&array)[Size]
```

This parameter defines `array` as a reference to an array having `Size` elements of type `Type` that may not be modified.

- In the parameter definition, both `Type` and `Size` are used. `Type` is of course the template's type parameter `Type`, but `Size` is also a template parameter. It is a `size_t`, whose value must be inferable by the compiler when it compiles an actual call of the `sum` function template. Consequently, `Size` must be a `const` value. Such a constant expression is called a *template non-type parameter*, and its type is named in the template's parameter list.
- When the function template is called, the compiler must be able to infer not only `Type`'s concrete value, but also `Size`'s value. Since the function `sum` only has one parameter, the compiler is only able to infer `Size`'s value from the function's actual argument. It can do so if the provided argument is an array (of known and fixed size) rather than a pointer to `Type` elements. So, in the following `main` function the first statement will compile correctly but the second statement will not:

```
int main()
{
    int values[5];
    int *ip = values;

    cout << sum(values) << '\n';    // compiles OK
    cout << sum(ip) << '\n';        // won't compile
}
```

- Inside the function's body the statement `Type tp = Type()` is used to initialize `tp` to a default value. Note here that no fixed value (like 0) is used. Any type's default value may be obtained using its default constructor rather than using a fixed numeric value. Of course, not every class accepts a numeric value as an argument to one of its constructors. But all types, even the primitive types, support default constructors (actually, some classes do not implement a default constructor, or make it inaccessible; but most do). The default constructor of primitive types will initialize their variables to 0 (or false). Furthermore, the statement `Type tp = Type()` is a true initialization: `tp` is initialized by `Type`'s default constructor, rather than using `Type`'s copy constructor to assign `Type`'s copy to `tp`.

It's interesting to note here (although not directly related to the current topic) that the syntactic construction `Type tp(Type())` *cannot* be used, even though it also looks like a proper initialization. Usually an initializing argument can be provided to an object's definition, like `string s("hello")`. Why, then, is `Type tp = Type()` accepted, whereas `Type tp(Type())` isn't? When `Type tp(Type())` is used it won't result in an error message. So we don't immediately detect that it's *not* a `Type` object's default initialization. Instead, the compiler will start generating error messages once `tp` is used. This is caused by the fact that in **C++** (and in **C** alike) the compiler will do its best to recognize a function or function pointer whenever possible: the *function prevalence rule*. According to this rule `Type()` is (because of the pair of parentheses) interpreted as a *pointer to a function* expecting no arguments; returning a `Type`. It will do so unless the compiler clearly is unable to do so. In the initialization `Type tp = Type()` it *can't* see a pointer to a function as a `Type` object cannot be given the value of a function pointer (remember: `Type()` is interpreted as `Type (*)()` whenever possible). But in `Type tp(Type())` it *can* use the pointer interpretation: `tp` is now *declared* as a *function* expecting a pointer to a function returning a `Type`, with `t` itself also returning a `Type`. E.g., `t` could have been defined as:

```
Type t(Type (*tp)())
{
    return (*tp)();
}
```

- Comparable to the first function template, `sum` also assumes the existence of certain public members in `Type`'s class. This time `operator+=` and `Type`'s copy constructor.

Like class definitions, template definitions should not contain `using` directives or declarations: the template might be used in a situation where such a directive overrides the programmer's intentions: ambiguities or other conflicts may result from the template's author and the programmer using different `using` directives (E.g, a `cout` variable defined in the `std` namespace and in the programmer's own namespace). Instead, within template definitions only fully qualified names, including all required namespace specifications should be used.

20.1.1 Late-specified return type (C++0x, 4.4)

Traditional C++ requires function templates to specify their return type or to specify the return type as a template type parameter. Consider the following function:

```
int add(int lhs, int rhs)
{
    return lhs + rhs;
}
```

The above function may be converted to a template function:

```
template <typename Lhs, typename Rh>
Lhs add(Lhs lhs, Rh rhs)
{
    return lhs + rhs;
}
```

Unfortunately, when the template function is called as

```
add(3, 3.4)
```

the intended return type is probably a `double` rather than an `int`. This can be solved by adding an additional template type parameter specifying the return type but then that type must explicitly be specified:

```
add<double>(3, 3.4);
```

Using `decltype` (cf. section 3.3.6) to define the return type won't work as `lhs` and `rhs` aren't known to the compiler by the time `decltype` is used. Thus the next attempt to get rid of the additional template type parameter will fail to compile:

```
template <typename Lhs, typename Rh>
decltype(lhs + rhs) add(Lhs lhs, Rh rhs)
{
    return lhs + rhs;
}
```

The `decltype`-based definition of a function's return type may become fairly complex. To reduce the complexities the C++0x standard provides the *late-specified return type* syntax that *does* allow the use of `decltype` to define a function's return type. It is primarily used with template functions but it may also be used for non-template functions:

```
template <typename Lhs, typename Rh>
auto add(Lhs lhs, Rh rhs) -> decltype(lhs + rhs)
{
    return lhs + rhs;
}
```

When this function is used in a statement like `cout << add(3, 3.4)` the resulting value will be 6.4, which is most likely the intended result, rather than 6. As an example how a late-specified return type may reduce the complexity of a function's return type definition consider the following:

```
template <class T, class U>
decltype((*(&T)0)+(*(&U)0)) add(T t, U u);
```

Using a late-specified return type we get the equivalent:

```
template <class T, class U>
auto add(T t, U u) -> decltype(t+u);
```

which most people think is easier to read.

The expression specified with `decltype` does not necessarily use the parameters `lhs` and `rhs` themselves. In the next function definition `lhs.length` is used instead of `lhs` itself:

```
template <typename Class, typename Rhs>
auto add(Class lhs, Rhs rhs) -> decltype(lhs.length() + rhs)
{
    return lhs.length() + rhs;
}
```

Any variable visible at the time `decltype` is compiled can be used in the `decltype` expression. However, it is currently not possible to handle member selection through pointers to members. The following code aims at specifying the address of a member function as `add`'s first argument and then use its return value type to determine the template function's return type:

```
std::string global;

template <typename MEMBER, typename RHS>
auto add(MEMBER mem, RHS rhs) -> decltype((global.*mem)() + rhs)
{
    return (global.*mem)() + rhs;
}
```

Although the above function compiles fine, it cannot currently be used as it results in a compiler error message like *unimplemented: mangling dotstar_expr* (generated for a statement like `cout << add(&string::length, 3.4)`).

20.2 Passing arguments by reference (reference wrappers) (C++0x)

Before using the reference wrappers discussed in this section the `<functional>` header file must have been included.

Situations exist where the compiler is unable to infer that a reference rather than a value is passed to a template function. In the following example the template function `outer` receives `int x` as its argument and the compiler will dutifully infer that `Type` is `int`:

```
template <typename Type>
void outer(Type t)
{
    t.x();
}

void useInt()
```

```

{
    int arg;
    outer(arg);
}

```

Compilation will of course fail and the compiler nicely reports the inferred type, e.g.:

```
In function 'void outer(Type) [with Type = int]': ...
```

Unfortunately the same error is generated when using `call` in the next example. The function `call` is a template expecting a function that takes an argument which is then itself modified, and a value to pass on to that function. Such a function is, e.g., `sqrtArg` expecting a reference to a double, which is modified by calling `std::sqrt`.

```

void sqrtArg(double &arg)
{
    arg = sqrt(arg);
}
template<typename Fun, typename Arg>
void call(Fun fun, Arg arg)
{
    fun(arg);
    cout << "In call: arg = " << arg << '\n';
}

```

Assuming `double value = 3` then `call(sqrtArg, value)` will not modify `value` as the compiler infers `Arg` to be `double` and hence passes `value` by value.

To have `value` itself changed the compiler must be informed that `value` must be passed by reference. Note that it might not be acceptable to define `call`'s template argument as `Arg &` as *not* changing the actual argument might be appropriate in some situations.

The C++0x standard offers the `ref(arg)` and `cref(arg)` *reference wrappers* that take an argument and return it as a reference-typed argument. To actually change `value` it can be passed to `call` using `ref(value)` as shown in the following main function:

```

int main()
{
    double value = 3;
    call(sqrtArg, value);
    cout << "Passed value, returns: " << value << '\n';

    call(sqrtArg, ref(value));
    cout << "Passed ref(value), returns: " << value << '\n';
}
/*
Displays:
    In call: arg = 1.73205
    Passed value, returns: 3
    In call: arg = 1.73205
    Passed ref(value), returns: 1.73205
*/

```

20.3 Template parameter deduction

In this section we'll concentrate on the process by which the compiler deduces the actual types of the template type parameters. These types are deduced when a template function is called using a

process called *template parameter deduction*. As we've already seen, the compiler is able to substitute a wide range of actual types for a single formal template type parameter. Even so, not every thinkable conversion is possible. In particular when a function has multiple parameters of the same template type parameter, the compiler is very restrictive when determining what argument types will actually be accepted.

When the compiler deduces the actual types for template type parameters it will *only* consider the types of the arguments that are actually used. Neither local variables nor the function's return value is considered in this process. This is understandable. When a function is called the compiler is only certain about the types of the function template's arguments. At the point of the call it will definitely not see the types of the function's local variables. Also, the function's return value might not actually be used or may be assigned to a variable of a subrange (or super-range) type of a deduced template type parameter. So, in the following example, the compiler won't ever be able to call `fun()`, as it won't be able to deduce the actual type for the `Type` template type parameter.

```
template <typename Type>
Type fun()           // can never be called as 'fun()'
{
    return Type();
}
```

Although the compiler won't be able to handle a call to `fun()`, it is possible to call `fun()` using an explicit type specification. E.g., `fun<int>()` calls `fun`, instantiated for `int`. This is of course *not* the same as *compiler* argument deduction.

In general, when a function has multiple parameters of identical template type parameters, the actual types must be exactly the same. So, whereas

```
void binarg(double x, double y);
```

may be called using an `int` and a `double`, with the `int` argument silently being converted to a `double`, a similar function template cannot be called using an `int` and `double` argument: the compiler won't by itself promote `int` to `double` deciding that `Type` should be `double`:

```
template <typename Type>
void binarg(Type const &p1, Type const &p2)
{}

int main()
{
    binarg(4, 4.5); // ?? won't compile: different actual types
}
```

What, then, are the transformations the compiler will apply when deducing the actual types of template type parameters? It will perform only three types of parameter type transformations and a fourth one to function template non-type parameters. If it cannot deduce the actual types using these transformations, the template function will not be considered. The transformations performed by the compiler are:

- *lvalue transformations*, creating an *rvalue* from an *lvalue*;
- *qualification transformations*, inserting a `const` modifier to a non-constant argument type;
- *transformation to a base class instantiated from a class template*, using a template base class when an argument of a template derived class type was provided in the call.
- Standard transformations for function template non-type parameters. This isn't a template type parameter transformation, but it refers to any remaining template non-type parameter of function templates. For these function parameters the compiler will perform any standard conversion it has available (e.g., `int` to `size_t`, `int` to `double`, etc.).

The purpose of the various template parameter type deduction transformations is *not* to match function arguments to function parameters, but rather, having matched arguments to parameters, to determine the *actual types* of the various template type parameters.

20.3.1 Lvalue transformations

There are three types of *lvalue transformations*:

- **lvalue-to-rvalue transformations.**

An lvalue-to-rvalue transformation is applied when an rvalue is required, but an lvalue is provided. This happens when a variable is used as argument to a function specifying a *value parameter*. For example,

```
template<typename Type>
Type negate(Type value)
{
    return -value;
}
int main()
{
    int x = 5;
    x = negate(x); // lvalue (x) to rvalue (copies x)
}
```

- **array-to-pointer transformations.**

An array-to-pointer transformation is applied when the name of an array is assigned to a pointer variable. This is frequently used with functions defining pointer parameters. Such functions frequently receive arrays as their arguments. The array's address is then assigned to the pointer-parameter and its type is used to deduce the corresponding template parameter's type. For example:

```
template<typename Type>
Type sum(Type *tp, size_t n)
{
    return accumulate(tp, tp + n, Type());
}
int main()
{
    int x[10];
    sum(x, 10);
}
```

In this example, the location of the array `x` is passed to `sum`, expecting a pointer to some type. Using the array-to-pointer transformation, `x`'s address is considered a pointer value which is assigned to `tp`, deducing that `Type` is `int` in the process.

- **function-to-pointer transformations.**

This transformation is most frequently used with function templates defining a parameter which is a pointer to a function. When calling such a function the name of a function may be specified as its argument. The address of the function is then assigned to the pointer-parameter, deducing the template type parameter in the process. This is called a function-to-pointer transformation. For example:

```
#include <cmath>

template<typename Type>
void call(Type (*fp)(Type), Type const &value)
{
```



```

        (*fp)(value);
    }
    int main()
    {
        call(&sqrt, 2.0);
    }

```

In this example, the address of the `sqrt` function is passed to `call`, expecting a pointer to a function returning a `Type` and expecting a `Type` for its argument. Using the function-to-pointer transformation, `sqrt`'s address is assigned to `fp`, deducing that `Type` is `double` in the process. The argument `2.0` could not have been specified as `2` as there is no `int sqrt(int)` prototype. Furthermore, the function's first parameter specifies `Type (*fp)(Type)`, rather than `Type (*fp)(Type const &)` as might have been expected from our previous discussion about how to specify the types of function template's parameters, preferring references over values. However, `fp`'s argument `Type` is not a function template parameter, but a parameter of the function `fp` points to. Since `sqrt` has prototype `double sqrt(double)`, rather than `double sqrt(double const &)`, `call`'s parameter `fp` *must* be specified as `Type (*fp)(Type)`. It's that strict.

20.3.2 Qualification transformations

A *qualification transformation* adds `const` or `volatile` qualifications to *pointers*. This transformation is applied when the function template's type parameter explicitly specifies `const` (or `volatile`) but the function's argument isn't a `const` or `volatile` entity. In that case `const` or `volatile` is provided by the compiler. Subsequently the compiler deduces the template's type parameter. For example:

```

template<typename Type>
Type negate(Type const &value)
{
    return -value;
}
int main()
{
    int x = 5;
    x = negate(x);
}

```

Here we see the function template's `Type const &value` parameter: a reference to a `const Type`. However, the argument isn't a `const int`, but an `int` that can be modified. Applying a qualification transformation, the compiler adds `const` to `x`'s type, and so it matches `int const x`. This is then matched against `Type const &value` allowing the compiler to deduce that `Type` must be `int`.

20.3.3 Transformation to a base class

Although the *construction* of class templates is the topic of chapter 21 class templates have already extensively been *used* earlier. For example, abstract containers (cf. chapter 12) are defined as class templates. Class templates can, like ordinary classes, participate in the construction of class hierarchies.

In section 21.10 it is shown how a class template can be derived from another class template.

As class template derivation remains to be covered, the following discussion is necessarily somewhat premature. The reader may of course skip briefly to section 21.10 returning back to this section thereafter.

In this section it should be assumed, for the sake of argument, that a class template `Vector` has somehow been derived from a `std::vector`. Furthermore, assume that the following function template has been constructed to sort a vector using some function object `obj`:

```
template <typename Type, typename Object>
void sortVector(std::vector<Type> vect, Object const &obj)
{
    sort(vect.begin(), vect.end(), obj);
}
```

To sort `std::vector<string>` objects case-insensitively, a class `Caseless` could be constructed as follows:

```
class CaseLess
{
public:
    bool operator()(std::string const &before,
                   std::string const &after) const
    {
        return strcasecmp(before.c_str(), after.c_str()) < 0;
    }
};
```

Now various vectors may be sorted using `sortVector()`:

```
int main()
{
    std::vector<string> vs;
    std::vector<int> vi;

    sortVector(vs, CaseLess());
    sortVector(vi, less<int>());
}
```

Applying the transformation *transformation to a base class instantiated from a class template*, the function template `sortVectors()` may now also be used to sort `Vector` objects. For example:

```
int main()
{
    Vector<string> vs;      // 'Vector' instead of 'std::vector'
    Vector<int> vi;

    sortVector(vs, CaseLess());
    sortVector(vi, less<int>());
}
```

In this example, `Vectors` were passed as argument to `sortVector`. Applying the transformation to a base class instantiated from a class template, the compiler considers `Vector` to be a `std::vector` enabling it to deduce the template's type parameter. A `std::string` for the `Vector` `vs`, an `int` for `Vector` `vi`.

20.3.4 The template parameter deduction algorithm

The compiler uses the following algorithm to deduce the actual types of its template type parameters:

- In turn, the function template's parameters are identified using the arguments of the called function.

- For each template parameter used in the function template's parameter list, the template type parameter is associated with the corresponding argument's type (e.g., `Type` is `int` if the argument is `int x`, and the function's parameter is `Type &value`).
- While matching the argument types to the template type parameters, the three allowed transformations (see section 20.3) for template type parameters are applied where necessary.
- If identical template type parameters are used with multiple function parameters, the deduced template types must exactly match. So, the next function template cannot be called with an `int` and a `double` argument:

```
template <typename Type>
Type add(Type const &lvalue, Type const &rvalue)
{
    return lvalue + rvalue;
}
```

When calling this function template, two identical types must be used (albeit that the three standard transformations are of course allowed). If the template deduction mechanism does not come up with identical actual types for identical template types, then the function template will not be instantiated.

20.3.5 Template type contractions

With function templates the combination of the types of template arguments and template parameters shows some interesting contractions. What happens, for example if a template type parameter is specified as an rvalue reference but an lvalue reference argument type is provided?

In such cases the compiler performs type contractions. Doubling identical reference types results in a simple contraction: the type is deduced to be a single reference type. Example: if the template parameter type is specified as a `Type &&` and the actual parameter is an `int &&` then `Type` is deduced to be an `int`, rather than an `int &&`.

This is fairly intuitive. But what happens if the actual type is `int &`? There is no such thing as an `int & ¶m` and so the compiler contracts the double reference by removing the rvalue reference, keeping the lvalue reference. Here a simple rule is followed: Any reference to an lvalue reference results in an lvalue reference and *vice versa*: an lvalue to any reference also results in an lvalue:

- if `Type` is `Actual &` then `Type &` is `Actual &` and `Type == Actual`;
- if `Type` is `Actual &` then `Type &&` still is `Actual &` and `Type == Actual`;
- if `Type` is `Actual &&` then `Type &` again is `Actual &` and `Type == Actual`;
- if `Type` is `Actual &&` then `Type &&` is `Actual &&` and `Type == Actual`;

Let's look at a concrete example where contraction occurs. Consider the following template function where a function parameter is defined as an rvalue reference to some template type parameter:

```
template <typename Type>
void function(Type &&param)
{
    callee(static_cast<Type &&>(param));
}
```

In this situation, when `function` is called with an (lvalue) argument of type `TP` & the template type parameter `Type` is deduced to be `TP &`. Therefore, `param` is considered to be instantiated as `TP ¶m` (as `TP & &¶m`) is contracted as `TP ¶m`. But with an rvalue typed argument (`TP &&`) it results in `TP &¶m` (again using contraction).

Likewise, when `callee` is called using the `static_cast` the same contraction occurs, so if `Type &¶m` is interpreted as `Tp ¶m` the static cast *also* uses type `Tp ¶m`. If `(Type &¶m)` is interpreted as `Tp &¶m` the static cast *also* uses type `Tp &¶m`.

This characteristics allows us to pass a function argument straight through to a nested function *without* changing its type: lvalues remain lvalues, rvalues remain rvalues. This characteristic is therefore also known as *perfect forwarding* which will be discussed in greater detail in section 21.5.2. Perfect forwarding prevents the template author from having to define multiply overloaded versions of a function template.

20.4 Declaring function templates

Up to now, we've only defined function templates. There are various consequences of including function template definitions in multiple source files, none of them serious, but worth knowing.

- Like class interfaces, template definitions are usually included in header files. Every time a header file containing a template definition is read by the compiler it must process the full definition. It must do so even if it does not actually use the template. This will relatively slow-down the compilation. For example, compiling a template header file like `algorithm` on my old laptop takes about four times the amount of time it takes to compile a plain header file like `cmath`. The header file `iostream` is even harder to process, requiring almost 15 times the amount of time it takes to process `cmath`. Clearly, processing templates is serious business for the compiler. On the other hand this drawback shouldn't be taken too seriously. Compilers are continuously improving their template processing capacity and computers keep getting faster and faster. What was a nuisance a few years ago is hardly noticeable today.
- Every time a function template is instantiated, its code appears in the resulting object module. However, if multiple instantiations of a template using the same actual types for its template parameter exist in multiple object files the *one definition rule* is lifted. The linker will weed out superfluous instantiations (i.e., identical definitions of instantiated templates). In the final program only one instantiation for a particular set of actual template type parameters will remain (see section 20.5 for an illustration). Therefore, the linker will have an additional task to perform (*viz.* weeding out multiple instantiations), which somewhat slows down the linking process.
- Sometimes the definitions themselves are *not*, but references or pointers to the templates *are* required. Requiring the compiler to process the full template definitions in those cases will needlessly slow down the compilation process.
- In the context of *template meta programming* (see chapter 22) it is sometimes not even required to provide a template implementation. Instead, only *specializations* (cf. section 20.8) are created which are based upon the mere *declaration*.

So in some contexts template *definitions* may not be required. Instead the software engineer may opt to *declare* a template rather than to include the template's definition time and again in various source files.

When templates are declared, the compiler does not have to process the template's definitions again and again; and no instantiations will be created on the basis of template declarations alone. Any actually required instantiation must then be available elsewhere (of course, this holds true for declarations in general). Unlike the situation we encounter with ordinary functions, which are usually stored in libraries, it is currently not possible to store templates in libraries (although the compiler may construct *precompiled header files*). Consequently, using template declarations puts a burden on the shoulders of the software engineer, who has to make sure that the required instantiations exist. Below a simple way to accomplish that is introduced.

To create a function template declaration simply replace the function's body by a semicolon. Note that this is exactly identical to the way ordinary function declarations are constructed. So, the previously defined function template `add` can simply be declared as

```
template <typename Type>
Type add(Type const &lvalue, Type const &rvalue);
```

We've already encountered template declarations. The header file `iosfwd` may be included in sources not requiring instantiations of elements from the class `ios` and its derived classes. For example, to compile the *declaration*

```
std::string getCsvLine(std::istream &in, char const *delim);
```

it is not necessary to include the `string` and `istream` header files. Rather, a single

```
#include <iosfwd>
```

is sufficient. Processing `iosfwd` requires only a fraction of the time it takes to process the `string` and `istream` header files.

20.4.1 Instantiation declarations

If declaring function templates speeds up the compilation and the linking phases of a program, how can we make sure that the required instantiations of the function templates will be available when the program is eventually linked together?

For this a variant of a template declaration is available, a so-called *explicit instantiation declaration*. An explicit instantiation declaration consists of the following elements:

- It starts with the keyword `template`, omitting the template parameter list.
- Next the function template's return type and name are specified.
- The function template's name is followed by a *type specification list*. A type specification list is an angle brackets enclosed list of type names. Each type specifies the actual type of the corresponding template type parameter in the template's parameter list.
- Finally the function template's parameter list is specified, terminated by a semicolon.

Although this is a declaration, it is understood by the compiler as a request to instantiate that particular variant of the function template.

Using explicit instantiation declarations all instantiations of template functions required by a program can be collected in one file. This file, which should be a normal *source* file, should include the template definition header file and should subsequently specify the required explicit instantiation declarations. Since it's a source file, it will not be included by other sources. So namespace using directives and declarations may safely be used once the required headers have been included. Here is an example showing the required instantiations for our earlier `add` function template, instantiated for `double`, `int`, and `std::string` types:

```
#include "add.h"
#include <string>
using namespace std;

template int add<int>(int const &lvalue, int const &rvalue);
template double add<double>(double const &lvalue, double const &rvalue);
template string add<string>(string const &lvalue, string const &rvalue);
```

If we're sloppy and forget to mention an instantiation required by our program then the repair is easily made by adding the missing instantiation declaration to the above list. After recompiling the file and relinking the program we're done.

20.5 Instantiating function templates

Different from an ordinary function that results in code once the compiler reads its definition a template is not instantiated when its definition is read. A template is merely a *recipe* telling the compiler how to create particular code once it's time to do so. It's indeed very much like a recipe in a cooking book. You reading how to bake a cake doesn't mean you have actually baked that cake by the time you've read the recipe.

So, when is a function template actually instantiated? There are two situations where the compiler decides to instantiate templates:

- They are instantiated when they are used (e.g., the function `add` is called with a pair of `size_t` values);
- When addresses of function templates are taken they are instantiated. Example:

```
char (*addptr)(char const &, char const &) = add;
```

The location of statements causing the compiler to instantiate a template is called the template's *point of instantiation*. The point of instantiation has serious implications for the function template's code. These implications are discussed in section [20.11](#).

The compiler is not always able to deduce the template's type parameters unambiguously. When the compiler reports an ambiguity it must be solved by the software engineer. Consider the following code:

```
#include <iostream>
#include "add.h"

size_t fun(int (*f)(int *p, size_t n));
double fun(double (*f)(double *p, size_t n));

int main()
{
    std::cout << fun(add);
}
```

When this little program is compiled, the compiler reports an ambiguity it cannot resolve. It has two candidate functions as for each overloaded version of `fun` an `add` function can be instantiated:

```
error: call of overloaded 'fun(<unknown type>)' is ambiguous
note: candidates are: int fun(size_t (*)(int*, size_t))
note:                  double fun(double (*)(double*, size_t))
```

Such situations should of course be avoided. Function templates can only be instantiated if there's no ambiguity. Ambiguities arise when multiple functions emerge from the compiler's function selection mechanism (see section [20.9](#)). It is up to us to resolve the ambiguities. They *could* be resolved using a blunt `static_cast` (by which we select among alternatives, all of them possible and available):

```
#include <iostream>
#include "add.h"

int fun(int (*f)(int const &lvalue, int const &rvalue));
double fun(double (*f)(double const &lvalue, double const &rvalue));

int main()
{
    std::cout << fun(
```

```

        static_cast<int (*)(int const &, int const &)>(add)
    );
}

```

But it's good practice to avoid type casts wherever possible. How to do this is explained in the next section (20.6).

As mentioned in section 20.4, the linker removes identical instantiations of a template from the final program, leaving only one instantiation for each unique set of actual template type parameters. To illustrate the linker's behavior we do as follows:

- First we construct several source files:

- `source1.cc` defines a function `fun`, instantiating `add` for `int`-type arguments, including `add`'s template definition. It displays `add`'s address:

```

union PointerUnion
{
    int (*fp)(int const &, int const &);
    void *vp;
};

#include <iostream>
#include "add.h"
#include "pointerunion.h"

void fun()
{
    PointerUnion pu = { add };

    std::cout << pu.vp << '\n';
}

```

- `source2.cc` defines the same function, but merely declares the proper `add` template using a template declaration (*not* an instantiation declaration). Here is `source2.cc`:

```

#include <iostream>
#include "pointerunion.h"

template<typename Type>
Type add(Type const &, Type const &);

void fun()
{
    PointerUnion pu = { add };

    std::cout << pu.vp << '\n';
}

```

- `main.cc` again includes `add`'s template definition, declares the function `fun` and defines `main`, defining `add` for `int`-type arguments as well and displaying `add`'s function address. It also calls the function `fun`. Here is `main.cc`:

```

#include <iostream>
#include "add.h"
#include "pointerunion.h"

void fun();

int main()
{
    PointerUnion pu = { add };
}

```



```

    fun();
    std::cout << pu.vp << '\n';
}

```

- All sources are compiled to object modules. Note the different sizes of `source1.o` (1912 bytes using `g++` version 4.3.4. All sizes reported here may differ somewhat for different compilers and/or run-time libraries) and `source2.o` (1740 bytes). Since `source1.o` contains the instantiation of `add`, it is somewhat larger than `source2.o`, containing only the template's declaration. Now we're ready to start our little experiment.
- Linking `main.o` and `source1.o`, we obviously link together two object modules, each containing its own instantiation of the same template function. The resulting program produces the following output:

```

0x80486d8
0x80486d8

```

Furthermore, the size of the resulting program is 6352 bytes.

- Linking `main.o` and `source2.o`, we now link together an object module containing the instantiation of the `add` template, and another object module containing the mere declaration of the same template function. So, the resulting program cannot but contain a single instantiation of the required function template. This program has exactly the same size, and produces exactly the same output as the first program.

From our little experiment we conclude that the linker indeed removes identical template instantiations from a final program. Furthermore we conclude that using mere template declarations does not result in template instantiations.

20.6 Using explicit template types

In the previous section we saw that the compiler may encounter ambiguities when attempting to instantiate a template. In an example overloaded versions of a function (`fun`) existed, expecting different types of arguments. The ambiguity resulted from the fact that both arguments could have been provided by an instantiation of a function template. The intuitive way to solve such an ambiguity is to use a `static_cast`. But casts should be avoided wherever possible.

With function templates static casts may indeed be avoided using *explicit template type arguments*. Explicit template type arguments can be used to inform the compiler about the actual types it should use when instantiating a template. To use explicit type arguments the function's name is followed by an *actual template type argument list* which may again be followed by the function's argument list. The actual types mentioned in the actual template argument list are used by the compiler to 'deduce' what types to use when instantiating the template. Here is the example from the previous section, now using explicit template type arguments:

```

#include <iostream>
#include "add.h"

int fun(int (*f)(int const &lvalue, int const &rvalue));
double fun(double (*f)(double const &lvalue, double const &rvalue));

int main()
{
    std::cout << fun(add<int>) << '\n';
}

```


Explicit template type arguments can be used in situations where the compiler has no way to detect which types should actually be used. E.g., in section 20.3 the function template `Type fun()` was defined. To instantiate this function for the `double` type, we can call `fun<double>()`.

20.7 Overloading function templates

Let's once again look at our `add` template. That template was designed to return the sum of two entities. If we would want to compute the sum of three entities, we could write:

```
int main()
{
    add(add(2, 3), 4);
}
```

This is an acceptable solution for the occasional situation. However, if we would have to add three entities regularly, an *overloaded* version of the `add` function expecting three arguments might be a useful function to have. There's a simple solution to this problem: function templates may be overloaded.

To define an overloaded function template, merely put multiple definitions of the template in its header file. For the `add` function this would boil down to:

```
template <typename Type>
Type add(Type const &lvalue, Type const &rvalue)
{
    return lvalue + rvalue;
}
template <typename Type>
Type add(Type const &lvalue, Type const &mvalue, Type const &rvalue)
{
    return lvalue + mvalue + rvalue;
}
```

The overloaded function does not have to be defined in terms of simple values. Like all overloaded functions, a unique set of function parameters is enough to define an overloaded function template. For example, here's an overloaded version that can be used to compute the sum of the elements of a vector:

```
template <typename Type>
Type add(std::vector<Type> const &vect)
{
    return accumulate(vect.begin(), vect.end(), Type());
}
```

When overloading function templates we do not have to restrict ourselves to the function's parameter list. The template's type parameter list itself may also be overloaded. The last definition of the `add` template allows us to specify a `vector` as its first argument, but no `deque` or `map`. Overloaded versions for those types of containers could of course be constructed, but how far should we go? A better approach seems to be to look for common characteristics of these containers. If found we may be able to define an overloaded function template based on these common characteristics. One common characteristic of the mentioned containers is that they all support `begin` and `end` members, returning iterators. Using this, we could define a template type parameter representing containers that must support these members. But mentioning a plain 'container type' doesn't tell us for what type of data it was instantiated. So we need a second template type parameter representing the container's data type, thus overloading the template's type parameter list. Here is the resulting overloaded version of the `add` template:

```
template <typename Container, typename Type>
```

```
Type add(Container const &cont, Type const &init)
{
    return std::accumulate(cont.begin(), cont.end(), init);
}
```

One may wonder whether the `init` parameter could not be left out of the parameter list as `init` will often have a default initialization value. The answer is a somewhat complex ‘yes’. It is possible to define the `add` function as follows:

```
template <typename Type, typename Container>
Type add(Container const &cont)
{
    return std::accumulate(cont.begin(), cont.end(), Type());
}
```

But note that the template’s type parameters were reordered, which is necessary because the compiler won’t be able to determine `Type` in a call like:

```
int x = add(vectorOfInts);
```

After reordering the template type parameters, putting `Type` first, an explicit template type argument can be provided for the first template type parameter:

```
int x = add<int>(vectorOfInts);
```

In this example we provided a `vector<int>` argument. One might wonder why we have to specify `int` explicitly to allow the compiler to determine the template type parameter `Type`. In fact, we don’t. A third kind of template parameter exists, a *template template parameter*, allowing the compiler to determine `Type` directly from the actual container argument. Template template parameters are discussed in section 22.3.

With all these overloaded versions in place, we may now start the compiler to compile the following function:

```
using namespace std;

int main()
{
    vector<int> v;

    add(3, 4);           // 1 (see text)
    add(v);              // 2
    add(v, 0);           // 3
}
```

- In statement 1 the compiler recognizes two identical types, both `int`. It will therefore instantiate `add<int>`, our very first definition of the `add` template.
- In statement 2 a single argument is used. Consequently, the compiler looks for an overloaded version of `add` requiring but one argument. It finds the overloaded function template expecting a `std::vector`, deducing that the template’s type parameter must be `int`. It instantiates

```
add<int>(std::vector<int> const &)
```

- In statement 3 the compiler again encounters an argument list having two arguments. However, this time the types of the arguments aren’t equal, so `add` template’s first definition can’t be used. But it *can* use the last definition, expecting entities having different types. As a `std::vector` supports `begin` and `end`, the compiler is now able to instantiate the function template

```
add<std::vector<int>, int>(std::vector<int> const &, int const &)
```

Having defined the add function template for two equal and two different template type parameters we've exhausted the possibilities for using an add function template having two template type parameters.

Although it is possible to define another function template add this will introduce an ambiguity as the compiler won't be able to choose which of the two overloaded versions defining two differently typed function parameters to use. For example when defining:

```
#include "add.h"

template <typename T1, typename T2>
T1 add(T1 const &lvalue, T2 const &rvalue)
{
    return lvalue + rvalue;
}
int main()
{
    add(3, 4.5);
}
```

the compiler will report an ambiguity like the following:

```
error: call of overloaded 'add(int, double)' is ambiguous
error: candidates are: Type add(const Container&, const Type&)
                        [with Container = int, Type = double]
error:                  T1 add(const T1&, const T2&)
                        [with T1 = int, T2 = double]
```

Now recall the overloaded function template accepting three arguments:

```
template <typename Type>
Type add(Type const &lvalue, Type const &mvalue, Type const &rvalue)
{
    return lvalue + mvalue + rvalue;
}
```

It may be considered as a disadvantage that only equally typed arguments are accepted by this function (three ints, three doubles, etc.). To remedy this we define yet another overloaded function template, this time accepting arguments of any type. This function template can only be used if operator+ is defined between the function's actually used types, but apart from that there appears to be no problem. Here is the overloaded version accepting arguments of any type:

```
template <typename Type1, typename Type2, typename Type3>
Type1 add(Type1 const &lvalue, Type2 const &mvalue, Type3 const &rvalue)
{
    return lvalue + mvalue + rvalue;
}
```

Now that we've defined the above two overloaded function templates expecting three arguments let's call add as follows:

```
add(1, 2, 3);
```

Should we expect an ambiguity here? After all, the compiler might select the former function, deducing that `Type == int`, but it might also select the latter function, deducing that `Type1 == int`, `Type2 == int` and `Type3 == int`. Remarkably, the compiler reports no ambiguity.

No ambiguity is reported because of the following. If overloaded template functions are defined using *less* and *more* specialized template type parameters (e.g., less specialized: all types different vs. more specialized: all types equal) then the compiler selects the more specialized function whenever possible.

As a rule of thumb: overloaded function templates must allow a unique combination of template type arguments to be specified to prevent ambiguities when selecting which overloaded function template to instantiate. The *ordering* of template type parameters in the function template's type parameter list is not important. E.g., trying to instantiate one of the following function templates results in an ambiguity:

```
template <typename T1, typename T2>
void binarg(T1 const &first, T2 const &second)
{
}
template <typename T1, typename T2>
void binarg(T2 const &first, T1 const &second)
{
}
```

This should not come as a surprise. After all, template type parameters are just formal names. Their names (T1, T2 or Whatever) have no concrete meanings.

Like any function overloaded functions may also be declared, either using plain declarations or instantiation declarations. Explicit template argument types may also be used. Example:

- To declare a function template add accepting certain containers:

```
template <typename Container, typename Type>
Type add(Container const &container, Type const &init);
```

- to use an instantiation declaration (in which case the compiler must already have seen the template's definition):

```
template int add<std::vector<int>, int>
(std::vector<int> const &vect, int const &init);
```

- to use explicit template type arguments:

```
std::vector<int> vi;
int sum = add<std::vector<int>, int>(vi, 0);
```

20.8 Specializing templates for deviating types

The initial add template, defining two identically typed parameters works fine for all types supporting `operator+` and a copy constructor. However, these assumptions are not always met. For example, when using `char *s` using `operator+` or a 'copy constructor' does not make sense. The compiler will first try to instantiate the function template, but then compilation fails as `operator+` is not defined for pointers.

In such situations the compiler may be able to resolve the template type parameters but it (or we ...) may then detect that the standard implementation is pointless or produces errors.

To solve this problem a *template explicit specialization* may be defined. A template explicit specialization defines the function template for which a generic definition already exists using specific actual template type parameters. As we saw in the previous section the compiler will always prefer a more specialized function over a less specialized one. So the template explicit specialization will be selected whenever possible.

A template explicit specialization may offer a specialization for its template type parameter(s). The special type will then consistently be substituted for the template type parameter in all of the template

function's code. For example if the explicitly specialized type is `char const *` then in the template definition

```
template <typename Type>
Type add(Type const &lvalue, Type const &rvalue)
{
    return lvalue + rvalue;
}
```

Type must be replaced by `char const *`, resulting in a function having prototype

```
char const *add(char const *const &lvalue, char const * const &rvalue);
```

Now we try to use this function:

```
int main(int argc, char **argv)
{
    add(argv[0], argv[1]);
}
```

However, the compiler ignores our specialization and tries to instantiate the initial function template. This fails leaving us wondering why it didn't select the explicit specialization....

To see what happened here we replay, step by step, the compiler's actions:

- `add` is called with `char *` arguments.
- Both types are equal, so the compiler deduces that `Type` equals `char *`.
- Now it inspects the specialization. Can a `char *` template type argument match a `char const *const &` template parameter? Here opportunities for the allowable transformations from section 20.3 may arise. A qualification transformation seems to be the only viable one, allowing the compiler to bind a `const`-parameter to a non-`const` argument.
- So, in terms of `Type` the compiler can match an argument of some `Type` or an argument of some `Type const &`.
- `Type` itself is not modified, and so `Type` is a `char *`.
- Next the compiler inspects the available explicit specializations. It finds one, specializing for `char const *`.
- Since a `char const *` is not a `char *` it rejects the explicit specialization and uses the generic form, resulting in a compilation error.

If our `add` function template should also be able to handle `char *` template type arguments another explicit specialization for `char *` may be required, resulting in the prototype

```
char *add(char *const &lvalue, char * const &rvalue);
```

Instead of defining another explicit specialization an *overloaded* function template could be designed expecting pointers. The following function template definition expects two pointers to constant `Type` values and returns a pointer to a non-constant `Type`:

```
template <typename Type>
Type *add(Type const *t1, Type const *t2)
{
    std::cout << "Pointers\n";
    return new Type;
}
```

What actual types may be bound to the above function parameters? In this case only a `Type const *`, allowing `char const *`'s to be passed as arguments. There's no opportunity for a qualification transformation here. The qualification transformation allows the compiler to add a `const` to a non-`const` argument if the parameter itself (and *not* `Type`) is specified in terms of a `const` or `const &`. Looking at, e.g., `t1` we see that it's defined as a `Type const *`. There's nothing `const` here that's referring to the parameter (in which case it would have been `Type const *const t1` or `Type const *const &t1`). Consequently a qualification transformation cannot be applied here.

As the above overloaded function template only accepts `char const *` arguments, it will not accept (without a reinterpret cast) `char *` arguments. So `main`'s `argv` elements cannot be passed to our overloaded function template.

So do we have to define yet another overloaded function template, this time expecting `Type *` arguments? It is possible, but at some point it should become clear that our approach doesn't scale. Like ordinary functions and classes, function templates should have one conceptually clear purpose. Trying to add overloaded function templates to overloaded function templates quickly turns the template into a kludge. Don't use this approach. A better approach is to construct the template so that it fits its original purpose, to make allowances for the occasional specific case and to describe its purpose clearly in its documentation.

In some situations constructing template explicit specialization may of course be defensible. Two specializations for `const` and non-`const` pointers to characters might be appropriate for our `add` function template. Here's how they are constructed:

- Start with the keyword `template`.
- Next, an empty set of angle brackets is written. This indicates to the compiler that there must be an *existing* template whose prototype matches the one we're about to define. If we err and there is no such template then the compiler reports an error like:

```
error: template-id 'add<char*>' for 'char* add(char* const&, char*
      const&)' does not match any template declaration
```

- Now the function's head is defined. It must match the prototype of the initial function template or the form of a template explicit instantiation declaration (see section 20.4.1) if its specialized type cannot be determined from the function's arguments. It must specify the correct return type, function name, maybe explicit template type arguments, as well as the function's parameter list.
- Finally the function's body is defined, providing the special implementation that is required for the specialization.

Here are two explicit specializations for the function template `add`, expecting `char *` and `char const *` arguments:

```
template <> char *add<char *>(char * const &p1,
                             char * const &p2)
{
    std::string str(p1);
    str += p2;
    return strcpy(new char[str.length() + 1], str.c_str());
}

template <> char const *add<char const *>(char const *const &p1,
                                          char const *const &p2)
{
    static std::string str;
    str = p1;
    str += p2;
    return str.c_str();
}
```

Template explicit specializations are normally included in the file containing the other function template's implementations.

Template explicit specializations can be declared in the usual way. I.e., by replacing its body with a semicolon.

When *declaring* a template explicit specialization the pair of angle brackets following the `template` keyword are essential. If omitted, we would have constructed a template instantiation declaration. The compiler would silently process it, at the expense of a somewhat longer compilation time.

When declaring a template explicit specialization (or when using an instantiation declaration) the explicit specification of the template type parameters can be omitted if the compiler is able to deduce these types from the function's arguments. As this is the case with the `char (const) *` specializations, they could also be declared as follows:

```
template <> char *add(char * const &p1, char * const &p2)
template <> char const *add(char const *const &p1,
                           char const *const &p2);
```

If in addition `template <>` could be omitted the template character would be removed from the declaration. The resulting declaration is now a mere function declaration. This is not an error: template functions and non-function templates may mutually overload each other. Ordinary functions are not as restrictive as function templates with respect to allowed type conversions. This could be a reason to overload a template with an ordinary function every once in a while.

A function template explicit specialization is not just another overloaded version of the the function template. Whereas an overloaded version may define a completely different set of template parameters, a specialization must use the same set of template parameters as its non-specialized variant. The compiler uses the specialization in situations where the actual template arguments match the types defined by the specialization (following the rule that the most specialized set of parameters matching a set of arguments will be used). For different sets of parameters overloaded versions of functions (or function templates) must be used.

Now that we've covered explicit specializations and overloading let's consider what happens when a class defines a `std::string` conversion operator (cf. section 10.3). A conversion operator is guaranteed to be used as an rvalue. This means that objects of a class defining a `string` conversion operator can be assigned to, e.g., `string` objects. But when trying to insert objects defining `string` conversion operators into streams then the compiler complains that we're attempting to insert an inappropriate type into an `ostream`. However, when this class defines an `int` conversion operator insertion is performed flawlessly. The reason for this distinction is that `operator<<` is defined as a plain (free) function when inserting a basic type (like `int`) but it is defined as a function template when inserting a `string`. Hence, when trying to insert an object of our class defining a `string` conversion operator the compiler visits all overloaded versions of insertion operators inserting into `ostream` objects. Since no basic type conversion is available the basic type insertion operators can't be used. Since the available conversions for template arguments do not allow the compiler to look for conversion operators our class defining the `string` conversion operator cannot be inserted into an `ostream`. If such a class should be insertable into `ostream` objects it must define its own overloaded insertion operator (in addition to the `string` conversion operator that was required to use the class's objects as rvalue in `string` assignments).

20.9 The function selection mechanism

When the compiler encounters a function call, it must decide which function to call when overloaded functions are available. Earlier we've encountered principles like 'the most specific function will be selected'. This is a fairly intuitive description of the compiler's function selection mechanism. In this section we'll have a closer look at this mechanism.

Assume we ask the compiler to compile the following `main` function:


```
int main()
{
    process(3, 3);
}
```

Furthermore assume that the compiler has encountered the following function declarations when it's about to compile main:

```
template <class T>
void process(T &t1, int i);           // 1

template <class T1, class T2>
void process(T1 const &t1, T2 const &t2); // 2

template <class T>
void process(T const &t, double d);    // 3

template <class T>
void process(T const &t, int i);       // 4

template <>
void process<int, int>(int i1, int i2); // 5

void process(int i1, int i2);          // 6

void process(int i, double d);         // 7

void process(double d, int i);         // 8

void process(double d1, double d2);    // 9

void process(std::string s, int i)     // 10

int add(int, int);                    // 11
```

The compiler, having read main's statement, must now decide which function must actually be called. It proceeds as follows:

- First, a set of *candidate functions* is constructed. This set contains all functions that:
 - are visible at the point of the call;
 - have the same names as the called function.

As function 11 has a different name, it is removed from the set. The compiler is left with a set of 10 candidate functions.

- Second, the set of *viable functions* is constructed. Viable functions are functions for which type conversions exist that can be applied to match the types of the function's parameters of the functions and the types of the actual arguments to the types of the actual arguments. This implies that at least the number of arguments must match the number of parameters of the viable functions. Function 10's first argument is a `string`. As a `string` cannot be initialized by an `int` value no appropriate conversion exists and function 10 is removed from the list of candidate functions. `double` parameters can be retained. Standard conversions *do* exist for `ints` to `doubles`, so all functions having ordinary `double` parameters can be retained. Therefore, the set of viable functions consists of functions 1 until 9.

At this point the compiler tries to determine the types of the template type parameters. It may use any of the three standard template parameter transformation procedures when trying to match actual

types to template type parameters. In this process it concludes that no type cannot be determined for the `T` in function 1's `T &t1` parameter as the argument 3 is a constant `int` value. Thus function 1 is removed from the list of viable functions. The compiler is now confronted with the following set of potentially instantiated function templates and ordinary functions:

```
void process(T1 [= int] const &t1, T2 [= int] const &t2);    // 2
void process(T [= int] const &t, double d);                // 3
void process(T [= int] const &t, int i);                   // 4
void process<int, int>(int i1, int i2);                    // 5
void process(int i1, int i2);                              // 6
void process(int i, double d);                             // 7
void process(double d, int i);                             // 8
void process(double d1, double d2);                       // 9
```

The compiler associates a *direct match count* value to each of the viable functions. The direct match count counts the number of arguments that can be matched to function parameters without an (automatic) type conversion. E.g., for function 2 this count equals 2, for function 6 it is 1 and for function 9 it is 0. The functions are now (decrementally) sorted by their direct match count values:

	match count
<code>void process(T1 [= int] const &t1, T2 [= int] const &t2);</code>	2 // 2
<code>void process(T [= int] const &t, int i);</code>	2 // 4
<code>void process<int, int>(int i1, int i2);</code>	2 // 5
<code>void process(int i1, int i2);</code>	2 // 6
<code>void process(T [= int] const &t, double d);</code>	1 // 3
<code>void process(int i, double d);</code>	1 // 7
<code>void process(double d, int i);</code>	1 // 8
<code>void process(double d1, double d2);</code>	0 // 9

If there is no draw for the top value the corresponding function is selected and the function selection process is completed.

When multiple functions appear at the top the compiler verifies that no ambiguity has been encountered. An ambiguity is encountered if the *sequences* of parameters for which type conversions were (not) required differ. As an example consider functions 3 and 8. Using `D` for 'direct match' and `C` for 'conversion' the arguments match function 3 as `D,C` and function 8 as `C,D`. If 2, 4, 5 and 6 would not have been present then the compiler would have reported an ambiguity as the sequences of argument/parameter matching procedures differ for functions 3 and 8. The same difference is encountered comparing functions 7 and 8 and no such difference is encountered comparing functions 3 and 7.

At this point there is a draw for the top value and the compiler proceeds with the subset of associated functions (functions 2, 4, 5 and 6). With each of these functions an 'ordinary parameter count' is associated counting the number of non-template parameters of the functions. The functions are decrementally sorted by this count, resulting in:

	ordin. param. count
<code>void process(int i1, int i2);</code>	2 // 6
<code>void process(T [= int] const &t, int i);</code>	1 // 4
<code>void process(T1 [= int] const &t1, T2 [= int] const &t2);</code>	0 // 2
<code>void process<int, int>(int i1, int i2);</code>	0 // 5

Now there is no draw for the top value. The corresponding function (`process(int, int)`, function 6) is selected and the function selection process is completed. Function 6 is used in `main`'s function call statement.

If function 6 would not have existed function 4 would have been used. Assuming that neither function 4 nor function 6 would have existed the selection process would continue with functions 2 and 5:




Figure 20.1: The function template selection mechanism

```
ordin. param.
count
void process(T1 [= int] const &t1, T2 [= int] const &t2); 0 // 2
void process<int, int>(int i1, int i2); 0 // 5
```

In this situation a draw is encountered once again and the selection process continues. A ‘type of function’ value is associated with each of the functions having the highest ordinary parameter count and these functions are decrementally sorted by their type of function values. Value 2 is associated to ordinary functions, value 1 to template explicit specializations and value 0 to plain function templates.

If there is no draw for the top value the corresponding function is selected and the function selection process is completed. If there is a draw the compiler reports and ambiguity and cannot determine which function to call. Assuming only functions 2 and 5 existed then this selection step would have resulted in the following ordering:

```
function
type
void process<int, int>(int i1, int i2); 1 // 5
void process(T1 [= int] const &t1, T2 [= int] const &t2); 0 // 2
```

Function 5, the template explicit specialization, would have been selected. Here is a summary of the function template selection mechanism (cf. figure Figure 20.1):

- The set of candidate functions is constructed: identical names;
- The set of viable functions is constructed: correct number of parameters and available type conversions;

- Template type determination, dropping templates whose type parameters cannot be determined;
- Decrementally sort the functions by their direct match count values. If there no draw for the top value the associated function is selected, completing the selection process.
- Inspect the functions associated with the top value for ambiguities in automatic type conversion sequences. If different sequences are encountered report an ambiguity and terminate the selection process.
- Decrementally sort the functions associated with the top value by their ordinary parameter count values. If there no draw for the top value the associated function is selected, completing the selection process.
- Decrementally sort the functions associated with the top value by their function type values using 2 for ordinary functions, 1 for template explicit specializations and 0 for plain template functions. parameter count values. If there no draw for the top value the associated function is selected, completing the selection process.
- Report an ambiguity and terminate the selection process.

20.10 SFINAE: Substitution Failure Is Not An Error

Consider the following struct definition:

```
struct Int
{
    typedef int type;
};
```

Although at this point it may seem strange to embed a typedef in a struct, in chapter 22 we'll encounter situations where this is actually very useful. It allows us to define a variable of a type that is required by the template. E.g., (ignore the use of typename in the following function parameter list, but see section 21.2.1 for details):

```
template <typename Type>
void func(typename Type::type value)
{
}
```

To call `func(10)` `Int` has to be specified explicitly since there may be many structs that define `type`: the compiler needs some assistance. The correct call is `func<Int>(10)`. Now that it's clear that `Int` is meant the compiler may correctly deduce that `value` is an `int`.

But templates may be overloaded and our next definition is:

```
template <typename Type>
void func(Type value)
{
}
```

Now, to make sure this function is used we specify `func<int>(10)` and again this compiles flawlessly.

But as we've seen in the previous section when the compiler determines which template to instantiate it creates a list of viable functions by matching the parameter types of available function prototypes with the provided actual argument types. To do so it has to *determine* the types of the parameters and herein lies a problem.

When evaluating `Type = int` the compiler encounters the prototypes `func(int::Type)` (first template definition) and `func(int)` (second template definition). But there is no `int::Type`, and so in a

way this generates an error. However, the error results from substituting the provided template type argument into the various template definitions.

A type-problem caused by substituting a type in a template definition is *not* considered an error, but merely an indication that that particular type cannot be used in that particular template. The template is therefore removed from the list of candidate functions.

This principle is known as *substitution failure is not an error* (SFINAE) and it is often used by the compiler to select not only a simple overloaded function (as shown here) but also to choose among available template specializations (see also chapters 21 and 22).

20.11 Compiling template definitions and instantiations

Consider this definition of the add function template:

```
template <typename Container, typename Type>
Type add(Container const &container, Type init)
{
    return std::accumulate(container.begin(), container.end(), init);
}
```

Here `std::accumulate` is called using `container`'s `begin` and `end` members.

The calls `container.begin()` and `container.end()` are said to *depend on template type parameters*. The compiler, not having seen `container`'s interface, cannot check whether `container` actually has members `begin` and `end` returning input iterators.

On the other hand, `std::accumulate` itself is independent of any template type parameter. Its *arguments* depend on template parameters, but the function call itself isn't. Statements in a template's body that are independent of template type parameters are said *not to depend on template type parameters*.

When the compiler encounters a template definition, it verifies the syntactic correctness of all statements not depending on template parameters. I.e., it must have seen all class definitions, all type definitions, all function declarations etc. that are used in those statements. If it hasn't seen the required definitions and declarations the compiler will reject the template's definition. Therefore, when submitting the above template to the compiler the header file `numeric` must first have been included as this header file declares `std::accumulate`.

With statements depending on template parameters the compiler cannot perform those extensive syntactic checks. It has no way to verify the existence of a member `begin` for the as yet unspecified type `Container`. In these cases the compiler performs superficial checks, assuming that the required members, operators and types eventually become available.

The location in the program's source where the template is instantiated is called its *point of instantiation*. At the point of instantiation the compiler deduces the actual types of the template's parameters. At that point it checks the syntactic correctness of the template's statements that depend on template type parameters. This implies that the compiler must have seen the required declarations *only at the point of instantiation*. As a rule of thumb, you should make sure that all required declarations (usually: header files) have been read by the compiler at every point of instantiation of the template. For the template's definition itself a more relaxed requirement can be formulated. When the definition is read only the declarations required for statements *not* depending on the template's type parameters must have been provided.

20.12 Static assertions (C++0x)

The

```
static_assert(constant expression, error message)
```

utility is defined by the C++0x standard to allow assertions to be made within template definitions. Here are two examples of its use:

```
static_assert(BUFSIZE1 == BUFSIZE2,
              "BUFSIZE1 and BUFSIZE2 must be equal");

template <typename Type1, typename Type2>
void rawswap(Type1 &type1, Type2 &type2)
{
    static_assert(sizeof(Type1) == sizeof(Type2),
                  "rawswap: Type1 and Type2 must have equal sizes");
    // ...
}
```

The first example shows how to avoid yet another preprocessor directive: `error` vs. `static_assert` (in this case the `#error` directive).

The second example shows how `static_assert` can be used to ensure that a template operates under the right condition(s).

The string defined in `static_assert`'s second argument is displayed and compilation stops if the condition specified in `static_assert`'s first argument is false.

Like the `#error` preprocessor directive `static_assert` is a compile-time matter that doesn't have any effect on the run-time efficiency of the code in which it is used.

20.13 Summary of the template declaration syntax

In this section the basic syntactic constructions for declaring templates are summarized. When *defining* templates, the terminating semicolon should be replaced by a function body.

Not every template declaration may be converted into a template definition. If a definition may be provided it is explicitly mentioned.

- A plain template declaration (a definition may be provided):

```
template <typename Type1, typename Type2>
void function(Type1 const &t1, Type2 const &t2);
```

- A template instantiation declaration (no definition may be provided):

```
template
void function<int, double>(int const &t1, double const &t2);
```

- A template using explicit types (no definition may be provided):

```
void (*fp)(double, double) = function<double, double>;
void (*fp)(int, int) = function<int, int>;
```

- A template explicit specialization (a definition may be provided):

```
template <>
void function<char *, char *>(char *const &t1, char *const &t2);
```

- A template declaration declaring friend function templates within class templates (covered in section 21.9, no definition may be provided):

```
friend void function<Type1, Type2>(parameters);
```


Chapter 21

Class Templates

Templates can not only be constructed for functions but also for complete classes. Consider constructing a class template when a class should be able to handle different types of data. Class templates are frequently used in **C++**: chapter 12 discusses data structures like `vector`, `stack` and `queue`, that are implemented as *class templates*. With class templates, the algorithms and the data on which the algorithms operate are completely separated from each other. To use a particular data structure in combination with a particular data type only the data type needs to be specified when defining or declaring a class template object (as in `stack<int> iStack`).

In this chapter constructing and using class templates is discussed. In a sense, class templates compete with object oriented programming (cf. chapter 14), that uses a mechanism resembling that of templates. Polymorphism allows the programmer to postpone the implementation of algorithms by deriving classes from base classes in which algorithms are only partially implemented. The actual definition and processing of the data upon which the algorithms operate may be postponed until derived classes are defined. Likewise, templates allow the programmer to postpone the specification of the data upon which the algorithms operate. This is most clearly seen with abstract containers, that completely specify the algorithms and that at the same time leave the data type on which the algorithms operate completely unspecified.

The correspondence between class templates and polymorphic classes is well known. In their book **C++ Coding Standards** (Addison-Wesley, 2005) Sutter and Alexandrescu (2005) refer to *static polymorphism* and *dynamic polymorphism*. *Dynamic* polymorphism is what we use when overriding virtual members. Using `vtables` the function that is actually called depends on the type of object a (base) class pointer points at. *Static* polymorphism is encountered in the context of templates. Depending on the actual types, the compiler *creates* the code, compile time, that's appropriate for those particular types. There's no need to consider static and dynamic polymorphism as mutually exclusive variants of polymorphism. Rather, both can be used together, combining their strengths. A warning is in place, though. When a class template defines virtual members *all* virtual members are instantiated for every instantiated type. All virtual members must be instantiated (whether they are used or not) as the compiler must construct the `vtable` for each data type for which an object of the class is instantiated.

Generally, class templates are easier to use than polymorphism. It is certainly easier to write `stack<int> istack` to create a stack of `ints` than to derive a new class `Istack`: `public stack` and to implement all necessary member functions defining a similar stack of `ints` using object oriented programming. On the other hand, for each different type for which an object of a class template is defined another, possibly complete class must be reinstantiated. This is not required in the context of object oriented programming where derived classes *use*, rather than *copy*, the functions that are already available in their base classes (but see also section 21.10).

Previously we've already used class templates. Objects like `vector<int> vi` and `vector<string> vs` are commonly used. The data types for which these templates are defined and instantiated are an inherent part of such container types. It is stressed that it is the *combination* of a class template type and its template parameter(s), rather than the mere class template's type that defines or generates a type. So `vector<int>` is a type as is `vector<string>`. Such types could very well be represented by

typedefs:

```
typedef std::vector<int>          IntVector;
typedef std::vector<std::string> StringVector;

IntVector vi;
StringVector vs;
```

21.1 Defining class templates

Having covered the construction of function templates, we're now ready for the next step: constructing class templates. Many useful class templates already exist. Rather than illustrating the construction of a class template by looking at an already existing class template the construction of another potentially useful new class template will be undertaken.

The new class implements a *circular queue*. a circular queue has a fixed number of `max_size` elements. New elements are inserted at its back and only its head and tail elements can be accessed. Only the head element can be removed from a circular queue. Once `n` elements have been appended the next element will again be inserted at the queue's (physical) first position. The circular queue allows insertions until it holds `max_size` elements. As long as a circular queue contains at least one element elements may be removed from it. Trying to remove an element from an empty circular queue or to add another element to a full circular queue results in exceptions being thrown. In addition to other constructors a circular queue must offer a constructor initializing its objects for `max_size` elements. This constructor must make available the memory for the `max_size` elements but must not call those elements default constructors (hinting at the use of the placement `new` operator). A circular queue should offer value semantics as well as a move constructor.

Please note that in the above description the actual data type that is used for the circular queue is nowhere mentioned. This is a clear indication that our class could very well be defined as a *class template*. Alternatively, the class could be defined for some concrete data type which is then abstracted when converting the class to a class template.

In this section the class template `CirQue` (circular queue) is constructed, having one template type parameter `Data` representing the data type that is stored in the circular queue. The outline of the interface of this class template looks like this:

```
template<typename Data>
class CirQue
{
    // member declarations
};
```

A class template's definition starts like a function template's definition:

- The keyword `template`, starting a template definition or declaration.
- The angle bracket enclosed list following `template`: a list containing one or more comma-separated elements called the enclosed list is called the *template parameter list*. Template parameter lists may have multiple elements, like this:

```
typename Type1, typename Type2, typename Type3
```

When a class template defines multiple template type parameters they are matched in sequence with the list of template type arguments provided when defining objects of such a class template. Example:

```
template <typename Type1, typename Type2, typename Type3>
```



```

class MultiTypes
{
    ...
};

MultiTypes<int, double, std::string> multiType;
// Type1 is int, Type2 is double, Type3 is std::string

```

- Inside the template parameter list we find the *formal type* name (Data for CirQue). It is a formal (type) name, like the formal types used in function template parameter lists.
- Following the template header the class interface is defined. It may use the formal type names defined in the template header as type names.

Once the CirQue class template has been defined it can be used to create all kinds of circular queues. As one of its constructors expects a `size_t` argument defining the maximum number of elements that can be stored in the circular queue circular queues could be defined like this:

```

CirQue<int> cqi(10);           // max 10 ints
CirQue<std::string> cqstr(30); // max 30 strings

```

As noted in the introductory section of this chapter the combination of name of the class template and the data type for which it is instantiated defines a data type. Also note the similarity between defining a `std::vector` (of some data type) and a CirQue (of some data type).

Like `std::map` containers class templates may be defined with multiple template type parameters.

Back to CirQue. A CirQue must be capable of storing `max_size` Data elements. These elements are eventually stored in memory pointed at by a pointer `Data *d_data`, initially pointing to raw memory. New elements are added at the backside of the CirQue. A pointer `Data *d_back` is used to point to the location where the next element will be stored. Likewise, `Data *d_front` points to the location of the CirQue's first element. Two `size_t` data members are used to monitor the filling state of the CirQue: `d_size` represents the number of elements currently stored in the CirQue, `d_maxSize` represents the maximum number of elements that the CirQue can contain. Thus, the CirQue's data members are:

```

size_t d_size;
size_t d_maxSize;
Data *d_data;
Data *d_front;
Data *d_back;

```

The class CirQue offers various member functions. Normal design principles should be adhered to when constructing class template members. Class template type parameters should preferably be defined as `Type const &`, rather than `Type`, to prevent unnecessary copying of large data structures. Template class constructors should use member initializers rather than member assignment within the body of the constructors. Member function definitions should preferably not be provided in-class but below the class interface. Since class template member functions are function templates their definitions should be provided in the header file offering the class interface. They *may* be given the `inline` attribute.

CirQue declares the following (public) members (their definitions are provided as well; all definitions are provided below the class interface):

- `explicit CirQue(size_t maxSize = 0):`

Constructor initializing a CirQue capable of storing `max_size` Data elements. As the constructor's parameter is given a default argument value this constructor can also be used as a default constructor, allowing us to define, e.g., vectors of CirQues. The constructor initializes the CirQue object's `d_data` member to a block of raw memory and

`d_front` and `d_back` are initialized to `d_data`. As class template member functions are themselves function templates their implementations outside of the class template's interface must start with the class template's template header. Here is the implementation of the `CirQue(size_t)` constructor:

```
template<typename Data>
CirQue<Data>::CirQue(size_t maxSize)
:
    d_size(0),
    d_maxSize(maxSize),
    d_data(
        maxSize == 0 ?
            0
        :
            static_cast<Data *>(
                operator new(maxSize * sizeof(Data)))
    ),
    d_front(d_data),
    d_back(d_data)
{ }
```

- `CirQue(CirQue<Data> const &other):`

The copy constructor has no special features. It uses a private support member `inc` to increment `d_back` (see below) and placement `new` to copy the other's `Data` elements to the current object. The implementation of the copy constructor is straightforward:

```
template<typename Data>
CirQue<Data>::CirQue(CirQue<Data> const &other)
:
    d_size(other.d_size),
    d_maxSize(other.d_maxSize),
    d_data(
        d_maxSize == 0 ?
            0
        :
            static_cast<Data *>(
                operator new(d_maxSize * sizeof(Data)))
    ),
    d_front(d_data + (other.d_front - other.d_data))
{
    Data const *src = other.d_front;
    d_back = d_front;
    for (size_t count = 0; count != d_size; ++count)
    {
        new(d_back) Data(*src);
        d_back = inc(d_back);
        if (++src == other.d_data + d_maxSize)
            src = other.d_data;
    }
}
```

- `CirQue(CirQue<Data> const &&tmp):`

The move constructor merely initializes the current object's `d_data` pointer to 0 and swaps (see the member `swap`, below) the temporary object with the current object. `CirQue`'s destructor will inspect `d_data` and will immediately return when it's zero. Implementation:

```
template<typename Data>
CirQue<Data>::CirQue(CirQue<Data> const &&tmp)
:
    d_data(0)
```

```

        d_data(0)
    {
        swap(const_cast<CirQue<Data> &>(tmp));
    }

```

- `~CirQue()`:

The destructor inspects the `d_data` member. If it is zero then nothing has been allocated and the destructor immediately returns. This may occur in two situations: the circular queue contains no elements or the information was grabbed from a temporary object by some move operation, setting the temporary's `d_data` member to zero. Otherwise `d_size` elements are destroyed by explicitly calling their destructors followed by returning the element's raw memory to the common pool. Implementation:

```

template<typename Data>
CirQue<Data>::~~CirQue()
{
    if (d_data == 0)
        return;
    for (; d_size--; )
    {
        d_front->~Data();
        d_front = inc(d_front);
    }
    operator delete(d_data);
}

```

- `CirQue &operator=(CirQue<Data> const &other)`:

The copy assignment operator has a standard implementation:

```

template<typename Data>
CirQue<Data> &CirQue<Data>::operator=(CirQue<Data> const &rhs)
{
    CirQue<Data> tmp(rhs);
    swap(tmp);
}

```

- `CirQue &operator=(CirQue<Data> const &&tmp)`:

The move assignment operator also has a standard implementation. As its implementation merely calls `swap` it is defined as an inline function template:

```

template<typename Data>
inline CirQue<Data> &CirQue<Data>::operator=(CirQue<Data> const &&tmp)
{
    swap(const_cast<CirQue<Data> &>(tmp));
}

```

- `void pop_front()`:

removes the element pointed at by `d_front` from the `CirQue`. Throws an exception if the `CirQue` is empty. The exception is thrown as a `CirQue<Data>::EMPTY` value, defined by the enum `CirQue<Data>::Exception` (see `push_back`). The implementation is straightforward (explicitly calling the destructor of the element that is removed):

```

template<typename Data>
void CirQue<Data>::pop_front()
{
    if (d_size == 0)
        throw EMPTY;

    d_front->~Data();
    d_front = inc(d_front);
}

```

```
        --d_size;
    }
```

- `void push_back(Data const &object):`

adds another element to the `CirQue`. Throws a `CirQue<Data>::FULL` exception if the `CirQue` is full. The exceptions that can be thrown by a `CirQue` are defined in its Exception enum:

```
enum Exception
{
    EMPTY,
    FULL
};
```

A copy of `object` is installed in the `CirQue`'s raw memory using placement new and its `d_size` is incremented.

```
template<typename Data>
void CirQue<Data>::push_back(Data const &object)
{
    if (d_size == d_maxSize)
        throw FULL;

    new (d_back) Data(object);
    d_back = inc(d_back);
    ++d_size;
}
```

- `void swap(CirQue<Data> &other):`

swaps the current `CirQue` object with another `CirQue<Data>` object;

```
template<typename Data>
void CirQue<Data>::push_back(Data const &object)
{
    if (d_size == d_maxSize)
        throw FULL;

    new (d_back) Data(object);
    d_back = inc(d_back);
    ++d_size;
}
```

The remaining public members all consist of one-liners and are implemented as inline function templates:

- `Data &back():`

returns a reference to the element pointed at by `d_back` (undefined result if the `CirQue` is empty):

```
template<typename Data>
inline Data &CirQue<Data>::back()
{
    return d_back == d_data ? d_data[d_maxSize - 1] : d_back[-1];
}
```

- `Data &front():`

returns reference to the element pointed at by `d_front` (undefined result if the `CirQue` is empty);

```
template<typename Data>
```

```

inline Data &CirQue<Data>::front()
{
    return *d_front;
}

```

- `bool empty() const:`

returns true if the CirQue is empty;

```

template<typename Data>
void CirQue<Data>::push_back(Data const &object)
{
    if (d_size == d_maxSize)
        throw FULL;

    new (d_back) Data(object);
    d_back = inc(d_back);
    ++d_size;
}

```

- `bool full() const:`

returns true if the CirQue is full;

```

template<typename Data>
void CirQue<Data>::push_back(Data const &object)
{
    if (d_size == d_maxSize)
        throw FULL;

    new (d_back) Data(object);
    d_back = inc(d_back);
    ++d_size;
}

```

- `size_t size() const:`

returns the number of elements currently stored in the CirQue;

```

template<typename Data>
void CirQue<Data>::push_back(Data const &object)
{
    if (d_size == d_maxSize)
        throw FULL;

    new (d_back) Data(object);
    d_back = inc(d_back);
    ++d_size;
}

```

- `size_t maxSize() const:`

returns the maximum number of elements that can be stored in the CirQue;

```

template<typename Data>
void CirQue<Data>::push_back(Data const &object)
{
    if (d_size == d_maxSize)
        throw FULL;

    new (d_back) Data(object);
    d_back = inc(d_back);
    ++d_size;
}

```

Finally, the class has one private member, `inc`, returning a cyclically incremented pointer into `CirQue`'s raw memory:

```
template<typename Data>
Data *CirQue<Data>::inc(Data *ptr)
{
    ++ptr;
    return ptr == d_data + d_maxSize ? d_data : ptr;
}
```

When objects of a class template are instantiated, *only* the definitions of all the template's member functions that are used must have been seen by the compiler. That characteristic of templates could be refined to the point where each definition is stored in a separate function template definition file. In that case only the definitions of the function templates that are actually needed would have to be included. However, it is hardly ever done that way. Instead, the usual way to define class templates is to define the interface and to define the remaining function templates immediately below the class template's interface (defining some functions inline).

Now that the class `CirQue` has been defined, it can be used. To use the class its object must be instantiated for a particular data type. In the following example it is initialized for data type `std::string`:

```
#include "cirque.h"
#include <iostream>
#include <string>
using namespace std;

int main()
{
    CirQue<string> ci(4);
    ci.push_back("1");
    ci.push_back("2");
    cout << ci.size() << ' ' << ci.front() << ' ' << ci.back() << '\n';

    ci.push_back("3");
    ci.pop_front();
    ci.push_back("4");
    ci.pop_front();
    ci.push_back("5");
    cout << ci.size() << ' ' << ci.front() << ' ' << ci.back() << '\n';

    CirQue<string> copy(ci);
    copy.pop_front();
    cout << copy.size() << ' ' << copy.front() << ' ' << copy.back() << '\n';

    int arr[] = {1, 3, 5, 7, 9};
    CirQue<int> ca(arr);
    cout << ca.size() << ' ' << ca.front() << ' ' << ca.back() << '\n';

    //    int *ap = arr;
    //    CirQue<int> cap(ap);
}
```

21.1.1 Default class template parameters

Different from function templates, template parameters of template classes may be given default argument values. This holds true for both template type- and template non-type parameters. If default template arguments were defined and if a class template object is instantiated without specifying arguments for its template parameters then the template parameter's defaults are used.

When defining defaults keep in mind that they should be suitable for the majority of instantiations of the class. E.g., for the class template `CirQue` the template's type parameter list could have been altered by specifying `int` as its default type:

```
template <typename Data = int>
```

Even though default arguments can be specified, the compiler must still be informed that object definitions refer to templates. When instantiating class template objects using default template arguments the type specifications may be omitted but the angle brackets must be retained. Assuming a default type for the `CirQue` class, an object of that class may be defined as:

```
CirQue<> intCirQue(10);
```

Default template arguments cannot be specified when defining template members. So, the definition of, e.g., the `push_back` member must always begin with the same template specification:

```
template <typename Data>
```

When a class template uses multiple template parameters, all may be given default values. Like default function arguments, once a default value is used all remaining template parameters must also use their default values. A template type specification list may not start with a comma, nor may it contain multiple consecutive commas.

21.1.2 Declaring class templates

Class templates may also be *declared*. This may be useful in situations where forward class declarations are required. To declare a class template, simply remove its interface (the part between the curly braces):

```
template <typename Data>
class CirQue;
```

Default template arguments may also be specified when declaring class templates. However, default template arguments cannot be specified for both the declaration and the definition of a class template. As a rule of thumb default template arguments should be omitted from *declarations*, as class template declarations are never used when instantiating objects but are only occasionally used as forward references. Note that this differs from default parameter value specifications for member functions in ordinary classes. Such defaults are always specified when declaring the member functions in the class interface.

21.1.3 Preventing template instantiations (C++0x)

In C++ templates are instantiated when the address of a function template or class template object is taken or when a function template or class template is used. As described in section 21.1.2 it is possible to (forward) declare a class template to allow the definition of a pointer or reference to that template class or to allow it being used as a return type.

In other situations templates are instantiated when they are being used. If this happens many times (i.e., in many different source files) then this may slow down the compilation process considerably. The C++0x standard allows programmers to *prevent* templates from being instantiated. For this the C++0x standard introduces the `extern template` syntax. Example:

```
extern template class std::vector<int>;
```

Having declared the class template it can be used in its translation unit. E.g., the following function will properly compile:

```
#include <vector>
#include <iostream>
using namespace std;

extern template class vector<int>;

void vectorUser()
{
    vector<int> vi;
    cout << vi.size() << '\n';
}
```

But be careful:

- The declaration by itself does not make the class definition available. The `vector` header file still needs to be included to make the features of the class `vector` known to the compiler. But due to the `extern template` declaration none of the used members will be instantiated for the current compilation unit;
- The compiler *assumes* (as it always does) that what's declared is implemented elsewhere. In this case the compiler encounters an *implicit declaration*: the features of the `vector` class that are actually used by the above program are not individually declared but they are declared as a group, using the `extern template` declaration. This not only holds true for explicitly used members but hidden members (copy constructors, move constructors, conversion operators, constructors called during promotions, to name a few): all are assumed by the compiler to have been instantiated elsewhere;
- The above source file will *compile* but the compiler must find the instantiations before its linker can produce a final program. To accomplish this one or more sourcefiles may be constructed in which all required instantiations are made available.

In a stand-alone program one might postpone defining the required members and wait for the linker to complain about unresolved external references. These may then be used to create a series of instantiation declarations which are then linked to the program to satisfy the linker. Not a very simple task, though, as the declarations must strictly match the way the members are declared in the class interface. An easier approach is to define an *instantiation source file* in which all facilities that are used by the program are actually instantiated in a function that is never called by the program. By adding this instantiation function to the source file containing `main` we can be sure that all required members will be instantiated as well. Here is an example of how this can be done:

```
#include <vector>
#include <iostream>

extern void vectorUser();

int main()
{
    vectorUser();
}

// this part is never called. It is added to make sure all required
// features of declared templates will also be instantiated.

namespace
{
    void instantiator()
```



```

    {
        std::vector<int> vi;
        vi.size();
    }
}

```

21.1.4 Non-type parameters

Function template parameters are either template type parameters or template non-type parameters (actually, a third type of template parameter exists, the *template template parameter*, which is discussed in chapter 22 (section 22.3)).

Class templates may also define non-type parameters. Like the function template non-type parameters they must be (integral) constants whose values must be known at object instantiation time.

Different from function template non-type parameters the values of class template non-type parameters are not deduced by the compiler using arguments passed to class template members. Assume we modify the class template `CirQue` so that it has an additional non-type parameter `size_t Size`. Next we use this `Size` parameter in a new constructor defining an array parameter of `Size` elements of type `Data`. Only showing the relevant constructors (section 21.1.5 provides the rationale for using the type `Data2`);

Now two template type parameters are required, e.g., when specifying the type of the copy constructor's parameter. The new `CirQue` class template becomes (showing only the relevant constructors):

```

template <typename Data, size_t Size>
class CirQue
{
    // ... data members
public:
    CirQue(CirQue<Data, Size> &other);
    CirQue(Data *data);
    CirQue(Data const (&arr)[Size]);
    ...
};

template <typename Data, size_t Size>
CirQue<Data, Size>::CirQue(Data const (&arr)[Size])
:
    d_maxSize(Size),
    d_size(0),
    d_data(operator new(Size * sizeof(Data))),
    d_front(d_data),
    d_back(d_data),
{
    std::copy(arr, arr + Size, back_inserter(*this));
}

```

Unfortunately, this setup doesn't satisfy our needs as the values of template non-type parameters are not deduced by the compiler. When the compiler is asked to compile the following `main` function it reports a mismatch between the required and actual number of template parameters:

```

int main()
{
    int arr[30];

    CirQue<int> ap(arr);
}

```

```

/*
    Error reported by the compiler:

    In function 'int main()':
        error: wrong number of template arguments (1, should be 2)
        error: provided for 'template<class Data, size_t Size>
            class CirQue'
*/

```

Defining `Size` as a non-type parameter having a default value doesn't work either. The compiler always uses the default unless its value is explicitly specified. Reasoning that `Size` can be 0 unless we need another value, we might be tempted to specify `size_t Size = 0` in the template's parameter type list. Doing so we create a mismatch between the default value 0 and the actual size of the array `arr` as defined in the above `main` function. The compiler, using the default value, reports:

```

In instantiation of 'CirQue<int, 0>':
...
error: creating array with size zero ('0')

```

So, although class templates may use non-type parameters they must always be specified like type parameters when an object of that class is defined. Default values can be specified for those non-type parameters causing the compiler to use the default when the non-type parameter is left unspecified.

Default template parameter values (either type or non-type template parameters) may *not* be specified when defining template member functions. In general: function template definitions (and thus: class template member functions) may not be given default template (non) type arguments. If default template arguments are to be used for class template members, they *have* to be specified by the class interface.

Similar to non-type parameters of function templates default argument values for non-type class template parameters may only be specified as constants:

- Global variables have constant addresses, which can be used as arguments for non-type parameters.
- Local and dynamically allocated variables have addresses that are *not* known by the compiler when the source file is compiled. These addresses can therefore *not* be used as arguments for non-type parameters.
- Lvalue transformations are allowed: if a pointer is defined as a non-type parameter, an array name may be specified.
- Qualification conversions are allowed: a pointer to a non-const object may be used with a non-type parameter defined as a `const` pointer.
- Promotions are allowed: a constant of a 'narrower' data type may be used when specifying a default argument for a non-type parameter of a 'wider' type (e.g., a `short` can be used when an `int` is called for, a `long` when a `double` is called for).
- Integral conversions are allowed: if a `size_t` parameter is specified, an `int` may be used as well.
- Variables cannot be used to specify template non-type parameters as their values are not constant expressions. Variables defined using the `const` modifier, however, may be used as their values never change.

Although our attempts to define a constructor of the class `CirQue` accepting an array as its argument has failed so far, we're not yet out of options. In the next section a method is described that *does* allowing us to reach our goal.

21.1.5 Member templates

Our previous attempt to define a template non-type parameter that is initialized by the compiler to the number of elements of an array failed because the template's parameters are not implicitly deduced when a constructor is called. Instead, they must explicitly be specified when an object of the class template is defined. As the template arguments are specified just before the template's constructor is called the compiler doesn't have to deduce anything and it can simply use the explicitly specified template arguments.

In contrast, when *function* templates are used, the actual template parameters are deduced from the arguments used when calling the function. This opens up an alley leading to the solution of our problem. If the constructor itself is turned into a function template (having its own template header), then the compiler *will* be able to deduce the non-type parameter's value and there is no need anymore to specify it explicitly using a class template non-type parameter.

Members (functions or nested classes) of class templates that are themselves templates are called *member templates*.

Member templates are defined as any other template, including its own template header.

When converting our earlier `CirQue(Data const (&array)[Size])` constructor into a member template the class template's `Data` type parameter can still be used, but we must provide the member template with a non-type parameter of its own. Its declaration in the (partially shown) class interface looks like this:

```
template <typename Data>
class CirQue
{
    public:
        template <size_t Size>
        explicit CirQue(Data const (&arr)[Size]);
};
```

Its implementation becomes:

```
template <typename Data>
template <size_t Size>
CirQue<Data>::CirQue(Data const (&arr)[Size])
:
    d_size(0),
    d_maxSize(Size),
    d_data(static_cast<Data *>(operator new(Size * sizeof(Data)))),
    d_front(d_data),
    d_back(d_data)
{
    std::copy(arr, arr + Size, back_inserter(*this));
}
```

The implementation uses the STL's `copy` algorithm and a `back_inserter` adapter to insert the array's elements into the `CirQue`. To use the `back_inserter` `CirQue` must define two (public) typedefs (cf. section 18.2.1):

```
typedef Data value_type;
typedef value_type const &const_reference;
```

Member templates have the following characteristics:

- Two template headers must be used: the class template's template header is specified first followed by the member template's template header;

- Normal access rules apply: the member template can be used by programs to construct an `CirQue` object of a given data type. As usual for class templates, the data type must be specified when the object is constructed. To construct a `CirQue` object from the array `int array[30]` we define:

```
CirQue<int> object(array);
```

- Any member can be defined as a member template, not just a constructor;
- When a template member is implemented below its class interface, the template class header must precede the function template header of the member template;
- The implementation of the member template must specify its proper scope. The member template is defined as a member of the class `CirQue`, instantiated for the formal template parameter type `Data`;
- The template parameter names in the declaration and implementation must be identical;
- The member template should be defined inside its proper namespace environment. The organization of files defining class templates within a namespace should therefore be:

```
namespace SomeName
{
    template <typename Type, ...>    // class template definition
    class ClassName
    {
        ...
    };

    template <typename Type, ...>    // non-inline member definition(s)
    ClassName<Type, ...>::member(...)
    {
        ...
    }
}                                     // namespace closes
```

A potentially occurring problem remains. Assume that in addition to the above member template a `CirQue<Data>::CirQue(Data const *data)` has been defined. Some (here not further elaborated) protocol may be defined allowing the constructor to determine the number of elements that should be stored in the `CirQue` object. When we now define

```
CirQue<int> object(array);
```

it is this latter constructor, rather than the member template, that is used by the compiler. The compiler selects this latter constructor as it is a more specialized version of a constructor of the class `CirQue` than the member template (cf. section 20.9). Problems like these can be solved by defining the constructor `CirQue(Data const *data)` into a member template as well. It could receive a template type parameter `Data2`. Data cannot be used as template parameters of a member template may not shadow template parameters of its class. Using `Data2` instead of `Data` takes care of this subtlety. Here is the declaration of the constructor `CirQue(Data2 const *)` as it could appear in the `CirQue` header file:

```
template <typename Data>
class CirQue
{
    template <typename Data2>
    explicit CirQue(Data2 const *data);
}
```

Here is how the two constructors are selected in code defining two `CirQue` objects:

```
int main()
```

```

{
    int array[30];
    int *iPtr = array;

    CirQue<int> ac(array);          // calls CirQue(Data const (&arr)[Size])
    CirQue<int> acPtr(iPtr);        // calls CirQue(Data2 const *)
}

```

21.2 Static data members

When static members are defined in class templates, they are defined for every new type for which the class template is instantiated. As they are static members, there will only be one member per type for which the class template is instantiated. For example, in a class like:

```

template <typename Type>
class TheClass
{
    static int s_objectCounter;
};

```

There will be *one* `TheClass<Type>::objectCounter` for each different `Type` specification. The following object definitions result in the instantiation of just one single static variable, shared among the two objects:

```

TheClass<int> theClassOne;
TheClass<int> theClassTwo;

```

Mentioning static members in interfaces does not mean these members are actually defined. They are only *declared* and must be *defined* separately. With static members of class templates this is no different. The definition of static members is usually provided immediately following (i.e., below) the template class interface. The static member `s_objectCounter` will usually be defined as follows, just below its class interface:

```

template <typename Type>                // definition, following
int TheClass<Type>::s_objectCounter = 0; // the interface

```

Here `s_objectCounter` is an `int` and thus independent of the template type parameter `Type`.

In list-like constructions, where a pointer to objects of the class itself is required, the template type parameter `Type` must be used when defining the static variable. Example:

```

template <typename Type>
class TheClass
{
    static TheClass *s_objectPtr;
};

template <typename Type>
TheClass<Type> *TheClass<Type>::s_objectPtr = 0;

```

As usual, the definition can be read from the variable name back to the beginning of the definition: `s_objectPtr` of the class `TheClass<Type>` is a pointer to an object of `TheClass<Type>`.

When a static variable of a template's type parameter's type is defined, it should of course not be given the initial value 0. The default constructor (e.g., `Type()` is usually more appropriate). Example:

```
template <typename Type>                                // s_type's definition
Type TheClass<Type>::s_type = Type();
```

21.2.1 Extended use of the keyword ‘typename’

Until now the keyword `typename` has been used to indicate a template type parameter. However, it is also used to disambiguate code inside templates. Consider the following function template:

```
template <typename Type>
Type function(Type t)
{
    Type::Ambiguous *ptr;

    return t + *ptr;
}
```

When this code is processed by the compiler, it will complain with an -at first sight puzzling- error message like:

```
4: error: 'ptr' was not declared in this scope
```

The error message is puzzling as it was the programmer’s intention to declare a pointer to a type `Ambiguous` defined within the class template `Type`. But the compiler, confronted with `Type::Ambiguous` may interpret the statement in various ways. Clearly it cannot inspect `Type` itself trying to uncover `Type`’s true nature as `Type` is a template type. Because of this `Type`’s actual definition isn’t available yet.

The compiler is confronted with two possibilities: either `Type::Ambiguous` is a *static member* of the as yet mysterious template `Type`, or it is a *subtype* of `Type`. As the standard specifies that the compiler must assume the former, the statement

```
Type::Ambiguous *ptr;
```

is interpreted as a *multiplication* of the static member `Type::Ambiguous` and the (now undeclared) entity `ptr`. The reason for the error message should now be clear: in this context `ptr` is unknown.

To disambiguate code in which an identifier refers to a subtype of a template type parameter the keyword `typename` must be used. Accordingly, the above code is altered into:

```
template <typename Type>
Type function(Type t)
{
    typename Type::Ambiguous *ptr;

    return t + *ptr;
}
```

Classes fairly often define subtypes. When such subtypes appear inside template definitions as subtypes of template type parameters the `template` keyword *must* be used to identify them as subtypes. Example: a class template `Handler` defines a `typename Container` as its template type parameter. It also defines a data member storing the iterator returned by the container’s `begin` member. In addition `Handler` offers a constructor accepting any container supporting a `begin` member. `Handler`’s class interface could then look like this:

```
template <typename Container>
```

```

class Handler
{
    Container::const_iterator d_it;

public:
    Handler(Container const &container)
    :
        d_it(container.begin())
    {}
};

```

What did we have in mind when designing this class?

- The typename `Container` represents any container supporting iterators.
- The container presumably supports a member `begin`. The initialization `d_it(container.begin())` clearly depends on the template's type parameter, so it's only checked for basic syntactic correctness.
- Likewise, the container presumably supports a *subtype* `const_iterator`, defined in the class `Container`.

The final consideration is an indication that `typename` is required. If this is omitted and a `Handler` is instantiated the compiler produces a peculiar compilation error:

```

#include "handler.h"
#include <vector>
using namespace std;

int main()
{
    vector<int> vi;
    Handler<vector<int> > ph(vi);
}
/*
    Reported error:

handler.h:4: error: syntax error before ';' token
*/

```

Clearly the line

```
Container::const_iterator d_it;
```

in the class `Handler` causes a problem. It is interpreted by the compiler as a *static member* instead of a subtype. The problem is solved using `typename`:

```

template <typename Container>
class Handler
{
    typename Container::const_iterator d_it;
    ...
};

```

An interesting illustration that the compiler indeed assumes `X::a` to be a member `a` of the class `X` is provided by the error message we get when we try to compile `main` using the following implementation of `Handler`'s constructor:

```
Handler(Container const &container)
```

```

:
    d_it(container.begin())
{
    size_t x = Container::ios_end;
}
/*
    Reported error:

    error: 'ios_end' is not a member of type 'std::vector<int,
        std::allocator<int> >'
*/

```

Now consider what happens if the function template introduced at the beginning of this section doesn't return a `Type` value, but a `Type::Ambiguous` value. Again, a subtype of a template type is referred to, and `typename` must be used:

```

template <typename Type>
typename Type::Ambiguous function(Type t)
{
    return t.ambiguous();
}

```

Using `typename` in the specification of a return type is further discussed in section [22.1.1](#).

Typenames can be embedded in typedefs. As is often the case, this reduces the complexities of declarations and definitions appearing elsewhere. In the next example the type `Iterator` is defined as a subtype of the template type `Container`. `Iterator` may now be used without requiring the use of the keyword `typedef`:

```

template <typename Container>
class Handler
{
    typedef typename Container::const_iterator Iterator;

    Iterator d_it;
    ...
};

```

21.3 Specializing class templates for deviating types

The class `CirQue` can be used for many different types. Their common characteristic is that they can simply be pointed at by class's `d_data` member. But this is not always as simple as it looks. What if `Data` turns out to be a `vector<int>`? For such data types the vanilla `CirQue` implementation will not properly work and a specialization could be considered. When considering a specialization one should also consider inheritance. Often a class derived from the class template accepting the incompatible data structure as its argument but otherwise equal to the original class template can easily be designed. The developmental advantage of inheritance over specialization is clear: the inherited class inherits the members of its base class while the specialization inherits nothing. All members defined by the original class template must be implemented again by the class template's specialization.

The specialization considered here is a true specialization in that the data members and representation used by the specialization greatly differ from the original `CirQue` class template. Therefore all members defined by the original class template must be modified to fit the specialization's data organization.

Like function template specializations class template specializations start with a template header that may or may not have an empty template parameter list. If the template parameters are directly specialized by the specialization it remains empty (e.g., `CirQue`'s template type parameter `Data` is specialized

for `char * data`). But the template parameter list may show typename `Data` when specializing for a `vector<Data>`, i.e., a vector storing any type of data. This leads to the following principle:

A template specialization is recognized by the template argument list following a function or class template's *name* and *not* by an empty template parameter list. Class template specializations may have non-empty template parameter lists. If so, a *partial class template specialization* is defined.

A completely specialized class has the following characteristics:

- The class template specialization must be provided after the generic class template definition. As it is a specialization the compiler must first have seen the original class template;
- The completely specialized class template's template parameter list is empty;
- All of the class's template parameters are given explicit type names or (for the non-type parameters) explicit values. These explicitations are provided in a template parameter specification list (surrounded by angle brackets) that is inserted immediately after the specialized template's class *name*;
- All members of the specialized class template use specialized types and values where original template parameters are used in the original template definition;
- All original template's members (maybe with the exception of some constructors) *should* be redefined by the specialization. If a member is left out of the specialization, it cannot be used for a specialized class template object;
- The specialization may define additional members (but maybe shouldn't as it breaks the one-to-one correspondence between the original and specialized class template);
- Member functions of specialized class templates may be declared by the specializing class and implemented below their class interface. If their implementations follow the class interface they may *not* begin with a `template <>` header, but must immediately start with the member function's header.

Here is an example of a completely specialized `CirQue` class, specialized for a `vector<int>`. All members of the specialized class are declared, but only non-trivial implementations of its members are provided. The specialized class uses a copy of the `vector` passed to the constructor and implements a circular queue using its `vector` data member:

```
#ifndef INCLUDED_CIRQUEVECTOR_H_
#define INCLUDED_CIRQUEVECTOR_H_

#include <vector>
#include "cirque.h"

template<>
class CirQue<std::vector<int>>
{
    typedef std::vector<int> IntVect;

    IntVect d_data;
    size_t d_size;

    typedef IntVect::iterator iterator;
    iterator d_front;
    iterator d_back;

public:
    typedef int value_type;
```

```

typedef value_type const &const_reference;

enum Exception
{
    EMPTY,
    FULL
};

CirQue();
CirQue(IntVect const &iv);
CirQue(CirQue<IntVect> const &other);

CirQue &operator=(CirQue<IntVect> const &other);

int &back();
int &front();
bool empty() const;
bool full() const;
size_t maxSize() const;
size_t size() const;
void pop_front();
void push_back(int const &object);
void swap(CirQue<IntVect> &other);

private:
    iterator inc(iterator const &iter);
};

CirQue<std::vector<int>>::CirQue()
:
    d_size(0)
{}
CirQue<std::vector<int>>::CirQue(IntVect const &iv)
:
    d_data(iv),
    d_size(iv.size()),
    d_front(d_data.begin()),
    d_back(d_data.begin())
{}
CirQue<std::vector<int>>::CirQue(CirQue<IntVect> const &other)
:
    d_data(other.d_data),
    d_size(other.d_size),
    d_front(d_data.begin() + (other.d_front - other.d_data.begin())),
    d_back(d_data.begin() + (other.d_back - other.d_data.begin()))
{}
CirQue<std::vector<int>> &CirQue<std::vector<int>>::operator=(
    CirQue<IntVect> const &rhs)
{
    CirQue<IntVect> tmp(rhs);
    swap(tmp);
}

void CirQue<std::vector<int>>::swap(CirQue<IntVect> &other)
{
    char tmp[sizeof(CirQue<IntVect>)];
    memcpy(tmp, &other, sizeof(CirQue<IntVect>));
    memcpy(&other, this, sizeof(CirQue<IntVect>));
    memcpy(this, tmp, sizeof(CirQue<IntVect>));
}

```

```

void CirQue<std::vector<int>>>::pop_front()
{
    if (d_size == 0)
        throw EMPTY;

    d_front = inc(d_front);
    --d_size;
}
void CirQue<std::vector<int>>>::push_back(int const &object)
{
    if (d_size == d_data.size())
        throw FULL;

    *d_back = object;
    d_back = inc(d_back);
    ++d_size;
}
inline int &CirQue<std::vector<int>>>::back()
{
    return d_back == d_data.begin() ? d_data.back() : d_back[-1];
}
inline int &CirQue<std::vector<int>>>::front()
{
    return *d_front;
}
CirQue<std::vector<int>>>::iterator CirQue<std::vector<int>>>::inc(
    CirQue<std::vector<int>>>::iterator const &iter)
{
    iterator tmp(iter + 1);
    tmp = tmp == d_data.end() ? d_data.begin() : tmp;
    return tmp;
}

#endif

```

Here is an example showing the use of the specialized CirQue class:

```

static int iv[] = {1, 2, 3, 4, 5};

int main()
{
    vector<int> vi(iv, iv + 5);
    CirQue<vector<int>> ci(vi);

    cout << ci.size() << ' ' << ci.front() << ' ' << ci.back() << '\n';
    ci.pop_front();
    ci.pop_front();

    CirQue<vector<int>> cp;

    cp = ci;
    cout << cp.size() << ' ' << cp.front() << ' ' << cp.back() << '\n';
    cp.push_back(6);
    cout << cp.size() << ' ' << cp.front() << ' ' << cp.back() << '\n';
}

```

21.4 Partial specializations

In the previous section class template specializations were introduced. In this section we'll introduce a variant of this specialization, both in number and type of template parameters that are specialized. *Partial specializations* may be defined for class templates having multiple template parameters. Function templates cannot be partially specialized.

With partial specializations a subset (any subset) of template type parameters are given specific values. It is also possible to use a class template partial specialization when the intent is to specialize the class template, but to parameterize the data type that is processed by the specialization.

To start our discussion with an example of the latter use of a partial class template specialization consider the class `CirQue<vector<int>>` developed in the previous section. When designing `CirQue<vector<int>>` you may have asked yourself how many specializations you'd have to implement. One for `vector<int>`, one for `vector<string>`, one for `vector<double>`? As long as the data types handled by the vector used by the class `CirQue<vector<...>>` behaves like an `int` (i.e., is a value-type of class) the answer is: zero. Instead of defining full specializations for each new data type the data type itself can be parameterized, resulting in a partial specialization:

```
template <typename Data>
class CirQue<std::vector<Data>>
{
    ...
};
```

The above class is a specialization as a template argument list is appended to the `CirQue` class name. But as the class template itself has a non-empty template parameter list it is in fact recognized as a partial specialization. There is one characteristic that distinguishes the implementation (subsequent to the class template's interface) of a class template member function of a partial specialization from the implementation of a member function of a full specialization. Implementations of partially specialized class template member functions receives a template header. No template headers are used when implementing fully specialized class template members.

Implementing the partial specialization for `CirQue` is not difficult and is left as an exercise for the reader (hints: simply change `int` into `Data` in the `CirQue<vector<int>>` specialization of the previous section). Remember to prefix the type iterator by `typename` (as in `typedef typename DataVect::iterator iterator`) (as discussed in section 21.2.1).

The remainder of this section concentrates on specializing class template non-type template parameters. These partial specializations will be illustrated using some simple concepts defined in matrix algebra, a branch of linear algebra.

A matrix is commonly thought of as a table of some rows and columns, filled with numbers. Immediately we recognize an opening for using templates: the numbers might be plain `double` values, but they could also be complex numbers, for which our complex container (cf. section 12.4) might prove useful. Our class template is therefore provided with a `DataType` template type parameter. It is specified when a matrix is constructed. Some simple matrices using `double` values, are:

1	0	0		An identity matrix,
0	1	0		(a 3 x 3 matrix).
0	0	1		
1.2	0	0	0	A rectangular matrix,
0.5	3.5	18	23	(a 2 x 4 matrix).
1	2	4	8	A matrix of one row
				(a 1 x 4 matrix), also known as a
				'row vector' of 4 elements.
				(column vectors are analogously defined)

Since matrices consist of well defined numbers of rows and columns (the *dimensions* of the matrix), that normally do not change when matrices are used, we might consider specifying their values as template non-type parameters. Since the `DataType = double` selection will be used in the majority of cases, `double` can be selected as the template's default type argument. Since it's a sensible default, the `DataType` template type parameter is used last in the template type parameter list.

Our template class `Matrix` begins its life as:

```
template <size_t Rows, size_t Columns, typename DataType = double>
class Matrix
...

```

Various operations are defined on matrices. They may, for example be added, subtracted or multiplied. Here we will not focus on these operations. Rather, we concentrate on some simple operations: computing marginals and sums:

- *Row marginals* are obtained by adding, for each row, all the row's elements and putting these (Rows) sums in corresponding elements of a column vector of Rows elements.
- *Column marginals* are obtained by adding, for each column, all the column's elements and putting these (Columns) sums in corresponding elements of a row vector of Columns elements.
- The sum of all elements of a matrix can of course be computed as the sum of the elements of one of its marginals.

The following example shows a matrix, its marginals, and the sum of its values:

	matrix:			row	
				marginals:	
	1	2	3		6
	4	5	6		15
column	5	7	9	21	(sum)
marginals					

What do we want our class template to offer?

- It needs a place to store its matrix elements. This can be defined as an array of 'Rows' rows each containing 'Columns' elements of type `DataType`. It can be an array, rather than a pointer, since the matrix' dimensions are known *a priori*. Since a vector of Columns elements (a *row* of the matrix), as well as a vector of Row elements (a *column* of the matrix) is often used, the class could use *typedefs* to represent them. The class interface's initial section thus contains:

```
typedef Matrix<1, Columns, DataType>      MatrixRow;
typedef Matrix<Rows, 1, DataType>         MatrixColumn;

MatrixRow d_matrix[Rows];

```

- It should offer constructors: a default constructor and (e.g.,) a constructor initializing the matrix from a stream. A copy or move constructor is not required as the class does not use pointers. Likewise, no overloaded assignment operator or destructor is required. Implementations:

```
template <size_t Rows, size_t Columns, typename DataType>
Matrix<Rows, Columns, DataType>::Matrix()
{
    std::fill(d_matrix, d_matrix + Rows, MatrixRow());
}

```

```

template <size_t Rows, size_t Columns, typename DataType>
Matrix<Rows, Columns, DataType>::Matrix(std::istream &str)
{
    for (size_t row = 0; row < Rows; row++)
        for (size_t col = 0; col < Columns; col++)
            str >> d_matrix[row][col];
}

```

- The class's `operator[]` member (and its `const` variant) only handles the first index, returning a reference to a complete `MatrixRow`. How elements in a `MatrixRow` can be retrieved is shortly covered. To keep the example simple, no array bound check has been implemented:

```

template <size_t Rows, size_t Columns, typename DataType>
Matrix<1, Columns, DataType>
&Matrix<Rows, Columns, DataType>::operator[](size_t idx)
{
    return d_matrix[idx];
}

```

- Now we get to the interesting parts: computing marginals and the sum of all elements in a `Matrix`. Marginals are vectors (either a `MatrixRow`, containing the column marginals; a `MatrixColumn`, containing the row marginals; or a single value) computed as the sum of a vector of marginals or as the value of a 1×1 matrix initialized from a generic `Matrix`. As marginals can be considered special forms of matrices we can now construct *partial specializations* to handle `MatrixRow` and `MatrixColumn` objects, and a partial specialization handling 1×1 matrices. The required specializations are shortly defined. They are used here to compute marginals and the sum of all elements in a matrix. Here are the implementations of the members computing the marginals and the sum of all elements of a matrix:

```

template <size_t Rows, size_t Columns, typename DataType>
Matrix<1, Columns, DataType>
Matrix<Rows, Columns, DataType>::columnMarginals() const
{
    return MatrixRow(*this);
}

template <size_t Rows, size_t Columns, typename DataType>
Matrix<Rows, 1, DataType>
Matrix<Rows, Columns, DataType>::rowMarginals() const
{
    return MatrixColumn(*this);
}

template <size_t Rows, size_t Columns, typename DataType>
DataType Matrix<Rows, Columns, DataType>::sum() const
{
    return rowMarginals().sum();
}

```

Class template *partial specializations* can be defined for any (subset) of template parameters. They can be defined for template type parameters and for template non-type parameters alike. Our first partial specialization defines a row of a generic `Matrix`, mainly (but not only) used for the construction of column marginals. Here is how such a partial specialization is designed:

- The partial specialization starts with a template header defining all template parameters that are *not* specialized in the partial specialization. This template header cannot specify any defaults (like `DataType = double`) since defaults were already specified by the generic class template definition. The specialization *must* follow the definition of the generic class template's definition, or the compiler complains that it doesn't know what class is being specialized. Following the

template header, the class's interface starts. It's a class template (partial) specialization so the class name must be followed by a template argument list specifying the template arguments used by the partial specialization. The arguments specify explicit types or values for some of the template's parameters. Remaining types are simply copied from the class template partial specialization's template parameter list. E.g., the `MatrixRow` specialization specifies 1 for the generic class template's `Rows` type parameter (as we're talking here about a single row). Both `Columns` and `DataType` remain to be specified. The `MatrixRow` partial specialization therefore starts as follows:

```
template <size_t Columns, typename DataType> // no default allowed
class Matrix<1, Columns, DataType>
```

- A `MatrixRow` holds the data of a single row. So it needs a data member storing `Columns` values of type `DataType`. Since `Columns` is a constant value, the `d_row` data member can be defined as an array:

```
DataType d_column[Columns];
```

- The class template partial specialization's constructors require some attention. The default constructor is simple. It merely initializes the `MatrixRow`'s data elements using `DataType`'s default constructor:

```
template <size_t Columns, typename DataType>
Matrix<1, Columns, DataType>::Matrix()
{
    std::fill(d_column, d_column + Columns, DataType());
}
```

Another constructor is needed initializing a `MatrixRow` object with the column marginals of a generic `Matrix` object. This requires us to provide the constructor with a non-specialized `Matrix` parameter.

The rule of thumb here is to define a member template that allows us to keep the general nature of the parameter. Since the generic `Matrix` template requires three template parameters. Two of these were already provided by the template specialization. The third parameter is mentioned in the member template's template header. Since this parameter refers to the number of rows of the generic matrix it is simply called `Rows`.

Here then is the implementation of the second constructor, initializing the `MatrixRow`'s data with the column marginals of a generic `Matrix` object:

```
template <size_t Columns, typename DataType>
template <size_t Rows>
Matrix<1, Columns, DataType>::Matrix(
    Matrix<Rows, Columns, DataType> const &matrix)
{
    std::fill(d_column, d_column + Columns, DataType());

    for (size_t col = 0; col < Columns; col++)
        for (size_t row = 0; row < Rows; row++)
            d_column[col] += matrix[row][col];
}
```

The constructor's parameter is a reference to a `Matrix` template using the additional `Row` template parameter as well as the template parameters of the partial specialization.

- We don't really require additional members to satisfy our current needs. To access the data elements of the `MatrixRow` an overloaded operator `[]()` is of course useful. Again, the `const` variant can be implemented like the non-`const` variant. Here is its implementation:

```
template <size_t Columns, typename DataType>
```

```

DataType &Matrix<1, Columns, DataType>::operator[](size_t idx)
{
    return d_column[idx];
}

```

Now that we have defined the generic `Matrix` class and the partial specialization defining a single row the compiler will select the row's specialization whenever a `Matrix` is defined using `Row = 1`. For example:

```

Matrix<4, 6> matrix;           // generic Matrix template is used
Matrix<1, 6> row;             // partial specialization is used

```

The partial specialization for a `MatrixColumn` is constructed similarly. Let's present its highlights (the full `Matrix` class template definition as well as all its specializations are provided in the `cplusplus.yo.zip` archive (at [SourceForge](http://sourceforge.net/projects/cppannotations/)¹) in the file `yo/classtemplates/examples/matrix.h`):

- The class template partial specialization once again starts with a template header. Now the class interface specifies a fixed value for the second template parameter of the generic class template. This illustrates that we can construct partial specializations for every single template parameter; not just for the first or the last:

```

template <size_t Rows, typename DataType>
class Matrix<Rows, 1, DataType>

```

- Its constructors are implemented completely analogously to the way the `MatrixRow` constructors were implemented. Their implementations are left as an exercise to the reader (and they can be found in `matrix.h`).
- An additional member `sum` is defined to compute the sum of the elements of a `MatrixColumn` vector. It's simply implemented using the `accumulate` generic algorithm:

```

template <size_t Rows, typename DataType>
DataType Matrix<Rows, 1, DataType>::sum()
{
    return std::accumulate(d_row, d_row + Rows, DataType());
}

```

The reader might wonder what happens if we specify the following matrix:

```

Matrix<1, 1> cell;

```

Is this a `MatrixRow` or a `MatrixColumn` specialization? The answer is: neither. It's ambiguous, precisely because *both* the columns *and* the rows could be used with a (different) template partial specialization. If such a `Matrix` is actually required, yet another specialized template must be designed. Since this template specialization can be useful to obtain the sum of the elements of a `Matrix`, it's covered here as well.

- This class template partial specialization also needs a template header, this time only specifying `DataType`. The class definition specifies two fixed values: 1 for the number of rows and 1 for the number of columns:

```

template <typename DataType>
class Matrix<1, 1, DataType>

```

¹<http://sourceforge.net/projects/cppannotations/>

- The specialization defines the usual batch of constructors. Constructors expecting a more generic `Matrix` type are again implemented as member templates. For example:

```
template <typename DataType>
template <size_t Rows, size_t Columns>
Matrix<1, 1, DataType>::Matrix(
    Matrix<Rows, Columns, DataType> const &matrix)
:
    d_cell(matrix.rowMarginals().sum())
{}

template <typename DataType>
template <size_t Rows>
Matrix<1, 1, DataType>::Matrix(Matrix<Rows, 1, DataType> const &matrix)
:
    d_cell(matrix.sum())
{}

```

- Since `Matrix<1, 1>` is basically a wrapper around a `DataType` value, we need members to access that latter value. A type conversion operator might be usefull, but we also defined a `get` member to obtain the value if the conversion operator isn't used by the compiler (which happens when the compiler is given a choice, see section 10.3). Here are the accessors (leaving out their `const` variants):

```
template <typename DataType>
Matrix<1, 1, DataType>::operator DataType &()
{
    return d_cell;
}

template <typename DataType>
DataType &Matrix<1, 1, DataType>::get()
{
    return d_cell;
}

```

The next main function shows how the `Matrix` class template and its partial specializations can be used:

```
#include <iostream>
#include "matrix.h"
using namespace std;

int main(int argc, char **argv)
{
    Matrix<3, 2> matrix(cin);

    Matrix<1, 2> colMargins(matrix);
    cout << "Column marginals:\n";
    cout << colMargins[0] << " " << colMargins[1] << '\n';

    Matrix<3, 1> rowMargins(matrix);
    cout << "Row marginals:\n";
    for (size_t idx = 0; idx < 3; idx++)
        cout << rowMargins[idx] << '\n';

    cout << "Sum total: " << Matrix<1, 1>(matrix) << '\n';
    return 0;
}

```

```

/*
    Generated output from input: 1 2 3 4 5 6

    Column marginals:
    9 12
    Row marginals:
    3
    7
    11
    Sum total: 21
*/

```

21.5 Variadic templates (C++0x)

Up to this point we've only encountered templates having a fixed number of template parameters. The C++0x standard extends this with *variadic templates*.

Variadic templates are defined for function templates and for class templates. Variadic templates allow us to specify an arbitrary number of template arguments of any type.

Variadic templates were added to the language to prevent us from having to define many overloaded templates and to be able to create *type safe* variadic functions.

Although C (and C++) support variadic functions, their use has always been deprecated in C++ as those functions are notoriously *type-unsafe*. Variadic function templates can be used to process objects that until now couldn't be processed properly by C-style variadic functions.

Template header of variadic templates show the phrase `typename ... Params` in their template headers (Params being a formal name). A variadic class template `Variadic` could be declared as follows:

```
template<typename ... Params> class Variadic;
```

Assuming the class template's definition is available then this template can be instantiated using any number of template arguments. Example:

```

class Variadic<
    int,
    std::vector<int>,
    std::map<std::string, std::vector<int>>
> v1;

```

The template argument list of a variadic template can be empty. Example:

```
class Variadic<> empty;
```

If this is considered undesirable an empty template argument list can be prevented by providing one or more fixed parameters. Example:

```

template<typename First, typename ... Rest>
class tuple;

```

C's function `printf` is a well-known example of a type-unsafe function. It is turned into a type-safe function when it is implemented as a variadic function template. Not only does this turn the function

into a type-safe function but it is also automatically extended to accept any type that can be defined by C++. Here is a possible declaration of a variadic function template `printcpp`:

```
template<typename ... Params>
void printcpp(std::string const &strFormat, Params ... parameters);
```

The ellipsis (...) used in the declaration serves two purposes:

- In the template header it is written to the *left* of a template parameter name where it declares a *parameter pack*. A parameter pack allows us to specify any number of template arguments when instantiating the template. Parameter packs can be used to bind type and non-type template arguments to template parameters.
- In a template implementation it appears to the *right* of the template pack's parameter name. In that case it represents a series of template arguments that are subsequently matched with a function parameter that in turn is provided to the right of the ellipsis. Here the ellipsis is known as the *unpack operator* as it 'unpacks' a series of arguments in a function's argument list thereby implicitly defining its parameters.

C++ offers no syntax to determine the individual template arguments. However, the arguments can be determined recursively. An example is provided in the next section. The *number* of arguments can be determined using a new invocation of the `sizeof` operator:

```
template<typename ... Params>
struct StructName
{
    static size_t const s_size = sizeof ... (Params);
};

// StructName<int, char>::s_size          -- initialized to 2
```

21.5.1 Defining and using variadic templates (C++0x)

The arguments associated with a variadic template parameter are not directly available to the implementation of a function or class template. resort to other means to obtain them.

By defining an partial specialization of a variadic template explicitly defining an additional template type parameter we can associate the first template argument of a parameter pack with the additional type parameter. The setup of such a variadic function template (e.g., `printcpp`, see the previous section) is as follows:

- The `printcpp` function receives at least a format string. Following the format string any number of additional arguments may be specified.
- If there are no arguments trailing the format string then there is no need to use a function template. An overloaded (non-template) function is defined to handle this situation.
- A variadic function template handles all remaining situations. In this case there is always at least one arguments trailing the format string. That argument's type is matched with the variadic template function's first (ordinary) template type parameter `First`. The types of any remaining arguments are bound to the template function's second template parameter, which is a parameter pack.
- The variadic function template processes the argument trailing the format string. Then it recursively calls itself passing the format string and the parameter pack to the recursive call
- If the recursive call merely receives the format string the overloaded (non-template) function is called (cf. section 20.9) ending the recursion. Otherwise the parameter pack's first argument is matched with the recursive call's `First` parameter. As reduces the size of the recursive call's parameter pack the recursion will eventually stop.

The overloaded non-template function prints the remainder of the format string, *en passant* checking for any left-over format specifications:

```
void printcpp(string const &format)
{
    size_t left = 0;
    size_t right = 0;

    while (true)
    {
        if ((right = format.find('%', right)) == string::npos)
            break;
        if (format.find("%%", right) != right)
            throw std::runtime_error(
                "printcpp: missing arguments");
        ++right;
        cout << format.substr(left, right - left);
        left = ++right;
    }
    cout << format.substr(left);
}
```

Here is the variadic function template's implementation:

```
template<typename First, typename ... Params>
void printcpp(std::string const &format, First value, Params ... params)
{
    size_t left = 0;
    size_t right = 0;
    while (true)
    {
        if ((right = format.find('%', right)) == string::npos) // 1
            throw std::logic_error("printcpp: too many arguments");

        if (format.find("%%", right) != right) // 2
            break;

        ++right;
        cout << format.substr(left, right - left);
        left = ++right;
    }
    cout << format.substr(left, right - left) << value;
    printcpp(format.substr(right + 1), params ...);
}
```

- At 1 the format string is searched for a parameter specification %. If none is found then the function is called with too many arguments and it throws an exception;
- At 2 it verifies that it has not encountered %%. If only a single % has been seen the while-loop ends, the format string is inserted into `cout` up to the % followed by `value`, and the recursive call receives the remaining part of the format string as well as the remaining parameter pack;
- If %% was seen the format string is inserted up to the second %, which is ignored, and processing of the format string continues beyond the %%.

Make sure that the overloaded function is at least declared before the compiler processes the function template's definition or it won't call the overloaded function `printcpp` when compiling the function template.

Different from C's `printf` function `printf` only recognizes `%` and `%%` as format specifiers. The above implementation does not recognize, e.g., field widths. Type specifiers like `%c` and `%x` are of course not needed as `ostream`'s insertion operator is aware of the types of the arguments that are inserted into the `ostream`. Extending the format specifiers so that field widths etc. are recognized by this `printf` implementation is left as an exercise to the reader. Here is an example showing how `printf` can be called:

```
printf("Hello % with %%main%% called with % args"
      " and a string showing %\n",
      "world", argc, string("A String"));
```

21.5.2 Perfect forwarding (C++0x)

Consider `string`'s member `insert`. `String::insert` has several overloaded implementations. It can be used to insert text (completely or partially) provided in a `string` or in a `char const *` argument; to insert single characters a specified number of times; iterators can be used to specify the range of characters to be inserted; etc., etc.. All in, `string` offers five overloaded `insert` members.

Assume the existence of a class `Inserter` that is used to insert information into all kinds of objects. Such a class could have a `string` data member into which information can be inserted. `Inserter`'s interface only partially has to copy `string`'s interface to realize this: only `string::insert`'s interfaces must be duplicated. These duplicating interfaces often contain one statement (calling the appropriate member function of the object's data member) and are for this reason often implemented in-line. These wrapper functions merely *forward* their parameters to the appropriate member function of the object's data member.

Factory functions also frequently forward their parameters to the constructors of objects that they return.

Before the C++0x standard the interfaces of overloaded functions needed to be duplicated by the forwarding entity: `Inserter` needed to duplicate the interfaces of all five `string::insert` members; a factory function needed to duplicate the interfaces of the constructors of the class of the objects it returned.

The C++0x standard simplifies and generalizes forwarding of parameters by offering *perfect forwarding*, implemented through rvalue references and variadic templates. With perfect forwarding the arguments passed to functions are 'perfectly forwarded' to nested functions. Forwarding is called *perfect* as the arguments are forwarded in a type-safe way. To use perfect forwarding nested functions must define parameter lists matching the forwarding parameters both in types and number.

Perfect forwarding is easily implemented:

- The forwarding function is defined as a variadic template;
- The forwarding function's parameter list is an *rvalue reference parameter pack* (e.g., `Params && ... params`);
- `std::forward` is used to forward the forwarding function's arguments to the nested function, keeping track of their types and number. Before using `forward` the `<utility>` header file must have been included. The nested function is then called using this stanza for its arguments: `std::forward<Params>(params)`

In the following example perfect forwarding is used to implement `Inserter::insert`. The `insert` function that's actually called now depends on the types and number of arguments that are passed to `Inserter::insert`:

```
class Inserter
{
    std::string d_str; // somehow initialized
```

```

public:
    // constructors not implemented,
    // but see below
    Inserter();
    Inserter(std::string const &str);
    Inserter(Inserter const &other);
    Inserter(Inserter const &&other);

    template<typename ... Params>
    void insert(Params && ... params)
    {
        d_str.insert(std::forward<Params>(params) ...);
    }
};

```

A factory function returning a `Inserter` can also easily be implemented using perfect forwarding. Rather than defining four overloaded factory functions a single one now suffices. By providing the factory function with an additional template type parameter specifying the class of the object to construct the factory function is turned into a completely general factory function:

```

template <typename Class, typename ... Params>
Class factory(Params && ... params)
{
    return Class(std::forward<Params>(params) ...);
}

```

Here are some examples showing its use:

```

Inserter inserter(factory<Inserter>("hello"));
string delimiter(factory<string>(10, '='));
Inserter copy(factory<Inserter>(inserter));

```

The function `std::forward` is provided by the standard library. It performs no magic, but merely returns `params` as an nameless object. That way it acts like `std::move` that also removes the name from an object, returning it as a nameless object. The unpack operator has nothing to do with the use of `forward` but merely tells the compiler to apply `forward` to each of the arguments in turn. Thus it behaves similarly to C's ellipsis operator used by variadic functions.

Perfect forwarding was introduced in section 20.3.5: a template function defining a `Type &¶m`, with `Type` being a template type parameter will convert `Type &&` to `Tp &` if the function is called with an argument of type `Tp &`. Otherwise it will bind `Type` to `Tp`, with `param` being defined as `Tp &¶m`. As a result an *lvalue* argument will bind to an lvalue-type (`Tp &`), while an *rvalue* argument will bind to an rvalue-type (`Tp &&`).

The function `std::forward` merely passes the argument (and its type) on to the called function or object. Here is its simplified implementation:

```

typedef <type T>
T &&forward(T &&a)
{
    return a;
}

```

Since `T &&` turns into an lvalue reference when `forward` is called with an lvalue (or lvalue reference) and remains an rvalue reference if `forward` is called with an rvalue reference and since `forward` (like `std::move`) anonymizes the variable passed as argument to `forward` the argument value is forwarded while keeping its type from the function's parameter to the called function's argument. This is called *perfect forwarding* as the called function will only be called if the types of the arguments used when

calling the ‘outer’ function (e.g., `factory`) exactly match the types of the parameters of the called function (e.g., `Class`’s constructor). Perfect forwarding therefore is a tool to uphold type safety.

A cosmetic improvement to `forward` forces users of `forward` to specify the type to use rather than to have the compiler deduct the type as a result of the function template parameter type deduction’s process. This is realized by a small support struct template:

```
template <typename T>
struct identity
{
    typedef T type;
};
```

This struct merely defines `identity::type` as `T`, but as it is a struct it must be specified explicitly. It cannot be determined from the function’s argument itself. The subtle modification to the above implementation of `forward` thus becomes (cf. section 21.2.1 for an explanation of the use of `typename`):

```
typedef <type T>
T &&forward(typename identity<T>::type&& a)
{
    return a;
}
```

Now `forward` must explicitly state the `a`’s plain type, as in:

```
std::forward<Params>(params)
```

Using the `std::forward` function and the rvalue reference specification is not restricted to the context of parameter packs. Because of the special way rvalue references to template type parameters are treated (cf. section 20.3.5) they can profitably be used to forward individual function parameters as well. Here is an example showing how an argument to a function can be forwarded from a template to a function that is itself passed to the template as a pointer to a (unspecified) function:

```
template<typename Fun, typename ArgType>
void caller(Fun fun, ArgType &&arg)
{
    fun(std::forward<ArgType>(arg));
}
```

A function `display(ostream &out)` and `increment(int &x)` may now both be called through `caller`. Example:

```
caller(display, cout);
int x = 0;
caller(increment, x);
```

21.5.3 The unpack operator (C++0x)

The *unpack operator* is used to obtain template arguments in many situations. No mechanism other than recursion (as shown in section 21.5.1) is available to obtain the individual types and values of a variadic template.

The unpack operator can also be used to define template classes that are derived from any number of base classes. Here is how it’s done:

```
template <typename... BaseClasses>
```

```

class Combi: public BaseClasses ...           // derive from base classes
{
    public:

                                // specify base class objects
                                // to its constructor using
                                // perfect forwarding
    Combi(BaseClasses && ... baseClasses)
    :
        BaseClasses(baseClasses) ...         // use base class initializers
    {}                                         // for each of the base
};                                           // classes

```

This allows us to define classes that combine the features of any number of other classes. If the class `Combi` is derived of classes `A`, `B`, and `C` then `Combi` is-a `A`, `B`, and `C`. It should of course be given a virtual destructor. A `Combi` object can be passed to functions expecting pointers or references to any of its base class type objects. Here is an example defining `Combi` as a class derived from a vector of complex numbers, a string and a pair of ints and doubles (using uniform initializers in a sequence matching the sequence of the types specified for the used `Combi` type):

```

typedef Combi<vector<double>>, string, pair<int, double>> MultiTypes;
MultiTypes mt = {{3.5, 4}, "mt", {1950, 1.72}};

```

The same construction can also be used to define template data members that support variadic type lists such as tuples (cf. section ref TUPLES). Such a class could be designed along these lines:

```

template <typename ... Types>
struct Multi
{
    std::tuple<Types ...> d_tup;           // define tuple for Types types

    Multi(Types ... types)
    :                                     // initialize d_tup from Multi's
        d_tup(std::forward<Types>(types) ...) // arguments
    {}
};

```

The ellipses that are used when forwarding parameter packs are essential. The compiler considers their omission an error. In the following struct definition it was the intent of the programmer to pass a parameter pack on to a nested object construction but ellipses were omitted while specifying the template parameters, resulting in a *parameter packs not expanded with '...'* error message:

```

template <int size, typename ... List>
struct Call
{
    Call(List && ... list)
    {
        Call<size - 1, List &&> call(std::forward<List>(list) ...);
    }
};

```

Instead of the above definition of the `call` object the programmer should have used:

```

Call<size - 1, List && ...> call(std::forward<List>(list) ...);

```


21.5.4 Computing the return type of function objects (C++0x)

As amply illustrated in chapter 19 function objects play an important role with generic algorithms. Like generic algorithms themselves, function objects can be generically defined as members of class templates. When the function call operator (`operator()`) of such classes themselves have arguments then the types of those arguments may also be abstracted by defining the function call operator itself as a member template. Example:

```
template <typename Class>
class Filter
{
    Class obj;
public:
    template <typename Param>
    Param operator()(Param const &param) const
    {
        return obj(param);
    }
};
```

The template class `Filter` is a wrapper around `Class`, filtering `Class`'s function call operator through its own function call operator. In the above example the return value of `Class`'s function call operator is simply passed on, but any other manipulation is of course also possible.

A type that is specified as `Filter`'s template type argument may of course have multiple function call operators:

```
struct Math
{
    int operator()(int x);
    double operator()(double x);
};
```

`Math` objects can now be filtered using `Filter<Math> fm` using `Math`'s first or second function call operator, depending on the actual argument type. With `fm(5)` the `int`-version is used, with `fm(12.5)` the `double`-version is used.

Unfortunately this scheme doesn't work if the function call operators have different return and argument types. Because of this the following class `Convert` cannot be used with `Filter`:

```
struct Convert
{
    double operator()(int x);           // int-to-double
    std::string operator()(double x);    // double-to-string
};
```

This problem can be tackled successfully by the class template `std::result_of<Functor(TypeList)>` that is defined by the C++0x standard. Before using `std::result_of` the header file `<functional>` must have been included.

The `result_of` class template offers a typedef, type, representing the type that is returned by `Functor<TypeList>`. It can be used to improve `Filter` as follows:

```
template <typename Class>
class Filter
{
    Class obj;
public:
```

```

        template <typename Arg>
            typename std::result_of<Class(Arg)>::type
            operator()(Arg const &arg) const
            {
                return obj(arg);
            }
};

```

Using this definition, `Filter<Convert> fc` can be constructed and `fc(5)` will return a double, while `fc(4.5)` returns a `std::string`.

The class `Convert` must define the relationships between its function call operators and their return types. Predefined function objects (like those in the standard template library) already do so, but self-defined function objects must do this explicitly.

If a function object class defines only one function call operator it can define its return type by a typedef. If the above class `Convert` would only define the first of its two function call operators then the typedef (in the class's public section) should be:

```
typedef double type;
```

If multiple function call operators are defined, each with its own signature and return type, then the association between signature and return type is set up as follows (all in the class's public section):

- define a generic struct `result` like this:

```

template <typename Signature>
struct result;

```

- For each function call signature define a *specialization* of struct `result`. `Convert`'s first function call operator gives rise to:

```

template <typename Class>
struct result<Class(int)>
{
    typedef double type;
};

```

and `Convert`'s second function call operator to:

```

template <typename Class>
struct result<Class(double)>
{
    typedef std::string type;
};

```

- In cases where function call operators have multiple arguments the specifications should again provide for the correct signatures. A function call operator called with an `int` and a `double`, returning a `size_t` gets:

```

template <typename Class>
struct result<Class(int, double)>
{
    typedef size_t type;
};

```

21.5.5 Tuples (C++0x)

The C++0x standard offers a *generalized pair* container: the *tuple*, covered in this section. Before tuples can be used the header file `<tuple>` must have been included.

Whereas `std::pair` containers have limited functionality and only support two members, tuples have slightly more functionality and may contain an unlimited number of different data types. In that respect a tuple can be thought of the ‘template’s answer to C’s `struct`’.

A tuple’s generic declaration (and definition) uses the variadic template notation:

```
template <class ...Types>
class tuple;
```

Here is an example of its use:

```
typedef std::tuple<int, double &, std::string, char const *> tuple_idsc;

double pi = 3.14;
tuple_idsc idsc(59, pi, "hello", "fixed");

// access a field:
std::get<2>(idsc) = "hello world";
```

The `std::get<idx>(tupleObject)` function template returns a reference to the `idx+sup(th)` field of the tuple `tupleObject`. Index 0 returns a reference to its first value. The index is specified as the function template’s non-type template argument.

Tuples may be constructed without specifying initial values. Primitive types are initialized to zeroes; class type fields are initialized by their default constructors. Be aware that in some situations the construction of a tuple may succeed but its use may fail. Consider:

```
tuple<int &> empty;
cout << get<0>(empty);
```

Here the tuple `empty` cannot be used as its `int &` field is an undefined reference. `Empty`’s construction, however, succeeds.

Tuples may be assigned to each other if their type lists are identical; if supported by their constituent types copy constructors are available as well. Copy construction and assignment is also available if a right-hand type can be converted to its matching left-hand type or if the left-hand type can be constructed from the matching right-hand type. Tuples (matching in number and (convertible) types) can be compared using relational operators as long as their constituent types support comparisons. In this respect tuples are like pairs.

Tuples offer the following static elements (using compile-time initialization):

- `std::tuple_size<Tuple>::value` returns the number of types defined for the tuple type `Tuple`. Example:

```
cout << tuple_size<tuple_idsc>::value << '\n'; // displays: 4
```

- `std::tuple_element<idx, Type>::type` returns the type of element `idx` of `Tuple`. Example:

```
tuple_element<2, tuple_idsc>::type text; // defines std::string text
```

The unpack operator can also be used to forward the arguments of a constructor to a tuple data member. Consider a class `Wrapper` that is defined as a variadic template:

```
template <typename ... Params>
class Wrapper
{
    ...
    public:
        Wrapper(Params && ... params);
};
```

This class may be given a tuple data member which should be initialized by the types and values that are used when initializing an object of the class `Wrapper` using perfect forwarding. Comparable to the way a class may inherit from its template types (cf. section 21.5.3) it may forward its types and constructor arguments to its tuple data member:

```
template <typename ... Params>
class Wrapper
{
    std::tuple<Params ...> d_tuple;    // same types as used for
                                      // Wrapper itself

    public:
        Wrapper(Params && ... params)
        :                                     // initialize d_tuple with
                                              // Wrapper's arguments
          d_tuple(std::forward<Params>(params) ...)
        {}
};
```

21.5.6 User-defined literals (C++0x, ?)

The C++0x standard offers *extensible literals*, also known as *user defined literals*. Standard C++ defines various kinds of literals, like numerical constants (with or without suffixes), character constants and string (textual) literals.

Under the C++0x standard a literal, e.g., 1013, can be looked at in two ways: as a *raw literal* in which the literal as ASCII string or series of characters is passed to a processing function or as a *cooked literal* in which case the compiler already performs some conversion.

To extend a literal either a processing function or a variadic function template must be defined. Both functions must start with an underscore and all user defined literals are suffixes.

Using `Type` to represent the resulting type of the literal a (raw) literal can be declared using the following syntax (the initial underscore in `_functionName` is required):

```
Type operator "" _functionName(char const *text [, size_t len]);
```

Here, `size_t len` is an optional parameter receiving `text`'s length (as returned by C's `strlen` function)

The function `_functionName` is implemented by the software engineer and must return a value of type `Type`. Here is an example of the definition and use of an user defined literal `_kmh` returning a `double`:

```
double _kmh(char const *speed)
{
    std::istringstream in(speed);
```

```

    double ret;
    in >> ret;
    return ret;
}
double operator "" _kmh(char const *speed);

double value = "120"_kmh;

```

21.6 Template typedefs and 'using' declarations (C++0x, ?)

The `typedef` keyword is frequently used to define 'shorthand' notations for extensive type names. Consider the following example:

```

typedef
    std::map<std::shared_ptr<KeyType>, std::vector<std::set<std::string>>>
        MapKey_VectorStringSet;

MapKey_VectorStringSet mapObject;

```

In situations like this the actual type of the key or the data stored in the map's vector might vary. Some may store `string` objects, other may store double values.

A class may be defined based on the above map allowing the specification of the final key and value types. Example:

```

template <typename DeepKey, typename DeepValue>
class DeepMap: public std::map<std::shared_ptr<DeepKey>,
                             std::vector<std::set<DeepMap>>>
{
};

```

This increases the flexibility of the initially defined map as it is now possible to write

```

DeepMap<KeyType, std::string> mapObject;

```

The C++0x standard adds to this the possibility to pre-specify either of these template type parameters. To preset the key's type to `std::string` leaving the data type open for later specification the following *template using declaration* syntax is available:

```

template<typename DeepValue>
using MapString_DeepValue = DeepMap<std::string, DeepValue>;

MapString_DeepValue<size_t> specialMap;

```

The `specialMap` now uses `shared_ptr<string>` for its key and `vector<set<size_t>` for its data type. A similar shorthand notation can be used to pre-specify the value type leaving the key type open for later specification.

In addition to the above template syntax the `using` keyword can also be used to separate a typedef name from a complex type definition. Consider constructing a typedef defining a pointer to a function expecting and returning a double. The traditional way to define such a type is as follows:

```

typedef double (*PFD)(double);

```

In addition the C++0x standard offers the following alternative syntax:

```

using PFD = double (*)(double);

```

21.7 Instantiating class templates

Class templates are instantiated when an object of a class template is defined. When a class template object is defined or declared its template parameters must explicitly be specified.

Template parameters are *also* specified when default template parameter values are specified albeit that in that case the compiler provides the defaults (cf. section 21.4 where `double` is used as the default type to use for the template's `DataType` parameter). The actual values or types of template parameters are *never* deduced from arguments as is done with function template parameters. So to define a `Matrix` of complex-valued elements, the following syntax is used:

```
Matrix<3, 5, std::complex> complexMatrix;
```

Since the class template `Matrix` uses a default data type a matrix of double-valued elements can be defined like this:

```
Matrix<3, 5> doubleMatrix;
```

A class template object may be *declared* using the keyword `extern`. For example, to *declare* the matrix `complexMatrix` use:

```
extern Matrix<3, 5, std::complex> complexMatrix;
```

A class template declaration suffices to compile return values or parameters that are of class template types. Example: the following source file may be compiled, although the compiler hasn't seen the definition of the `Matrix` class template. Generic classes and (partial) specializations may all be declared. A function expecting or returning a class template object, reference, or parameter automatically becomes a function template itself. This is necessary to allow the compiler to tailor the function to the types of various actual arguments that may be passed to the function:

```
#include <cstddef>

template <size_t Rows, size_t Columns, typename DataType = double>
class Matrix;

template <size_t Columns, typename DataType>
class Matrix<1, Columns, DataType>;

Matrix<1, 12> *function(Matrix<2, 18, size_t> &mat);
```

When class templates are *used* the compiler must first have seen their implementations. So, template member functions must be known to the compiler when the template is instantiated. This does not mean that *all* members of a template class are instantiated or must have been seen when a class template object is defined. The compiler only instantiates those members that are actually used. This is illustrated by the following simple class `Demo` that has two constructors and two members. When we use one constructor and call one member in `main` note the sizes of the resulting object file and executable program. Next the class definition is modified in that the unused constructor and member are commented out. Again we compile and link the program. Now observe that these latter sizes are identical to the former sizes. There are other ways to illustrate that only used members are instantiated. The `nm` program could be used. It shows the symbolic contents of object files. Using `nm` we'll reach the same conclusion: *only template member functions that are actually used are instantiated*. Here is the class template `Demo` that was used for our little experiment. In `main` only the first constructor and the first member function are called and thus only these members were instantiated:

```
#include <iostream>
```

```

template <typename Type>
class Demo
{
    Type d_data;
public:
    Demo();
    Demo(Type const &value);
    void member1();
    void member2(Type const &value);
};
template <typename Type>
Demo<Type>::Demo()
:
    d_data(Type())
{}
template <typename Type>
void Demo<Type>::member1()
{
    d_data += d_data;
}

// the following members should be commented out before
// compiling for the 2nd time:

template <typename Type>
Demo<Type>::Demo(Type const &value)
:
    d_data(value)
{}
template <typename Type>
void Demo<Type>::member2(Type const &value)
{
    d_data += value;
}

int main()
{
    Demo<int> demo;
    demo.member1();
}

```

21.8 Processing class templates and instantiations

In section [20.11](#) the distinction between code depending on template parameters and code not depending on template parameters was introduced. The same distinction also holds true when class templates are defined and used.

Code not depending on template parameters is verified by the compiler when the template is defined. If a member function in a class template uses a `qsort` function, then `qsort` does not depend on a template parameter. Consequently, `qsort` must be known to the compiler when it encounters `qsort`'s function call. In practice this implies that the `<cstdlib>` header file must have been processed by the compiler before it is able to compile the class template definition.

On the other hand, if a template defines a `<typename Ret>` template type parameter to parameterize the return type of some template member function as in:

```
Ret member();
```

then the compiler may encounter `member` or the class to which `member` belongs in the following locations:

- the location where a class template object is defined. This is called the *point of instantiation* of the class template object. The compiler must have read the class template's implementation and has performed a basic check for syntactic correctness of member functions like `member`. It won't accept a definition or declaration like `Ret && *member`, because C++ does not support functions returning pointers to rvalue references. Furthermore, it will check whether the actual type name that is used for instantiating the object is valid. This type name must be known to the compiler at the object's point of instantiation.
- the location where the template member function is used. This is called the template member function's point of instantiation. Here the `Ret` parameter must have been specified (or deduced) and at this point `member`'s statements that depend on the `Ret` template parameter are checked for syntactic correctness. For example, if `member` contains a statement like

```
Ret tmp(Ret(), 15);
```

then this is in principle a syntactically valid statement. However, when `Ret = int` the statement fails to compile as `int` does not have a constructor expecting two `int` arguments. Note that this is *not* a problem when the compiler instantiates an object of `member`'s class. At the point of instantiation of the object its member function '`member`' is not instantiated and so the invalid `int` construction remains undetected.

21.9 Declaring friends

Friend functions are normally constructed as *support* (free) functions of a class that cannot be implemented and declared as class members. The insertion operator for output streams is a well known example. Friend classes are most often seen in the context of nested classes. Here the inner class declares the outer class as its friend (or the other way around). Again we see a support mechanism: the inner class is constructed to support the outer class.

Like ordinary classes, class templates may declare other functions and classes as their friends. Conversely, ordinary classes may declare template classes as their friends. Here too, the friend is constructed as a special function or class augmenting or supporting the functionality of the declaring class. Although the `friend` keyword can be used by any type of class (ordinary or template) when using class templates the following cases should be distinguished:

- A class template may declare an ordinary function or class as its friend. This is a common friend declaration, such as the insertion operator for `ostream` objects.
- A class template may declare another function template or class template as its friend. In this case, the friend's template parameters may have to be specified.

If the actual values of the friend's template parameters *must* be equal to the template parameters of the class declaring the friend, the friend is said to be a *bound friend* class or function template. In this case the template parameters of the template specifying the `friend` declaration determine (*bind*) the values of the template parameters of the friend class or function. Bound friends result in a one-to-one correspondence between the template's parameters and the friend's template parameters.

- In the most general case a class template may declare another function template or class template to be its friend, irrespective of the friend's actual template arguments.

In this case an *unbound friend* class or function template is declared. The template parameters of the friend class or function template remain to be specified and are not related in some predefined way to the template parameters of the class declaring the friend. If a class template has data members of various types, specified by its template parameters and another class should be allowed direct access to these data members we want to specify any of the current template

arguments when specifying such a friend. Rather than specifying multiple bound friends, a single generic (unbound) friend may be declared, specifying the friend's actual template parameters only when this is required.

- The above cases, in which a template is declared as a friend, may also be encountered when ordinary classes are used:
 - The ordinary class declaring ordinary friends has already been covered (chapter 15).
 - The equivalent of bound friends occurs if a ordinary class specifies specific actual template parameters when declaring its friend.
 - The equivalent of unbound friends occurs if a ordinary class declares a generic template as its friend.

21.9.1 Non-function templates or classes as friends

A class template may declare a ordinary function, ordinary member function or ordinary class as its friend. Such a friend may access the class template's private members.

Concrete classes and ordinary functions can be declared as friends, but before a single member function of a class can be declared as a friend, the compiler must have seen the class interface declaring that member. Let's consider the various possibilities:

- A class template may declare a ordinary function to be its friend. It is not completely clear *why* we would like to declare a ordinary function as a friend. Usually we pass an object of the class declaring the friend to such a function. With class templates this requires us to provide the (friend) function with a template parameter without specifying its types. As the language does not support constructions like

```
void function(std::vector<Type> &vector)
```

unless function itself is a template, it is not immediately clear how and why such a friend should be constructed. One reason could be to allow the function access to the class's private static members. In addition such friends could instantiate objects of classes that declare them as their friends. This would allow the friend functions direct access to such object's private members. For example:

```
template <typename Type>
class Storage
{
    friend void basic();
    static size_t s_time;
    std::vector<Type> d_data;
public:
    Storage();
};
template <typename Type>
size_t Storage<Type>::s_time = 0;
template <typename Type>
Storage<Type>::Storage()
{}

void basic()
{
    Storage<int>::s_time = time(0);
    Storage<double> storage;
    std::random_shuffle(storage.d_data.begin(), storage.d_data.end());
}
```

- Declaring a ordinary class to be a class template's friend probably finds more applications. Here the ordinary (friend) class may instantiate any kind of object of the class template. The friend class may then access all private members of the instantiated class template:

```
template <typename Type>
class Composer
{
    friend class Friend;
    std::vector<Type> d_data;
public:
    Composer();
};

class Friend
{
    Composer<int> d_ints;
public:
    Friend(std::istream &input);
};

inline::Friend::Friend(std::istream &input)
{
    std::copy(std::istream_iterator<int>(input),
              std::istream_iterator<int>(),
              back_inserter(d_ints.d_data));
}
```

- Alternatively, just a single member function of a ordinary class may be declared as a friend. This requires that the compiler has read the friend class's interface before declaring the friend. Omitting the required destructor and overloaded assignment operators, the following shows an example of a class whose member randomizer is declared as a friend of the class Composer:

```
template <typename Type>
class Composer;

class Friend
{
    Composer<int> *d_ints;
public:
    Friend(std::istream &input);
    void randomizer();
};

template <typename Type>
class Composer
{
    friend void Friend::randomizer();
    std::vector<Type> d_data;
public:
    Composer(std::istream &input)
    {
        std::copy(std::istream_iterator<int>(input),
                  std::istream_iterator<int>(),
                  back_inserter(d_data));
    }
};

inline Friend::Friend(std::istream &input)
:
    d_ints(new Composer<int>(input))
{
}
```

```

{}

inline void Friend::randomizer()
{
    std::random_shuffle(d_ints->d_data.begin(), d_ints->d_data.end());
}

```

In this example `Friend::d_ints` is a pointer member. It cannot be a `Composer<int>` object as the `Composer` class interface hasn't yet been seen by the compiler when it reads `Friend`'s class interface. Disregarding this and defining a data member `Composer<int> d_ints` results in the compiler generating the error

```
error: field 'd_ints' has incomplete type
```

Incomplete type, as the compiler at this point knows of the existence of the class `Composer` but as it hasn't seen `Composer`'s interface it doesn't know what size the `d_ints` data member will have.

21.9.2 Templates instantiated for specific types as friends

With *bound friend* class templates or functions there is a one-to-one mapping between the template arguments of the friend templates and template arguments of the class templates declaring them as friends. In this case, the friends themselves are templates too. Here are the various possibilities:

- A function template is a friend of a class template. In this case we don't experience the problems we encountered with ordinary functions declared as friends of class templates. Since the friend function template itself is a template it may be provided with the required template arguments allowing it become the declaring class's friend. The various declarations are organized like this:
 - The class template declaring the bound template friend function is defined;
 - The (friend) function template is defined, now having access to all the class template's (private) members.

The bound template friend declaration specifies the required template arguments immediately following the template's function name. Without the template argument list affixed to the function name it would remain an ordinary friend function. Here is an example showing a bound friend to create a subset of the entries of a dictionary. For real life examples, a dedicated function object returning `!key1.find(key2)` is probably more useful. For the current example, `operator==` is acceptable:

```

template <typename Key, typename Value>
class Dictionary
{
    friend Dictionary<Key, Value>
        subset<Key, Value>(Key const &key,
                           Dictionary<Key, Value> const &dict);

    std::map<Key, Value> d_dict;
public:
    Dictionary();
};

template <typename Key, typename Value>
Dictionary<Key, Value>
    subset(Key const &key, Dictionary<Key, Value> const &dict)
{
    Dictionary<Key, Value> ret;

```

```

        std::remove_copy_if(dict.d_dict.begin(), dict.d_dict.end(),
                           std::inserter(ret.d_dict, ret.d_dict.begin()),
                           std::bind2nd(std::equal_to<Key>(), key));
    return ret;
}

```

- By declaring a full class template as a class template's friend, all members of the friend class may access all private members of the class declaring the friend. As the friend class only needs to be declared, the organization of the declaration is much easier than when function templates are declared as friends. In the following example a class `Iterator` is declared as a friend of a class `Dictionary`. Thus, the `Iterator` is able to access `Dictionary`'s private data. There are some interesting points to note here:

- To declare a class template as a friend, that class only needs to be declared as a class template before it is declared as a friend:

```

template <typename Key, typename Value>
class Iterator;

template <typename Key, typename Value>
class Dictionary
{
    friend class Iterator<Key, Value>;
}

```

- However, members of the friend class may already be used, even though the compiler hasn't seen the friend class's interface yet:

```

template <typename Key, typename Value>
template <typename Key2, typename Value2>
Iterator<Key2, Value2> Dictionary<Key, Value>::begin()
{
    return Iterator<Key, Value>(*this);
}
template <typename Key, typename Value>
template <typename Key2, typename Value2>
Iterator<Key2, Value2> Dictionary<Key, Value>::subset(Key const &key)
{
    return Iterator<Key, Value>(*this).subset(key);
}

```

- Of course, the friend class's interface must eventually be seen by the compiler. Since it's a support class for `Dictionary` it can safely define a `std::map` data member that is initialized by the friend class's constructor. The constructor may then access the `Dictionary`'s private data member `d_dict`:

```

template <typename Key, typename Value>
class Iterator
{
    std::map<Key, Value> &d_dict;

public:
    Iterator(Dictionary<Key, Value> &dict)
    :
        d_dict(dict.d_dict)
    {}
}

```

- The `Iterator` member `begin` may return a `map` iterator. Since the compiler does not know what the instantiation of the `map` will look like, a `map<Key, Value>::iterator` is a template subtype. So it cannot be used as-is, but it must be prefixed by `typename` (see the function `begin`'s return type in the next example):

```

template <typename Key, typename Value>
typename std::map<Key, Value>::iterator Iterator<Key, Value>::begin()

```

```

{
    return d_dict.begin();
}

```

- In the previous example we might decide that only a `Dictionary` should be able to construct an `Iterator` (maybe because we consider `Iterator` to be conceptually tied to `Dictionary`). This can be accomplished by defining `Iterator`'s constructor in its private section, and declaring `Dictionary` `Iterator`'s friend. Consequently, only a `Dictionary` can create an `Iterator`. By declaring `Iterator`'s constructor as a *bound* friend we ensure that it can only create `Iterators` using template parameters identical to its own. Here is how it's done:

```

template <typename Key, typename Value>
class Iterator
{
    friend Dictionary<Key, Value>::Dictionary();
    std::map<Key, Value> &d_dict;
    Iterator(Dictionary<Key, Value> &dict);
public:

```

In this example, `Dictionary`'s constructor is `Iterator`'s friend. The friend is a template member. Other members can be declared as a class's friend as well. In those cases their prototypes must be used, also specifying the types of their return values. Assuming that

```
std::vector<Value> sortValues()
```

is a member of `Dictionary` then the matching bound friend declaration is:

```
friend std::vector<Value> Dictionary<Key, Value>::sortValues();
```

Finally, the following example can be used as a prototype for situations where bound friends are useful:

```

template <typename T>    // a function template
void fun(T *t)
{
    t->not_public();
};

template <typename X>    // a class template
class A
{
    // fun() is used as friend bound to A,
    // instantiated for X, whatever X may be
    friend void fun<A<X>>(A<X> *);

public:
    A();

private:
    void not_public();
};

template <typename X>
A<X>::A()
{
    fun(this);
}

template <typename X>
void A<X>::not_public()
{}

int main()
{

```



```

    public:
        void process();

    private:
        void rows(std::vector<Type> &row);
        void columns(Type &str);
};

template <typename Type>
void Vector2<Type>::process()
{
    ForEach<iterator, Vector2<Type>, std::vector<Type> >
        (this->begin(), this->end(), *this, &Vector2<Type>::rows);
}

template <typename Type>
void Vector2<Type>::rows(std::vector<Type> &row)
{
    ForEach(row.begin(), row.end(), *this,
            &Vector2<Type>::columns);

    std::cout << '\n';
}

template <typename Type>
void Vector2<Type>::columns(Type &str)
{
    std::cout << str << " ";
}

using namespace std;

int main()
{
    Vector2<string> c;
    c.push_back(vector<string>(3, "Hello"));
    c.push_back(vector<string>(2, "World"));

    c.process();
}
/*
    Generated output:

    Hello Hello Hello
    World World
*/

```

- Analogously, a full class template may be declared as friend. This allows all instantiations of the friend's member functions to instantiate objects of the class template declaring the friend class. In this case, the class declaring the friend should offer functionality that is useful to different instantiations of its friend class (i.e., instantiations using different template arguments). The syntactic convention is comparable to the convention used when declaring an unbound friend function template:

```

template <typename Type>
class PtrVector
{
    template <typename Iterator, typename Class>
    friend class Wrapper;          // unbound friend class
};

```

All members of the class template `Wrapper` may now instantiate `PtrVectors` using any actual type for its `Type` parameter. This allows the `Wrapper` instantiation to access all of `PtrVector`'s private members.

- When only some members of a class template need access to private members of another class template (e.g., the other class template has private constructors and only some members of the first class template need to instantiate objects of the second class template), then the latter class template may declare only those members of the former class template requiring access to its private members as its friends. Again, the friend class's interface may be left unspecified. However, the compiler must be informed that the friend member's class is indeed a class. A forward declaration of that class must therefore be provided. In the next example `PtrVector` declares `Wrapper::begin` as its friend. Note the forward declaration of the class `Wrapper`:

```
template <typename Iterator>
class Wrapper;

template <typename Type>
class PtrVector
{
    template <typename Iterator> friend
        PtrVector<Type> Wrapper<Iterator>::begin(Iterator const &t1);
    ...
};
```

21.10 Class template derivation

Class templates can be used for inheritance purposes as well. When a class template is used in class derivation, the following situations should be distinguished:

- An existing class template is used as base class when deriving an ordinary class. The derived class will itself partially be a class template, but this is somewhat hidden from view when an object of the derived class is defined.
- An existing class template is used as the base class when deriving another class template. Here the class template characteristics remain clearly visible.
- A ordinary class is used as the base class when deriving a template class. This interesting hybrid allows us to construct class templates that are *partially compiled*.

These three variants of class template derivation are elaborated in this and the upcoming sections.

Consider the following base class:

```
template<typename T>
class Base
{
    T const &t;

public:
    Base(T const &t);
};
```

The above class is a class template that can be used as a base class for the following derived class template `Derived`:

```
template<typename T>
class Derived: public Base<T>
```



```

{
    public:
        Derived(T const &t);
};
template<typename T>
Derived<T>::Derived(T const &t)
:
    Base(t)
{}

```

Other combinations are also possible. The base class may be instantiated by specifying template arguments, turning the derived class into an ordinary class (showing a class object's definition as well):

```

class Ordinary: public Base<int>
{
    public:
        Ordinary(int x);
};
inline Ordinary::Ordinary(int x)
:
    Base(x)
{}

Ordinary ordinary(5);

```

This approach allows us to add functionality to a class template, without the need for constructing a derived class template.

Class template derivation pretty much follows the same rules as ordinary class derivation, not involving class templates. Some subtleties that are specific for class template derivation may easily cause confusion like the use of `this` when members of a template base class are called from a derived class. The reasons for using `this` are discussed in section 22.1. In the upcoming sections the focus will be on the class derivation proper.

21.10.1 Deriving ordinary classes from class templates

When an existing class template is used as a base class for deriving an ordinary class, the class template parameters are specified when defining the derived class's interface. If in a certain context an existing class template lacks a particular functionality, then it may be useful to derive an ordinary class from a class template. For example, although the class `map` can easily be used in combination with the `find_if()` generic algorithm (section 19.1.16), it requires the construction of a class and at least two additional function objects of that class. If this is considered too much overhead then extending a class template with tailor-made functionality might be considered.

Example: a program executing commands entered at the keyboard might accept all unique initial abbreviations of the commands it defines. E.g., the command `list` might be entered as `l`, `li`, `lis` or `list`. By deriving a class `Handler` from

```
map<string, void (Handler::*)(string const &cmd)>
```

and by defining a member function `process(string const &cmd)` to do the actual command processing a program might simply execute the following `main()` function:

```

int main()
{
    string line;

```

```

    Handler cmd;

    while (getline(cin, line))
        cmd.process(line);
}

```

The class `Handler` itself is derived from a `std::map`, in which the map's values are pointers to `Handler`'s member functions, expecting the command line entered by the user. Here are `Handler`'s characteristics:

- The class is derived from a `std::map`, expecting the command associated with each command-processing member as its keys. Since `Handler` uses the map merely to define associations between the commands and the processing member functions and to make available map's typedefs, private derivation is used:

```

class Handler: private std::map<std::string,
                               void (Handler::*)(std::string const &cmd)>

```

- The actual association can be defined using static private data members: `s_cmds` is an array of `Handler::value_type` values, and `s_cmds_end` is a constant pointer pointing beyond the array's last element:

```

    static value_type s_cmds[];
    static value_type *const s_cmds_end;

```

- The constructor simply initializes the map from these two static data members. It could be implemented inline:

```

inline Handler::Handler()
:
    std::map<std::string,
             void (Handler::*)(std::string const &cmd)>
    (s_cmds, s_cmds_end)
{}

```

- The member `process` iterates along the map's elements. Once the first word on the command line matches the initial characters of the command, the corresponding command is executed. If no such command is found, an error message is issued:

```

void Handler::process(std::string const &line)
{
    istringstream istr(line);
    string cmd;
    istr >> cmd;
    for (iterator it = begin(); it != end(); it++)
    {
        if (it->first.find(cmd) == 0)
        {
            (this->*it->second)(line);
            return;
        }
    }
    cout << "Unknown command: " << line << '\n';
}

```

21.10.2 Deriving class templates from class templates

Although it's perfectly acceptable to derive an ordinary class from a class template, the resulting class of course has limited generality compared to its template base class. If generality is important, it's

probably a better idea to derive a class template from a class template. This allows us to extend an existing class template with new functionality or to override the functionality of the existing class template.

The class template `SortVector` presented below is derived from the existing class template `std::vector`. It allows us to perform a *hierarchical sort* of its elements using any ordering of any data members its data elements may contain. To accomplish this there is but one requirement. `SortVector`'s data type must offer dedicated member functions comparing its members.

For example, if `SortVector`'s data type is an object of class `MultiData`, then `MultiData` should implement member functions having the following prototypes for each of its data members which can be compared:

```
bool (MultiData::*)(MultiData const &rhv)
```

So, if `MultiData` has two data members, `int d_value` and `std::string d_text` and both may be used by a hierarchical sort, then `MultiData` should offer the following two members:

```
bool intCmp(MultiData const &rhv); // returns d_value < rhv.d_value
bool textCmp(MultiData const &rhv); // returns d_text < rhv.d_text
```

Furthermore, as a convenience it is assumed that `operator<<` and `operator>>` have been defined for `MultiData` objects.

The class template `SortVector` is directly derived from the template class `std::vector`. Our implementation inherits all members from that base class. It also offers two simple constructors:

```
template <typename Type>
class SortVector: public std::vector<Type>
{
public:
    SortVector()
    {}
    SortVector(Type const *begin, Type const *end)
    :
        std::vector<Type>(begin, end)
    {}
}
```

Its member `hierarchicSort` is the true *raison d'être* for the class. It defines the hierarchical sort criteria. It expects a pointer to a series of pointers to member functions of the class `Type` as well as a `size_t` representing the size of the array.

The array's first element indicates `Type`'s most significant sort criterion, the array's last element indicates the class's least significant sort criterion. Since the `stable_sort` generic algorithm was designed explicitly to support hierarchical sorting, the member uses this generic algorithm to sort `SortVector`'s elements. With hierarchical sorting, the least significant criterion should be sorted first. `hierarchicSort`'s implementation is therefore easy. It requires a support class `SortWith` whose objects are initialized by the addresses of the member functions passed to the `hierarchicSort()` member:

```
template <typename Type>
void SortVector<Type>::hierarchicSort(
    bool (Type::**arr)(Type const &rhv) const,
    size_t n)
{
    while (n--)
        stable_sort(this->begin(), this->end(), SortWith<Type>(arr[n]));
}
```

The class `SortWith` is a simple wrapper class around a pointer to a predicate function. Since it depends on `SortVector`'s actual data type the class `SortWith` must also be a class template:

```
template <typename Type>
class SortWith
{
    bool (Type::*d_ptr)(Type const &rhv) const;
```

`SortWith`'s constructor receives a pointer to a predicate function and initializes the class's `d_ptr` data member:

```
template <typename Type>
SortWith<Type>::SortWith(bool (Type::*ptr)(Type const &rhv) const)
:
    d_ptr(ptr)
{}
```

Its binary predicate member (`operator()`) must return true if its first argument should eventually be placed ahead of its second argument:

```
template <typename Type>
bool SortWith<Type>::operator()(Type const &lhv, Type const &rhv) const
{
    return (lhv.*d_ptr)(rhv);
}
```

The following main function provides an illustration:

- First, A `SortVector` object is created for `MultiData` objects. It uses the copy generic algorithm to fill the `SortVector` object from information appearing at the program's standard input stream. Having initialized the object its elements are displayed to the standard output stream:

```
SortVector<MultiData> sv;

copy(istream_iterator<MultiData>(cin),
     istream_iterator<MultiData>(),
     back_inserter(sv));
```

- An array of pointers to members is initialized with the addresses of two member functions. The text comparison is the most significant sort criterion:

```
bool (MultiData::*arr[])(MultiData const &rhv) const =
{
    &MultiData::textCmp,
    &MultiData::intCmp,
};
```

- Next, the array's elements are sorted and displayed to the standard output stream:

```
sv.hierarchicSort(arr, 2);
```

- Then the two elements of the array of pointers to `MultiData`'s member functions are swapped, and the previous step is repeated:

```
swap(arr[0], arr[1]);
sv.hierarchicSort(arr, 2);
```

After compiling the program the following command can be given:

```
echo a 1 b 2 a 2 b 1 | a.out
```

This results in the following output:

```
a 1 b 2 a 2 b 1
====
a 1 a 2 b 1 b 2
====
a 1 b 1 a 2 b 2
====
```

21.10.3 Deriving class templates from ordinary classes

An ordinary class may be used as the base class for deriving a template class. The advantage of such an inheritance tree is that the base class's members may all be compiled beforehand. When objects of the class template are now instantiated only the actually used members of the derived class template must be instantiated.

This approach may be used for all class templates having member functions whose implementations do not depend on template parameters. These members may be defined in a separate class which is then used as a base class of the class template derived from it.

As an illustration of this approach we'll develop such a class template below. We'll develop a class `Table` derived from an ordinary class `TableType`. The class `Table` displays elements of some type in a table having a configurable number of columns. The elements are either displayed horizontally (the first k elements occupy the first row) or vertically (the first r elements occupy a first column).

When displaying the table's elements they are inserted into a stream. The table is handled by a separate class (`TableType`), implementing the table's presentation. Since the table's elements are inserted into a stream, the conversion to text (or string) is implemented in `Table`, but the handling of the strings themselves is left to `TableType`. We'll cover some characteristics of `TableType` shortly, concentrating on `Table`'s interface first:

- The class `Table` is a class template, requiring only one template type parameter: `Iterator` referring to an iterator to some data type:

```
template <typename Iterator>
class Table: public TableType
{
```

- `Table` doesn't need any data members. All data manipulations are performed by `TableType`.
- `Table` has two constructors. The constructor's first two parameters are `Iterators` used to iterate over the elements that must be entered into the table. The constructors require us to specify the number of columns we would like our table to have as well as a *FillDirection*. `FillDirection` is an enum, defined by `TableType`, having values `HORIZONTAL` and `VERTICAL`. To allow `Table`'s users to exercise control over headers, footers, captions, horizontal and vertical separators, one constructor has `TableSupport` reference parameter. The class `TableSupport` will be developed later as a virtual class allowing clients to exercise this control. Here are the class's constructors:

```
    Table(Iterator const &begin, Iterator const &end,
          size_t nColumns, FillDirection direction);
    Table(Iterator const &begin, Iterator const &end,
          TableSupport &tableSupport,
          size_t nColumns, FillDirection direction);
```

- The constructors are `Table`'s only two public members. Both constructors use a base class initializer to initialize their `TableType` base class and then call the class's private member `fill` to insert data into the `TableType` base class object. Here are the constructor's implementations:

```
template <typename Iterator>
Table<Iterator>::Table(Iterator const &begin, Iterator const &end,
                      TableSupport &tableSupport,
                      size_t nColumns, FillDirection direction)
:
    TableType(tableSupport, nColumns, direction)
{
    fill(begin, end);
}

template <typename Iterator>
Table<Iterator>::Table(Iterator const &begin, Iterator const &end,
                      size_t nColumns, FillDirection direction)
:
    TableType(nColumns, direction)
{
    fill(begin, end);
}
```

- The class's `fill` member iterates over the range of elements `[begin, end)`, as defined by the constructor's first two parameters. As we will see shortly, `TableType` defines a protected data member `std::vector<std::string> d_string`. One of the requirements of the data type to which the iterators point is that this data type can be inserted into streams. So, `fill` uses a `ostringstream` object to obtain the textual representation of the data, which is then appended to `d_string`:

```
template <typename Iterator>
void Table<Iterator>::fill(Iterator it, Iterator const &end)
{
    while (it != end)
    {
        std::ostringstream str;
        str << *it++;
        d_string.push_back(str.str());
    }
    init();
}
```

This completes the implementation of the class `Table`. Note that this class template only has three members, two of them constructors. Therefore, in most cases only two function templates will have to be instantiated: a constructor and the class's `fill` member. For example, the following defines a table having four columns, vertically filled by strings extracted from the standard input stream:

```
Table<istream_iterator<string> >
table(istream_iterator<string>(cin), istream_iterator<string>(),
      4, TableType::Vertical);
```

The fill-direction is specified as `TableType::VERTICAL`. It could also have been specified using `Table`, but since `Table` is a class template its specification would have been slightly more complex: `Table<istream_iterator<string>::VERTICAL`.

Now that the `Table` derived class has been designed, let's turn our attention to the class `TableType`. Here are its essential characteristics:

- It is a ordinary class, designed to operate as `Table`'s base class.

- It uses various private data members, among which `d_colWidth`, a vector storing the width of the widest element per column and `d_indexFun`, pointing to the class's member function returning the element in `table[row][column]`, conditional to the table's fill direction. `TableType` also uses a `TableSupport` pointer and a reference. The constructor not requiring a `TableSupport` object uses the `TableSupport *` to allocate a (default) `TableSupport` object and then uses the `TableSupport &` as the object's alias. The other constructor initializes the pointer to 0 and uses the reference data member to refer to the `TableSupport` object provided by its parameter. Alternatively, a static `TableSupport` object could have been used to initialize the reference data member in the former constructor. The remaining private data members are probably self-explanatory:

```

TableSupport      *d_tableSupportPtr;
TableSupport      &d_tableSupport;
size_t            d_maxWidth;
size_t            d_nRows;
size_t            d_nColumns;
WidthType         d_widthType;
std::vector<size_t> d_colWidth;
size_t            (TableType::*d_widthFun)
                  (size_t col) const;
std::string const &(TableType::*d_indexFun)
                  (size_t row, size_t col) const;

```

- The actual string objects populating the table are stored in a protected data member:

```
std::vector<std::string> d_string;
```

- The (protected) constructors perform basic tasks: they initialize the object's data members. Here is the constructor expecting a reference to a `TableSupport` object:

```

#include "tabletype.ih"

TableType::TableType(TableSupport &tableSupport, size_t nColumns,
                     FillDirection direction)
:
    d_tableSupportPtr(0),
    d_tableSupport(tableSupport),
    d_maxWidth(0),
    d_nRows(0),
    d_nColumns(nColumns),
    d_widthType(COLUMNWIDTH),
    d_colWidth(nColumns),
    d_widthFun(&TableType::columnWidth),
    d_indexFun(direction == HORIZONTAL ?
                &TableType::hIndex
                :
                &TableType::vIndex)
{}

```

- Once `d_string` has been filled, the table is initialized by `Table::fill`. The `init` protected member resizes `d_string` so that its size is exactly `rows x columns`, and it determines the maximum width of the elements per column. Its implementation is straightforward:

```

#include "tabletype.ih"

void TableType::init()
{
    if (!d_string.size()) // no elements
        return;          // then do nothing
}

```

```

d_nRows = (d_string.size() + d_nColumns - 1) / d_nColumns;
d_string.resize(d_nRows * d_nColumns); // enforce complete table

// determine max width per column,
// and max column width
for (size_t col = 0; col < d_nColumns; col++)
{
    size_t width = 0;
    for (size_t row = 0; row < d_nRows; row++)
    {
        size_t len = stringAt(row, col).length();
        if (width < len)
            width = len;
    }
    d_colWidth[col] = width;

    if (d_maxWidth < width) // max. width so far.
        d_maxWidth = width;
}
}

```

- The public member `insert` is used by the insertion operator (`operator<<`) to insert a `Table` into a stream. First it informs the `TableSupport` object about the table's dimensions. Next it displays the table, allowing the `TableSupport` object to write headers, footers and separators:

```

#include "tabletype.ih"

ostream &TableType::insert(ostream &ostr) const
{
    if (!d_nRows)
        return ostr;

    d_tableSupport.setParam(ostr, d_nRows, d_colWidth,
                           d_widthType == EQUALWIDTH ? d_maxWidth : 0);

    for (size_t row = 0; row < d_nRows; row++)
    {
        d_tableSupport.hline(row);

        for (size_t col = 0; col < d_nColumns; col++)
        {
            size_t colwidth = width(col);

            d_tableSupport.vline(col);
            ostr << setw(colwidth) << stringAt(row, col);
        }

        d_tableSupport.vline();
    }
    d_tableSupport.hline();

    return ostr;
}

```

- The `cplusplus.yo.zip` archive contains `TableSupport`'s full implementation. This implementation is found in the directory `yo/classtemplates/examples/table`. Most of its remaining members are private. Among those, these two members return table element `[row][column]` for, respectively, a horizontally filled table and a vertically filled table:

```

inline std::string const &TableType::hIndex(size_t row, size_t col) const

```



```

{
    return d_string[row * d_nColumns + col];
}
inline std::string const &TableType::vIndex(size_t row, size_t col) const
{
    return d_string[col * d_nRows + row];
}

```

The support class `TableSupport` is used to display headers, footers, captions and separators. It has four virtual members to perform those tasks (and, of course, a virtual constructor):

- `hline(size_t rowIndex)`: called just before the elements in row `rowIndex` will be displayed.
- `hline()`: called immediately after displaying the final row.
- `vline(size_t colIndex)`: called just before the element in column `colIndex` will be displayed.
- `vline()`: called immediately after displaying all elements in a row.

The reader is referred to the `cplusplus.yo.zip` archive for the full implementation of the classes `Table`, `TableType` and `TableSupport`. Here is a little program showing their use:

```

/*
                                table.cc
*/

#include <fstream>
#include <iostream>
#include <string>
#include <iterator>
#include <sstream>

#include "tablesupport/tablesupport.h"
#include "table/table.h"

using namespace std;
using namespace FBB;

int main(int argc, char **argv)
{
    size_t nCols = 5;
    if (argc > 1)
    {
        istreamstring iss(argv[1]);
        iss >> nCols;
    }

    istream_iterator<string> iter(cin);    // first iterator isn't const

    Table<istream_iterator<string> >
        table(iter, istream_iterator<string>(), nCols,
              argc == 2 ? TableType::VERTICAL : TableType::HORIZONTAL);

    cout << table << '\n';
    return 0;
}
/*
Example of generated output:

```

```

After: echo a b c d e f g h i j | demo 3
a e i
b f j
c g
d h
After: echo a b c d e f g h i j | demo 3 h
a b c
d e f
g h i
j
*/

```

21.11 Class templates and nesting

When a class is nested within a class template, it automatically becomes a class template itself. The nested class may use the template parameters of the surrounding class, as shown by the following skeleton program. Within a class `PtrVector`, a class `iterator` is defined. The nested class receives its information from its surrounding class, a `PtrVector<Type>` class. Since this surrounding class should be the only class constructing its iterators, `iterator`'s constructor is made private and the surrounding class is given access to the private members of `iterator` using a *bound friend* declaration. Here is the initial section of `PtrVector`'s class interface:

```

template <typename Type>
class PtrVector: public std::vector<Type *>

```

This shows that the `std::vector` base class stores pointers to `Type` values, rather than the values themselves. Of course, a destructor is now required as the (externally allocated) memory for the `Type` objects must eventually be freed. Alternatively, the allocation might be part of `PtrVector`'s tasks, when it stores new elements. Here it is assumed that `PtrVector`'s clients do the required allocations and that the destructor is implemented later on.

The nested class defines its constructor as a private member, and allows `PtrVector<Type>` objects access to its private members. Therefore only objects of the surrounding `PtrVector<Type>` class type are allowed to construct their `iterator` objects. However, `PtrVector<Type>`'s clients may construct *copies* of the `PtrVector<Type>::iterator` objects they use.

Here is the nested class `iterator`, using a (required) friend declaration. Note the use of the `typename` keyword: since `std::vector<Type *>::iterator` depends on a template parameter, it is not yet an instantiated class. Therefore `iterator` becomes an implicit typename. The compiler issues a warning if `typename` has been omitted. Here is the class interface:

```

class iterator
{
    friend class PtrVector<Type>;
    typename std::vector<Type *>::iterator d_begin;

    iterator(PtrVector<Type> &vector);

public:
    Type &operator*();
};

```

The implementation of the members shows that the base class's `begin` member is called to initialize `d_begin`. `PtrVector<Type>::begin`'s return type must again be preceded by `typename`:

```

template <typename Type>

```

```

PtrVector<Type>::iterator::iterator(PtrVector<Type> &vector)
:
    d_begin(vector.std::vector<Type *>::begin())
{}

template <typename Type>
Type &PtrVector<Type>::iterator::operator*()
{
    return **d_begin;
}

```

The remainder of the class is simple. Omitting all other functions that might be implemented, the function `begin` returns a newly constructed `PtrVector<Type>::iterator` object. It may call the constructor since the class `iterator` declared its surrounding class as its friend:

```

template <typename Type>
typename PtrVector<Type>::iterator PtrVector<Type>::begin()
{
    return iterator(*this);
}

```

Here is a simple skeleton program, showing how the nested class `iterator` might be used:

```

int main()
{
    PtrVector<int> vi;

    vi.push_back(new int(1234));

    PtrVector<int>::iterator begin = vi.begin();

    std::cout << *begin << '\n';
}

```

Nested enumerations and nested typedefs can also be defined by class templates. The class `Table`, mentioned before (section 21.10.3) inherited the enumeration `TableType::FillDirection`. If `Table` would have been implemented as a full class template, then this enumeration would have been defined in `Table` itself as:

```

template <typename Iterator>
class Table: public TableType
{
public:
    enum FillDirection
    {
        HORIZONTAL,
        VERTICAL
    };
    ...
};

```

In this case, the actual value of the template type parameter must be specified when referring to a `FillDirection` value or to its type. For example (assuming `iter` and `nCols` are defined as in section 21.10.3):

```

Table<istream_iterator<string> >::FillDirection direction =
    argc == 2 ?

```

```

        Table<istream_iterator<string> >::VERTICAL
    :
        Table<istream_iterator<string> >::HORIZONTAL;

    Table<istream_iterator<string> >
        table(iter, istream_iterator<string>(), nCols, direction);

```

21.12 Constructing iterators

In section 18.2 the iterators used with generic algorithms were introduced. We've seen that several types of iterators were distinguished: InputIterators, ForwardIterators, OutputIterators, BidirectionalIterators and RandomAccessIterators.

To ensure that an object of a class is interpreted as a particular type of iterator, the class must be derived from the class `std::iterator`. Before a class can be derived from this class the `<iterator>` header file must have been included.

In section 18.2 the characteristics of iterators were discussed. All iterators should support an increment operation, a dereference operation and a comparison for (in)equality.

When iterators must be used in the context of generic algorithms they must meet additional requirements. This is caused by the fact that generic algorithms check the types of the iterators they receive. Simple pointers are usually accepted, but if an iterator-object is used it must be able to specify the kind of iterator it represents.

To ensure that an object of a class is interpreted as a particular type of iterator, the class must be derived from the class `iterator`. The particular type of iterator is defined by the class template's *first* parameter, and the particular data type to which the iterator points is defined by the class template's *second* parameter.

The type of iterator that is implemented by the derived class is specified using a so-called *iterator_tag*, provided as the first template argument of the class `iterator`. For the five basic iterator types, these tags are:

- `std::input_iterator_tag`. This tag defines an InputIterator. Iterators of this type allow reading operations, iterating from the first to the last element of the series to which the iterator refers.
- `std::output_iterator_tag`. This tag defines an OutputIterator. Iterators of this type allow for assignment operations, iterating from the first to the last element of the series to which the iterator refers.
- `std::forward_iterator_tag`. This tag defines a ForwardIterator. Iterators of this type allow reading *and* assignment operations, iterating from the first to the last element of the series to which the iterator refers.
- `std::bidirectional_iterator_tag`. This tag defines a BidirectionalIterator. Iterators of this type allow reading *and* assignment operations, iterating step by step, possibly in alternating directions, over all elements of the series to which the iterator refers.
- `std::random_access_iterator_tag`. This tag defines a RandomAccessIterator. Iterators of this type allow reading *and* assignment operations, iterating, possibly in alternating directions, over all elements of the series to which the iterator refers using any available (random) stepsize.

Each iterator tag assumes that a certain set of operators is available. The *RandomAccessIterator* is the most complex of iterators, as it implies all other iterators.

Note that iterators are always defined over a certain range (`[begin, end)`). Increment and decrement operations may result in undefined behavior of the iterator if the resulting iterator value would refer to a location outside of this range.

Often, iterators only access the elements of the series to which they refer. Internally, an iterator may use an ordinary pointer but it is hardly ever necessary for the iterator to allocate its own memory. Therefore, as the assignment operator and the copy constructor do not have to allocate any memory, their *default implementations* usually suffice. For the same reason iterators usually don't require destructors.

Most classes offering members returning iterators do so by having members construct the required iterators that are thereupon returned as objects by those member functions. As the *caller* of these member functions only has to *use* or sometimes *copy* the returned iterator objects, there is usually no need to provide any publicly available constructor, except for the copy constructor. Therefore these constructors are usually defined as *private* or *protected* members. To allow an outer class to create iterator objects, the iterator class usually declares the outer class as its *friend*.

In the following sections the construction of a *RandomAccessIterator*, the most complex of all iterators, and the construction of a *reverse RandomAccessIterator* is discussed. The container class for which a random access iterator must be developed may actually store its data elements in many different ways (e.g., using containers or pointers to pointers). Therefore it is difficult to construct a template iterator class which is suitable for a large variety of container classes.

In the following sections the available `std::iterator` class is used to construct an inner class representing a random access iterator. The reader may follow the approach illustrated there to construct iterator classes for other contexts. An example of such a template iterator class is provided in section [23.7](#).

The random access iterator developed in the next sections reaches data elements that are only accessible through pointers. The iterator class is designed as an inner class of a class derived from a vector of string pointers.

21.12.1 Implementing a 'RandomAccessIterator'

In the chapter about containers (chapter [12](#)) it was noted that containers own the information they contain. If they contain objects, then those objects are destroyed once the containers are destroyed. As pointers are not objects their use in containers is discouraged (STL's `unique_ptr` and `shared_ptr` type objects may be used, though). Although discouraged, we might be able to use pointer data types in specific contexts. In the following class `StringPtr`, an ordinary class is derived from the `std::vector` container that uses `std::string *` as its data type:

```
#ifndef INCLUDED_STRINGPTR_H_
#define INCLUDED_STRINGPTR_H_

#include <string>
#include <vector>

class StringPtr: public std::vector<std::string *>
{
public:
    StringPtr(StringPtr const &other);
    ~StringPtr();

    StringPtr &operator=(StringPtr const &other);
};

#endif
```

This class needs a destructor: as the object stores string pointers, a destructor is required to destroy the strings once the `StringPtr` object itself is destroyed. Similarly, a copy constructor and overloaded assignment is required. Other members (in particular: constructors) are not explicitly declared here as they are not relevant to this section's topic.

Assume that we want to be able to use the `sort` generic algorithm with `StringPtr` objects. This algorithm (see section 19.1.58) requires two *RandomAccessIterators*. Although these iterators are available (via `std::vector`'s `begin` and `end` members), they return iterators to `std::string *`s, which cannot sensibly be compared.

To remedy this, we may define an internal type `StringPtr::iterator`, not returning iterators to pointers, but iterators to the *objects* these pointers point to. Once this iterator type is available, we can add the following members to our `StringPtr` class interface, hiding the identically named, but useless members of its base class:

```
StringPtr::iterator begin();    // returns iterator to the first element
StringPtr::iterator end();     // returns iterator beyond the last
                              // element
```

Since these two members return the (proper) iterators, the elements in a `StringPtr` object can easily be sorted:

```
in main()
{
    StringPtr sp;                // assume sp is somehow filled

    sort(sp.begin(), sp.end()); // sp is now sorted
}
```

To make this all work, the type `StringPtr::iterator` must be defined. As suggested by its type name, `iterator` is a nested type of `StringPtr`. To use a `StringPtr::iterator` in combination with the `sort` generic algorithm it must also be a `RandomAccessIterator`. Therefore, `StringPtr::iterator` itself must be derived from the existing class `std::iterator`.

To derive a class from `std::iterator`, both the iterator type and the data type the iterator points to must be specified. Caveat: our iterator will take care of the `string *` dereferencing; so the required data type will be `std::string`, and *not* `std::string *`. The class `iterator` therefore starts its interface as:

```
class iterator:
    public std::iterator<std::random_access_iterator_tag, std::string>
```

Since its base class specification is quite complex, we could consider associating this type with a shorter name using the following typedef:

```
typedef std::iterator<std::random_access_iterator_tag, std::string>
    Iterator;
```

In practical situations, if the type (`Iterator`) is used only once or twice, the type definition only adds clutter to the interface, and is better not used.

Now we're ready to redesign `StringPtr`'s class interface. It offers members returning (reverse) iterators, and a nested iterator class. The members will next be discussed in some detail.

```
class StringPtr: public std::vector<std::string *>
{
public:
    class iterator: public
        std::iterator<std::random_access_iterator_tag, std::string>
    {
        friend class StringPtr;
        std::vector<std::string *>::iterator d_current;
```

```

    iterator(std::vector<std::string *>::iterator const &current);

public:
    iterator &operator--();
    iterator const operator--(int);
    iterator &operator++();
    iterator &operator++(int);
    bool operator==(iterator const &other) const;
    bool operator!=(iterator const &other) const;
    int operator-(iterator const &rhs) const;
    std::string &operator*() const;
    bool operator<(iterator const &other) const;
    iterator const operator+(int step) const;
    iterator const operator-(int step) const;
    iterator &operator+=(int step); // increment over 'n' steps
    iterator &operator-=(int step); // decrement over 'n' steps
    std::string *operator->() const; // access the fields of the
                                    // struct an iterator points
                                    // to. E.g., it->length()
};

typedef std::reverse_iterator<iterator> reverse_iterator;

iterator begin();
iterator end();
reverse_iterator rbegin();
reverse_iterator rend();
};

```

First we have a look at `StringPtr::iterator`'s characteristics:

- `iterator` defines `StringPtr` as its friend, so `iterator`'s constructor may remain private. Only the `StringPtr` class itself is now able to construct iterators, which seems like a sensible thing to do. Under the current implementation, *copy-construction* should of course also be possible. Furthermore, since an iterator is already provided by `StringPtr`'s base class, we can use that iterator to access the information stored in the `StringPtr` object.
- `StringPtr::begin` and `StringPtr::end` may simply return iterator objects. They are implemented like this:

```

inline StringPtr::iterator StringPtr::begin()
{
    return iterator(this->std::vector<std::string *>::begin());
}
inline StringPtr::iterator StringPtr::end()
{
    return iterator(this->std::vector<std::string *>::end());
}

```

- All of `iterator`'s remaining members are public. It's very easy to implement them, mainly manipulating and dereferencing the available iterator `d_current`. A `RandomAccessIterator` (which is the most complex of iterators) requires a series of operators. They usually have very simple implementations, making them good candidates for inline-members:

- `iterator &operator++()`; the pre-increment operator:

```

inline StringPtr::iterator &StringPtr::iterator::operator++()
{
    ++d_current;
}

```

```

        return *this;
    }
- iterator operator++(int); the post-increment operator:
    inline StringPtr::iterator const StringPtr::iterator::operator++(int)
    {
        return iterator(d_current++);
    }
- iterator &operator--(); the pre-decrement operator:
    inline StringPtr::iterator &StringPtr::iterator::operator--()
    {
        --d_current;
        return *this;
    }
- iterator operator--(int); the post-decrement operator:
    inline StringPtr::iterator const StringPtr::iterator::operator--(int)
    {
        return iterator(d_current--);
    }
- iterator &operator=(iterator const &other); the overloaded assignment operator.
  Since iterator objects do not allocate any memory themselves, the default assignment op-
  erator will do.
- bool operator==(iterator const &rhv) const; testing the equality of two iterator
  objects:
    inline bool StringPtr::iterator::operator==(iterator const &other) const
    {
        return d_current == other.d_current;
    }
- bool operator<(iterator const &rhv) const; testing whether the left-hand side it-
  erator points to an element of the series located before the element pointed to by the right-
  hand side iterator:
    inline bool StringPtr::iterator::operator<(iterator const &other) const
    {
        return **d_current < **other.d_current;
    }
- int operator-(iterator const &rhv) const; returning the number of elements be-
  tween the element pointed to by the left-hand side iterator and the right-hand side iterator
  (i.e., the value to add to the left-hand side iterator to make it equal to the value of the right-
  hand side iterator):
    inline int StringPtr::iterator::operator-(iterator const &rhs) const
    {
        return d_current - rhs.d_current;
    }
- Type &operator*() const; returning a reference to the object to which the current itera-
  tor points. With an InputIterator and with all const_iterators, the return type of this
  overloaded operator should be Type const &. This operator returns a reference to a string.
  This string is obtained by dereferencing the dereferenced d_current value. As d_current
  is an iterator to string * elements, two dereference operations are required to reach the
  string itself:
    inline std::string &StringPtr::iterator::operator*() const
    {
        return **d_current;
    }

```


- `iterator const operator+(int stepsize) const`; this operator advances the current iterator by stepsize steps:


```
inline StringPtr::iterator const
    StringPtr::iterator::operator+(int step) const
{
    return iterator(d_current + step);
}
```
- `iterator const operator-(int stepsize) const`; this operator decreases the current iterator by stepsize steps:


```
inline StringPtr::iterator const
    StringPtr::iterator::operator-(int step) const
{
    return iterator(d_current - step);
}
```
- `iterator(iterator const &other)`; iterators may be constructed from existing iterators. This constructor doesn't have to be implemented, as the default copy constructor can be used.
- `std::string *operator->() const` is an additionally added operator. Here only one dereference operation is required, returning a pointer to the string, allowing us to access the members of a string via its pointer.


```
inline std::string *StringPtr::iterator::operator->() const
{
    return *d_current;
}
```
- Two more additionally added operators are `operator+=` and `operator-=`. They are not formally required by `RandomAccessIterators`, but they come in handy anyway:


```
inline StringPtr::iterator &StringPtr::iterator::operator+=(int step)
{
    d_current += step;
    return *this;
}
inline StringPtr::iterator &StringPtr::iterator::operator-=(int step)
{
    d_current -= step;
    return *this;
}
```

The interfaces required for other iterator types are simpler, requiring only a subset of the interface required by a random access iterator. E.g., the forward iterator is never decremented and never incremented over arbitrary step sizes. Consequently, in that case all decrement operators and `operator+(int step)` can be omitted from the interface. Of course, the tag to use would then be `std::forward_iterator_tag`. The tags (and the set of required operators) varies accordingly for the other iterator types.

21.12.2 Implementing a 'reverse_iterator'

Once we've implemented an iterator, the matching *reverse iterator* can be implemented in a jiffy. Comparable to the `std::iterator` a `std::reverse_iterator` exists, that nicely implements the reverse iterator for us once we have defined an iterator class. Its constructor merely requires an object of the iterator type for which we want to construct a reverse iterator.

To implement a reverse iterator for `StringPtr` we only need to define the `reverse_iterator` type in its interface. This requires us to specify only one line of code, which must be inserted after the interface of the class `iterator`:

```
typedef std::reverse_iterator<iterator> reverse_iterator;
```

Also, the well known members `rbegin` and `rend` are added to `StringPtr`'s interface. Again, they can easily be implemented inline:

```
inline StringPtr::reverse_iterator StringPtr::rbegin()
{
    return reverse_iterator(end());
}
inline StringPtr::reverse_iterator StringPtr::rend()
{
    return reverse_iterator(begin());
}
```

Note the arguments the `reverse_iterator` constructors receive: the *begin point* of the reversed iterator is obtained by providing `reverse_iterator`'s constructor with the value returned by the member `end`: the *endpoint* of the normal iterator range; the *endpoint* of the reversed iterator is obtained by providing `reverse_iterator`'s constructor with the value returned by the member `begin`: the *begin point* of the normal iterator range.

The following small program illustrates the use of `StringPtr`'s `RandomAccessIterator`:

```
#include <iostream>
#include <algorithm>
#include "stringptr.h"
using namespace std;

int main(int argc, char **argv)
{
    StringPtr sp;

    while (*argv)
        sp.push_back(new string(*argv++));

    sort(sp.begin(), sp.end());
    copy(sp.begin(), sp.end(), ostream_iterator<string>(cout, " "));

    cout << "\n=====\n";

    sort(sp.rbegin(), sp.rend());
    copy(sp.begin(), sp.end(), ostream_iterator<string>(cout, " "));

    cout << '\n';
}
/*
    when called as:
    a.out bravo mike charlie zulu quebec

    generated output:
    a.out bravo charlie mike quebec zulu
    =====
    zulu quebec mike charlie bravo a.out
*/
```

Although it is thus possible to construct a reverse iterator from a normal iterator, the opposite does not hold true: it is not possible to initialize a normal iterator from a reverse iterator.

Assume we would like to process all lines stored in `vector<string>` lines up to any trailing empty lines (or lines only containing blanks) it might contain. How should we proceed? One approach is to start the processing from the first line in the vector, continuing until the first of the trailing empty

lines. However, once we encounter an empty line it does of course not have to be the first line of the set of trailing empty lines. In that case, we'd better use the following algorithm:

- First, use

```
rit = find_if(lines.rbegin(), lines.rend(), NonEmpty());
```

to obtain a `reverse_iterator` `rit` pointing to the last non-empty line.

- Next, use

```
for_each(lines.begin(), --rit, Process());
```

to process all lines up to the first empty line.

However, we can't mix iterators and reverse iterators when using generic algorithms. So how can we initialize the second iterator using the available `reverse_iterator`? The solution is not very difficult, as an iterator may be initialized from a pointer. Although the reverse iterator `rit` is not a pointer, `&*(rit - 1)` or `&*--rit` is. So we use

```
for_each(lines.begin(), &*--rit, Process());
```

to process all the lines up to the first of the set of trailing empty lines. In general, if `rit` is a `reverse_iterator` pointing to some element and we need an iterator to point to that element, we may use `&*rit` to initialize the iterator. Here, the dereference operator is applied to reach the element the reverse iterator refers to. Then the address operator is applied to obtain its address with which we can initialize the iterator.

Chapter 22

Advanced Template Use

The main purpose of templates is to provide a generic definition of classes and functions that may then be tailored to specific types.

But templates allow us to do more than that. If not for compiler implementation limitations, templates could be used to program, compile-time, just about anything we use computers for. This remarkable feat, offered by no other current-day computer language, stems from the fact that templates allow us to do three things compile-time:

- Templates allow us to do integer arithmetic (and to save computed values symbolically);
- Templates allow us to make compile-time decisions;
- Templates allow us to do things repeatedly.

Of course, asking the compiler to compute, e.g., prime numbers, is one thing. But it's a completely different thing to do so in an award winning way. Don't expect speed records to be broken when the compiler performs complex calculations for us. But that's all beside the point. In the end we *can* ask the compiler to compute virtually anything using C++'s template language, including prime numbers....

In this chapter these remarkable features of templates are discussed. Following a short overview of subtleties related to templates the main characteristics of template meta programming are introduced.

In addition to template type and template non-type parameters there is a third kind of template parameter, the *template template parameter*. This kind of template parameter is introduced next, laying the groundwork for the discussion of *trait classes* and *policy classes*.

This chapter ends with the discussion of several additional and interesting applications of templates: adapting compiler error messages, conversions to class types and an elaborate example discussing compile-time list processing.

Much of the inspiration for this chapter came from two highly recommended books: Andrei Alexandrescu's 2001 book **Modern C++ design** (Addison-Wesley) and Nicolai Josutis and David Vandevor's 2003 book **Templates** (Addison-Wesley)

22.1 Subtleties

In section 21.2.1 a special application of the keyword `typename` was discussed. There we learned that it is not only used to define a name for a (complex) type, but also to distinguish types defined by class templates from members defined by class templates. In this section two more applications of `typedef` are introduced:

- In section 22.1.1 we will apply `typename` to situations where types nested in templates are returned from member functions of class templates;
- in section 22.1.2 we cover the problem of how to refer to base class templates from derived class templates.

In addition to the special applications of `typedef` section 22.1.3 introduces some new syntax that is related to the extended use of the keyword `typedef`: `::template`, `.template` and `->template` are used to inform the compiler that a name used inside a template is itself a class template.

22.1.1 Returning types nested under class templates

In the following example a nested class, not depending on a template parameter, is defined inside a class template. The class template member `nested` returns an object of this nested class. The example uses a (deprecated) in-class member implementation. The reason for this will become clear shortly.

```
template <typename T>
class Outer
{
    public:
        class Nested
        {
        };
        Nested nested() const
        {
            return Nested();
        }
};
```

The above example compiles flawlessly. Inside the class `Outer` there is no ambiguity with respect to the meaning of `nested`'s return type.

However, following good practices inline and template members should be implemented below their class interfaces (see section 7.6.1). So we remove the implementation from the interface and put it below the interface:

```
template <typename T>
class Outer
{
    public:
        class Nested
        {
        };

        Nested nested() const;
};

template <typename T>
Outer<T>::Nested Outer<T>::nested() const
{
    return Nested();
}
```

Suddenly the compiler refuses to compile the `nested` member, producing an error message like

error: expected constructor, destructor, or type conversion before 'Outer'.

Now that the implementation is moved out of the interface the return type (i.e., `Outer<T>::Nested`) refers to a type defined by `Outer<T>` rather than to a member of `Outer<T>`.

Here, too, `typename` must be used. The general rule being: the keyword `typename` must be used whenever a type is referred to that is a *subtype* of a type that itself depends on a template type parameter.

Writing `typename` in front of `Outer<T>::Nested` removes the compilation error. Thus, the correct implementation of the function `nested` becomes:

```
template <typename T>
typename Outer<T>::Nested Outer<T>::nested() const
{
    return Nested();
}
```

22.1.2 Type resolution for base class members

Below we see two class templates. `Base` is used as a base class of `Derived`:

```
#include <iostream>

template <typename T>
class Base
{
public:
    void member();
};

template <typename T>
void Base<T>::member()
{
    std::cout << "This is Base<T>::member()\n";
}

template <typename T>
class Derived: public Base<T>
{
public:
    Derived();
};

template <typename T>
Derived<T>::Derived()
{
    member();
}
```

This example won't compile, and the compiler tells us something like:

```
error: there are no arguments to 'member' that depend on a template
parameter, so a declaration of 'member' must be available
```

This error causes some confusion as ordinary (non-template) base classes readily make their public and protected members available to classes that are derived from them. This is no different for class templates, but only if the compiler can figure out what we mean. In the above example the compiler *can't* as it doesn't know for what type `T` the member function `member` must be initialized when called from `Derived<T>::Derived`.

To appreciate why this is true, consider the situation where we have defined a specialization:

```
template <>
Base<int>::member()
{
```

```

        std::cout << "This is the int-specialization\n";
    }

```

Since the compiler, when `Derived<SomeType>::Derived` is called, does not know whether a specialization of member will be in effect, it can't decide (when compiling `Derived<T>::Derived`) for what type to instantiate member. It can't decide this when compiling `Derived<T>::Derived` as member's call in `Derived::Derived` doesn't require a template type parameter.

In cases like these, where no template type parameter is available to determine which type to use, the compiler must be told that it should postpone its decision about the template type parameter to use (and therefore about the particular (here: member) function to call) until instantiation time.

This may be implemented in two ways: either by using `this` or by explicitly mentioning the base class, instantiated for the derived class's template type(s). When `this` is used the compiler is informed that we're referring to the type `T` for which the template was instantiated. Any confusion about which member function to use (the derived class or base class member) is resolved in favor of the derived class member. Alternatively, the base or derived class can explicitly be mentioned (using `Base<T>` or `Derived<T>`) as shown in the next example. Note that with the `int` template type the `int` specialization is used.

```

#include <iostream>

template <typename T>
class Base
{
    public:
        virtual void member();
};

template <typename T>
void Base<T>::member()
{
    std::cout << "This is Base<T>::member()\n";
}

template <>
void Base<int>::member()
{
    std::cout << "This is the int-specialization\n";
}

template <typename T>
class Derived: public Base<T>
{
    public:
        Derived();
        virtual void member();
};

template <typename T>
void Derived<T>::member()
{
    std::cout << "This is Derived<T>::member()\n";
}

template <typename T>
Derived<T>::Derived()
{
    this->member();           // Using 'this' implies using the
                             // type for which T was instantiated
    Derived<T>::member();     // Same: calls the Derived member
    Base<T>::member();        // Same: calls the Base member
    std::cout << "Derived<T>::Derived() completed\n";
}

```



```

int main()
{
    Derived<double> d;
    Derived<int> i;
}

/*
    Generated output:
This is Derived<T>::member()
This is Derived<T>::member()
This is Base<T>::member()
Derived<T>::Derived() completed
This is Derived<T>::member()
This is Derived<T>::member()
This is the int-specialization
Derived<T>::Derived() completed
*/

```

The above example might also define virtual member templates (although virtual member templates aren't often used). E.g., Base might declare a virtual void member() and Derived might define its overriding function member. In that case this->member() in Derived::Derived will, due to member's virtual nature, of course call Derived::member. The statement Base<T>::member(), however, will always call Base's member function and can be used to bypass dynamic polymorphism.

22.1.3 ::template, .template and ->template

In general, the compiler is able to determine the true nature of a name. As discussed, this is not always the case and sometimes we have to advise the compiler. The typename keyword may often be used for that purpose.

But typename cannot always come to the rescue. While parsing a source the compiler receives a series of *tokens*, representing meaningful units of text encountered in the program's source. A token could represent, e.g., an identifier or a number. Other tokens represent operators, like =, + or <. It is precisely the last token that may cause problems as it may have very different meanings. The correct meaning cannot always be determined from the context in which the compiler encounters <. In some situations the compiler *does* know that < does not represent the *less than* operator, as when a template parameter list follows the keyword template, e.g.,

```
template <typename T, int N>
```

Clearly, in this case < does not represent a 'less than' operator.

The special meaning of < when it is preceded by template forms the basis for the syntactic constructs discussed in this section.

Assume the following class has been defined:

```

template <typename Type>
class Outer
{
    public:
        template <typename InType>
        class Inner
        {
            public:
                template <typename X>

```

```

        void nested();
    };
};

```

The class template `Outer` defines a nested class template `Inner`. `Inner` in turn defines a template member function.

Next a class template `Usage` is defined, offering a member function caller expecting an object of the above `Inner` type. An initial setup for `Usage` looks like this:

```

template <typename T1, typename T2>
class Usage
{
    public:
        void fun(Outer<T1>::Inner<T2> &obj);
        ...
};

```

The compiler won't accept this as it interprets `Outer<T1>::Inner` as a class type. But there is no class `Outer<T1>::Inner`. Here the compiler generates an error like:

```

error: 'class Outer<T1>::Inner' is not a type

```

To inform the compiler that `Inner` itself is a template, using the template type parameter `<T2>`, the `::template` construction is required. It tells the compiler that the next `<` should not be interpreted as a 'less than' token, but rather as a template type argument. So, the declaration is modified to:

```

void fun(Outer<T1>::template Inner<T2> &obj);

```

This still doesn't get us where we want to be: after all `Inner<T2>` is a type, nested under a class template, depending on a template type parameter. In fact, the original `Outer<T1>::Inner<T2> &obj` declaration results in a series of error messages, one of them looking like this:

```

error: expected type-name before '&' token

```

As is often the case this error message nicely indicates what should be done to get it right: add `typename`:

```

void fun(typename Outer<T1>::template Inner<T2> &obj);

```

Of course, `fun` itself is not only just declared, it must also be implemented. Assume that its implementation should call `Inner`'s member `nested`, instantiated for yet another type `X`. The class template `Usage` should therefore receive a third template type parameter, called `T3`. Assume it has been defined. To implement `fun`, we write:

```

void fun(typename Outer<T1>::template Inner<T2> &obj)
{
    obj.nested<T3>();
}

```

Once again we run into a problem. In the function's body the compiler once again interprets `<` as 'less than', seeing a logical expression having as its right-hand side a primary expression instead of a function call specifying a template type `T3`.

To tell the compiler that it should interpret `<T3>` as a type to instantiate `nested` with the `template` keyword is used once more. This time it is used in the context of the member selection operator. We

write `.template` to inform the compiler that what follows is not a ‘less than’ operator, but rather a type specification. The function’s final implementation becomes:

```
void fun(typename Outer<T1>::template Inner<T2> &obj)
{
    obj.template nested<T3>();
}
```

Instead of defining value or reference parameters functions may also define pointer parameters. If `obj` would have been defined as a pointer parameter the implementation would have had to use the `->template` construction, rather than the `.template` construction. E.g.,

```
void fun(typename Outer<T1>::template Inner<T2> *ptr)
{
    ptr->template nested<T3>();
}
```

22.2 Template Meta Programming

22.2.1 Values according to templates

In template programming values are preferably represented by `enum` values. Enums are preferred over, e.g., `int` `const` values since enums never require any linkage. They are pure symbolic values with no memory representation whatsoever.

Consider the situation where a programmer must use a cast, say a `reinterpret_cast`. A problem with a `reinterpret_cast` is that it is the ultimate way to turn off all compiler checks. All bets are off, and we can write extreme but absolutely pointless `reinterpret_cast` statements, like

```
int value = 12;
ostream &ostr = reinterpret_cast<ostream &>(value);
```

Wouldn’t it be nice if the compiler would warn us against such oddities by generating an error message?

If that’s what we’d like the compiler to do, there must be some way to distinguish madness from weirdness. Let’s assume we agree on the following distinction: `reinterpret` casts are never acceptable if the target type represents a larger type than the expression (source) type, since that would immediately result in exceeding the amount of memory that’s actually available to the target type. For this reason it’s clearly silly to `reinterpret_cast<double *>(&intVar)`, but `reinterpret_cast<char *>(&intVar)` could be defensible.

The intent is now to create a new kind of cast, let’s call it `reinterpret_to_smaller_cast`. It should only be allowed to perform a `reinterpret_to_smaller_cast` if the target type occupies less memory than the source type (note that this exactly the opposite reasoning as used by Alexandrescu (2001), section 2.1).

To start, we construct the following template:

```
template<typename Target, typename Source>
Target &reinterpret_to_smaller_cast(Source &source)
{
    // determine whether Target is smaller than source
    return reinterpret_cast<Target &>(source);
}
```

At the comment an enum-definition is inserted defining a symbol having a suggestive name. A compile-time error results if the required condition is not met and the error message displays the name of the

symbol. A division by zero is clearly not allowed, and noting that a false value represents a zero value, the condition could be:

```
1 / (sizeof(Target) <= sizeof(Source));
```

The interesting part is that this condition doesn't result in any code at all. The enum's value is a plain value that's computed by the compiler while evaluating the expression:

```
template<typename Target, typename Source>
Target &reinterpret_to_smaller_cast(Source &source)
{
    enum
    {
        the_Target_size_exceeds_the_Source_size =
            1 / (sizeof(Target) <= sizeof(Source))
    };
    return reinterpret_cast<Target &>(source);
}
```

When `reinterpret_to_smaller_cast` is used to cast from `int` to `double` an error is produced by the compiler, like this:

```
error: enumerator value for 'the_Target_size_exceeds_the_Source_size'
      is not an integer constant
```

whereas no error is reported if, e.g., `reinterpret_to_smaller_cast<int>(doubleVar)` is requested with `doubleVar` defined as a `double`.

In the above example a `enum` was used to compute (compile-time) a value that is illegal if an assumption is not met. The creative part is finding an appropriate expression.

Enum values are well suited for these situations as they do not consume any memory and their evaluation does not produce any executable code. They can be used to accumulate values too: the resulting enum value then contains a final value, computed by the compiler rather than by executable code as the next sections illustrate. In general, programs shouldn't do run-time what they can do compile-time and performing complex calculations resulting in constant values is a clear example of this principle.

22.2.1.1 Converting integral types to types

Another use of values buried inside templates is to 'templatize' simple scalar `int` values. This is useful in situations where a scalar value (often a `bool` value) is available to select a specialization but a type is required to base the selection on. This situation will be encountered shortly (section [22.2.2](#)).

Templatizing integral values is based on the fact that a class template together with its template arguments defines a type. E.g., `vector<int>` and `vector<double>` are different types.

Turning integral values into templates is easily done. Define a template (it does not have to have any contents at all) and store the integral value in an `enum`:

```
template <int x>
struct IntType
{
    enum { value = x };
};
```

As `IntType` does not have any members the 'class `IntType`' can be defined as 'struct `IntType`', saving us from having to type `public`:

Defining the enum value ‘value’ allows us to retrieve the value used at the instantiation at no cost in storage. Enum values are neither variables nor data members and thus have no address. They are mere values.

It’s easy to use the struct `IntType`. An anonymous or named object can be defined by specifying a value for its `int` non-type parameter. Example:

```
int main()
{
    IntType<1> it;
    cout << "IntType<1> objects have value: " << it.value << "\n" <<
        "IntType<2> objects are of a different type "
        "and have values " << IntType<2>().value << '\n';
}
```

Actually, neither the named object nor the anonymous object is required. As the enum is defined as a plain value, associated with the struct `IntType` we merely have to specify the specific `int` for which the struct `IntType` is defined to retrieve its ‘value’, like this:

```
int main()
{
    cout << "IntType<100>, no object, defines 'value': " <<
        IntType<100>::value << "\n";
}
```

22.2.2 Selecting alternatives using templates

An essential characteristic of programming languages is that they allow the conditional execution of code. For this **C++** offers the `if` and `switch` statements. If we want to be able to ‘program the compiler’ this feature must also be offered by templates.

Like templates storing values templates making choices do not require any code to be executed run-timed. The selection is purely made by the compiler, compile-time. The essence of template meta programming is that we are *not* using or relying on any executable code. The result will often be executable code, but the code that is produced by the meta program is a function of decisions the compiler made by itself.

Template (member) functions are only instantiated when they are actually used. Consequently we can define specializations of functions that are mutually exclusive. Thus it is possible to define a specialization that can be compiled in one situation, but not in another and to define another specialization that can be compiled in the other situation, but not in the first situation. Using specializations code can be generated that is tailored to the demands of a particular situation.

A feature like this cannot be implemented in run-time executable code. For example, when designing a generic storage class the software engineer may intend to store *value class* type objects as well as objects of *polymorphic class* types in the final storage class. Thus the software engineer may conclude that the storage class should contain pointers to objects, rather than the objects themselves. The initially designed code may look like this:

```
template <typename Type>
void Storage::add(Type const &obj)
{
    d_data.push_back(
        d_ispolymorphic ?
            obj.clone()
        :
            new Type(obj)
    );
}
```

```
}
```

The intent is to use the `clone` member function of the `Type` class if `Type` is a polymorphic class and the standard copy constructor if `Type` is a value class.

Unfortunately, this scheme normally fails as value classes do not define `clone` member functions and polymorphic base classes should delete their copy constructors (cf. section 7.4). It doesn't matter to the compiler that `clone` is never called for value classes and the copy constructor is unavailable in polymorphic classes. It merely has some code to compile, and can't do that because of missing members. It's as simple as that.

Template meta programming comes to the rescue. Knowing that class template member functions are only instantiated when used, we intend to design overloaded `add` member functions of which only one will be called (and thus instantiated). Our selection will be based on an additional (in addition to `Type` itself) template non-type parameter that indicates whether we'll use `Storage` for polymorphic or non-polymorphic classes. Our class `Storage` starts like this:

```
template <typename Type, bool isPolymorphic>
class Storage
```

Initially two *overloaded* versions of our `add` member are defined: one used with `Storage` objects storing polymorphic objects (using `true` as its template non-type argument) and one storing value class objects (using `false` as its template non-type argument).

We run into a small problem: functions cannot be overloaded by their argument values but only by their argument types. But a solution exists. Realizing that types are defined by the combination of templates and their template arguments we may convert the values `true` and `false` into types using the knowledge obtained in section 22.2.1.1 about how to convert integral values to types.

We'll provide one (private) `add` member with a `IntType<true>` parameter (implementing the polymorphic class) and another (private) `add` member with a `IntType<false>` parameter (implementing the non-polymorphic class).

In addition to these two private members a third (public) member `add` is defined calling the appropriate private `add` member by providing an `IntType` argument, constructed from `Storage`'s template non-type parameter.

Here are the implementations of the three `add` members:

```
// declared in Storage's private section:

template <typename Type, bool isPolymorphic>
void Storage<Type, isPolymorphic>::add(Type const &obj, IntType<true>)
{
    d_data.push_back(obj.clone());
}

template <typename Type, bool isPolymorphic>
void Storage<Type, isPolymorphic>::add(Type const &obj, IntType<false>)
{
    d_data.push_back(new Type(obj));
}

// declared in Storage's public section:

template <typename Type, bool isPolymorphic>
void Storage<Type, isPolymorphic>::add(Type const &obj)
{
    add(obj, IntType<isPolymorphic>());
}
```

The appropriate `add` member is instantiated and called because a primitive value can be converted to a type. Each of the possible template non-type values is thus used to define an overloaded class template member function.

Since class template members are only instantiated when used only one of the overloaded private `add` members is instantiated. Since the other one is never called (and thus never instantiated) compilation errors are prevented.

Some software engineers have reservations when thinking about the `Storage` class that uses pointers to store copies of value class objects. Their argument is that value class objects can very well be stored by value, rather than by pointer. They'd rather store value class objects by value and polymorphic class objects by pointer.

Such distinctions frequently occur in template meta programming and the following `struct IfElse` may be used to obtain one of two types, depending on a `bool` selector value.

First define the *generic form* of the template:

```
template<bool selector, typename FirstType, typename SecondType>
struct IfElse
{
    typedef FirstType type;
};
```

Then define a partial specialization. The specialization represents a specific selector value (e.g., `false`) and leaves the remaining types open to further specification:

```
template<typename FirstType, typename SecondType>
struct IfElse<false, FirstType, SecondType>
{
    typedef SecondType type;
};
```

The former (generic) definition associates `FirstType` with the `IfElse::type` type definition, the latter definition (partially specialized for the logical value `false`) associates `SecondType` partial specialization with the `IfElse::type` type definition.

The `IfElse` template allows us to define class templates whose data organization is conditional to the template's parameters. Using `IfElse` the `Storage` class may define *pointers* to store copies of polymorphic class type objects and *values* to store value class type objects:

```
template <typename Type, bool isPolymorphic>
class Storage
{
    typedef typename IfElse<isPolymorphic, Type *, Type>::type
        DataType;

    std::vector<DataType> d_data;

private:
    void add(Type const &obj, IntType<true>);
    void add(Type const &obj, IntType<false>);
public:
    void add(Type const &obj);
}

template <typename Type, bool isPolymorphic>
void Storage<Type, isPolymorphic>::add(Type const &obj, IntType<true>)
{
```

```

        d_data.push_back(obj.clone());
    }

    template <typename Type, bool isPolymorphic>
    void Storage<Type, isPolymorphic>::add(Type const &obj, IntType<false>)
    {
        d_data.push_back(obj);
    }

    template <typename Type, bool isPolymorphic>
    void Storage<Type, isPolymorphic>::add(Type const &obj)
    {
        add(obj, IntType<isPolymorphic>());
    }

```

The above example uses `IfElse`'s type, defined by `IfElse` as either `FirstType` or `SecondType`. `IfElse`'s type defines the actual data type to use for `Storage`'s vector data type.

The remarkable result in this example is that the *data organization* of the `Storage` class now depends on its template arguments. Since the `isPolymorphic == true` situation uses different data types than the `t(isPolymorphic == false)` situation, the overloaded private `add` members can utilize this difference immediately. E.g., `add(Type const &obj, IntType<false>)` uses direct copy construction to store a copy of `obj` in `d_vector`.

It is also possible to make a selection from multiple types as `IfElse` structs can be nested. Realize that using `IfElse` never has any effect on the size or execution time of the final executable program. The final program simply contains the appropriate type, conditional to the type that's eventually selected.

The following example, defining `MapType` as a map having plain types or pointers for either its key or value types, illustrates this approach:

```

template <typename Key, typename Value, int selector>
class Storage
{
    typedef typename IfElse<
        selector == 1,                // if selector == 1:
        map<Key, Value>,              // use map<Key, Value>

        typename IfElse<
            selector == 2,            // if selector == 2:
            map<Key, Value *>,        // use map<Key, Value *>

            typename IfElse<
                selector == 3,        // if selector == 3:
                map<Key *, Value>,    // use map<Key *, Value>
                // otherwise:
                map<Key *, Value *> // use map<Key *, Value *>

            >::type
        >::type
    >::type
    MapType;

    MapType d_map;

public:
    void add(Key const &key, Value const &value);
private:
    void add(Key const &key, Value const &value, IntType<1>);
    ...

```



```
};
template <typename Key, typename Value, int selector>
inline void Storage<selector, Key, Value>::add(Key const &key,
                                              Value const &value)
{
    add(key, value, IntType<selector>());
}
```

The principle used in the above examples is: if class templates may use data types that depend on template non-type parameters, an `ifElse` struct can be used to select the appropriate data types. Knowledge about the various data types may also be used to define overloaded member functions. The implementations of these overloaded members may then be optimized to the various data types. In programs only one of these alternate functions (the one that is optimized to the actually used data types) will then be instantiated.

The private `add` functions define the same parameters as the public `add` wrapper function, but add a specific `IntType` type, allowing the compiler to select the appropriate overloaded version based on the template's non-type selector parameter.

22.2.3 Templates: Iterations by Recursion

As there are no variables in template meta programming, there is no template equivalent to a `for` or `while` statement. However, iterations can always be rewritten as recursions. Recursions *are* supported by templates and so iterations can always be implemented as (tail) recursions.

To implement iterations by (tail) recursion do as follows:

- define a specialization implementing the end-condition;
- define all other steps using recursion.
- store intermediate values as `enum` values.

The compiler selects a more specialized template implementation over a more generic one. By the time the compiler reaches the end-condition the recursion stops since the specialization does not use recursion.

Most readers will be familiar with the recursive implementation of the mathematical '*factorial*' operator, commonly represented by the exclamation mark (!). Factorial `n` (so: `n!`) returns the successive products `n * (n - 1) * (n - 2) * ... * 1`, representing the number of ways `n` objects can be permuted. Interestingly, the factorial operator is itself usually defined by a *recursive* definition:

```
n! = (n == 0) ?
      1
    :
      n * (n - 1)!
```

To compute `n!` from a template, a template `Factorial` can be defined using an `int n` template non-type parameter. A specialization is defined for the case `n == 0`. The generic implementation uses recursion according to the factorial definition. Furthermore, the `Factorial` template defines an `enum` value '`value`' containing its factorial value. Here is the generic definition:

```
template <int n>
struct Factorial
{
    enum { value = n * Factorial<n - 1>::value };
};
```

Note how the expression assigning a value to ‘value’ uses constant values that can be determined by the compiler. The value `n` is provided, and `Factorial<n - 1>` is computed using *template meta programming*. `Factorial<n-1>` in turn results in value that can be determined by the compiler (*viz.* `Factorial<n-1>::value`). `Factorial<n-1>::value` represents the value defined by the *type* `Factorial<n - 1>`. It is *not* the value returned by an *object* of that type. There are no objects here but merely values defined by types.

The recursion ends in a specialization. The compiler will select the specialization (provided for the terminating value 0) instead of the generic implementation whenever possible. Here is the specialization’s implementation:

```
template <>
struct Factorial<0>
{
    enum { value = 1 };
};
```

The `Factorial` template can be used to determine, compile time, the number of permutations of a fixed number of objects. E.g.,

```
int main()
{
    cout << "The number of permutations of 5 objects = " <<
        Factorial<5>::value << "\n";
}
```

Once again, `Factorial<5>::value` is *not* evaluated run-time, but compile-time. The run-time equivalent of the above `cout` statement is, therefore:

```
int main()
{
    cout << "The number of permutations of 5 objects = " <<
        120 << "\n";
}
```

22.3 Template template parameters

Consider the following situation: a software engineer is asked to design a storage class `Storage`. Data stored in `Storage` objects may either make and store copies of the data or store the data as received. `Storage` objects may also either use a vector or a linked list as its underlying storage medium. How should the engineer tackle this request? Should four different `Storage` classes be designed?

The engineer’s first reaction could be to develop an all-in `Storage` class. It could have having two data members, a list and a vector, and to provide the constructor with maybe an enum value indicating whether the data itself or new copies should be stored. The enum value can be used to initialize a series of pointers to member functions performing the requested tasks (e.g., using a vector to store the data or a list to store copies).

Complex, but doable. Then the engineer is asked to modify the class: in the case of new copies a custom-made allocation scheme should be used rather than the standard `new` operator. It should also be possible to use yet another type of container, in addition to the vector and list that were already part of the design. E.g., a deque could be preferred or maybe even a stack.

It’s clear that the approach aiming at implementing all functionality and all possible combinations in one class doesn’t scale. The class `Storage` would soon become a monolithic giant which is hard to understand, maintain, test, and deploy.

One of the reasons why the big, all-encompassing class is hard to deploy and understand is that a well-designed class should *enforce constraints*: the design of the class should, by itself, disallow certain operations, violations of which should be detected by the compiler, rather than by a program that might terminate with a fatal error.

Consider the above request. If the class offers both an interface to access the vector data storage *and* an interface to access the list data storage, then it's likely that the class will offer an overloaded `operator[]` member to access elements in the vector. This member, however, will be syntactically present, but semantically invalid when the *list* data storage is selected, which doesn't support `operator[]`.

Sooner or later, *users* of the monolithic all-encompassing class `Storage` will fall into the trap of using `operator[]` even though they've selected the list as the underlying data storage. The compiler won't be able to detect the error, which will only appear once the program is running, confusing *users*.

The question remains: how should the engineer proceed, when confronted with the above questions? It's time to introduce *policies*.

22.3.1 Policy classes - I

A *policy* defines (in some contexts: prescribes) a particular kind of behavior. In **C++** a *policy class* defines a certain part of the class interface. It may also define inner types, member functions, and data members.

In the previous section the problem of creating a class that might use any of a series of allocation schemes was introduced. These allocation schemes all depend on the actual data type to be used, and so the 'template' reflex should kick in. Allocation schemes should probably be defined as template classes, applying the appropriate allocation procedures to the data type at hand. E.g. (using in-class implementations to save some space), the following three allocation classes could be defined:

- No special allocation takes place, data is used 'as is':

```
template <typename Data>
class PlainAlloc
{
    template<typename IData>
    friend std::ostream &operator<<(std::ostream &out,
                                   PlainAlloc<IData> const &alloc);

    Data d_data;

public:
    PlainAlloc()
    {}
    PlainAlloc(Data data)
    :
        d_data(data)
    {}
    PlainAlloc(PlainAlloc<Data> const &other)
    :
        d_data(other.d_data)
    {}
};
```

- The second allocation scheme uses the standard `new` operator to allocate a new copy of the data:

```
template <typename Data>
class NewAlloc
{
    template<typename IData>
```

```

friend std::ostream &operator<<(std::ostream &out,
                                NewAlloc<IData> const &alloc);

Data *d_data;

public:
    NewAlloc()
    :
        d_data(0)
    {}
    NewAlloc(Data const &data)
    :
        d_data(new Data(data))
    {}
    NewAlloc(NewAlloc<Data> const &other)
    :
        d_data(new Data(*other.d_data))
    {}
    ~NewAlloc()
    {
        delete d_data;
    }
};

```

- The third allocation scheme uses the placement new operator (see section 8.1.5), requesting memory from a common pool of bytes (the implementation of the member `request()`, obtaining the required amount of memory, is left as an exercise to the reader):

```

template<typename Data>
class PlacementAlloc
{
    template<typename IData>
    friend std::ostream &operator<<(std::ostream &out,
                                    PlacementAlloc<IData> const &alloc);

    Data *d_data;

    static char s_commonPool[];
    static char *s_free;

    public:
        PlacementAlloc()
        :
            d_data(0)
        {}
        PlacementAlloc(Data const &data)
        :
            d_data(new(request()) Data(data))
        {}
        PlacementAlloc(PlacementAlloc<Data> const &other)
        :
            d_data(new(request()) Data(*other.d_data))
        {}
        ~PlacementAlloc()
        {
            d_data->~Data();
        }
    private:
        static char *request();
};

```

The above three classes define *policies* that may be selected by the user of the class `Storage`, introduced

in the previous section. In addition to this, additional allocation schemes could be implemented by the user as well.

In order to be able to apply the proper allocation scheme to the class `Storage` it should be designed as a class template itself. The class will also need a template type parameter allowing users to specify the data type.

The data type to be used by a particular allocation scheme can of course be specified when the allocation scheme itself is specified. This would result in code like this:

```
template <typename Data, typename Scheme>
class Storage ...
```

`Storage` would then be used as follows:

```
Storage<string, NewAlloc<string> > storage;
```

This implementation is needlessly complex, as it requires the user to specify the data type twice. Instead, the allocation scheme should be specified using a new type of template parameter, not requiring the user to specify the data type to be used by the allocation scheme. This new kind of template parameter (in addition to the well-known *template type parameter* and *template non-type parameter*) is called the *template template parameter*.

22.3.2 Policy classes - II: template template parameters

Template template parameters allow us to specify a *class template* as a template parameter. By specifying a class template, it is possible to add a certain kind of behavior, called a *policy* to an existing class template.

Consider the class `Storage`, introduced at the beginning of this section. Also consider the allocation classes discussed in the previous section. To allow us to specify an *allocation policy* for the class `Storage` its definition starts as follows:

```
template <typename Data, template <typename> class Policy>
class Storage ...
```

The second template parameter is the *template template parameter*. It consists of the following elements:

- The keyword `template`, starting the template template parameter;
- It is followed (between pointed brackets) by a list of template parameters that must be specified for the template template parameter. These parameters *may* be given names, but names are usually omitted as those names cannot be used in subsequent template definitions. On the other hand, providing formal names may help the reader of the template to understand the kinds of templates that may be specified as template template parameters.
- Template template parameters must match, in numbers and types (i.e., template type parameters, template non-type parameters, template template parameters) the template parameters that must be specified for the policy.
- Following the bracketed list the keyword `class` must be specified. In this case, `typename` can *not* be used.
- All parameters may be provided with default arguments. This is shown in the next example of a hypothetical class template:

```
template <
```

```

template <
    typename = std::string,
    int = 12,
    template < typename = int > class Inner = std::vector
>
class Policy
>
class Demo
{
    ...
};

```

Since the policy class should be an inherent part of the class under consideration, it is often deployed as a base class. So, `Policy` becomes a base class of `Storage`.

The policy operates on the class `Storage`'s data type. Therefore the policy is informed about that data type as well. From this we reach the following setup:

```

template <typename Data, template <typename> class Policy>
class Storage: public Policy<Data>

```

This scheme allows us to use the policy's members when implementing the members of the class `Storage`.

The allocation classes shown before do not really provide us with many useful members. Except for the extraction operator they offer no immediate access to the data. This can easily be repaired by providing additional members. E.g., the class `NewAlloc` could be provided with the following operators, allowing access to and modification of stored data:

```

operator Data &()    // optionally add a 'const' member too
{
    return *d_data;
}
NewAlloc &operator=(Data const &data)
{
    *d_data = data;
}

```

Other allocation classes can be given comparable members.

The next step consists of using the allocation schemes in some real code. The next example shows how a storage can be defined using some data type and an allocation scheme. First, define a class `Storage`:

```

template <typename Data, template <typename> class Policy>
class Storage: public std::vector<Policy<Data> >
{
};

```

That's all we have to do. All required functionality is offered by the `vector` base class, while the policy is 'factored into the equation' via the template template parameter. Here's an example showing its use:

```

Storage<std::string, NewAlloc> storage;

copy(istream_iterator<std::string>(cin), istream_iterator<std::string>(),
     back_inserter(storage));

cout << "Element index 1 is " << storage[1] << '\n';
storage[1] = "hello";

```

```
copy(storage.begin(), storage.end(),
      ostream_iterator<NewAlloc<std::string> >(cout, "\n"));
```

Now the STL `copy` function can be used in combination with the *back_inserter* iterator to add some data to `storage`. Its elements can be both accessed and modified directly using the index operator and then `NewAlloc<std::string>` objects are inserted into `cout` (also using the `copy` function).

Interestingly, this is not the end of the story. After all, the intention was to create a class allowing us to specify the *storage type* as well. What if we don't want to use a vector, but instead would like to use a list?

It's easy to change `Storage`'s setup so that a completely different storage type can be used on request, like a deque. To implement this, the storage class is parameterized as well, using yet another template parameter:

```
template <typename Data, template <typename> class Policy,
          template <typename> class Container =
          std::vector>
class Storage: public Container< Policy<Data> >
{
};
```

The earlier example using a `Storage` object can be used again without requiring any modifications at all (except for the above redefinition). It clearly can't be used with a list container, as the list lacks `operator[]`. But that's immediately recognized by the compiler, producing an error if an attempt is made to use `operator[]` on, e.g., a `list`¹.

22.3.2.1 The destructor of Policy classes

In the previous section policy classes were used as base classes of template classes. This resulted in the interesting observation that a policy class may serve as a *base class* of a derived class. As a policy class may act as a base class, a pointer or reference to such a policy class can be used to point or refer to the derived class using the policy.

This situation, although legal, should be avoided for various reasons:

- Destruction of a derived class object using the base class's destructor requires the implementation of a virtual destructor;
- A virtual destructor introduces overhead to a class that normally has no data members, but merely defines behavior: suddenly a vtable is required as well as a data member pointing to the vtable;
- Virtual member functions somewhat reduce the efficiency of code; thus virtual member functions using *dynamic polymorphism*, somewhat counteract the *static polymorphism* offered by templates;
- Virtual member functions in templates may result in *code bloat*: once an instantiation of a class's member is required, the class's vtable and *all* its virtual members must be implemented too.

To avoid these drawbacks, it is good practice to prevent the use of references or pointers to policy classes to refer or point to derived class objects. This is accomplished by providing policy classes with *nonvirtual protected destructors*. With a non-virtual destructor there is no performance penalty and since its destructor is protected users cannot refer to classes derived from the policy class using a pointer or reference to the policy class.

¹A complete example showing the definition of the allocation classes and the class `Storage` as well as its use is provided in the Annotation's distribution in the file `yo/advancedtemplates/examples/storage.cc`.

22.3.3 Structure by Policy

Policy classes usually define behavior, not structure. Policy classes are normally used to parameterize some aspect of the behavior of classes that are derived from them. However, different policies may require different data members. These data members may also be defined by the policy classes. Policy classes may therefore be used to define both behavior and structure.

By providing a well-defined interface a class derived from a policy class may define member specializations using the different structures of policy classes to their advantage. For example, a plain pointer-based policy class could offer its functionality by resorting to C-style pointer juggling, whereas a vector-based policy class could use the vector's members directly.

In this example a generic class template `Size` could be designed expecting a container-like policy using features commonly found in containers, defining the data (and hence the structure) of the container specified in the policy. E.g.:

```
template <typename Data, template <typename> class Container>
struct Size: public Container<Data>
{
    size_t size()
    {
        // relies on the container's 'size()'
        // note: can't use 'this->size()'
        return Container<Data>::size();
    }
};
```

A specialization can now be defined for a much simpler storage class using, e.g., plain pointers (the implementation capitalizes on `first` and `second`, data members of `std::pair`. Cf. the example at the end of this section):

```
template <typename Data>
struct Size<Data, Plain>: public Plain<Data>
{
    size_t size()
    {
        // relies on pointer data members
        return this->second - this->first;
    }
};
```

Depending on the intentions of the template's author other members could be implemented as well.

To ease the real use of the above templates, a generic wrapper class can be constructed: it will use the `Size` template matching the actually used storage type (e.g., a `std::vector` or some plain storage class) to define its structure:

```
template <typename Data, template <typename> class Store>
class Wrapper: public Size<Data, Store>
{};
```

The above classes could now be used as follows (*en passant* showing an extremely basic `Plain` class):

```
#include <iostream>
#include <vector>

template <typename Data>
struct Plain: public std::pair<Data *, Data *>
{};
```



```
int main()
{
    Wrapper<int, std::vector> wiv;
    std::cout << wiv.size() << "\n";

    Wrapper<int, Plain> wis;
    std::cout << wis.size() << "\n";
}
```

The `wiv` object now defines vector-data, the `wis` object merely defines a `std::pair` object's data members.

22.4 Trait classes

Scattered over the `std` namespace *trait classes* are found. E.g., most C++ programmers will have seen the compiler mentioning ‘`std::char_traits<char>`’ when performing an illegal operation on `std::string` objects, as in `std::string s(1)`.

Trait classes are used to make compile-time decisions about types. Traits classes allow us to apply the proper code to the proper data type, be it a pointer, a reference, or a plain value, all this maybe in combination with `const`. The particular type of data to use can be inferred from the actual type that is specified (or implied) when the template is used. This can be fully automated, not requiring the template writer to make any decision.

Trait classes allow us to develop a template `<typename Type1, typename Type2, ...>` without the need to specify many specializations covering all combinations of, e.g., values, (const) pointers, or (const) references, which would soon result in an unmaintainable exponential explosion of template specializations (e.g., allowing these five different types for each template parameter already results in 25 combinations when two template type parameters are used: each must be covered by potentially different specializations).

Having available a trait class, the actual type can be inferred compile time, allowing the compiler to deduct whether or not the actual type is a pointer, a pointer to a member, a const pointer and make comparable deductions in case the actual type is, e.g., an lvalue or rvalue reference type. This in turn allows us to write templates that define types like `argument_type`, `first_argument_type`, `second_argument_type` and `result_type`, which are required by several generic algorithms (e.g., `count_if()`).

A trait class usually performs no behavior. I.e., it has no constructor and no members that can be called. Instead, it defines a series of types and enum values that have certain values depending on the actual type that is passed to the trait class template. The compiler uses one of a set of available specializations to select the one appropriate for an actual template type parameter.

The point of departure when defining a trait template is a plain vanilla `struct`, defining the characteristics of a plain value type like an `int`. This sets the stage for specific specializations, modifying the characteristics for any other type that could be specified for the template.

To make matters concrete, assume the intent is to create a trait class `BasicTraits` telling us whether a type is a plain value type, a pointer type, an lvalue reference type or an rvalue reference type (all of which may or may not be `const` types).

Whatever the actually provided type, we want to be able to determine the ‘plain’ type (i.e., the type without any modifiers, pointers or references), the ‘pointer type’ and the ‘reference type’, allowing us to define in all cases, e.g., an rvalue reference to its built-in type, even though we passed a const pointer to that type.

Our point of departure, as mentioned, is a plain `struct` defining the required parameter. Maybe something like this:

```

template <typename T>
struct Basic
{
    typedef T Type;
    enum
    {
        isPointer = false,
        isConst = false,
        isRef = false,
        isRRef = false
    };
};

```

Although some conclusions can be drawn by combining various enum values (e.g., a plain type is not a pointer or a reference or a rvalue reference or a const), it is good practice to provide a full implementation of trait classes, not requiring its users to construct these logical expressions themselves. Therefore, the basic decisions in a trait class are usually made by a nested trait class, leaving the task of creating appropriate logical expressions to a surrounding trait class.

So, the struct `Basic` defines the generic form of our inner trait class. Specializations handle specific details. E.g., a pointer type is recognized by the following specialization:

```

template <typename T>
struct Basic<T *>
{
    typedef T Type;
    enum
    {
        isPointer = true,
        isConst = false,
        isRef = false,
        isRRef = false
    };
};

```

whereas a pointer to a const type is matched with the next specialization:

```

template <typename T>
struct Basic<T const *>
{
    typedef T Type;
    enum
    {
        isPointer = true,
        isConst = true,
        isRef = false,
        isRRef = false
    };
};

```

Several other specializations should be defined: e.g., recognizing const value types or (rvalue) reference types. Eventually all these specializations are implemented as nested structs of an outer class `BasicTraits`, offering the public traits class interface. The outline of the outer trait class is:

```

template <typename TypeParam>
class BasicTraits
{
    // Define specializations of the template 'Base' here

```

```

public:
    BasicTraits(BasicTraits const &other) = delete;

    typedef typename Basic<TypeParam>::Type ValueType;
    typedef ValueType *PtrType;
    typedef ValueType &RefType;
    typedef ValueType &&RvalueRefType;

    enum
    {
        isPointerType = Basic<TypeParam>::isPointer,
        isReferenceType = Basic<TypeParam>::isRef,
        isRvalueReferenceType = Basic<TypeParam>::isRRef,
        isConst = Basic<TypeParam>::isConst,
        isPlainType = not (isPointerType or isReferenceType or
                           isRvalueReferenceType or isConst)
    };
};

```

The trait class's public interface explicitly deletes its copy constructor. As it therefore defines no constructor at all and as it has no static members it does not offer any run-time executable code. All the trait class's facilities must therefore be used compile time.

A trait class template can be used to obtain the proper type, irrespective of the template type argument provided. It can also be used to select a proper specialization that depends on, e.g., the const-ness of a template type. Example:

```

cout <<
"int: plain type? "      << BasicTraits<int>::isPlainType << "\n"
"int: ptr? "            << BasicTraits<int>::isPointerType << "\n"
"int: const? "          << BasicTraits<int>::isConst << "\n"
"int *: ptr? "          << BasicTraits<int *>::isPointerType << "\n"
"int const *: ptr? "    << BasicTraits<int const *>::isPointerType <<
                                                                    "\n"
"int const: const? "    << BasicTraits<int const>::isConst << "\n"
"int: reference? "      << BasicTraits<int>::isReferenceType << "\n"
"int &: reference? "    << BasicTraits<int &>::isReferenceType << "\n"
"int const &: ref ? "   << BasicTraits<int const &>::isReferenceType <<
                                                                    "\n"
"int const &: const ? " << BasicTraits<int const &>::isConst << "\n"
"int &&: r-reference? " << BasicTraits<int &&>::isRvalueReferenceType <<
                                                                    "\n"
"int &&: const? " << BasicTraits<int &&>::isConst << "\n"
"int const &&: r-ref ? " << BasicTraits<int const &&>::
                                                                    isRvalueReferenceType << "\n"
"int const &&: const ? " << BasicTraits<int const &&>::isConst << "\n"
"\n";

BasicTraits<int *>::ValueType      value = 12;
BasicTraits<int const *>::RvalueRefType rvalue = int(10);
BasicTraits<int const &&>::PtrType    ptr = new int(14);
cout << value << ' ' << rvalue << ' ' << *ptr << '\n';

```

22.4.1 Distinguishing class from non-class types

In the previous section the `TypeTrait` trait class was developed. Using specialized versions of a nested `struct` `Type` modifiers, pointers, references and values could be distinguished.

Knowing whether a type is a class type or not (e.g., the type represents a primitive type) could also be a useful bit of knowledge to a template developer. The class template developer might want to define a specialization when the template's type parameter represents a class type (maybe using some member function that should be available) and another specialization for non-class types.

This section addresses the question how a trait class can distinguish class types from non-class types.

In order to distinguish classes from non-class types a distinguishing feature that can be used compile-time must be found. It may take some thinking to find such a distinguishing characteristic, but a good candidate eventually is found in the pointer to members syntactic construct. Pointers to members are only available for classes. Using the pointer to member construct as the distinguishing characteristic, a specialization can be developed that uses the pointer to member if available. Another specialization (or the generic template) does something else if the pointer to member construction is not available.

How can we distinguish a pointer to a member from 'a generic situation', not being a pointer to a member? Fortunately, such a distinction is possible. A function template specialization can be defined having a parameter which is a pointer to a member function. The generic function template will then accept any other argument. The compiler will *select* the former (specialized) function when the provided type is a class type as class types *may* support a pointer to a member. The interesting verb here is '*may*': the class does not *have* to define a pointer to member.

Furthermore, the compiler will not actually *call* any function: we're talking compile-time here. All the compiler does is to *select* the appropriate function by evaluating a constant expression.

So, our intended function template will look like this:

```
template <typename ClassType>
static 'some returntype' fun(void (ClassType::*)());
```

The function's return type ('(some returntype)') will be defined shortly. Let's first have a closer look at the function's parameter. The function's parameter defines a pointer to a member returning `void`. Such a function does *not* have to exist for the concrete class-type that's specified when the function is used. In fact, *no* implementation will be provided. The function `fun` is only declared as a *static* member in the trait class. It's not implemented and no trait class object is required to call it. What, then, is its use?

To answer the question we now have a look at the generic function template that should be used when the template's argument is *not* a class type. The language offers a 'worst case' parameter in its *ellipsis* parameter list. The ellipsis is a final resort the compiler may turn to if everything else fails. The generic function template specifies a plain ellipsis in its parameter list:

```
template <typename NonClassType>
static 'some returntype' fun(...);
```

It would be an error to define the generic alternative as a function expecting an `int`. The compiler, when confronted with alternatives, will favor the simplest, most specified alternative over a more complex, generic one. So, when providing `fun` with an argument it will select `int` whenever possible and it won't select `fun(void (ClassType::*)())`. When given the choice between `fun(void (ClassType::*)())` and `fun(...)` it will select the former unless it can't do that.

The question now becomes: what argument can be used for both a pointer to a member and for the ellipsis? Actually, there is such a 'one size fits all' argument: `0`. The value `0` can be used as argument value to initialize and pointers to members alike.

But `0` does not specify a particular class. Therefore, `fun` must specify an explicit template argument and it will appear in our code as `fun<Type>(0)`, with `Type` being the template type parameter of the trait class.

Now for the return type. The function's return type cannot be a simple value (like `true` or `false`). Our eventual intent is to provide the trait class with an enum telling us whether the trait class's template argument represents a class type or not. That enum will be something like this:

```
enum { isClass = some class/non-class distinguishing expression } ;
```

The distinguishing expression cannot be

```
enum { isClass = fun<Type>(0) } ;
```

as `fun<Type>(0)` is not a constant expression and enum values *must* be defined by constant expressions so they can be determined compile-time.

To determine `isClass`'s value we must find an expression that allows compile-time discriminates between `fun<Type>(...)` and `fun<Type>(void (Type::*)())`.

In situations like these the `sizeof` operator often is our tool of choice as it is evaluated compile-time. By defining different sized return types for the two `fun` declarations we are able to distinguish (compile-time) which of the two `fun` alternatives is selected by the compiler.

The `char` type is by definition a type having size 1. By defining another type containing two consecutive `char` values a larger type is obtained. A `char [2]` is of course not a type, but a `char[2]` can be defined as a data member of a struct, and a struct *does* define a type. That struct will then have a size exceeding 1. E.g.,

```
struct Char2
{
    char data[2];
};
```

`Char2` can be defined as a nested type of our traits class. The two `fun` function template declarations become:

```
template <typename ClassType>
static Char2 fun(void (ClassType::*)());

template <typename NonClassType>
static char fun(...);
```

Since `typeof` expressions can be evaluated compile-time we can now determine `isClass`'s value:

```
enum { isClass = sizeof(fun<Type>(0)) == sizeof(Char2) } ;
```

This expression has several interesting implications:

- no `fun` function template is ever instantiated;
- the compiler considers `Type` and selects `fun`'s function template specialization if `Type` is a class type and the generic function template if not;
- From the selected function it determines the return type and thus the return type's size;
- Resulting in the proper evaluation of `isClass`.

Without requiring any instantiation the trait class can now provide an answer to the question whether a template type argument represents a class type or not. **Marvelous!**

22.4.2 Available type traits (C++0x)

The C++0x standard offers many facilities to identify and modify characteristics of types. Before using these facilities the `<type_traits>` header file must be included.

All facilities offered by `type_traits` are defined in the `std` namespace (omitted from the examples given below) allowing programmers to

- determine whether a type is an lvalue reference
(`is_lvalue_reference<typename Type>::value`);
- determine whether a type is an rvalue reference
(`is_rvalue_reference<typename Type>::value`);
- determine whether a type is a reference
(`is_reference<typename Type>::value`);
- determine whether a type is a signed type
(`is_signed<typename Type>::value`);
- determine whether a type is an unsigned type
(`is_unsigned<typename Type>::value`);
- determine whether a type is *plain old data* (e.g., a struct not having members)
(`is_pod<typename Type>::value`);
- determine whether a type has a trivial default constructor
(`has_trivial_default_constructor<typename Type>::value`); This concept of a trivial member is also used in the next few type trait facilities.
- determine whether a type has a trivial copy constructor
(`has_trivial_copy_constructor<typename Type>::value`);
- determine whether a type has a trivial destructor
(`has_trivial_destructor<typename Type>::value`);
- determine whether a type has a trivial assignment operator
(`has_trivial_assign<typename Type>::value`);
- determine whether a type has a constructor not throwing exceptions
(`has_nothrow_default_constructor<typename Type>::value`);
- determine whether a type has a destructor not throwing exceptions
(`has_nothrow_destructor<typename Type>::value`);
- determine whether a type has a copy constructor not throwing exceptions
(`has_nothrow_copy_constructor<typename Type>::value`);
- determine whether a type has an assignment operator operator not throwing exceptions
(`has_nothrow_assign<typename Type>::value`);
- determine whether a type `Base` is a base class of another type `Derived`
(`is_base_of<typename Base, typename Derived>::value`);
- determine whether a type `From` may be converted to a type `To` (e.g., using a `static_cast`)
(`is_convertible<typename From, typename To>::value`);
- conditionally define `Type` if `cond` is true
(`enable_if<bool cond, typename Type>::type`);
- conditionally use `TrueType` if `cond` is true, `FalseType` if not
(`conditional<bool cond, typename TrueType, typename FalseType>::type`);
- remove a reference from a type
(`remove_reference<typename Type>::type`);
- add an lvalue reference to a type
(`add_lvalue_reference<typename Type>::type`);
- add an rvalue reference to a type
(`add_rvalue_reference<typename Type>::type`);

- construct an unsigned type
(make_unsigned<typename Type>::type);
- construct a signed type
(make_signed<typename Type>::type);

22.5 More conversions to class types

22.5.1 Types to types

Although *class* templates may be partially specialized, *function* templates may not. At times this is annoying. Assume a function template is available implementing a certain unary operator that could be used with the transform (cf. section 19.1.63) generic algorithm:

```
template <typename Return, typename Argument>
Return chop(Argument const &arg)
{
    return Return(arg);
}
```

Furthermore assume that if `Return` is `std::string` then the above implementation should not be used. Instead, with `std::string` a second argument `l` should always be provided. This would allow us, if `Argument` is a **C++** string, to return a copy of `arg` from which its first character has been chopped off.

Since `chop` is a function, it is not possible to define a partial specialization like this:

```
template <typename Argument>                // This won't compile!
std::string chop<std::string, Argument>(Argument const &arg)
{
    return string(arg, 1);
}
```

Although a function template cannot be partially specialized it *is* possible to use overloading, defining a second, dummy string parameter:

```
template <typename Argument>
std::string chop(Argument const &arg, std::string )
{
    return string(arg, 1);
}
```

Now it *is* possible to distinguish the two cases, but at the expense of a more complex function call. At the downside, in code this function may require the use of the `bind2nd` binder (cf. section 18.1.4) to provide the dummy second argument or it may require a (possibly expensive to construct) dummy argument to allow the compiler to choose among the two overloaded function templates.

Instead of providing a string dummy argument the functions *could* use the `IntType` template (cf. section 22.2.1.1) to select the proper overloaded version. E.g., `IntType<0>` could be defined as the type of the second argument of the first overloaded `chop` function, and `IntType<1>` could be used for the second overloaded function. From the point of view of program efficiency this is an attractive option, as the provided `IntType` objects are extremely lightweight. `IntType` objects contain no data at all. But there's also an obvious disadvantage as there is no intuitively clear association between the `int` value used and the intended type.

Instead of defining arbitrary `IntType` types it is more attractive to use another lightweight solution, using an automatic type-to-type association. The `struct TypeType` is a lightweight type wrapper, much like `IntType`. Here is its definition:

```
template <typename T>
struct TypeType
{
    typedef T Type;
};
```

`TypeType` is also a lightweight type as it doesn't have any data fields either. `TypeType` allows us to use a natural type association for `chop`'s second argument. E.g, the overloaded functions can now be defined as follows:

```
template <typename Return, typename Argument>
Return chop(Argument const &arg, TypeType<Argument> )
{
    return Return(arg);
}

template <typename Argument>
std::string chop(Argument const &arg, TypeType<std::string> )
{
    return std::string(arg, 1);
}
```

Using the above implementations any type can be specified for `Result`. If it happens to be a `std::string` the appropriate overloaded version is automatically selected. The following additional overload of the function `chop` capitalizes on this:

```
template <typename Result>
Result chop(char const *txt)      // char const * could also be a 2nd
{                                // template type parameter
    return chop(std::string(txt), TypeType<Result>());
}
```

Using the third `chop` function, the following statement produces the text 'ello world':

```
cout << chop<string>("hello world") << '\n';
```

Template functions do not support partial specializations. But they can be overloaded. By providing overloads with dummy type-arguments that depend on other parameters and calling these overloads from a overloaded function that does not require the dummy type argument a situation similar to partial specializations with class templates can often be realized.

22.5.2 An empty type

At times (cf. section 22.6) an empty `struct` is a useful tool. It can be used as a *type* acting analogously to the ASCII-Z (final 0-byte) in C-strings. It can simply be defined as:

```
struct NullType
{ };
```


22.5.3 Type convertability

In what situations can a type `T` be used as a ‘stand in’ for another type `U`? Since **C++** is a strongly typed language the answer is surprisingly simple: `T`s can be used instead of `U`s if a `T` is accepted as argument in cases where `U`s are requested.

This reasoning is behind the following class which can be used to determine whether a type `T` can be used where a type `U` is expected. The interesting part is that no code is actually generated or executed. All decisions are made by the compiler.

In the second part of this section we’ll show how the code developed in the first part can be used to detect whether a class `B` is a base class of another class `D` (the `is_base_of` template (cf. section 22.4.2) also provides an answer to this question). The code developed here closely follows the example provided by Alexandrescu (2001, p. 35).

First, a function `test` is designed accepting a type `U`. The function `test` returns a value of the as yet unknown type `Convertible`:

```
Convertible test(U const &);
```

The function `test` is never implemented. It is only declared. If a type `T` can be used instead of a type `U` then `T` can also be passed as argument to the above `test` function.

On the other hand, if the alternate type `T` cannot be used where a `U` is expected, then the compiler won’t be able to use the above `test` function. Instead, it will use an alternative function that has a lower selection priority but that can *always* be used with *any* `T` type.

C (and **C++**) offer a very general parameter list, a parameter list that will always be considered acceptable. This parameter list is the familiar *ellipsis* which represents the *worst* case the compiler may encounter. If everything else fails, then the function defining an ellipsis as its parameter list is selected.

Usually that’s not a productive alternative, but in the current situation it is *exactly* what is needed. When confronted with two candidate functions, one of which defines an ellipsis parameter, the compiler will select the function defining the ellipsis parameter only if the alternative(s) can’t be used.

Following the above reasoning an alternative function `test(...)` is declared as well. This alternate function does not return a `Convertible` value but a `NotConvertible` value:

```
NotConvertible test(...);
```

The return type `test` provided with a value of type `T` will be `Convertible` if `T` can be converted to `U`. Otherwise `NotConvertible` is returned.

This situation clearly shows similarities with the situation encountered in section 22.4.1 where the value `isClass` had to be determined compile time. Here two related problems must be solved:

- how do we obtain a `T` argument? This is more difficult than might be expected at first sight as it might not be possible to define a `T`. If type `T` does not define any constructor then no `T` object can be defined.
- how can `Convertible` be distinguished from `NotConvertible`?

The first problem is solved by realizing that no `T` *needs* to be defined. After all, the intent is to decide *compile-time* whether a type is convertible and not to define a `T` value or object. Defining objects is not a compile-time but a *run-time* matter.

By simply *declaring* a function returning a `T` we can tell the compiler where it should assume a `T`:

```
T makeT();
```

This mysterious function has the magical power of enticing the compiler into thinking that a `T` object will come out of it. This happens in the following code:

```
test(makeT())
```

Now that the compiler sees `test` being called with a `T` argument it will decide that its return value is `Convertible` if a conversion is in fact possible. Otherwise it will decide that its return value is `NotConvertible` (as it selected `test(...)` in that case).

The second problem, distinguishing `Convertible` from `NotConvertible` is solved exactly the way `isClass` could be determined in section 22.4.1, *viz.* by making their sizes different. Having done so the following expression determines whether `T` is convertible from `U` or not:

```
isConvertible = sizeof(test(makeT())) == sizeof(Convertible);
```

By using `char` for `Convertible` and `Char2` (cf. section 22.4.1) for `NotConvertible` the distinction can be made.

The above can be summarized in a class template `LconvertibleToR`, having two template type parameters:

```
template <typename T, typename U>
class LconvertibleToR
{
    struct Char2
    {
        char array[2];
    };
    static T makeT();
    static char test(U const &);
    static Char2 test(...);

public:
    LconvertibleToR(LconvertibleToR const &other) = delete;
    enum { yes = sizeof(test(makeT())) == sizeof(char) };
    enum { sameType = 0 };
};

template <typename T>
class LconvertibleToR<T, T>
{
public:
    LconvertibleToR(LconvertibleToR const &other) = delete;
    enum { yes = 1 };
    enum { sameType = 1 };
};
```

As the class template deletes its copy constructor no object can be created. Only its enum values can be interrogated. The next example writes 1 0 1 0 when run from a main function:

```
cout <<
    LconvertibleToR<ofstream, ostream>::yes << " " <<
    LconvertibleToR<ostream, ofstream>::yes << " " <<
    LconvertibleToR<int, double>::yes << " " <<
    LconvertibleToR<int, string>::yes <<
    "\n";
```

22.5.3.1 Determining inheritance

Now that `Conversion` has been defined it's easy to determine whether a type `Base` is a (public) base class of a type `Derived`.

Inheritance is determined a class teminspecting convertability of (const) pointers. `Derived const *` can be converted to `Base const *` if

- both types are identical;
- `Base` is a public and unambiguous base class of `Derived`;
- and (usually not intended) if `Base` is `void`.

Assuming the last conversion isn't used inheritance can be determined using the following trait class `LBaseRDerived`. `LBaseRDerived` provides an enum `yes` which is 1 if the left type is a base class of the right type and both types are different:

```
template <typename Base, typename Derived>
struct LBaseRDerived
{
    LBaseRDerived(LBaseRDerived const &) = delete;
    enum {
        yes =
            LconvertibleToR<Derived const *, Base const *>::yes &&
            not LconvertibleToR<Base const *, void const *>::sameType
    };
};
```

If code should not consider a class to be its own base class, then the trait class `LBaseRtrulyDerived` can be used to perform a strict test. This trait class adds a test for type-equality:

```
template <typename Base, typename Derived>
struct LBaseRtrulyDerived
{
    LBaseRtrulyDerived(LBaseRtrulyDerived const &) = delete;
    enum {
        yes =
            LBaseRDerived<Base, Derived>::yes &&
            not LconvertibleToR<Base const *, Derived const *>::sameType
    };
};
```

Example: the next statement displays 1: 0, 2: 1, 3: 0, 4: 1, 5: 0 when executed from a main function:

```
cout << "\n" <<
    "1: " << LBaseRDerived<ofstream, ostream>::yes << ", " <<
    "2: " << LBaseRDerived<ostream, ofstream>::yes << ", " <<
    "3: " << LBaseRDerived<void, ofstream>::yes << ", " <<
    "4: " << LBaseRDerived<ostream, ostream>::yes << ", " <<
    "5: " << LBaseRtrulyDerived<ostream, ostream>::yes <<
    "\n";
```

22.6 Template TypeList processing

This section serves two purposes. On the one hand it illustrates capabilities of the various meta-programming capabilities of templates, which can be used as a source of inspiration when developing

your own templates. On the other hand, it culminates in a concrete example, showing some of the power template meta-programming has.

This section itself was inspired by Andrei Alexandrescu's (2001) book **Modern C++ design**. It diverts from Alexandrescu's book in its use of variadic templates which were not yet available when he wrote his book. Even so, the algorithms used by Alexandrescu are still useful when using variadic templates.

The C++0x standard offers the tuple to store and retrieve values of multiple types. Here the focus is merely on processing types. A simple struct `TypeList` will be our working horse for the upcoming subsections. Here is its definition:

```
template <typename ... Types>
struct TypeList
{
    TypeList(TypeList const &) = delete;
    enum { size = sizeof ... (Types) };
};
```

A typelist allows us to store any number of types. Here is an example storing the three types `char`, `short`, `int` in a `TypeList`:

```
TypeList<char, short, int>
```

22.6.1 The length of a TypeList

As the number of types in a parameter pack may be obtained using the `sizeof` operator (cf. section 21.5) it is easy to obtain the number of types that were specified with a certain `TypeList`. For example, the following statement displays the value 3:

```
std::cout << TypeList<int, char, bool>::size << '\n';
```

However, it's illustrative to see how the number of types specified with a `TypeList` could be determined if `sizeof` hadn't been available.

To obtain the number of types that were specified with a `TypeList` the following algorithm is used:

- If the `TypeList` contains no types, its size equals zero;
- If the `TypeList` contains types, its size equals 1 plus the number of types that follow its first type.

The algorithm uses recursion to define the length of a `TypeList`. In executable C++ recursion could also be used in comparable situations. For example recursion can be used to determine the length of a plain C (ascii-Z) string:

```
size_t c_length(char const *cp)
{
    return *cp == 0 ? 0 : 1 + c_length(cp + 1);
}
```

While C++ functions usually use iteration rather than recursion, iteration is not available to template meta programming algorithms. In template meta programming repetition *must* be implemented using recursion. Furthermore, while C++ run-time code may use conditions to decide whether or not to start the next recursion template meta programming cannot do so. Template meta programming algorithms must resort to (partial) specializations. The specializations are used to select alternatives.

The number of types that are specified in a `TypeList` can be computed using the following alternate implementation of `TypeList`, using a generic struct declaration and two specialization for the empty and non-empty `TypeList` (cf. the above description of the algorithm):

```
template <typename ... Types>
struct TypeList;

template <typename Head, typename ... Tail>
struct TypeList
{
    enum { size = 1 + TypeList<Tail ...>::size };
};
template <>
struct TypeList<>
{
    enum { size = 0 };
};
```

22.6.2 Searching a TypeList

To determine whether a particular type (called *SearchType* below) is present in a given `TypeList`, an algorithm is used that either defines ‘index’ as -1 (if *SearchType* is not an element of the `TypeList`) or it defines ‘index’ as the index of the first occurrence of *SearchType* in the `TypeList`. The following algorithm is used:

- If the `TypeList` is empty, ‘index’ is -1;
- If the `TypeList`’s first element equals *SearchType*, ‘index’ is 0;
- Otherwise ‘index’ is:
 - -1 if searching for *SearchType* in `TypeList`’s tail results in ‘index’ == -1;
 - Otherwise (*SearchType* was found in `TypeList`’s tail) index is set to 1 + the index obtained when searching for *SearchType* in the `TypeList`’s tail.

The algorithm is implemented using a variadic template struct `ListSearch` expecting a parameter pack:

```
template <typename ... Types>
struct ListSearch
{
    ListSearch(ListSearch const &) = delete;
};
```

Specializations handle the alternatives mentioned with the algorithm:

- If `TypeList` is empty, ‘index’ is -1:

```
template <typename SearchType>
struct ListSearch<SearchType, TypeList<>>
{
    ListSearch(ListSearch const &) = delete;
    enum { index = -1 };
};
```

- If `TypeList`'s head equals `SearchType`, 'index' is 0. Note that `SearchType` is explicitly mentioned as the `TypeList`'s first element:

```
template <typename SearchType, typename ... Tail>
struct ListSearch<SearchType, TypeList<SearchType, Tail ...>>
{
    ListSearch(ListSearch const &) = delete;
    enum { index = 0 };
};
```

- Otherwise a search is performed on the `TypeList`'s tail. The index value returned by this search is stored in a `tmp` enum value, which is then used to determine index's value.

```
template <typename SearchType, typename Head, typename ... Tail>
struct ListSearch<SearchType, TypeList<Head, Tail ...> >
{
    ListSearch(ListSearch const &) = delete;
    enum { tmp = ListSearch<SearchType, TypeList<Tail ...>>::index };
    enum { index = tmp == -1 ? -1 : 1 + tmp };
};
```

Here is an example showing how `ListSearch` can be used:

```
std::cout <<
    ListSearch<char, TypeList<int, char, bool>>::index << "\n" <<
    ListSearch<float, TypeList<int, char, bool>>::index << "\n";
```

22.6.3 Selecting from a TypeList

The inverse operation of determining the index of a certain type in a `TypeList` is retrieving the type given its index. This inverse operation is the topic of this section.

The algorithm is implemented using a struct `TypeAt`. `TypeAt` uses a `typedef` to define the type matching a given index. But the index might be out of bounds. In that case we have several options:

- Use a `static_assert` to stop the compilation. This is an appropriate action if the index should simply not be out of bounds;
- Define a local type (e.g., `Null`) that should not be used as a type in the `TypeList`. Using that local type as a type in a `TypeList` is considered an error as its use in a `TypeList` could easily cause confusion (was the index invalid? did we actually stumble across `Null`?). A `static_cast` may be used to prevent `Null` from being returned as the type matching the search index;
- The struct `TypeAt` may define a enum value `validIndex` set to `true` if the index was valid and set to `false` if not.

The first alternative is implemented below. The other alternatives are not difficult to implement and are left as exercises for the reader. Here's how `TypeAt` works:

- The foundation consists of a variadic template struct `TypeAt`, expecting an index and a `TypeList`:

```
template <size_t index, typename Typelist>
struct TypeAt;
```

- If the `typelist` is empty a `static_assert` ends the compilation

```
template <size_t index>
```

```
struct TypeAt<index, TypeList<>>
{
    static_assert(index < 0, "TypeAt index out of bounds");
    typedef TypeAt Type;
};
```

- If the search index equals 0, define Type as the first type in the TypeList:

```
template <typename Head, typename ... Tail>
struct TypeAt<0, TypeList<Head, Tail ...>>
{
    typedef Head Type;
};
```

- Otherwise, Type is defined as Type defined by TypeAt<index - 1> operating on the TypeList's tail:

```
template <size_t index, typename Head, typename ... Tail>
struct TypeAt<index, TypeList<Head, Tail ...>>
{
    typedef typename TypeAt<index - 1, TypeList<Tail ...>>::Type Type;
};
```

Here is how typeAt can be used. Uncommenting the first variable definition causes a TypeAt index out of bounds compilation error:

```
typedef TypeList<int, char, bool> list3;

// TypeAt<3, list3>::Type invalid;
TypeAt<0, list3>::Type intVariable = 13;
TypeAt<2, list3>::Type boolVariable = true;

cout << "The size of the first type is " <<
    sizeof(TypeAt<0, list3>::Type) << ", "
    "the size of the third type is " <<
    sizeof(TypeAt<2, list3>::Type) << "\n";

if (typeid(TypeAt<1, list3>::Type) == typeid(char))
    cout << "The typelist's 2nd type is char\n";

if (typeid(TypeAt<2, list3>::Type) != typeid(char))
    cout << "The typelist's 3rd type is not char\n";
```

22.6.4 Prefixing/Appending to a TypeList

Prepending or appending a type to a TypeList is easy and doesn't require recursive template meta programs. Two variadic template structs Append and Prefix and two specializations are all it takes.

Here are the declarations of the two variadic template structs:

```
template <typename ... Types>
struct Append;

template <typename ... Types>
struct Prefix;
```

To append or prefix a new type to a typelist specializations expect a typelist and a type to add and simply define a new TypeList also including the new type. The Append specialization shows that a

template pack does not have to be used as the first argument when defining another variadic template type:

```
template <typename NewType, typename ... Types>
struct Append<TypeList<Types ...>, NewType>
{
    typedef TypeList<Types ..., NewType> List;
};

template <typename NewType, typename ... Types>
struct Prefix<NewType, TypeList<Types ...>>
{
    typedef TypeList<NewType, Types ...> List;
};
```

22.6.5 Erasing from a TypeList

It is also possible to erase types from a `TypeList`. Again, there are several possibilities, each resulting in a different algorithm.

- The type to erase is specified, and the first occurrence of that type is removed from the `TypeList`;
- The index of the type to erase is specified, and the type at that index position is erased from the `TypeList`;
- The type to erase is specified, and all occurrences of that type are removed from the `TypeList`.
- As a variant of erasure: we may want to erase all multiply occurring types in a `TypeList`, keeping each type only once.

Doubtlessly there are other ways of erasing types from a `TypeList`. Which ones eventually will be implemented depends of course on the circumstances. As template meta programming is very powerful most if not all algorithms can probably be implemented. As an illustration of how to erase types from a `TypeList` the abovementioned algorithms are now developed in the upcoming subsections.

22.6.5.1 Erasing the first occurrence

To erase the first occurrence of a specified `EraseType` from a `TypeList` a recursive algorithm is used once again. The template meta program uses a generic `Erase` struct and several specializations. The specializations define a type `List` containing the resulting `TypeList` after the erasure. Here is the algorithm:

- The foundation of the algorithm consists of a struct template `Erase` expecting the type to erase and a `TypeList`:

```
template <typename EraseType, typename TypeList>
struct Erase;
```

- If the `typelist` is empty, there's nothing to erase, and an empty `TypeList` results:

```
template <typename EraseType>
struct Erase<EraseType, TypeList<>>
{
    typedef TypeList<> List;
};
```


- If the `TypeList`'s head matches the type to erase, then `List` will be a `TypeList` containing the original `TypeList`'s tail types:

```
template <typename EraseType, typename ... Tail>
struct Erase<EraseType, TypeList<EraseType, Tail ...>>
{
    typedef TypeList<Tail ...> List;
};
```

- In all other cases the erase operation is applied to the `TypeList`'s tail. This results in a `TypeList` to which the original `TypeList`'s head must be prefixed. The `TypeList` returned by the prefix operation is then returned as `Erase::Type`:

```
template <typename EraseType, typename Head, typename ... Tail>
struct Erase<EraseType, TypeList<Head, Tail ...>>
{
    typedef typename
        Prefix<Head,
            typename Erase<EraseType, TypeList<Tail ...>>::List
        >::List List;
};
```

Here is a statement showing how `Erase` can be used:

```
cout <<
    Erase<int, TypeList<char, double, int>>::List::size << '\n' <<
    Erase<char, TypeList<int>>::List::size << '\n' <<
    Erase<int, TypeList<int>>::List::size << '\n' <<
    Erase<int, TypeList<>>::List::size << "\n";
```

22.6.5.2 Erasing a type by its index

To erase a type from a `TypeList` by its index we again use a recursive template meta program. `EraseIdx` expects a `size_t` index value and a `TypeList` from which its `idxsup(th)` type must be erased. `EraseIdx` defines the type `List` containing the resulting `TypeList`. Here is the algorithm:

- The foundation of the algorithm consists of a struct template `EraseIdx` expecting the index of the type to erase and a `TypeList`:

```
template <size_t idx, typename TypeList>
struct EraseIdx;
```

- If the typelist is empty, there's nothing to erase, and an empty `TypeList` results:

```
template <size_t idx>
struct EraseIdx<idx, TypeList<>>
{
    typedef TypeList<> List;
};
```

- The recursion otherwise ends once `idx` becomes 0. At that point the `TypeList`'s first type is ignored and `Type` is initialized to a `TypeList` containing the types in the original `TypeList`'s tail:

```
template <typename EraseType, typename ... Tail>
struct EraseIdx<0, TypeList<EraseType, Tail ...>>
{
    typedef TypeList<Tail ...> List;
};
```

- In all other cases `EraseIdx` is applied to the `TypeList`'s tail, providing it with a decremented value of `idx`. To the resulting `TypeList` the original `TypeList`'s head is prefixed. The `TypeList` returned by the prefix operation is then returned as `EraseIdx::Type`:

```
template <size_t idx, typename Head, typename ... Tail>
struct EraseIdx<idx, TypeList<Head, Tail ...>>
{
    typedef typename Prefix<
        Head,
        typename EraseIdx<idx - 1, TypeList<Tail ...>>::List
    >::List List;
};
```

Here is a statement showing how `EraseIdx` can be used:

```
if
(
    typeid(TypeAt<2,
        EraseIdx<1,
            TypeList<int, char, size_t, double, int>>::List
        >::Type
    )
    == typeid(double)
)
    cout << "the third type is now a double\n";
```

22.6.5.3 Erasing all occurrences of a type

Erasing all types `EraseType` from a `TypeList` can easily be accomplished by applying the erasure procedure not only to the head of the `TypeList` but also to the `TypeList`'s tail.

Here is the algorithm, described in a slightly different order than `Erase`'s algorithm:

- If the `TypeList` is empty, there's nothing to erase, and an empty `TypeList` results. This is exactly what we do with `Erase`, so we can use inheritance to prevent us from having to duplicate elements of a template meta program:
- The foundation of the algorithm is therefore a struct template `EraseAll` expecting the type to erase and a `TypeList` that is derived from `Erase`, thus already offering the empty `TypeList` handling specialization:

```
template <typename EraseType, typename TypeList>
struct EraseAll: public Erase<EraseType, TypeList>
{
};
```

- If `TypeList`'s head matches `EraseType` `EraseAll` is also applied to the `TypeList`'s tail, thus removing all occurrences of `EraseType` from `TypeList`:

```
template <typename EraseType, typename ... Tail>
struct EraseAll<EraseType, TypeList<EraseType, Tail ...>>
{
    typedef typename EraseAll<EraseType, TypeList<Tail ...>>::List List;
};
```

- In all other cases (i.e., `TypeList`'s head does *not* match `EraseType`) `EraseAll` is applied to the `TypeList`'s tail. The returned `TypeList` consists of the original `TypeList`'s initial type and the types of the `TypeList` returned by the recursive `EraseAll` call:

```
template <typename EraseType, typename Head, typename ... Tail>
```

```

struct EraseAll<EraseType, TypeList<Head, Tail ...>>
{
    typedef typename Prefix<
        Head,
        typename EraseAll<EraseType, TypeList<Tail ...>>::List
    >::List List;
};

```

Here is a statement showing how EraseAll can be used:

```

cout <<
    "After erasing size_t from "
    "TypeList<char, int, size_t, double, size_t>\n"
    "it contains " <<
    EraseAll<size_t,
        TypeList<char, int, size_t, double, size_t>
    >::List::size << " types\n";

```

22.6.5.4 Erasing duplicates

To remove all duplicates from a TypeList all the TypeList's first elements must be erased from the TypeList's tail, applying the procedure recursively to the TypeList's tail. The algorithm, outlined below, merely expects a TypeList:

- First, the generic EraseDup struct template is declared. EraseDup structures define a type List representing the TypeList that they generate. EraseDup calls expect a TypeList as their template type parameters:

```

template <typename TypeList>
struct EraseDup;

```

- If the TypeList is empty it can be returned empty and we're done:

```

template <>
struct EraseDup<TypeList<>>
{
    typedef TypeList<> List;
};

```

- In all other cases

- EraseDup is first applied to the original TypeList's tail. By definition this will result in a TypeList from which all duplicates have been removed;
- The TypeList returned by the previous step might contain the original TypeList's initial type. If so, it will be removed by applying Erase on the returned TypeList, specifying the original TypeList's initial type as the type to remove;
- The returned TypeList consists of the original TypeList's initial type to which the types of the TypeList produced by the previous step are appended.

This specialization is implemented like this:

```

template <typename Head, typename ... Tail>
struct EraseDup<TypeList<Head, Tail ...>>
{
    typedef typename EraseDup<TypeList<Tail ...>>::List UniqueTail;
    typedef typename Erase<Head, UniqueTail>::List NewTail;

    typedef typename Prefix<Head, NewTail>::List List;
};

```

Here is an example showing how `EraseDup` can be used:

```
cout <<
    "After erasing duplicates from "
    "TypeList<double, char, int, size_t, int, double, size_t>\n"
    "it contains " <<
    EraseDup<
        TypeList<double, char, int, size_t, int, double, size_t>
    >::List::size << " types\n";
```

22.7 Using a TypeList

In the previous sections the definition and some of the features of typelists were discussed. Most **C++** programmers consider typelists both exciting and an intellectual challenge, honing their skills in the area of recursive programming.

But there's more to typelist than a mere intellectual challenge. In the final sections of this chapter the following topics are covered: will be covered:

- Creating classes from a typelist.
Here the aim is to construct a new class consisting of instantiations of an existing basic template for each of the types mentioned in a provided typelist;
- Accessing data members from the thus constructed conglomerate class by index, rather than name.

Again, much of the material covered by these sections was inspired by Alexandrescu's (2001) book, this time combined with the features offered by the C++0x standard.

22.7.1 The Wrap and Multi class templates

As an illustration of template meta programming concepts the template class `Multi` is now developed. The class template `Multi` creates a new class from a template template parameter `Policy` defining the data storage policy and a series of types from which `Multi` is eventually derived. It does so by passing its template parameters to its base class `MultiBase` that in turn creates a final class inheritance tree. Since we don't know how many types will be used `Multi` is defined as a variadic class template using a template pack ... `Types`.

In fact, the types that are specified with `Multi` aren't that interesting. They primarily serve to 'seed' the class `Policy` with. Therefore, rather than forwarding `Multi`'s types to `MultiBase` they are passed to `Policy` and the sequence of `Policy<Type>` types is then forwarded to `MultiBase`. `Multi`'s constructor expects initialization values for its various `Policy<Type>`s which are perfectly forwarded to `MultiBase`.

The class `Multi` (implementing its constructor in-class to save some space) shows how a template pack can be wrapped into a policy. Here is `Multi`'s definition:

```
template <template <typename> class Policy, typename ... Types>
struct Multi: public MultiBase<0, Policy<Types> ...>
{
    typedef TypeList<Types ...> PlainTypes;
    typedef MultiBase<0, Policy<Types> ...> Base;

    enum { size = PlainTypes::size };

    Multi(Policy<Types> &&... types)
```

```

:
    MultiBase<0, Policy<Types> ...>(
        std::forward<Policy<Types>>(types) ...)
    {}
};

```

Unfortunately, the design as described contains some flaws.

- As the Policy template parameter is defined as `template <typename> class Policy` it can only accept policies expecting one type argument. Contrary to this, `std::vector` is a template expecting two template arguments, the second one defining the allocation scheme used by `std::vector`. This allocation scheme is hardly ever changed, and most applications merely define objects of types like `vector<int>`, `vector<string>` etc.. Template template parameters must, however, be specified with the correct number and types of required template parameters so `vector` can't be specified as a policy for `Multi`. This can be solved by *wrapping* a more complex template in a simpler wrapper template, like so:

```

template <class Type>
struct Vector: public std::vector<Type>
{
    Vector(std::initializer_list<Type> iniValues)
    :
        std::vector<Type>(iniValues)
    {}
};

```

Now `Vector` will provide `std::vector`'s second parameter using its default template argument. Alternatively, a *template using declaration* could be used.

- If the `TypeList` contains two types like `int` and `double` and the policy class is `Vector`, then the `MultiBase` class will eventually inherit from `vector<int>` and `vector<double>`. But if the `TypeList` contains identical types, like two `int` type specifications `MultiBase` would inherit from *two* `vector<int>` classes. Classes cannot be derived from identical base classes as that would make it impossible to distinguish among their members. Regarding this, Alexandrescu (2001) writes (p.67):

*There is one major source of annoyance...: you cannot use it when you have duplicate types in your TypeList.
 There is no easy way to solve the ambiguity, [as the eventually derived class/FBB] ends up inheriting [the same base class/FBB] twice.*

There is a way around the problem of duplicate base class types. If instead of inheriting directly from base classes these base classes are first wrapped in unique type defining classes, then these unique classes can be used to access the base classes using principles of inheritance. As these unique type-defining wrapper classes are merely classes that are derived from the 'real' base classes they inherit (and thus: offer) the functionality of their base classes. A unique type defining wrapper class can be designed after the class `IntType`, defined earlier. The wrapper class we're looking combines class derivation with the uniqueness offered by `IntType`. The class template `UWrap` has two template parameters: one non-type parameter `idx` and one type parameter. By ensuring that each `UWrap` definition uses a unique `idx` value unique class types are created. These unique class types are then used as base classes of the derived class `MultiBase`:

```

template <size_t nr, typename Type>
struct UWrap: public Type
{
    UWrap(Type const &type)
    :
        Type(type)
    {}
};

```

Using `UWrap` it's easy to distinguish, e.g., two `vector<int>` classes: `UWrap<0, vector<int>` could refer to the first `vector<int>`, `UWrap<1, vector<int>` to the second `vector`.

Uniqueness of the various `UWrap` types is assured by the class template `MultiBase` as discussed in the next section.

It must also be possible to initialize a `Multi` class object. Its constructor therefore expects the initialization values for all its `Policy` values. So if a `Multi` is defined for `Vector`, `int`, `string` then its constructor can receive the matching initialization values. E.g.,

```
Multi<Vector, int, string> mvis({1, 2, 3}, {"one", "two", "three"});
```

22.7.2 The `MultiBase` class template

The class template `MultiBase` is `Multi`'s base class. It defines a class that, eventually, is derived from the list of `Policy` types that, in turn, were created by `Multi` using any additional types that were passed to it.

`MultiBase` itself has no concept of a `Policy`. To `MultiBase` the world consists of a simple template pack whose types will be used to define a class from. In addition to the `PolicyTypes` template pack, `MultiBase` also defines a `size_t` `nr` non-type parameter that is used to create unique `UWrap` types. Here is `MultiBase`'s generic class declaration:

```
template <size_t nr, typename ... PolicyTypes>
struct MultiBase;
```

Two specializations handle all possible `MultiBase` invocations. One specialization is a recursive template. This template handles the first type of `MultiBase`'s template parameter pack and recursively uses itself to handle the remaining types. The second specialization is invoked once the template parameter pack is exhausted and does nothing. Here is the definition of the latter specialization:

```
template <size_t nr>
struct MultiBase<nr>
{};
```

The recursively defined specialization is the interesting one. It performs the following tasks:

- It is derived from a unique `UWrap` type. The uniqueness is guaranteed by using `MultiBase`'s `nr` parameter when defining `UWrap`. In addition to `nr` the `UWrap` class receives the first type of the template parameter pack made available to `MultiBase`;
- It is also recursively derived from itself. The recursive `MultiBase` type is defined using as its first template argument an incremented `nr` value (thus ensuring the uniqueness of the `UWrap` types defined by recursive `MultiWrap` types). Its second template argument is the tail of the template parameter pack made available to `MultiBase`

An illustration showing the layout of the `MultiBase` class hierarchy is provided in figure [22.1](#).

`MultiBase`'s constructor simply receives the initialization values that were passed to (originally) the `Multi` object. To accomplish this perfect forwarding is used. `MultiBase`'s constructor passes its first parameter value to its `UWrap` base class, also using perfect forwarding. `MultiBase`'s recursive definition is:

```
template <size_t nr, typename PolicyT1, typename ... PolicyTypes>
struct MultiBase<nr, PolicyT1, PolicyTypes ...> :
    public UWrap<nr, PolicyT1>,
    public MultiBase<nr + 1, PolicyTypes ...>
```




Figure 22.1: Layout of a MultiBase class hierarchy

```

{
    typedef PolicyT1 Type;
    typedef MultiBase<nr + 1, typename PolicyTypes ...> Base;

    MultiBase(PolicyT1 && policyt1, PolicyTypes &&... policytypes)
    :
        UWrap<nr, PolicyT1>(std::forward<PolicyT1>(policyt1)),
        MultiBase<nr + 1, PolicyTypes ...>(
            std::forward<PolicyTypes>(policytypes) ...)
    {}
};

```

22.7.3 Support templates

The `Multi` class template defines `PlainTypes` as the `TypeList` holding all the types of its parameter pack. Each `MultiType` derived from a `UWrap` type also defines a type `Type` representing the policy type that was used to define the `UWrap` type and a type `Base` representing the type of its nested `MultiBase` class.

These three type definitions allow us to access the types from which the `Multi` object was created as well as the values of those types.

The class template `typeAt`, is a pure template meta program class template (it has no run-time executable code). It expects a `size_t idx` template argument specifying the index of the policy type in a `Multi` type object as well as a `Multi` class type. It defines the type `Type` as the `Type` defined by `Multi`'s `MultiBase<idx, ... base class>`. Example:

```
typeAt<0, Multi<Vector, int, double>>::Type // Type is vector<double>
```

The class template `typeAt` defines (and uses) a nested class template `PolType` doing all the work. `PolType`'s generic definition specifies two template parameters: an index used to specify the index of the requested type and a typename which initialized by a `MultiBase` type argument. `PolType`'s recursive definition recursively reduces its index non-type parameter, passing the next base class in `MultiBase`'s inheritance tree to the recursive call. As `PolType` eventually defines the type `Type` to be the requested policy type the recursive definition defines its `Type` as the type defined by the recursive call. The final (non-recursive) specialization defines the initial policy type of the `MultiBase` type as `Type`. Here is `typeAt`'s definition:

```

template <size_t index, typename Multi>
class typeAt
{
    template <size_t idx, typename MultiBase>
    struct PolType;

    template <size_t idx,
              size_t nr, typename PolicyT1, typename ... PolicyTypes>
    struct PolType<idx, MultiBase<nr, PolicyT1, PolicyTypes ...>>
    {
        typedef typename PolType<
            idx - 1, MultiBase<nr + 1, PolicyTypes ...>>::Type Type;
    };

    template <size_t nr, typename PolicyT1, typename ... PolicyTypes>
    struct PolType<0, MultiBase<nr, PolicyT1, PolicyTypes ...>>
    {
        typedef PolicyT1 Type;
    };
public:
    typeAt(typeAt const &) = delete;
    typedef typename PolType<index, typename Multi::Base>::Type Type;
};

```

The types specified by `Multi`'s parameter pack can also be retrieved using a second helper class template: `plainTypeAt`. Example:

```

plainTypeAt<0, Multi<Vector, int, double>>::Type // Type is double

```

The class template `plainTypeAt` uses a comparable (but simpler) implementation than `typeAt`. It is also a pure template meta program class template defining a nested class template `At`. `At` is implemented like `typeAt` but it visits the types of the original template pack that was passed to `Multi`, and made available by `Multi` as its `PlainTypes` type. Here is `plainTypeAt`'s definition:

```

template <size_t index, typename Multi>
class plainTypeAt
{
    template <size_t idx, typename List>
    struct At;

    template <size_t idx, typename Head, typename ... Tail>
    struct At<idx, TypeList<Head, Tail...>>
    {
        typedef typename At<idx - 1, TypeList<Tail ...>>::Type Type;
    };

    template <typename Head, typename ... Tail>
    struct At<0, TypeList<Head, Tail...>>
    {
        typedef Head Type;
    };
public:
    plainTypeAt(plainTypeAt const &) = delete;
    typedef typename At<index, typename Multi::PlainTypes>::Type Type;
};

```

Arguably the neatest support template is `get`. This is a function template defining `size_t idx` as its first template parameter and `typename Multi` as its second template parameter. `Get` defines one

function parameter: a reference to a `Multi`, so it can deduct `Multi`'s type by itself. Knowing that it's a `Multi`, we reason that it is also a `UWrap<nr, PolicyType>` and therefore also a `PolicyType`, as the latter class is defined as a base class of `UWrap`.

Since class type objects can initialize references to their base classes the `PolicyType` & can be initialized by an appropriate `UWrap` reference, which in turn can be initialized by a `Multi` object. Since we can determine `PolicyType` using `TypeAt` (note that evaluating `typename typeAt<idx, Multi>::Type` is a purely compile-time matter), the `get` function can very well be implemented *inline* by a single return statement:

```
template <size_t idx, typename Multi>
inline typename typeAt<idx, Multi>::Type &get(Multi &multi)
{
    return static_cast<
        UWrap<idx, typename typeAt<idx, Multi>::Type> &>(multi);
}
```

The intermediate `UWrap` cast is required to disambiguate between identical policy types (like two `vector<int>` types). As `UWrap` is uniquely determined by its `nr` template argument and this is the number argument that is passed to `get` ambiguities can easily be prevented.

22.7.4 Using Multi

Now that `Multi` and its support templates have been developed, how can a `Multi` be used?

A word of warning is in place. To reduce the size of the developed classes they were designed in a minimalist way. For example, the `get` function template cannot be used with `Multi` `const` objects and there is no default, or move constructor available for `Multi` types. `Multi` was designed to illustrate some of the possibilities of template meta programming and hopefully `Multi`'s implementation served that purpose well. But can it be used? If so, how?

This section provides some annotated examples. They may be concatenated to define a series of statements that could be placed in a `main` function's body, which would result in a working program.

- A simple `Policy` could be defined:

```
template <typename Type>
struct Policy
{
    Type d_type;
    Policy(Type &&type)
    :
        d_type(std::forward<Type>(type))
    {}
};
```

`Policy` defines a data member and it can be used to define `Multi` objects:

```
Multi<Policy, string> ms(Policy<string>("hello"));
Multi<Policy, string, string> ms2s(Policy<string>("hello"),
                                   Policy<string>("world"));

typedef Multi<Policy, string, int> MPSI;
MPSI mpsi(string("hello"), 4);
```

- To obtain the number of types defined by a `Multi` class or object either use the `::size` enum value (using the `Multi` class) or the `.size` member (using the `Multi` object):

```
cout << "There are " << MPSI::size << " types in MPSI\n"
```

```
"There are " << mpsi.size << " types in mpsi\n";
```

- Variables of constituting types can be defined using `plainTypeAt`:

```
plainTypeAt<0, MPSI>::Type sx = "String type";
plainTypeAt<1, MPSI>::Type ix = 12;
```

- Raw static casts can be used to obtain the constituent type:

```
cout << static_cast<Policy<string>> &>(mpsi).d_type << '\n' <<
      static_cast<Policy<int>> &>(mpsi).d_type << '\n';
```

- However, this won't work when the template parameter pack contains identical types, as a cast can't distinguish between identical `Policy<Type>` types. In that case `get` still works fine:

```
typedef Multi<Policy, int, int> MPII;
MPII mpii(4, 18);

cout << get<0>(mpii).d_type << ' ' << get<1>(mpii).d_type << '\n';
```

- Here is an example wrapping a `std::vector` in a `Vector`:

```
typedef Multi<Vector, int, double> MVID;
MVID mi({1, 2, 3}, {1.2, 3.4, 5.6, 7.8});
```

- Such a vector can be defined by its `Multi` type:

```
typeAt<0, Multi<Vector, int>>::Type vi = {1, 2, 3};
```

- Knowing that a `Vector` is a `std::vector`, the reference returned by `get` support index operators that can be used as left hand side or right hand side operands:

```
cout << get<0>(mi)[2] << '\n';
get<1>(mi)[3] = get<0>(mi)[0];
cout << get<1>(mi)[3] << '\n';
```

Chapter 23

Concrete Examples

In this chapter concrete examples of **C++** programs, classes and templates will be presented. Topics covered by the **C++** Annotations such as virtual functions, `static` members, etc. are illustrated in this chapter. The examples roughly follow the organization of earlier chapters.

As an additional topic, not just providing examples of **C++** the subjects of scanner and parser generators are covered. We show how these tools may be used in **C++** programs. These additional examples assume a certain familiarity with the concepts underlying these tools, like grammars, parse-trees and parse-tree decoration. Once the input for a program exceeds a certain level of complexity, it's attractive to use scanner- and parser-generators to create the code doing the actual input processing. One of the examples in this chapter describes the usage of these tools in a **C++** environment.

23.1 Using file descriptors with ‘streambuf’ classes

23.1.1 Classes for output operations

Reading and writing from and to *file descriptors* are not part of the **C++** standard. But on most operating systems file descriptors *are* available and can be considered a device. It seems natural to use the class `std::streambuf` as the starting point for constructing classes interfacing such file descriptor devices.

Below we'll construct classes that can be used to write to a device given its file descriptor. The devices may be files, but they could also be pipes or sockets. Section [23.1.2](#) covers reading from such devices; section [23.3.1](#) reconsiders redirection, discussed earlier in section [6.6.1](#).

Using the `streambuf` class as a base class it is relatively easy to design classes for output operations. The only member function that *must* be overridden is the (virtual) member `int streambuf::overflow(int c)`. This member's responsibility is to write characters to the device. If `fd` is an output file descriptor and if output should not be buffered then the member `overflow()` can simply be implemented as:

```
class UnbufferedFD: public std::streambuf
{
    public:
        virtual int overflow(int c);
        ...
};

int UnbufferedFD::overflow(int c)
{
    if (c != EOF)
    {
```

```

        if (write(d_fd, &c, 1) != 1)
            return EOF;
    }
    return c;
}

```

The argument received by `overflow` is either written to the file descriptor (and returned from `overflow`), or `EOF` is returned.

This simple function does not use output buffering. For various reasons, using a buffer is usually a good idea (see also the next section).

When output buffering is used, the `overflow` member is a bit more complex as it is only called when the buffer is full. Once the buffer is full, we *first* have to flush the buffer. Flushing the buffer is the responsibility of the (virtual) function `streambuf::sync` is available. Since `sync` is a virtual function, classes derived from `streambuf` may redefine `sync` to flush a buffer `streambuf` itself doesn't know about.

Overriding `sync` and using it in `overflow` is not all that has to be done. When the object of the class defining the buffer reaches the end of its lifetime the buffer may be only partially full. In that situation the buffer must also be flushed. This is easily done by simply calling `sync` from the class's destructor.

Now that we've considered the consequences of using an output buffer, we're almost ready to design our derived class. Several more features will be added as well, though:

- First, we should allow the user of the class to specify the size of the output buffer.
- Second, it should be possible to construct an object of our class before the file descriptor is actually known. Later, in section 23.3 we'll encounter a situation where this feature will be used.

To save some space in the C++ Annotations, the successful completion of the functions designed here is not checked in the example code. In 'real life' implementations these checks should of course not be omitted. Our class `OFdnStreambuf` has the following characteristics:

- Its member functions use low-level functions operating on file descriptors. So apart from `streambuf` the `<unistd.h>` header file must have been read by the compiler before its member functions can be compiled.
- The class is derived from `std::streambuf`.
- It defines three data members. These data members keep track of, respectively, the size of the buffer, the file descriptor, and the buffer itself. Here is the full class interface

```

class OFdnStreambuf: public std::streambuf
{
    size_t d_bufsize;
    int    d_fd;
    char   *d_buffer;

public:
    OFdnStreambuf();
    OFdnStreambuf(int fd, size_t bufsize = 1);
    virtual ~OFdnStreambuf();
    void open(int fd, size_t bufsize = 1);
private:
    virtual int sync();
    virtual int overflow(int c);
};

```

- Its default constructor merely initializes the buffer to 0. Slightly more interesting is its constructor expecting a file descriptor and a buffer size. This constructor passes its arguments on to the class’s open member (see below). Here are the constructors:

```
inline OFdnStreambuf::OFdnStreambuf()
:
    d_bufsize(0),
    d_buffer(0)
{}
inline OFdnStreambuf::OFdnStreambuf(int fd, size_t bufsize)
{
    open(fd, bufsize);
}
```

- The destructor calls sync, flushing any characters stored in the output buffer to the device. In implementations not using a buffer the destructor can be given a default implementation:

```
inline OFdnStreambuf::~~OFdnStreambuf()
{
    if (d_buffer)
    {
        sync();
        delete[] d_buffer;
    }
}
```

This implementation does not close the device. It is left as an exercise to the reader to change this class in such a way that the device is optionally closed (or optionally remains open). This approach was adopted by, e.g., the Bobcat library¹. See also section 23.1.2.2.

- The open member initializes the buffer. Using streambuf::setp, the begin and end points of the buffer are defined. This is used by the streambuf base class to initialize streambuf::pbase, streambuf::pptr, and streambuf::epptr:

```
inline void OFdnStreambuf::open(int fd, size_t bufsize)
{
    d_fd = fd;
    d_bufsize = bufsize == 0 ? 1 : bufsize;

    d_buffer = new char[d_bufsize];
    setp(d_buffer, d_buffer + d_bufsize);
}
```

- The member sync flushes the as yet unflushed contents of the buffer to the device. After the flush the buffer is reinitialized using setp. After successfully flushing the buffer sync returns 0:

```
inline int OFdnStreambuf::sync()
{
    if (pptr() > pbase())
    {
        write(d_fd, d_buffer, pptr() - pbase());
        setp(d_buffer, d_buffer + d_bufsize);
    }
    return 0;
}
```

- The member streambuf::overflow is also overridden. Since this member is called from the streambuf base class when the buffer is full it should first call sync to flush the buffer to the

¹<http://bobcat.sourceforge.net>

device. Next it should write the character `c` to the (now empty) buffer. The character `c` should be written using `pptr` and `streambuf::pbump`. Entering a character into the buffer should be implemented using available `streambuf` member functions, rather than ‘by hand’ as doing so might invalidate `streambuf`’s internal bookkeeping. Here is `overflow`’s implementation:

```
inline int OFdnStreambuf::overflow(int c)
{
    sync();
    if (c != EOF)
    {
        *pptr() = c;
        pbump(1);
    }
    return c;
}
```

The next program uses the `OFfdStreambuf` class to copy its standard input to file descriptor `STDOUT_FILENO`, which is the symbolic name of the file descriptor used for the standard output:

```
#include <string>
#include <iostream>
#include <istream>
#include "fdout.h"
using namespace std;

int main(int argc, char **argv)
{
    OFdnStreambuf    fds(STDOUT_FILENO, 500);
    ostream          os(&fds);

    switch (argc)
    {
        case 1:
            for (string s; getline(cin, s); )
                os << s << '\n';
            os << "COPIED cin LINE BY LINE\n";
            break;

        case 2:
            cin >> os.rdbuf();          // Alternatively, use: cin >> &fds;
            os << "COPIED cin BY EXTRACTING TO os.rdbuf()\n";
            break;

        case 3:
            os << cin.rdbuf();
            os << "COPIED cin BY INSERTING cin.rdbuf() into os\n";
            break;
    }
}
```

23.1.2 Classes for input operations

When classes for input operation are derived from `std::streambuf`, they should be provided with an input buffer of at least one character. The one-character input buffer allows for the use of the member functions `istream::putback` or `istream::ungetc`. Strictly speaking it is not necessary to implement a buffer in classes derived from `streambuf`. But using buffers in these classes is strongly advised. Their implementation is very simple and straightforward and the applicability of such classes

will be greatly improved. Therefore, in all our classes derived from the class `streambuf` a buffer of *at least* one character will be defined.

23.1.2.1 Using a one-character buffer

When deriving a class (e.g., `IFdStreambuf`) from `streambuf` using a buffer of one character, at least its member `streambuf::underflow` should be overridden, as this member eventually receives all requests for input. The member `streambuf::setg` is used to inform the `streambuf` base class of the size and location of the input buffer, so that it is able to set up its input buffer pointers accordingly. This will ensure that `streambuf::eback`, `streambuf::gp`, and `streambuf::egp` return correct values.

The class `IFdStreambuf` is designed like this:

- Its member functions use low-level functions operating on file descriptors. Therefore, in addition to `streambuf`, the `<unistd.h>` header file must have been read by the compiler before its member functions can be compiled.
- Like most classes designed for input operations, this class is derived from `std::streambuf` as well.
- The class defines two data members, one of them a fixed-sized one character buffer. The data members are defined as protected data members so that derived classes (e.g., see section 23.1.2.3) can access them. Here is the full class interface:

```
class IFdStreambuf: public std::streambuf
{
    protected:
        int      d_fd;
        char     d_buffer[1];
    public:
        IFdStreambuf(int fd);
    private:
        int underflow();
};
```

- The constructor initializes the buffer. However, the initialization sets `gp`’s return value equal to `egp`’s return value. This implies that the buffer is empty so `underflow` is immediately called to fill the buffer:

```
inline IFdStreambuf::IFdStreambuf(int fd)
:
    d_fd(fd)
{
    setg(d_buffer, d_buffer + 1, d_buffer + 1);
}
```

- Finally `underflow` is overridden. The buffer is refilled by reading from the file descriptor. If this fails (for whatever reason), `EOF` is returned. More sophisticated implementations could act more intelligently here, of course. If the buffer could be refilled, `setg` is called to set up `streambuf`’s buffer pointers correctly:

```
inline int IFdStreambuf::underflow()
{
    if (read(d_fd, d_buffer, 1) <= 0)
        return EOF;

    setg(d_buffer, d_buffer, d_buffer + 1);
    return *gp;
```

The following main function shows how `IFdStreambuf` can be used:

```
int main()
{
    IFdStreambuf fds(STDIN_FILENO);
    istream      is(&fds);

    cout << is.rdbuf();
}
```

23.1.2.2 Using an n-character buffer

How complex would things get if we would decide to use a buffer of substantial size? Not that complex. The following class allows us to specify the size of a buffer, but apart from that it is basically the same class as `IFdStreambuf` developed in the previous section. To make things a bit more interesting, in the class `IFdNStreambuf` developed here, the member `streambuf::xsgetn` is also overridden, to optimize reading a series of characters. Also a default constructor is provided that can be used in combination with the `open` member to construct an `istream` object before the file descriptor becomes available. In that case, once the descriptor becomes available, the `open` member can be used to initiate the object's buffer. Later, in section 23.3, we'll encounter such a situation.

To save some space, the success of various calls was not checked. In 'real life' implementations, these checks should of course not be omitted. The class `IFdNStreambuf` has the following characteristics:

- Its member functions use low-level functions operating on file descriptors. So apart from `streambuf` the `<unistd.h>` header file must have been read by the compiler before its member functions can be compiled.
- As usual, it is derived from `std::streambuf`.
- Like the class `IFdStreambuf` (section 23.1.2.1), its data members are protected. Since the buffer's size is configurable, this size is kept in a dedicated data member, `d_bufsize`:

```
class IFdNStreambuf: public std::streambuf
{
    protected:
        int          d_fd;
        size_t       d_bufsize;
        char*        d_buffer;
    public:
        IFdNStreambuf();
        IFdNStreambuf(int fd, size_t bufsize = 1);
        virtual ~IFdNStreambuf();
        void open(int fd, size_t bufsize = 1);
    private:
        virtual int underflow();
        virtual std::streamsize xsgetn(char *dest, std::streamsize n);
};
```

- The default constructor does not allocate a buffer. It can be used to construct an object before the file descriptor becomes known. A second constructor simply passes its arguments to `open`. `Open` will then initialize the object so that it can actually be used:

```
inline IFdNStreambuf::IFdNStreambuf()
:
    d_bufsize(0),
    d_buffer(0)
{ }
```



```
inline IFdNStreambuf::IFdNStreambuf(int fd, size_t bufsize)
{
    open(fd, bufsize);
}
```

- Once the object has been initialized by `open`, its destructor will both delete the object’s buffer and use the file descriptor to close the device:

```
IFdNStreambuf::~~IFdNStreambuf()
{
    if (d_bufsize)
    {
        close(d_fd);
        delete[] d_buffer;
    }
}
```

Even though the device is closed in the above implementation this may not always be desirable. In cases where the open file descriptor is already available the intention may be to use that descriptor repeatedly, each time using a newly constructed `IFdNStreambuf` object. It is left as an exercise to the reader to change this class in such a way that the device may optionally be closed. This approach was followed in, e.g., the `Bobcat` library².

- The `open` member simply allocates the object’s buffer. It is assumed that the calling program has already opened the device. Once the buffer has been allocated, the base class member `setg` is used to ensure that `streambuf::eback`, `streambuf::gp` and `streambuf::egp` return correct values:

```
void IFdNStreambuf::open(int fd, size_t bufsize)
{
    d_fd = fd;
    d_bufsize = bufsize;
    d_buffer = new char[d_bufsize];
    setg(d_buffer, d_buffer + d_bufsize, d_buffer + d_bufsize);
}
```

- The overridden member `underflow` is implemented almost identically to `IFdStreambuf`’s (section 23.1.2.1) member. The only difference is that the current class supports buffers of larger sizes. Therefore, more characters (up to `d_bufsize`) may be read from the device at once:

```
int IFdNStreambuf::underflow()
{
    if (gp() < egp())
        return *gp();

    int nread = read(d_fd, d_buffer, d_bufsize);

    if (nread <= 0)
        return EOF;

    setg(d_buffer, d_buffer, d_buffer + nread);
    return *gp();
}
```

- Finally `xsgetn` is overridden. In a loop, `n` is reduced until 0, at which point the function terminates. Alternatively, the member returns if `underflow` fails to obtain more characters. This member optimizes the reading of series of characters. Instead of calling `streambuf::sbumpc`

²<http://bobcat.sourceforge.net>

`n` times, a block of `avail` characters is copied to the destination, using `streambuf::gbump` to consume `avail` characters from the buffer using one function call:

```
std::streamsize IFdNStreambuf::xsgetn(char *dest, std::streamsize n)
{
    int nread = 0;

    while (n)
    {
        if (!in_avail())
        {
            if (underflow() == EOF)
                break;
        }

        int avail = in_avail();

        if (avail > n)
            avail = n;

        memcpy(dest + nread, gptr(), avail);
        gbump(avail);

        nread += avail;
        n -= avail;
    }

    return nread;
}
```

The member function `xsgetn` is called by `streambuf::sgetn`, which is a `streambuf` member. Here is an example illustrating the use of this member function with a `IFdNStreambuf` object:

```
#include <unistd.h>
#include <iostream>
#include <istream>
#include "ifdnbuf.h"
using namespace std;

int main()
{
    // internally: 30 char buffer
    IFdNStreambuf fds(STDIN_FILENO, 30);

    char buf[80]; // main() reads blocks of 80
                 // chars

    while (true)
    {
        size_t n = fds.sgetn(buf, 80);
        if (n == 0)
            break;
        cout.write(buf, n);
    }
}
```

23.1.2.3 Seeking positions in ‘streambuf’ objects

When devices support *seek operations*, classes derived from `std::streambuf` should override the members `streambuf::seekoff` and `streambuf::seekpos`. The class `IFdSeek`, developed in this section, can be used to read information from devices supporting seek operations. The class `IFdSeek` was derived from `IFdStreambuf`, so it uses a character buffer of just one character. The facilities to perform seek operations, which are added to our new class `IFdSeek`, ensure that the input buffer is reset when a seek operation is requested. The class could also be derived from the class `IFdNStreambuf`. In that which case the arguments to reset the input buffer must be adapted so that its second and third parameters point beyond the available input buffer. Let’s have a look at the characteristics of `IFdSeek`:

- As mentioned, `IFdSeek` is derived from `IFdStreambuf`. Like the latter class, `IFdSeek`’s member functions use facilities declared in `unistd.h`. So, the header file `<unistd.h>` must have been read by the compiler before it can compile the class’s members functions. To reduce the amount of typing when specifying types and constants from `streambuf` and `std::ios`, several typedefs are defined by the class. These typedefs refer to types that are defined in the header file `<ios>`, which must therefore also be included before the compiler can compile `IFdSeek`’s class interface:

```
class IFdSeek: public IFdStreambuf
{
    typedef std::streambuf::pos_type      pos_type;
    typedef std::streambuf::off_type      off_type;
    typedef std::ios::seekdir             seekdir;
    typedef std::ios::openmode            openmode;

public:
    IFdSeek(int fd);
private:
    pos_type seekoff(off_type offset, seekdir dir, openmode);
    pos_type seekpos(pos_type offset, openmode mode);
};
```

- The class has a very basic interface. Its (only) constructor expects the device’s file descriptor. It has no special tasks to perform and just calls its base class constructor:

```
inline IFdSeek::IFdSeek(int fd)
:
    IFdStreambuf(fd)
{ }
```

- The member `seek_off` is responsible for performing the actual seek operations. It calls `lseek` to seek a new position in a device whose file descriptor is known. If seeking succeeds, `setg` is called to define an already empty buffer, so that the base class’s `underflow` member refills the buffer at the next input request.

```
IFdSeek::pos_type IFdSeek::seekoff(off_type off, seekdir dir, openmode)
{
    pos_type pos =
        lseek
        (
            d_fd, off,
            (dir == std::ios::beg) ? SEEK_SET :
            (dir == std::ios::cur) ? SEEK_CUR :
                                   SEEK_END
        );

    if (pos < 0)
        return -1;
```

```

        setg(d_buffer, d_buffer + 1, d_buffer + 1);
        return pos;
    }

```

- Finally, the companion function `seekpos` is overridden as well: it is actually defined as a call to `seekoff`:

```

inline IFdSeek::pos_type IFdSeek::seekpos(pos_type off, openmode mode)
{
    return seekoff(off, std::ios::beg, mode);
}

```

Here is an example of a program using the class `IFdSeek`. If this program is given its own source file using input redirection then seeking is supported (and with the exception of the first line, every other line is shown twice):

```

#include "fdinseek.h"
#include <string>
#include <iostream>
#include <istream>
#include <iomanip>
using namespace std;

int main()
{
    IFdSeek fds(0);
    istream is(&fds);
    string s;

    while (true)
    {
        if (!getline(is, s))
            break;

        streampos pos = is.tellg();

        cout << setw(5) << pos << ": \" << s << "\"\n";

        if (!getline(is, s))
            break;

        streampos pos2 = is.tellg();

        cout << setw(5) << pos2 << ": \" << s << "\"\n";

        if (!is.seekg(pos))
        {
            cout << "Seek failed\n";
            break;
        }
    }
}

```

23.1.2.4 Multiple ‘`unget`’ calls in ‘`streambuf`’ objects

`Streambuf` classes and classes derived from `streambuf` should support *at least* ungetting the last read character. Special care must be taken when *series* of `unget` calls must be supported. In this section the

construction of a class supporting a configurable number of `istream::unget` or `istream::putback` calls is discussed.

Support for multiple (say ‘n’) `unget` calls is implemented by reserving an initial section of the input buffer, which is gradually filled up to contain the last n characters read. The class was implemented as follows:

- Once again, the class is derived from `std::streambuf`. It defines several data members, allowing the class to perform the bookkeeping required to maintain an `unget`-buffer of a configurable size:

```
class FdUnget: public std::streambuf
{
    int      d_fd;
    size_t   d_bufsize;
    size_t   d_reserved;
    char     *d_buffer;
    char     *d_base;
public:
    FdUnget(int fd, size_t bufsz, size_t unget);
    virtual ~FdUnget();
private:
    int underflow();
};
```

- The class’s constructor expects a file descriptor, a buffer size and the number of characters that can be `unget` or pushed back as its arguments. This number determines the size of a *reserved* area, defined as the first `d_reserved` bytes of the class’s input buffer.
 - The input buffer will always be at least one byte larger than `d_reserved`. So, a certain number of bytes may be read. Once `d_reserved` bytes have been read at most `d_reserved` bytes can be `unget`.
 - Next, the starting point for reading operations is configured. It is called `d_base`, pointing to a location `d_reserved` bytes from the start of `d_buffer`. This will always be the point where buffer refills start.
 - Now that the buffer has been constructed, we’re ready to define `streambuf`’s buffer pointers using `setg`. As no characters have been read yet, all pointers are set to point to `d_base`. If `unget` is called at this point, no characters are available, so `unget` will (correctly) fail.
 - Eventually, the refill buffer’s size is determined as the number of allocated bytes minus the size of the reserved area.

Here is the class’s constructor:

```
FdUnget::FdUnget(int fd, size_t bufsz, size_t unget)
:
    d_fd(fd),
    d_reserved(unget)
{
    size_t allocate =
        bufsz > d_reserved ?
            bufsz
        :
            d_reserved + 1;

    d_buffer = new char[allocate];

    d_base = d_buffer + d_reserved;
    setg(d_base, d_base, d_base);
```

```

        d_bufsize = allocate - d_reserved;
    }

```

- The class's destructor simply returns the memory allocated for the buffer to the common pool:

```

inline FdUnget::~FdUnget()
{
    delete[] d_buffer;
}

```

- Finally, underflow is overridden as follows:

- First underflow determines the number of characters that could potentially be ungot. If that number of characters are ungot, the input buffer is exhausted. So this value may be any value between 0 (the initial state) or the input buffer's size (when the reserved area has been filled up completely, and all current characters in the remaining section of the buffer have also been read);
- Next the number of bytes to move into the reserved area is computed. This number is at most `d_reserved`, but it is set equal to the actual number of characters that can be ungot if this value is smaller;
- Now that the number of characters to move into the reserved area is known, this number of characters is moved from the input buffer's end to the area immediately before `d_base`;
- Then the buffer is refilled. This all is standard, but notice that reading starts from `d_base` and not from `d_buffer`;
- Finally, `streambuf's` read buffer pointers are set up. `Eback` is set to move locations before `d_base`, thus defining the guaranteed unget-area, `gptr` is set to `d_base`, since that's the location of the first read character after a refill, and is set just beyond the location of the last character read into the buffer.

Here is underflow's implementation:

```

int FdUnget::underflow()
{
    size_t ungetsize = gptr() - eback();
    size_t move = std::min(ungetsize, d_reserved);

    memcpy(d_base - move, egptr() - move, move);

    int nread = read(d_fd, d_base, d_bufsize);
    if (nread <= 0)        // none read -> return EOF
        return EOF;

    setg(d_base - move, d_base, d_base + nread);

    return *gptr();
}

```

The example program illustrates the class `FdUnget`. It reads at most 10 characters from the standard input, stopping at EOF. A guaranteed unget-buffer of 2 characters is defined in a buffer holding 3 characters. Just before reading a character, the program tries to unget at most 6 characters. This is, of course, not possible; but the program will nicely unget as many characters as possible, considering the actual number of characters read:

```

#include "fdunget.h"
#include <string>
#include <iostream>
#include <istream>
using namespace std;

```

```

int main()
{
    FdUnget fds(0, 3, 2);
    istream is(&fds);
    char    c;

    for (int idx = 0; idx < 10; ++idx)
    {
        cout << "after reading " << idx << " characters:\n";
        for (int ug = 0; ug <= 6; ++ug)
        {
            if (!is.unget())
            {
                cout
                << "\tunget failed at attempt " << (ug + 1) << "\n"
                << "\trereading: '";

                is.clear();
                while (ug--)
                {
                    is.get(c);
                    cout << c;
                }
                cout << "'\n";
                break;
            }
        }

        if (!is.get(c))
        {
            cout << " reached\n";
            break;
        }
        cout << "Next character: " << c << '\n';
    }
}
/*

```

Generated output after 'echo abcde | program':

```

after reading 0 characters:
    unget failed at attempt 1
    rereading: ''
Next character: a
after reading 1 characters:
    unget failed at attempt 2
    rereading: 'a'
Next character: b
after reading 2 characters:
    unget failed at attempt 3
    rereading: 'ab'
Next character: c
after reading 3 characters:
    unget failed at attempt 4
    rereading: 'abc'
Next character: d
after reading 4 characters:
    unget failed at attempt 4
    rereading: 'bcd'

```

```

Next character: e
after reading 5 characters:
    unget failed at attempt 4
    rereading: 'cde'
Next character:

after reading 6 characters:
    unget failed at attempt 4
    rereading: 'de'
,
    reached
*/

```

23.2 Fixed-sized field extraction from istream objects

Usually when extracting information from `istream` objects `operator>>`, the standard extraction operator, is perfectly suited for the task as in most cases the extracted fields are white-space (or otherwise clearly separated) from each other. But this does not hold true in all situations. For example, when a web-form is posted to some processing script or program, the receiving program may receive the form field's values as *url-encoded* characters: letters and digits are sent unaltered, blanks are sent as + characters, and all other characters start with % followed by the character's ascii-value represented by its two digit hexadecimal value.

When decoding url-encoded information, simple hexadecimal extraction won't work, since that will extract as many hexadecimal characters as available, instead of just two. Since the letters a-f and 0-9 are legal hexadecimal characters, a text like `My name is 'Ed'`, url-encoded as

```
My+name+is+%60Ed%27
```

results in the extraction of the hexadecimal values 60ed and 27, instead of 60 and 27. The name Ed disappears from view, which is clearly not what we want.

In this case, having seen the %, we could extract 2 characters, put them in an `istringstream` object, and extract the hexadecimal value from the `istringstream` object. A bit cumbersome, but doable. Other approaches are possible as well.

The class `Fistream` for *fixed-sized field istream* defines an `istream` class supporting both fixed-sized field extractions and blank-delimited extractions (as well as unformatted `read` calls). The class may be initialized as a *wrapper* around an existing `istream`, or it can be initialized using the name of an existing file. The class is derived from `istream`, allowing all extractions and operations supported by `istreams` in general. `Fistream` defines the following data members:

- `d_filebuf`: a `filebuffer` used when `Fistream` reads its information from a named (existing) file. Since the `filebuffer` is only needed in that case, and since it must be allocated dynamically, it is defined as a `unique_ptr<filebuf>` object.
- `d_streambuf`: a pointer to `Fistream`'s `streambuf`. It points to `d_filebuf` when `Fistream` opens a file by name. When an existing `istream` is used to construct an `Fistream`, it will point to the existing `istream`'s `streambuf`.
- `d_iss`: an `istringstream` object used for the fixed field extractions.
- `d_width`: a `size_t` indicating the width of the field to extract. If 0 no fixed field extractions is used, but information is extracted from the `istream` base class object using standard extractions.

Here is the initial section of `Fistream`'s class interface:

```
class Fistream: public std::istream
```



```

{
    std::unique_ptr<std::filebuf> d_filebuf;
    std::streambuf *d_streambuf;
    std::istreamstream d_iss;
    size_t d_width;
}

```

As stated, `Fistream` objects can be constructed from either a filename or an existing `istream` object. The class interface therefore declares two constructors:

```

Fistream(std::istream &stream);
Fistream(char const *name,
          std::ios::openmode mode = std::ios::in);

```

When an `Fistream` object is constructed using an existing `istream` object, the `Fistream`'s `istream` part simply uses the stream's `streambuf` object:

```

Fistream::Fistream(istream &stream)
:
    istream(stream.rdbuf()),
    d_streambuf(rdbuf()),
    d_width(0)
{}

```

When an `fstream` object is constructed using a filename, the `istream` base initializer is given a new `filebuf` object to be used as its `streambuf`. Since the class's data members are not initialized before the class's base class has been constructed, `d_filebuf` can only be initialized thereafter. By then, the `filebuf` is only available as `rdbuf`, returning a `streambuf`. However, as it is actually a `filebuf`, a `reinterpret_cast` is used to cast the `streambuf` pointer returned by `rdbuf` to a `filebuf *`, so `d_filebuf` can be initialized:

```

Fistream::Fistream(char const *name, ios::openmode mode)
:
    istream(new filebuf()),
    d_filebuf(reinterpret_cast<filebuf *>(rdbuf())),
    d_streambuf(d_filebuf.get()),
    d_width(0)
{
    d_filebuf->open(name, mode);
}

```

There is only one additional public member: `setField(field const &)`. This member defines the size of the next field to extract. Its parameter is a reference to a field class, a *manipulator class* defining the width of the next field.

Since a `field &` is mentioned in `Fistream`'s interface, `field` must be declared before `Fistream`'s interface starts. The class `field` itself is simple and declares `Fistream` as its friend. It has two data members: `d_width` specifies the width of the next field, and `d_newWidth` which is set to `true` if `d_width`'s value should actually be used. If `d_newWidth` is `false`, `Fistream` returns to its standard extraction mode. The class `field` has two constructors: a default constructor, setting `d_newWidth` to `false`, and a second constructor expecting the width of the next field to extract as its value. Here is the class `field`:

```

class field
{
    friend class Fistream;
    size_t d_width;
    bool    d_newWidth;
}

```

```

    public:
        field(size_t width);
        field();
};

inline field::field(size_t width)
:
    d_width(width),
    d_newWidth(true)
{}

inline field::field()
:
    d_newWidth(false)
{}

```

Since `field` declares `Fistream` as its friend, `setField` may inspect `field`'s members directly.

Time to return to `setField`. This function expects a reference to a `field` object, initialized in one of three different ways:

- `field()`: When `setField`'s argument is a `field` object constructed by its default constructor the next extraction will use the same fieldwidth as the previous extraction.
- `field(0)`: When this `field` object is used as `setField`'s argument, fixed-sized field extraction stops, and the `Fistream` will act like any standard `istream` object.
- `field(x)`: When the `field` object itself is initialized by a non-zero `size_t` value `x`, then the next field width will be `x` characters wide. The preparation of such a field is left to `setBuffer`, `Fistream`'s only private member.

Here is `setField`'s implementation:

```

std::istream &Fistream::setField(field const &params)
{
    if (params.d_newWidth)                // new field size requested
        d_width = params.d_width;        // set new width

    if (!d_width)                         // no width?
        rdbuf(d_streambuf);              // return to the old buffer
    else
        setBuffer();                      // define the extraction buffer

    return *this;
}

```

The private member `setBuffer` defines a buffer of `d_width + 1` characters and uses `read` to fill the buffer with `d_width` characters. The buffer is terminated by an ASCII-Z character. This buffer is used to initialize the `d_str` member. `Fistream`'s `rdbuf` member is used to extract the `d_str`'s data via the `Fistream` object itself:

```

void Fistream::setBuffer()
{
    char *buffer = new char[d_width + 1];

    rdbuf(d_streambuf);                  // use istream's buffer to
    buffer[read(buffer, d_width).gcount()] = 0; // read d_width chars,

```

```

// terminated by ascii-Z
d_iss.str(buffer);
delete buffer;

rdbuf(d_iss.rdbuf());           // switch buffers
}

```

Although `setField` could be used to configure `Fistream` to use or not to use fixed-sized field extraction, using manipulators is probably preferable. To allow field objects to be used as manipulators an overloaded extraction operator was defined. This extraction operator accepts `istream &` and a field `const &` objects. Using this extraction operator, statements like

```
fis >> field(2) >> x >> field(0);
```

are possible (assuming `fis` is a `Fistream` object). Here is the overloaded operator `>>`, as well as its declaration:

```

istream &std::operator>>(istream &str, field const &params)
{
    return reinterpret_cast<Fistream *>(&str)->setField(params);
}

```

Declaration:

```

namespace std
{
    istream &operator>>(istream &str, FBB::field const &params);
}

```

Finally, an example. The following program uses a `Fistream` object to url-decode url-encoded information appearing at its standard input:

```

int main()
{
    Fistream fis(cin);

    fis >> hex;
    while (true)
    {
        size_t x;
        switch (x = fis.get())
        {
            case '\n':
                cout << '\n';
                break;
            case '+':
                cout << ' ';
                break;
            case '%':
                fis >> field(2) >> x >> field(0);
                // FALLING THROUGH
            default:
                cout << static_cast<char>(x);
                break;
            case EOF:
                return 0;
        }
    }
}

```

```

    }
}
/*
Generated output after:
    echo My+name+is+%60Ed%27 | a.out

My name is 'Ed'
*/

```

23.3 The ‘fork’ system call

From the C programming language the `fork` system call is well known. When a program needs to start a new process, `system` can be used. `System` requires the program to wait for the *child process* to terminate. The more general way to spawn subprocesses is to use `fork`.

In this section we investigate how C++ can be used to wrap classes around a complex system call like `fork`. Much of what follows in this section directly applies to the Unix operating system, and the discussion therefore focuses on that operating system. Other systems usually provide comparable facilities. What follows is closely related to the *Template Design Pattern* (cf. *Gamma et al.* (1995) *Design Patterns*, Addison-Wesley)

When `fork` is called, the current program is duplicated in memory, thus creating a new process. Following the duplication both processes continue their execution just below the `fork` system call. The two processes may inspect `fork`’s return value: the return value in the original process (called the *parent process*) differs from the return value in the newly created process (called the *child process*):

- In the *parent process* `fork` returns the *process ID* of the (child) process that was created by the `fork` system call. This is a positive integer value.
- In the *child process* `fork` returns 0.
- If `fork` fails, -1 is returned.

A basic `Fork` class should hide all bookkeeping details of a system call like `fork` from its users. The class `Fork` developed here will do just that. The class itself only ensures the proper execution of the `fork` system call. Normally, `fork` is called to start a child process, usually boiling down to the execution of a separate process. This child process may expect input at its standard input stream and/or may generate output to its standard output and/or standard error streams. `Fork` does not know all this, and does not have to know what the child process will do. `Fork` objects should be able to start their child processes.

`Fork`’s constructor cannot know what actions its child process should perform. Similarly, it cannot know what actions the parent process should perform. For these kind of situations, the *template method design pattern* was developed. According to Gamma c.s., the *template method design pattern*

“Define(s) the skeleton of an algorithm in an operation, deferring some steps to subclasses.
[The] Template Method (design pattern) lets subclasses redefine certain steps of an algorithm, without changing the algorithm’s structure.”

This design pattern allows us to define an *abstract base class* already providing the essential steps related to the `fork` system call, deferring the implementation of other parts of the `fork` system call to subclasses.

The `Fork` abstract base class has the following characteristics:

- It defines a data member `d_pid`. In the parent process this data member contains the child’s *process id* and in the child process it has the value 0. Its public interface declares only two members:

- a fork member function, responsible for the actual forking (i.e., it will create the (new) child process);
- an (default) virtual destructor `~Fork`.

Here is Fork's interface:

```
class Fork
{
    int d_pid;

public:
    virtual ~Fork() = default;
    void fork();

protected:
    int pid() const;
    int waitForChild();           // returns the status

private:
    virtual void childRedirections();
    virtual void parentRedirections();

    virtual void childProcess() = 0;    // pure virtual members
    virtual void parentProcess() = 0;
};
```

- All non-virtual member functions are declared in the class's protected section and can thus *only* be used by derived classes. They are:

- `pid()`: The member function `pid` allows derived classes to access the system fork's return value:

```
inline int Fork::pid() const
{
    return d_pid;
}
```

- `waitForChild()`: The member `int waitForChild` can be called by parent processes to wait for the completion of their child processes (as discussed below). This member is declared in the class interface. Its implementation is:

```
#include "fork.ih"

int Fork::waitForChild()
{
    int status;

    waitpid(d_pid, &status, 0);

    return WEXITSTATUS(status);
}
```

This simple implementation returns the child's *exit status* to the parent. The called system function `waitpid` *blocks* until the child terminates.

- When fork system calls are used, *parent processes* and *child processes* must always be distinguished. The main distinction between these processes is that `d_pid` becomes the child's process-id in the parent process, while `d_pid` becomes 0 in the child process itself. Since these two processes must always be distinguished (and present), their implementation by classes derived from Fork is enforced by Fork's interface: the members `childProcess`, defining the child process' actions and `parentProcess`, defining the parent process' actions were defined as pure virtual functions.

- communication between parent- and child processes may use standard streams or other facilities, like *pipes* (cf. section 23.3.3). To facilitate this inter-process communication, derived classes *may* implement:
 - `childRedirections()`: this member should be implemented if any standard stream (`cin`, `cout`) or `cerr` must be redirected in the *child* process (cf. section 23.3.1);
 - `parentRedirections()`: this member should be implemented if any standard stream (`cin`, `cout`) or `cerr` must be redirected in the *parent* process.

Redirection of the standard streams is necessary if parent- and child processes must communicate with each other via the standard streams. Here are their default definitions provided by the class's interface:

```
inline void Fork::childRedirections()
{
}
inline void Fork::parentRedirections()
{
}
```

The member function `fork` calls the system function `fork` (Caution: since the system function `fork` is called by a member function having the same name, the `::` scope resolution operator must be used to prevent a recursive call of the member function itself). `::fork`'s return value determines whether `parentProcess` or `childProcess` is called. Maybe redirection is necessary. `Fork::fork`'s implementation calls `childRedirections` just before calling `childProcess`, and `parentRedirections` just before calling `parentProcess`:

```
#include "fork.ih"

void Fork::fork()
{
    if ((d_pid = ::fork()) < 0)
        throw "Fork::fork() failed";

    if (d_pid == 0)                // childprocess has pid == 0
    {
        childRedirections();
        childProcess();
        exit(1);                  // we shouldn't come here:
    }                             // childProcess() should exit

    parentRedirections();
    parentProcess();
}
```

In `fork.cc` the class's *internal header file* `fork.ih` is included. This header file takes care of the inclusion of the necessary system header files, as well as the inclusion of `fork.h` itself. Its implementation is:

```
#include "fork.h"
#include <cstdlib>
#include <unistd.h>
#include <sys/types.h>
#include <sys/wait.h>
```

Child processes should not return: once they have completed their tasks, they should terminate. This happens automatically when the child process performs a call to a member of the `exec...` family, but if the child itself remains active, then it must make sure that it terminates properly. A child process normally uses `exit` to terminate itself, but note that `exit` prevents the activation of destructors of objects defined at the same or more superficial nesting levels than the level at which `exit` is called.

Destructors of globally defined objects *are* activated when `exit` is used. When using `exit` to terminate `childProcess`, it should either itself call a support member function defining all nested objects it needs, or it should define all its objects in a compound statement (e.g., using a `throw` block) calling `exit` beyond the compound statement.

Parent processes should normally wait for their children to complete. Terminating child processes inform their parents that they are about to terminate by sending a *signal* that should be caught by their parents. If child processes terminate and their parent processes do not catch those signals then such child processes remain visible as so-called *zombie* processes.

If parent processes must wait for their children to complete, they may call the member `waitForChild`. This member returns the exit status of a child process to its parent.

There exists a situation where the *child* process *continues* to live, but the *parent* dies. This is a fairly natural event: parents tend to die before their children do. In our context (i.e. **C++**), this is called a *daemon* program. In a daemon the parent process dies and the child program continues to run as a child of the basic `init` process. Again, when the child eventually dies a signal is sent to its 'step-parent' `init`. This does not create a zombie as `init` catches the termination signals of all its (step-) children. The construction of a daemon process is very simple, given the availability of the class `Fork` (cf. section 23.3.2).

23.3.1 Redirection revisited

Earlier, in section 6.6.1 streams were redirected using the `ios::rdbuf` member function. By assigning the `streambuf` of a stream to another stream, both stream objects access the same `streambuf`, thus implementing redirection at the level of the programming language itself.

This may be fine within the context of a **C++** program, but once we leave that context the redirection terminates. The operating system does not know about `streambuf` objects. This situation is encountered, e.g., when a program uses a system call to start a subprogram. The example program at the end of this section uses **C++** redirection to redirect the information inserted into `cout` to a file, and then calls

```
system("echo hello world")
```

to echo a well-known line of text. Since `echo` writes its information to the standard output, this would be the program's redirected file if the operating system would recognize **C++**'s redirection.

But redirection doesn't happen. Instead, `hello world` still appears at the program's standard output and the redirected file is left untouched. To write `hello world` to the redirected file redirection must be realized at the operating system level. Some operating systems (e.g., Unix and friends) provide system calls like `dup` and `dup2` to accomplish this. Examples of the use of these system calls are given in section 23.3.3.

Here is the example of the *failing redirection* at the system level following **C++** redirection using `streambuf` redirection:

```
#include <iostream>
#include <fstream>
#include <cstdlib>
using namespace std;

int main()
{
    ofstream of("outfile");

    streambuf *buf = cout.rdbuf(of.rdbuf());
    cout << "To the of stream\n";
    system("echo hello world");
```

```

    cout << "To the of stream\n";
    cout.rdbuf(buf);
}
/*
    Generated output: on the file 'outfile'

    To the of stream
    To the of stream

    On standard output:

    hello world
*/

```

23.3.2 The 'Daemon' program

Applications exist in which the only purpose of `fork` is to start a child process. The parent process terminates immediately after spawning the child process. If this happens, the child process continues to run as a child process of `init`, the always running first process on Unix systems. Such a process is often called a *daemon*, running as a background process.

Although the next example can easily be constructed as a plain C program, it was included in the C++ Annotations because it is so closely related to the current discussion of the `Fork` class. I thought about adding a `daemon` member to that class, but eventually decided against it because the construction of a daemon program is very simple and requires no features other than those currently offered by the class `Fork`. Here is an example illustrating the construction of such a daemon program. Its child process doesn't do `exit` but throw 0 which is caught by the `catch` clause of the child's main function. Doing this ensures that any objects defined by the child process are properly destroyed:

```

#include <iostream>
#include <unistd.h>
#include "fork.h"

class Daemon: public Fork
{
    virtual void parentProcess()          // the parent does nothing.
    {}
    virtual void childProcess()           // actions by the child
    {
        sleep(3);
                                // just a message...
        std::cout << "Hello from the child process\n";
        throw 0;                  // The child process ends
    }
};

int main()
try
{
    Daemon().fork();
}
catch(...)
{}

/*
    Generated output:

    The next command prompt, then after 3 seconds:
    Hello from the child process
*/

```


*/

23.3.3 The class 'Pipe'

Redirection at the system level requires the use of *file descriptors*, created by the `pipe` system call. When two processes want to communicate using such file descriptors, the following happens:

- The process constructs two *associated file descriptors* using the `pipe` system call. One of the file descriptors is used for writing, the other file descriptor is used for reading.
- Forking takes place (i.e., the system `fork` function is called), duplicating the file descriptors. Now we have four file descriptors as the child process and the parent process both have their own copies of the two file descriptors created by `pipe`.
- One process (say, the parent process) uses the file descriptors for *reading*. It should close its file descriptor intended for *writing*.
- The other process (say, the child process) uses the file descriptors for *writing*. It should therefore close its file descriptor intended for *reading*.
- All information written by the child process to the file descriptor intended for writing, can now be read by the parent process from the corresponding file descriptor intended for reading, thus establishing a communication channel between the child- and the parent process.

Though basically simple, errors may easily creep in. Functions of file descriptors available to the two processes (child- or parent-) may easily get mixed up. To prevent bookkeeping errors, the bookkeeping may be properly set up once, to be hidden thereafter inside a class like the `Pipe` class developed here. Let's have a look at its characteristics (before using functions like `pipe` and `dup` the compiler must have read the `<unistd.h>` header file):

- The `pipe` system call expects a pointer to two `int` values, which will represent, subsequent to the `pipe` call, the file descriptor used for reading and the file descriptor used for writing, respectively. To avoid confusion, the class `Pipe` defines an `enum` having values associating the indices of the array of 2-ints with symbolic constants. The two file descriptors themselves are stored in a data member `d_fd`. Here is the initial section of the class's interface:

```
class Pipe
{
    enum    RW { READ, WRITE };
    int     d_fd[2];
```

- The class only needs a default constructor. This constructor calls `pipe` to create a set of associated file descriptors used for accessing both ends of a pipe:

```
Pipe::Pipe()
{
    if (pipe(d_fd))
        throw "Pipe::Pipe(): pipe() failed";
}
```

- The members `readOnly` and `readFrom` are used to configure the pipe's reading end. The latter function is used when using redirection. It is provided with an alternate file descriptor to be used for reading from the pipe. Usually this alternate file descriptor is `STDIN_FILENO`, allowing `cin` to extract information from the pipe. The former function is merely used to configure the reading end of the pipe. It closes the matching writing end and returns a file descriptor that can be used to read from the pipe:

```
int Pipe::readOnly()
```

```

{
    close(d_fd[WRITE]);
    return d_fd[READ];
}
void Pipe::readFrom(int fd)
{
    readOnly();

    redirect(d_fd[READ], fd);
    close(d_fd[READ]);
}

```

- `writeOnly` and two `writtenBy` members are available to configure the writing end of a pipe. The former function is only used to configure the writing end of the pipe. It closes the reading end, and returns a file descriptor that can be used for writing to the pipe:

```

int Pipe::writeOnly()
{
    close(d_fd[READ]);
    return d_fd[WRITE];
}
void Pipe::writtenBy(int fd)
{
    writtenBy(&fd, 1);
}
void Pipe::writtenBy(int const *fd, size_t n)
{
    writeOnly();

    for (size_t idx = 0; idx < n; idx++)
        redirect(d_fd[WRITE], fd[idx]);

    close(d_fd[WRITE]);
}

```

For the latter member two overloaded versions are available:

- `writtenBy(int fileDescriptor)` is used to configure *single* redirection, so that a specific file descriptor (usually `STDOUT_FILENO` or `STDERR_FILENO`) can be used to write to the pipe;
- (`writtenBy(int *fileDescriptor, size_t n = 2)`) may be used to configure *multiple* redirection, providing an array argument containing file descriptors. Information written to any of these file descriptors is actually written to the pipe.
- The class has one private data member, `redirect`, used to set up redirection through the `dup2` system call. This function expects two file descriptors. The first file descriptor represents a file descriptor that can be used to access the device's information; the second file descriptor is an alternate file descriptor that may also be used to access the device's information. Here is `redirect`'s implementation:

```

void Pipe::redirect(int d_fd, int alternateFd)
{
    if (dup2(d_fd, alternateFd) < 0)
        throw "Pipe: redirection failed";
}

```

Now that redirection can be configured easily using one or more `Pipe` objects, we'll use `Fork` and `Pipe` in various example programs.

23.3.4 The class 'ParentSlurp'

The class `ParentSlurp`, derived from `Fork`, starts a child process executing a stand-alone program (like `/bin/ls`). The (standard) output of the executed program is not shown on the screen but is read by the parent process.

For demonstration purposes the parent process will write the lines it receives to its standard output stream, prepending linenumbers to the lines. It is attractive to redirect the parent's standard *input* stream to allow the parent to read the *output* from the child process using its `std::cin` *input* stream. Therefore, the only pipe in the program is used as an *input* pipe for the parent, and an *output* pipe for the child.

The class `ParentSlurp` has the following characteristics:

- It is derived from `Fork`. Before starting `ParentSlurp`'s class interface, the compiler must have read `fork.h` and `pipe.h`. The class only uses one data member, a `Pipe` object `d_pipe`.
- As `Pipe`'s constructor already defines a pipe, and as `d_pipe` is automatically initialized by `ParentSlurp`'s default constructor, which is implicitly provided. All additional members are only there for `ParentSlurp`'s own benefit so they can be defined in the class's (implicit) private section. Here is the class's interface:

```
class ParentSlurp: public Fork
{
    Pipe    d_pipe;

    virtual void childRedirections();
    virtual void parentRedirections();
    virtual void childProcess();
    virtual void parentProcess();
};
```

- The `childRedirections` member configures the writing end of the pipe. So, all information written to the child's standard output stream will end up in the pipe. The big advantage of this is that no additional streams are needed to write to a file descriptor:

```
inline void ParentSlurp::childRedirections()
{
    d_pipe.writtenBy(STDOUT_FILENO);
}
```

- The `parentRedirections` member, configures the reading end of the pipe. It does so by connecting the reading end of the pipe to the parent's standard input file descriptor (`STDIN_FILENO`). This allows the parent to perform extractions from `cin`, not requiring any additional streams for reading.

```
inline void ParentSlurp::parentRedirections()
{
    d_pipe.readFrom(STDIN_FILENO);
}
```

- The `childProcess` member only needs to concentrate on its own actions. As it only needs to execute a program (writing information to its standard output), the member can consist of one single statement:

```
inline void ParentSlurp::childProcess()
{
    execl("/bin/ls", "/bin/ls", 0);
}
```

- The `parentProcess` member simply ‘slurps’ the information appearing at its standard input. Doing so, it actually reads the child’s output. It copies the received lines to its standard output stream prefixing line numbers to them:

```
void ParentSlurp::parentProcess()
{
    std::string    line;
    size_t        nr = 1;

    while (getline(std::cin, line))
        std::cout << nr++ << ": " << line << '\n';

    waitForChild();
}
```

The following program simply constructs a `ParentSlurp` object, and calls its `fork()` member. Its output consists of a numbered list of files in the directory where the program is started. Note that the program also needs the `fork.o`, `pipe.o` and `waitforchild.o` object files (see earlier sources):

```
int main()
{
    ParentSlurp().fork();
}
/*
Generated Output (example only, actually obtained output may differ):

1: a.out
2: bitand.h
3: bitfunctional
4: bitnot.h
5: daemon.cc
6: fdinseek.cc
7: fdinseek.h
...
*/
```

23.3.5 Communicating with multiple children

The next step up the ladder is the construction of a child-process monitor. Here, the parent process is responsible for all its child processes, but it also must read their standard output. The user enters information at the standard input of the parent process. A simple *command language* is used for this:

- `start:` this start a new child process. The parent returns the child’s ID (a number) to the user. The ID is thereupon be used to identify a particular child process
- `<nr> text` sends “text” to the child process having ID `<nr>`;
- `stop <nr>` terminates the child process having ID `<nr>`;
- `exit` terminates the parent as well as all its child processes.

The child process that hasn’t received text for some time will complain by sending a message to the parent-process. Those messages are simply transmitted to the user by copying them to the standard output stream.

A problem with programs like our monitor is that they programs allow *asynchronous input* from multiple sources. Input may appear at the standard input as well as at the input-sides of pipes. Also, multiple output channels are used. To handle situations like these, the `select` system call was developed.

23.3.5.1 The class 'Selector'

The `select` system call was developed to handle asynchronous *I/O multiplexing*. The `select` system call is used to handle, e.g., input appearing simultaneously at a set of file descriptors.

The `select` function is rather complex, and its full discussion is beyond the C++ Annotations' scope. By encapsulating `select` in a class `Selector`, hiding its details and offering an intuitively attractive interface, its use is simplified. The `Selector` class has these features:

- **Efficiency.** As most of `Selector`'s members are very small, most members can be implemented inline. The class requires quite a few data members. Most of these data members belong to types that require some system headers to be included first:

```
#include <limits.h>
#include <unistd.h>
#include <sys/time.h>
#include <sys/types.h>
```

- The class interface can now be defined. The data type `fd_set` is a type designed to be used by `select` and variables of this type contain the set of file descriptors on which `select` may sense some activity. Furthermore, `select` allows us to fire an *asynchronous alarm*. To set the alarm time, the class `Selector` defines a `timeval` data member. Other members are used for internal bookkeeping purposes. Here is the class `Selector`'s interface:

```
class Selector
{
    fd_set      d_read;
    fd_set      d_write;
    fd_set      d_except;
    fd_set      d_ret_read;
    fd_set      d_ret_write;
    fd_set      d_ret_except;
    timeval     d_alarm;
    int         d_max;
    int         d_ret;
    int         d_readidx;
    int         d_writeidx;
    int         d_exceptidx;

public:
    Selector();

    int exceptFd();
    int nReady();
    int readFd();
    int wait();
    int writeFd();
    void addExceptFd(int fd);
    void addReadFd(int fd);
    void addWriteFd(int fd);
    void noAlarm();
    void rmExceptFd(int fd);
    void rmReadFd(int fd);
    void rmWriteFd(int fd);
    void setAlarm(int sec, int usec = 0);

private:
    int checkSet(int *index, fd_set &set);
    void addFd(fd_set *set, int fd);
};
```

Selector's member functions serve the following tasks:

- `Selector()`: the (default) constructor. It clears the read, write, and execute `fd_set` variables, and switches off the alarm. Except for `d_max`, the remaining data members do not require specific initializations:

```
Selector::Selector()
{
    FD_ZERO(&d_read);
    FD_ZERO(&d_write);
    FD_ZERO(&d_except);
    noAlarm();
    d_max = 0;
}
```

- `int wait()`: this member *blocks* until the *alarm* times out or until activity is sensed at any of the file descriptors monitored by the `Selector` object. It throws an exception when the `select` system call itself fails:

```
int Selector::wait()
{
    timeval t = d_alarm;

    d_ret_read = d_read;
    d_ret_write = d_write;
    d_ret_except = d_except;

    d_readidx = 0;
    d_writeidx = 0;
    d_exceptidx = 0;

    d_ret = select(d_max, &d_ret_read, &d_ret_write, &d_ret_except,
                  t.tv_sec == -1 && t.tv_usec == -1 ? 0 : &t);

    if (d_ret < 0)
        throw "Selector::wait()/select() failed";

    return d_ret;
}
```

- `int nReady`: this member function's return value is only defined when `wait` has returned. In that case it returns 0 for an alarm-timeout, -1 if `select` failed, and otherwise the number of file descriptors on which activity was sensed:

```
inline int Selector::nReady()
{
    return d_ret;
}
```

- `int readFd()`: this member function's return value is also only defined after `wait` has returned. Its return value is -1 if no (more) input file descriptors are available. Otherwise the next file descriptor available for reading is returned:

```
inline int Selector::readFd()
{
    return checkSet(&d_readidx, d_ret_read);
}
```

- `int writeFd()`: operating analogously to `readFd`, it returns the next file descriptor to which output is written. It uses `d_writeidx` and `d_ret_read` and is implemented analogously to `readFd`;

- `int exceptFd()`: operating analogously to `readFd`, it returns the next exception file descriptor on which activity was sensed. It uses `d_except_idx` and `d_ret_except` and is implemented analogously to `readFd`;
- `void setAlarm(int sec, int usec = 0)`: this member activates `Select`'s alarm facility. At least the number of seconds to wait for the alarm to go off must be specified. It simply assigns values to `d_alarm`'s fields. At the next `Select::wait` call, the alarm will fire (i.e., `wait` returns with return value 0) once the configured alarm-interval has passed:

```
inline void Selector::setAlarm(int sec, int usec)
{
    d_alarm.tv_sec  = sec;
    d_alarm.tv_usec = usec;
}
```

- `void noAlarm()`: this member switches off the alarm, by simply setting the alarm interval to a very long period:

```
inline void Selector::noAlarm()
{
    setAlarm(-1, -1);
}
```

- `void addReadFd(int fd)`: this member adds a file descriptor to the set of input file descriptors monitored by the `Selector` object. The member function `wait` will return once input is available at the indicated file descriptor:

```
inline void Selector::addReadFd(int fd)
{
    addFd(&d_read, fd);
}
```

- `void addWriteFd(int fd)`: this member adds a file descriptor to the set of output file descriptors monitored by the `Selector` object. The member function `wait` will return once output is available at the indicated file descriptor. Using `d_write`, it is implemented analogously to `addReadFd`;
- `void addExceptFd(int fd)`: this member adds a file descriptor to the set of exception file descriptors to be monitored by the `Selector` object. The member function `wait` will return once activity is sensed at the indicated file descriptor. Using `d_except`, it is implemented analogously to `addReadFd`;
- `void rmReadFd(int fd)`: this member removes a file descriptor from the set of input file descriptors monitored by the `Selector` object:

```
inline void Selector::rmReadFd(int fd)
{
    FD_CLR(fd, &d_read);
}
```

- `void rmWriteFd(int fd)`: this member removes a file descriptor from the set of output file descriptors monitored by the `Selector` object. Using `d_write`, it is implemented analogously to `rmReadFd`;
- `void rmExceptFd(int fd)`: this member removes a file descriptor from the set of exception file descriptors to be monitored by the `Selector` object. Using `d_except`, it is implemented analogously to `rmReadFd`;

The class's remaining (two) members are support members, and should not be used by non-member functions. Therefore, they are declared in the class's `private` section:

- The member `addFd` adds a file descriptor to a `fd_set`:

```
void Selector::addFd(fd_set *set, int fd)
{
    FD_SET(fd, set);
    if (fd >= d_max)
        d_max = fd + 1;
}
```

- The member `checkSet` tests whether a file descriptor (`*index`) is found in a `fd_set`:

```
int Selector::checkSet(int *index, fd_set &set)
{
    int &idx = *index;

    while (idx < d_max && !FD_ISSET(idx, &set))
        ++idx;

    return idx == d_max ? -1 : idx++;
}
```

23.3.5.2 The class ‘Monitor’

The monitor program uses a `Monitor` object doing most of the work. The class `Monitor`'s public interface only offers a default constructor and one member, `run`, to perform its tasks. All other member functions are located in the class's `private` section.

`Monitor` defines the private enum `Commands`, symbolically listing the various commands its input language supports, as well as several data members. Among the data members are a `Selector` object and a map using child order numbers as its keys and pointer to `Child` objects (see section 23.3.5.3) as its values. Furthermore, `Monitor` has a static array member `s_handler[]`, storing pointers to member functions handling user commands.

A destructor should be implemented as well, but its implementation is left as an exercise to the reader. Here is `Monitor`'s interface, including the interface of the nested class `Find` that is used to create a function object:

```
class Monitor
{
    enum Commands
    {
        UNKNOWN,
        START,
        EXIT,
        STOP,
        TEXT,
        sizeofCommands
    };

    typedef std::map<int, std::shared_ptr<Child>> MapIntChild;

    friend class Find;
    class Find
    {
        int      d_nr;
```



```

    public:
        Find(int nr);
        bool operator()(MapIntChild::value_type &vt) const;
};

Selector    d_selector;
int         d_nr;
MapIntChild d_child;

static void (Monitor::*s_handler[])(int, std::string const &);
static int s_initialize;

public:
    enum Done
    {};

    Monitor();
    void run();

private:
    static void killChild(MapIntChild::value_type it);
    static int initialize();

    Commands    next(int *value, std::string *line);
    void        processInput();
    void        processChild(int fd);

    void        createNewChild(int, std::string const &);
    void        exiting(int = 0, std::string const &msg = std::string());
    void        sendChild(int value, std::string const &line);
    void        stopChild(int value, std::string const &);
    void        unknown(int, std::string const &);
};

```

Since there's only one non-class type data member, the class's constructor could be implemented inline. The array `s_handler`, storing pointers to functions needs to be initialized as well. This can be accomplished in several ways:

- Since the `Command` enumeration only contains a fairly limited set of commands, compile-time initialization could be considered:

```

void (Monitor::*Monitor::s_handler[])(int, string const &) =
{
    &Monitor::unknown,           // order follows enum Command's
    &Monitor::createNewChild,     // elements
    &Monitor::exiting,
    &Monitor::stopChild,
    &Monitor::sendChild,
};

```

The advantage of this is that it's simple, not requiring any run-time effort. The disadvantage is of course relatively complex maintenance. If for some reason `Commands` is modified, `s_handler` must be modified as well. In cases like these, compile-time initialization often is asking for trouble. There is a simple alternative though.

- Looking at `Monitor`'s interface we see a static data member `s_initialize` and a static member function `initialize`. The static member function handles the initialization of the `s_handler` array. It explicitly assigns the array's elements and any modification in ordering of the enum `Command`'s values is automatically accounted for by recompiling `initialize`:

```

void (Monitor::*Monitor::s_handler[sizeofCommands])(int, string const &);

int Monitor::initialize()
{
    s_handler[UNKNOWN] = &Monitor::unknown;
    s_handler[START] = &Monitor::createNewChild;
    s_handler[EXIT] = &Monitor::exiting;
    s_handler[STOP] = &Monitor::stopChild;
    s_handler[TEXT] = &Monitor::sendChild;
    return 0;
}

```

The member `initialize` is a static member and so it can be called to initialize `s_initialize`, a static `int` variable. The initialization is enforced by placing the initialization statement in the source file of a function that is known to be executed. It could be `main`, but if we're `Monitor`'s maintainers and only have control over the library containing `Monitor`'s code then that's not an option. In those cases the source file containing the destructor is a *very* good candidate. If a class has only one constructor and it's *not* defined inline then the constructor's source file is a good candidate as well. In `Monitor`'s current implementation the initialization statement is put in `run`'s source file, reasoning that `s_handler` is only needed when `run` is used.

`Monitor`'s constructor is a very simple function and may be implemented inline:

```

inline Monitor::Monitor()
:
    d_nr(0)
{}

```

The core of `Monitor`'s activities are performed by `run`. It performs the following tasks:

- Initially, the `Monitor` object only monitors its standard input. The set of input file descriptors to which `d_selector` listens is initialized to `STDIN_FILENO`.
- Then, in a loop `d_selector`'s wait function is called. If input on `cin` is available, it is processed by `processInput`. Otherwise, the input has arrived from a child process. Information sent by children is processed by `processChild`.
- To prevent *zombies*, the child processes must catch *their* children's termination signals. This is discussed below (in an earlier version `Monitor` caught the termination signals. As noted by Ben Simons (ben at mrxfx dot com) this is inappropriate. Instead, the process spawning child processes has that responsibility (so, the parent process is responsible for its child processes; a child process is in turn responsible for its own child processes). Thanks, Ben).
- As stated, `run`'s source file also defines and initializes `s_initialize` to ensure the proper initialization of the `s_handler` array.

Here is `run`'s implementation and `s_initialize`'s definition:

```

#include "monitor.ih"

int Monitor::s_initialize = Monitor::initialize();

void Monitor::run()
{
    d_selector.addReadFd(STDIN_FILENO);

    while (true)
    {

```

```

        cout << "? " << flush;
        try
        {
            d_selector.wait();

            int fd;
            while ((fd = d_selector.readFd()) != -1)
            {
                if (fd == STDIN_FILENO)
                    processInput();
                else
                    processChild(fd);
            }
            cout << "NEXT ... \n";
        }
        catch (char const *msg)
        {
            exiting(1, msg);
        }
    }
}

```

The member function `processInput` reads the commands entered by the user using the program's standard input stream. The member itself is rather simple. It calls `next` to obtain the next command entered by the user, and then calls the corresponding function using the matching element of the `s_handler[]` array. Here are the members `processInput` and `next`:

```

void Monitor::processInput()
{
    string line;
    int value;
    Commands cmd = next(&value, &line);
    (this->*s_handler[cmd])(value, line);
}

Monitor::Commands Monitor::next(int *value, string *line)
{
    if (!getline(cin, *line))
        exiting(1, "Command::next(): reading cin failed");

    if (*line == "start")
        return START;

    if (*line == "exit" || *line == "quit")
    {
        *value = 0;
        return EXIT;
    }

    if (line->find("stop") == 0)
    {
        istringstream istr(line->substr(4));
        istr >> *value;
        return !istr ? UNKNOWN : STOP;
    }

    istringstream istr(line->c_str());
    istr >> *value;
}

```

```

    if (istr)
    {
        getline(istr, *line);
        return TEXT;
    }

    return UNKNOWN;
}

```

All other input sensed by `d_select` is created by child processes. Because `d_select`'s `readFd` member returns the corresponding input file descriptor, this descriptor can be passed to `processChild`. Using a `IFdStreambuf` (see section 23.1.2.1), its information is read from an input stream. The communication protocol used here is rather basic. For every line of input sent to a child, the child replies by sending back exactly one line of text. This line is then read by `processChild`:

```

void Monitor::processChild(int fd)
{
    IFdStreambuf ifdbuf(fd);
    istream istr(&ifdbuf);
    string line;

    getline(istr, line);
    cout << d_child[fd]->pid() << ": " << line << '\n';
}

```

The construction `d_child[fd]->pid()` used in the above source deserves some special attention. `Monitor` defines the data member `map<int, shared_ptr<Child> d_child`. This map contains the child's order number as its key, and a (shared) pointer to the `Child` object as its value. A shared pointer is used here, rather than a `Child` object, since we want to use the facilities offered by the map, but don't want to copy a `Child` object time and again.

Now that `run`'s implementation has been covered, we'll concentrate on the various commands users might enter:

- When the `start` command is issued, a new child process is started. A new element is added to `d_child` by the member `createNewChild`. Next, the `Child` object should start its activities, but the `Monitor` object can not wait for the child process to complete its activities, as there is no well-defined endpoint in the near future, and the user will probably want to enter more commands. Therefore, the `Child` process must run as a *daemon*. So the forked process terminates immediately, but its own child process will continue to run (in the background). Consequently, `createNewChild` calls the child's `fork` member. Although it is the child's `fork` function that is called, it is still the monitor program wherein that `fork` function is called. So, the *monitor* program is duplicated by `fork`. Execution then continues:

- At the `Child`'s `parentProcess` in its parent process;
- At the `Child`'s `childProcess` in its child process

As the `Child`'s `parentProcess` is an empty function, returning immediately, the `Child`'s parent process effectively continues immediately below `createNewChild`'s `cp->fork()` statement. As the child process never returns (see section 23.3.5.3), the code below `cp->fork()` is never executed by the `Child`'s child process. This is exactly as it should be.

In the parent process, `createNewChild`'s remaining code simply adds the file descriptor that's available for reading information from the child to the set of input file descriptors monitored by `d_select`, and uses `d_child` to establish the association between that file descriptor and the `Child` object's address:

```

void Monitor::createNewChild(int, string const &)
{

```

```

    Child *cp = new Child(++d_nr);

    cp->fork();

    int fd = cp->readFd();

    d_selector.addReadFd(fd);
    d_child[fd].reset(cp);

    cerr << "Child " << d_nr << " started\n";
}

```

- Direct communication with the child is required for the `stop <nr>` and `<nr> text` commands. The former command terminates child process `<nr>`, by calling `stopChild`. This function locates the child process having the order number using an anonymous object of the class `Find`, nested inside `Monitor`. The class `Find` simply compares the provided `nr` with the children's order number returned by their `nr` members:

If the child process having order number `nr` was found, its file descriptor is removed from `d_selector`'s set of input file descriptors. Then the child process itself is terminated by the static member `killChild`. The member `killChild` is declared as a *static* member function, as it is used as function argument of the `for_each` generic algorithm by `erase` (see below). Here is `killChild`'s implementation:

```

void Monitor::killChild(MapIntChild::value_type it)
{
    if (kill(it.second->pid(), SIGTERM))
        cerr << "Couldn't kill process " << it.second->pid() << '\n';

    // reap defunct child process
    int status = 0;
    while( waitpid( it.second->pid(), &status, WNOHANG) > -1)
        ;
}

```

Having terminated the specified child process, the corresponding `Child` object is destroyed and its pointer is removed from `d_child`:

```

void Monitor::stopChild(int nr, string const &)
{
    auto it = find_if(d_child.begin(), d_child.end(), Find(nr));

    if (it == d_child.end())
        cerr << "No child number " << nr << '\n';
    else
    {
        d_selector.rmReadFd(it->second->readFd());
        d_child.erase(it);
    }
}

```

- The command `<nr> text` sends text to child process `nr` using the member function `sendChild`. This function too, will use a `Find` object to locate the process having order number `nr`, and then simply inserts the text into the writing end of a pipe connected to the indicated child process:

```

void Monitor::sendChild(int nr, string const &line)
{
    auto it = find_if(d_child.begin(), d_child.end(), Find(nr));

    if (it == d_child.end())

```

```

        cerr << "No child number " << nr << '\n';
    else
    {
        OFdnStreambuf ofdn(it->second->writeFd());
        ostream out(&ofdn);

        out << line << '\n';
    }
}

```

- When users enter `exit` or `quit` the member `exiting` is called. It terminates all child processes using the `for_each` generic algorithm (see section 19.1.17) to visit all elements of `d_child`. Then the program itself ends:

```

void Monitor::exiting(int value, string const &msg)
{
    for_each(d_child.begin(), d_child.end(), killChild);
    if (msg.length())
        cerr << msg << '\n';
    throw value;
}

```

The program's main function is simple and needs no further comment:

```

int main()
try
{
    Monitor().run();
}
catch (int exitValue)
{
    return exitValue;
}

```

23.3.5.3 The class 'Child'

When the `Monitor` object starts a child process, it creates an object of the class `Child`. The `Child` class is derived from the class `Fork`, allowing it to operate as a *daemon* (as discussed in the previous section). Since `Child` is a daemon class, we know that its parent process must be defined as an empty function. Its `childProcess` member has a non-empty implementation. Here are the characteristics of the class `Child`:

- The `Child` class has two `Pipe` data members, to handle communications between its own child- and parent processes. As these pipes are used by the `Child`'s child process, their names refer to the child process. The child process reads from `d_in`, and writes to `d_out`. Here is the interface of the class `Child`:

```

class Child: public Fork
{
    Pipe          d_in;
    Pipe          d_out;

    int           d_parentReadFd;
    int           d_parentWriteFd;
    int           d_nr;

public:

```

```

    Child(int nr);
    virtual ~Child();
    int readFd() const;
    int writeFd() const;
    int pid() const;
    int nr() const;
private:
    virtual void childRedirections();
    virtual void parentRedirections();
    virtual void childProcess();
    virtual void parentProcess();
};

```

- The Child's constructor simply stores its argument, a child-process order number, in its own `d_nr` data member:

```

inline Child::Child(int nr)
:
    d_nr(nr)
{}

```

- The Child's child process obtains commands from its standard input stream and writes its output to its standard output stream. Since the actual communication channels are pipes, redirections must be used. The `childRedirections` member looks like this:

```

void Child::childRedirections()
{
    d_in.readFrom(STDIN_FILENO);
    d_out.writtenBy(STDOUT_FILENO);
}

```

- Although the parent process performs no actions, it must configure some redirections. Realizing that the names of the pipes indicate their functions in the child process. So the parent *writes* to `d_in` and *reads* from `d_out`. Here is `parentRedirections`:

```

void Child::parentRedirections()
{
    d_parentReadFd = d_out.readOnly();
    d_parentWriteFd = d_in.writeOnly();
}

```

- The Child object exists until it is destroyed by the Monitor's `stopChild` member. By allowing its creator, the Monitor object, to access the parent-side ends of the pipes, the Monitor object can communicate with the Child's child process via those pipe-ends. The members `readFd` and `writeFd` allow the Monitor object to access these pipe-ends:

```

inline int Child::readFd() const
{
    return d_parentReadFd;
}
inline int Child::writeFd() const
{
    return d_parentWriteFd;
}

```

- The Child object's child process performs two tasks:
 - It must reply to information appearing at its standard input stream;
 - If no information has appeared within a certain time frame (the implementation uses an interval of five seconds), then a message is written to its standard output stream.

To implement this behavior, `childProcess` defines a local `Selector` object, adding `STDIN_FILENO` to its set of monitored input file descriptors.

Then, in an endless loop, `childProcess` waits for `selector.wait()` to return. When the alarm goes off it sends a message to its standard output (hence, into the writing pipe). Otherwise, it will echo the messages appearing at its standard input to its standard output. Here is the `childProcess` member:

```
void Child::childProcess()
{
    Selector    selector;
    size_t      message = 0;

    selector.addReadFd(STDIN_FILENO);
    selector.setAlarm(5);

    while (true)
    {
        try
        {
            if (!selector.wait())           // timeout
                cout << "Child " << d_nr << ": standing by\n";
            else
            {
                string line;
                getline(cin, line);
                cout << "Child " << d_nr << ":" << ++message << ": " <<
                    line << '\n';
            }
        }
        catch (...)
        {
            cout << "Child " << d_nr << ":" << ++message << ": " <<
                "select() failed" << '\n';
        }
    }
    exit(0);
}
```

- Two accessors are defined allowing the `Monitor` object to obtain the `Child`'s process ID and its order number:

```
inline int Child::pid() const
{
    return Fork::pid();
}
inline int Child::nr() const
{
    return d_nr;
}
```

- A `Child` process terminates when the user enters a `stop` command. When an existing child process number was entered, the corresponding `Child` object is removed from `Monitor`'s `d_child` map. As a result, its destructor is called. `Child`'s destructor calls `kill` to terminate its child, and then waits for the child to terminate. Once its child has terminated, the destructor has completed its work and returns, thus completing the erasure from `d_child`. The current implementation fails if the child process doesn't react to the `SIGTERM` signal. In this demonstration program this does not happen. In 'real life' more elaborate killing-procedures may be required (e.g., using `SIGKILL` in addition to `SIGTERM`). As discussed in section 9.11 it is important to ensure the proper destruction. Here is the `Child`'s destructor:


```

Child::~~Child()
{
    if (pid())
    {
        cout << "Killing process " << pid() << "\n";
        kill(pid(), SIGTERM);
        int status;
        wait(&status);
    }
}

```

23.4 Function objects performing bitwise operations

In section 18.1 several predefined function objects were introduced. Predefined function objects performing arithmetic operations, relational operations, and logical operations exist, corresponding to a multitude of binary- and unary operators.

Some operators appear to be missing: there appear to be no predefined function objects corresponding to bitwise operations. However, their construction is, given the available predefined function objects, not difficult. The following examples show a class template implementing a function object calling the bitwise and (`operator&`), and a template class implementing a function object calling the unary not (`operator~`). It is left to the reader to construct similar function objects for other operators.

Here is the implementation of a function object calling the bitwise `operator&`:

```

#include <functional>

template <typename _Tp>
struct bit_and: public std::binary_function<_Tp, _Tp, _Tp>
{
    _Tp operator()( _Tp const &__x, _Tp const &__y) const
    {
        return __x & __y;
    }
};

```

Here is the implementation of a function object calling `operator~()`:

```

#include <functional>

template <typename _Tp>
struct bit_not: public std::unary_function<_Tp, _Tp>
{
    _Tp operator()( _Tp const &__x) const
    {
        return ~__x;
    }
};

```

These and other missing predefined function objects are also implemented in the file `bitfunctional`, which is found in the `cplusplus.yo.zip` archive. These classes are derived from existing class templates (e.g., `std::binary_function` and `std::unary_function`). These base classes define several types which are expected (used) by various generic algorithms as defined in the STL (cf. chapter 19), thus following the advice offered in, e.g., the C++ header file `bits/stl_function.h`:

```

* The standard functors are derived from structs named unary_function

```

```
* and binary_function. These two classes contain nothing but typedefs,
* to aid in generic (template) programming. If you write your own
* functors, you might consider doing the same.
```

Here is an example using `bit_and`, removing all odd numbers from a vector of `int` values:

```
#include <iostream>
#include <algorithm>
#include <vector>
#include "bitand.h"
using namespace std;

int main()
{
    vector<int> vi;

    for (int idx = 0; idx < 10; ++idx)
        vi.push_back(idx);

    copy
    (
        vi.begin(),
        remove_if(vi.begin(), vi.end(), bind2nd(bit_and<int>(), 1)),
        ostream_iterator<int>(cout, " ")
    );
    cout << '\n';
}
/*
    Generated output:

    0 2 4 6 8
*/
```

23.5 A text to anything converter

The standard **C** library offers conversion functions like `atoi`, `atol`, and other functions that can be used to convert ASCII-Z strings to numeric values. In **C++**, these functions are still available, but a more *type safe* way to convert text to other types uses objects of the class `std::istringstream`.

Using the class `istringstream` instead of the **C** standard conversion functions may have the advantage of type-safety, but it also appears to be a rather cumbersome alternative. After all, we first have to construct and initialize a `std::istringstream` object before we're able to extract a value of some type from it. This requires us to use a variable. Then, in cases where the extracted value is only needed to initialize some function-parameter, one might wonder whether the added variable and the `istringstream` construction can somehow be avoided.

In this section we'll develop a class (`A2x`) preventing all the disadvantages of the standard **C** library functions, without requiring the cumbersome definitions of `istringstream` objects over and over again. The class is called `A2x`, meaning 'ascii to anything'.

`A2x` objects can be used to extract values of any type extractable from `std::istream` objects. Since `A2x` represents the object-variant of the **C** functions, it is not only type-safe but *also* extensible. So its use is greatly preferred over using the standard **C** functions. Here are its characteristics:

- `A2x` is derived from `std::istringstream`, and so all members of the class `istringstream` are available for `A2x` objects. Extractions of values of variables can always effortlessly be performed. Here's the class's interface:

```

class A2x: public std::istream
{
    public:
        A2x() = default;
        A2x(char const *txt);
        A2x(std::string const &str);

        template <typename Type>
        operator Type();

        template <typename Type>
        Type to();

        A2x &operator=(char const *txt);

        A2x &operator=(std::string const &str);
        A2x &operator=(A2x const &other);
};

```

- A2x has a default constructor and a constructor expecting a `std::string` argument. The latter constructor may be used to initialize A2x objects with text to be converted (e.g., a line of text obtained from reading a configuration file):

```

inline A2x::A2x(char const *txt)           // initialize from text
:
    std::istream(txt)
{}

inline A2x::A2x(std::string const &str)
:
    std::istream(str.c_str())
{}

```

- A2x's real strength comes from its `operator Type()` conversion member template. As it is a member template, it will automatically adapt itself to the type of the variable that should be given a value, obtained by converting the text stored inside the A2x object to the variable's type. When the extraction fails, A2x's inherited good member returns false.
- Occasionally the compiler may not be able to determine which type to convert to. In that case, an *explicit template type* could be used:

```

A2x.operator int<int>();
// or just:
A2x.operator int();

```

As neither syntax looks attractive, the member template `to` is provided too, allowing constructions like:

```
A2x.to<int>();
```

Here is its implementation:

```

template <typename Type>
inline Type A2x::to()
{
    Type t;

    return (*this >> t) ? t : Type();
}

```

- The `to` member makes it easy to implement `operator Type()`:

```
template <typename Type>
inline A2x::operator Type()
{
    return to<Type>();
}
```

- Once an `A2x` object is available, it may be reinitialized using `operator=`:

```
#include "a2x.h"

A2x &A2x::operator=(char const *txt)
{
    clear();           // very important!!! If a conversion failed, the object
                      // remains useless until executing this statement
    str(txt);
    return *this;
}
```

Here are some examples showing `A2x` being used:

```
int x = A2x("12");           // initialize int x from a string "12"
A2x a2x("12.50");           // explicitly create an A2x object

double d;
d = a2x;                     // assign a variable using an A2x object
cout << d << '\n';

a2x = "err";
d = a2x;                     // d is 0: the conversion failed,
cout << d << '\n';           // and a2x.good() == false

a2x = " a";                  // reassign a2x to new text
char c = a2x;                // c now 'a': internally operator>>() is used
cout << c << '\n';           // so initial blanks are skipped.

int expectsInt(int x);        // initialize a parameter using an
expectsInt(A2x("1200"));      // anonymous A2x object

d = A2x("12.45").to<int>();    // d is 12, not 12.45
cout << d << '\n';
```

A complementary class (`x2a`), converting values to text, can be constructed as well. Its construction is left as an exercise to the reader.

23.6 Distinguishing lvalues from rvalues with `operator[]()`

A problem with `operator[]` is that it can't distinguish between its use as an *lvalue* and as an *rvalue*. It is a familiar misconception to think that since

```
Type const &operator[](size_t index) const
```

is used as *rvalue* (since the object isn't modified) that that

```
Type &operator[](size_t index)
```

is used as *lvalue* (since the returned value can be modified). In fact, the compiler distinguishes between the two operators only by the `const`-status of the object for which `operator[]` is called. With `const` objects the former operator is called, with non-`const` objects the latter is always used. It is always used, irrespective of it being used as *lvalue* or *rvalue*.

Being able to distinguish between *lvalues* and *rvalues* can be very useful. Consider the situation where a class supporting `operator[]` stores data of a type that is very hard to copy. With data like that reference counting (e.g., using `shared_ptr`) is probably used to prevent needless copying.

As long as `operator[]` is used as *rvalue* there's no need to copy the data, but the information *must* be copied if it is used as *lvalue*.

The *Proxy Design Pattern* (cf. *Gamma et al.* (1995)) can be used to distinguish between *lvalues* and *rvalues*. With the Proxy Design Pattern an object of another class (the Proxy class) is used to acts as a *stand in* for the 'real thing'. The proxy class offers functionality that cannot be offered by the data themselves, like distinguishing between its use as *lvalue* or *rvalue*. A proxy class can be used in many situations where access to the real data cannot or should not be directly provided. In this regard *iterator* types are examples of proxy classes as they create a layer between the real data and the software using the data. Proxy classes could also dereference pointers in a class storing its data by pointers.

In this section we concentrate on the distinction between using `operator[]` as *lvalue* and *rvalue*. Let's assume we have a class `Lines` storing lines from a file. It's constructor expects the name of a stream from which the lines are read and it offers a non-`const` `operator[]` that can be used as *lvalue* or *rvalue* (the `const` version of `operator[]` is omitted as it offers no problem because it is always used as *rvalue*):

```
class Lines
{
    std::vector<std::string> d_line;

    public:
        Lines(std::istream &in);
        std::string &operator[](size_t idx);
};
```

To distinguish between *lvalues* and *rvalues* we must find distinguishing characteristics of *lvalues* and *rvalues* that we can exploit. Such distinguishing characteristics are `operator=` (which is always used as *lvalue*) and the conversion operator (which is always used as *rvalue*). Rather than having `operator[]` return a `string` & we can let it return a `Proxy` object that is able to distinguish between its use as *lvalue* and *rvalue*.

The class `Proxy` thus needs `operator=(string const &other)` (acting as *lvalue*) and `operator std::string const &() const` (acting as *rvalue*). Do we need more operators? The `std::string` class also offers `operator+=`, so we should probably implement that operator as well. Plain characters can also be assigned to `string` objects (even using their numeric values). As `string` objects cannot be *constructed* from plain characters *promotion* cannot be used with `operator=(string const &other)` if the right-hand side argument is a character. Implementing `operator=(char value)` could therefore also be considered. These additional operators are left out of the current implementation but 'real life' proxy classes should consider implementing these additional operators as well. Another subtlety is that `Proxy's operator std::string const &() const` will not be used when using `ostream's` insertion operator or `istream's` extraction operator as these operators are implemented as templates not recognizing our `Proxy` class type. So when stream insertion and extraction is required (it probably is) then `Proxy` must be given its own overloaded insertion and extraction operator. Here is an implementation of the overloaded insertion operator inserting the object for which `Proxy` is a stand-in:

```
inline std::ostream &operator<<(std::ostream &out, Lines::Proxy const &proxy)
{
    return out << static_cast<std::string const &>(proxy);
}
```

There's no need for any code (except Lines) to create or copy Proxy objects. Proxy's constructor should therefore be made private, and Proxy can declare Lines to be its friend. In fact, Proxy is intimately related to Lines and can be defined as a nested class. In the revised Lines class operator[] no longer returns a string but instead a Proxy is returned. Here is the revised Lines class, including its nested Proxy class:

```
class Lines
{
    std::vector<std::string> d_line;

public:
    class Proxy;
    Proxy operator[](size_t idx);
    class Proxy
    {
        friend Proxy Lines::operator[](size_t idx);
        std::string &d_str;
        Proxy(std::string &str);
        public:
            std::string &operator=(std::string const &rhs);
            operator std::string const &() const;
    };
    Lines(std::istream &in);
};
```

Proxy's members are very lightweight and can usually be implemented inline:

```
inline Lines::Proxy::Proxy(std::string &str)
:
    d_str(str)
{}
inline std::string &Lines::Proxy::operator=(std::string const &rhs)
{
    return d_str = rhs;
}
inline Lines::Proxy::operator std::string const &() const
{
    return d_str;
}
```

The member Lines::operator[] can also be implemented inline: it merely returns a Proxy object initialized with the idx+sup(th) string.

Now that the class Proxy has been developed it can be used in a program. Here is an example using the Proxy object as lvalue or rvalue. On the surface Lines objects won't behave differently from Lines objects using the original implementation, but adding an identifying cout statement to Proxy's members will show that operator[] will behave differently when used as lvalue or as rvalue:

```
int main()
{
    ifstream in("lines.cc");
    Lines lines(in);

    string s = lines[0];           // rvalue use
    lines[0] = s;                  // lvalue use
    cout << lines[0] << '\n';     // rvalue use
    lines[0] = "hello world";     // lvalue use
    cout << lines[0] << '\n';     // rvalue use
}
```

23.7 Implementing a ‘reverse_iterator’

In section 21.12.1 the construction of iterators and reverse iterators was discussed. In that section the iterator was constructed as an inner class in a class derived from a vector of pointers to strings.

An object of this nested iterator class handles the dereferencing of the pointers stored in the vector. This allowed us to sort the *strings* pointed to by the vector’s elements rather than the *pointers*.

A drawback of this is that the class implementing the iterator is closely tied to the derived class as the iterator class was implemented as a nested class. What if we would like to provide any class derived from a container class storing pointers with an iterator handling pointer-dereferencing?

In this section a variant of the earlier (nested class) approach is discussed. Here the iterator class is defined as a class template, not only parameterizing the data type to which the container’s elements point but also the container’s iterator type itself. Once again, we will concentrate on developing a *RandomIterator* as it is the most complex iterator type.

Our class is named *RandomPtrIterator*, indicating that it is a random iterator operating on pointer values. The class template defines three template type parameters:

- The first parameter specifies the derived class type (*Class*). Like before, *RandomPtrIterator*’s constructor is private. Therefore friend declarations are needed to allow client classes to construct *RandomPtrIterators*. However, a friend class *Class* cannot be used as template parameter types cannot be used in friend class ... declarations. But this is a minor problem as not every member of the client class needs to construct iterators. In fact, only *Class*’s *begin* and *end* members must construct iterators. Using the template’s first parameter, friend declarations can be specified for the client’s *begin* and *end* members.
- The second template parameter parameterizes the container’s iterator type (*BaseIterator*);
- The third template parameter indicates the data type to which the pointers point (*Type*).

RandomPtrIterator has one private data member, a *BaseIterator*. Here is the class interface and the constructor’s implementation:

```
#include <iterator>

template <typename Class, typename BaseIterator, typename Type>
class RandomPtrIterator:
    public std::iterator<std::random_access_iterator_tag, Type>
{
    friend RandomPtrIterator<Class, BaseIterator, Type> Class::begin();
    friend RandomPtrIterator<Class, BaseIterator, Type> Class::end();

    BaseIterator d_current;

    RandomPtrIterator(BaseIterator const &current);

public:
    bool operator!=(RandomPtrIterator const &other) const;
    int operator-(RandomPtrIterator const &rhs) const;
    RandomPtrIterator const operator+(int step) const;
    Type &operator*() const;
    bool operator<(RandomPtrIterator const &other) const;
    RandomPtrIterator &operator--();
    RandomPtrIterator const operator--(int);
    RandomPtrIterator &operator++();
    RandomPtrIterator const operator++(int);
    bool operator==(RandomPtrIterator const &other) const;
    RandomPtrIterator const operator-(int step) const;
```

```

    RandomPtrIterator &operator--(int step);
    RandomPtrIterator &operator+=(int step);
    Type *operator->() const;
};

template <typename Class, typename BaseIterator, typename Type>
RandomPtrIterator<Class, BaseIterator, Type>::RandomPtrIterator(
    BaseIterator const &current)
:
    d_current(current)
{}

```

Looking at its friend declarations, we see that the members `begin` and `end` of a class `Class`, returning a `RandomPtrIterator` object for the types `Class`, `BaseIterator` and `Type` are granted access to `RandomPtrIterator`'s private constructor. That is exactly what we want. `begin` and `end` are declared as *bound friends*.

All `RandomPtrIterator`'s remaining members are public. Since `RandomPtrIterator` is just a generalization of the nested class `iterator` developed in section 21.12.1, re-implementing the required member functions is easy and only requires us to change `iterator` into `RandomPtrIterator` and to change `std::string` into `Type`. For example, `operator<`, defined in the class `iterator` as

```

inline bool StringPtr::iterator::operator<(iterator const &other) const
{
    return **d_current < **other.d_current;
}

```

is now implemented as:

```

template <typename Class, typename BaseIterator, typename Type>
bool RandomPtrIterator<Class, BaseIterator, Type>::operator<(
    RandomPtrIterator const &other) const
{
    return **d_current < **other.d_current;
}

```

Some additional examples: `operator*`, defined in the class `iterator` as

```

inline std::string &StringPtr::iterator::operator*() const
{
    return **d_current;
}

```

is now implemented as:

```

template <typename Class, typename BaseIterator, typename Type>
Type &RandomPtrIterator<Class, BaseIterator, Type>::operator*() const
{
    return **d_current;
}

```

The pre- and postfix increment operators are now implemented as:

```

template <typename Class, typename BaseIterator, typename Type>
RandomPtrIterator<Class, BaseIterator, Type>
&RandomPtrIterator<Class, BaseIterator, Type>::operator++()

```



```

{
    ++d_current;
    return *this;
}
template <typename Class, typename BaseIterator, typename Type>
RandomPtrIterator<Class, BaseIterator, Type> const
RandomPtrIterator<Class, BaseIterator, Type>::operator++(int)
{
    return RandomPtrIterator(d_current++);
}

```

Remaining members can be implemented accordingly, their actual implementations are left as exercises to the reader (or can be obtained from the `cplusplus.yo.zip` archive, of course).

Re-implementing the class `StringPtr` developed in section 21.12.1 is not difficult either. Apart from including the header file defining the class template `RandomPtrIterator`, it only requires a single modification. Its iterator typedef must now be associated with a `RandomPtrIterator`. Here is the full class interface and the class's inline member definitions:

```

#ifndef INCLUDED_STRINGPTR_H_
#define INCLUDED_STRINGPTR_H_

#include <vector>
#include <string>
#include "iterator.h"

class StringPtr: public std::vector<std::string *>
{
public:
    typedef RandomPtrIterator
        <
            StringPtr,
            std::vector<std::string *>::iterator,
            std::string
        >
        iterator;

    typedef std::reverse_iterator<iterator> reverse_iterator;

    iterator begin();
    iterator end();
    reverse_iterator rbegin();
    reverse_iterator rend();
};

inline StringPtr::iterator StringPtr::begin()
{
    return iterator(this->std::vector<std::string *>::begin() );
}
inline StringPtr::iterator StringPtr::end()
{
    return iterator(this->std::vector<std::string *>::end());
}
inline StringPtr::reverse_iterator StringPtr::rbegin()
{
    return reverse_iterator(end());
}
inline StringPtr::reverse_iterator StringPtr::rend()
{

```

```

        return reverse_iterator(begin());
    }
#endif

```

Including `StringPtr`'s modified header file into the program given in section 21.12.2 results in a program behaving identically to its earlier version. In this case `StringPtr::begin` and `StringPtr::end` return iterator objects constructed from a template definition.

23.8 Using 'bisonc++' and 'flex'

The example discussed below digs into the peculiarities of using parser- and scanner generators generating C++ sources. Once the input for a program exceeds a certain level of complexity, it becomes attractive to use scanner- and parser-generators generating the code which does the actual input recognition.

The current example assumes that the reader knows how to use the scanner generator `flex` and the parser generator `bison`. Both `bison` and `flex` are well documented elsewhere. The original predecessors of `bison` and `flex`, called `yacc` and `lex` are described in several books, e.g. in O'Reilly's book 'lex & yacc'³.

Scanner- and parser generators are also available as free software. Both `bison` and `flex` are usually part of software distributions or they can be obtained from `ftp://prep.ai.mit.edu/pub/non-gnu`. Flex creates a C++ class when `%option c++` is specified.

For parser generators the program `bison` is available. In the early 90's Alain Coetmeur (coetmeur@icdc.fr⁴) created a C++ variant (`bison++`) creating a parser class. Although the `bison++` program produces code that can be used in C++ programs it also shows many characteristics that are more suggestive of a C context than a C++ context. In January 2005 I rewrote parts of Alain's `bison++` program, resulting in the original version of the program **bisonc++**. Then, in May 2005 a complete rewrite of the `bisonc++` parser generator was completed (version number 0.98). Current versions of `bisonc++` can be downloaded from `http://bisoncpp.sourceforge.net/`, where it is available as source archive and as binary (i386) Debian⁵ package (including `bisonc++`'s documentation).

`Bisonc++` creates a cleaner parser class than `bison++`. In particular, it derives the parser class from a base-class, containing the parser's token- and type-definitions as well as all member functions which should not be (re)defined by the programmer. As a result of this approach, the generated parser class is very small, declaring only members that are actually defined by the programmer (as well as some other members, generated by `bisonc++` itself, implementing the parser's `parse()` member). One member that is *not* implemented by default is `lex`, producing the next lexical token. When the directive `%scanner` (see section 23.8.2.1) is used, `bisonc++` produces a standard implementation for this member; otherwise it must be implemented by the programmer.

This section of the C++ Annotations focuses on `bisonc++` as our *parser generator*.

Using `flex` and `bisonc++` class-based scanners and parsers can be generated. The advantage of this approach is that the interface to the scanner and the parser tends to become cleaner than without using the `class` interface. Furthermore, classes allow us to get rid of most if not all global variables, making it easy to use multiple parsers in one program.

Below two examples programs are developed. The first example only uses `flex`. The generated scanner monitors the production of a file from several parts. That example focuses on the lexical scanner and on switching files while churning through the information. The second example uses both `flex` and `bisonc++` to generate a scanner and a parser transforming standard arithmetic expressions to their postfix notations, commonly used in code generated by compilers and in HP-calculators. In the second example the emphasis is mainly on `bisonc++` and on composing a scanner object inside a generated parser.

³<http://www.oreilly.com/catalog/lex>

⁴<mailto:coetmeur@icdc.fr>

⁵<http://www.debian.org>

23.8.1 Using 'flex' to create a scanner

The lexical scanner developed in this section is used to monitor the production of a file from several subfiles. The setup is as follows: the input-language knows of an `#include` directive, followed by a text string specifying the file (path) which should be included at the location of the `#include`.

In order to avoid complexities irrelevant to the current example, the format of the `#include` statement is restricted to the form `#include <filepath>`. The file specified between the pointed brackets should be available at the location indicated by `filepath`. If the file is not available, the program terminates after issuing an error message.

The program is started with one or two filename arguments. If the program is started with just one filename argument, the output is written to the standard output stream `cout`. Otherwise, the output is written to the stream whose name is given as the program's second argument.

The program defines a maximum nesting depth. Once this maximum is exceeded, the program terminates after issuing an error message. In that case, the filename stack indicating where which file was included is printed.

An additional feature of the program is that (standard C++) comment-lines are ignored. Include-directives in comment-lines are also ignored.

The program is created in five major steps:

- First, the file `lexer` is constructed, containing the input-language specifications.
- From the specifications in `lexer` the requirements for the class `Scanner` evolve. The `Scanner` class is a wrapper class around the class `yyFlexLexer` generated by `flex`. The requirements result in the interface of the class `Scanner`.
- Next, `main` is constructed. A `Scanner` object is created inspecting the command-line arguments. If successful, the scanner's member `yylex` is called to produce the program's output.
- Now that the global setup of the program has been specified, the member functions of the various classes are implemented.
- Finally, the program is compiled and linked.

23.8.1.1 The derived class 'Scanner'

The code associated with the regular expression rules is located inside the class `yyFlexLexer`. However, we of course want to use the derived class's members in this code. This causes a small problem. How does a base-class member know about members of classes derived from it?

Inheritance helps us to overcome this problem. In the specification of the class `yyFlexLexer`, we notice that the function `yylex` is a *virtual* function. The header file `FlexLexer.h` declares the virtual member `int yylex`:

```
class yyFlexLexer: public FlexLexer
{
public:
    yyFlexLexer( istream* arg_yyin = 0, ostream* arg_yyout = 0 );

    virtual ~yyFlexLexer();

    void yy_switch_to_buffer( struct yy_buffer_state* new_buffer );
    struct yy_buffer_state* yy_create_buffer( istream* s, int size );
    void yy_delete_buffer( struct yy_buffer_state* b );
    void yyrestart( istream* s );
```

```

        virtual int yylex();

        virtual void switch_streams( istream* new_in, ostream* new_out );
};

```

As this function is virtual it can be overridden by a *derived* class. In that case the overridden function will be called from its base class (i.e., `yyFlexLexer`) code. Since the derived class's `yylex()` is called, it will now have access to the members of the derived class, and also to the public and protected members of its base class.

By default, the context in which the generated scanner is placed is the function `yyFlexLexer::yylex`. This context changes if we use a derived class, e.g., `Scanner`. To derive `Scanner` from `yyFlexLexer`, generated by `flex`, do as follows:

- The function `yylex` must be declared in the derived class `Scanner`.
- *Options* (see below) are used to inform `flex` about the derived class's name.

Looking at the regular expressions themselves, notice that we need rules to recognize comment, `#include` directives, and all remaining characters. This is all fairly standard practice. When an `#include` directive is sensed, the directive is parsed by the scanner. This too is common practice. Here is what our lexical scanner will do:

- As usual, preprocessor directives are not analyzed by a parser, but by the lexical scanner;
- The scanner uses a mini scanner to extract the filename from the directive, throwing a `Scanner::Error` value (`invalidInclude`) if this fails;
- If the filename could be extracted, it is stored in `nextSource`;
- When the `#include` directive has been processed, `pushSource` is called to perform the switch to another file;
- When the end of the file (EOF) is reached, the derived class's member function `popSource` is called, popping the previously pushed file and returning `true`;
- Once the file-stack is empty, `popSource` returns `false`, resulting in calling `yyterminate`, terminating the scanner.

The lexical scanner specification file is organized similarly as the one used for `flex` in **C** contexts. However, in **C++** contexts, `flex` may create a class (`yyFlexLexer`) from which another class (e.g., `Scanner`) can be derived. `Flex`'s specification file itself has three sections:

- The lexer specification file's first section is a **C++** *preamble*, containing code which can be used in the code defining the actions that are performed once a regular expression has been matched. In the current setup, where each class has its own *internal header file*, the internal header file includes the file `scanner.h`, in turn including `FlexLexer.h`, which is part of the `flex` distribution. `FlexLexer.h` has a peculiar setup, due to which it should not be read twice by the code generated by `flex`. So, we now have the following situation:
 - First we look at the lexer specification file. It contains a preamble including `scanner.ih`. The class `Scanner` is declared in `scanner.h`, which is read by `scanner.ih`. Therefore `Scanner`'s members are known and can be called from the code associated with the regular expressions defined in the lexer specification file.
 - However, in `scanner.h`, defining class `Scanner`, the header file `FlexLexer.h`, declaring `Scanner`'s base class, *must* have been read by the compiler before the class `Scanner` itself is defined.
 - Code generated by `flex` already includes `FlexLexer.h`, and as mentioned, `FlexLexer.h` may not be read twice. Unfortunately, `flex` also inserts the specification file's preamble into the code it generates.

- Since this preamble includes `scanner.ih`, and so `scanner.h`, and so `FlexLexer.h`, we now *do* include `FlexLexer.h` twice in code generated by `flex`. This must be prevented.

This is how multiple inclusions of `FlexLexer.h` can be prevented:

- Although `scanner.ih` includes `scanner.h`, `scanner.h` itself is modified such that it includes `FlexLexer.h`, *unless* the C preprocessor variable `SKIP_FLEXLEXER_` is defined.
- In `flex`' specification file `SKIP_FLEXLEXER_` is defined just prior to including `scanner.ih`.

Using this scheme, code generated by `flex` now re-includes `FlexLexer.h`. At the same time the compilation of `Scanner`'s members proceeds independently of the lexer specification file's preamble, so here `FlexLexer.h` is properly included too. Here is the specification file's preamble:

```
%{
    #define _SKIP_YFLEXLEXER_
    #include "scanner.ih"
}%
```

- The specification file's second section is a *flex symbol area*, used to define symbols, like a mini scanner, or *options*. The following options are suggested:
 - `%option 8bit`: allowing the generated lexical scanner to read 8-bit characters (rather than 7-bit, which is the default).
 - `%option c++`: this results in `flex` generating C++ code.
 - `%option debug`: includes *debugging* code into the code generated by `flex`. Calling the member function `set_debug(true)` activates this debugging code run-time. When activated, information about which rules are matched is written to the standard error stream. To suppress the execution of debug code the member function `set_debug(false)` may be called.
 - `%option noyywrap`: when the scanner reaches the end of file, it will (by default) call a function `ywrap` which may perform the switch to another file. Calling this function is suppressed when `%option noyywrap` is specified. Since there exist alternatives which render this function superfluous (see below), it is suggested to specify this option as well.
 - `%option outfile="yylex.cc"`: this defines `yylex.cc` as the name of the generated C++ source file.
 - `%option warn`: this option is strongly suggested by the `flex` documentation, so it's mentioned here as well. See `flex`' documentation for details.
 - `%option yyclass="Scanner"`: this defines `Scanner` as the name of the class derived from `yyFlexLexer`.
 - `%option yylineno`: this option causes the lexical scanner to keep track of the line numbers of the files it is scanning. When processing nested files the variable `yylineno` is not automatically reset to the last line number of a file when `yylex` returns to a partially processed file. In those cases, `yylineno` must explicitly be reset to a former value. If specified, the current line number is returned by the public member `lineno`, returning an `int`.

Here is the specification file's symbol area:

```
%option yyclass="Scanner" outfile="yylex.cc" c++ 8bit warn noyywrap yylineno
%option debug

%x      comment
%x      include

eolnComment      "//" .*
anyChar          .|\n
```

- The specification file's third section is a *rules section*, in which the regular expressions and their associated actions are defined. In the example developed here, the lexer should copy information

from the istream `*yyin` to the ostream `*yyout`. For this the predefined macro `ECHO` can be used. Here is the used symbol area:

```
%%
/*
    The comment-rules: comment lines are ignored.
*/
{eolnComment}
"/*"          BEGIN comment;
<comment>{anyChar}
<comment>"*/"  BEGIN INITIAL;

/*
    File switching: #include <filepath>
*/
#include[ \t]+"<"      BEGIN include;
<include>[^ \t>]+      d_nextSource = yytext;
<include>">"[ \t]*\n    {
                        BEGIN INITIAL;
                        pushSource(YY_CURRENT_BUFFER, YY_BUF_SIZE);
                    }
<include>{anyChar}      throw invalidInclude;

/*
    The default rules: eating all the rest, echoing it to output
*/
{anyChar}              ECHO;

/*
    The <<EOF>> rule: pop a pushed file, or terminate the lexer
*/
<<EOF>>                {
                        if (!popSource(YY_CURRENT_BUFFER))
                            yyterminate();
                    }
%%
```

Since the derived class's members may now access the information stored in the lexical scanner itself (it can even access the information *directly*, since `yyFlexLexer`'s data members are protected, and thus accessible to derived classes), most processing can be left to the derived class's member functions. This results in a very clean setup of the lexer specification file, requiring no or hardly any code in the *preamble*.

23.8.1.2 Implementing 'Scanner'

The class `Scanner`, derived as usual from the class `yyFlexLexer`, is generated by **flex**. The derived class has access to data controlled by the lexical scanner. Specifically, it has access to the following members:

- `char *yytext`, containing the text matched by a regular expression. Clients may access this information using the scanner's `YYText` member;
- `int yyleng`, the length of the text in `yytext`. Clients may access this value using the scanner's `YYLeng` member;
- `int yylineno`: the current line number. This variable is only maintained if %option `yylineno` is specified. Clients may access this value using the scanner's `lineno` member.

Other members are available as well, but are used less often. Details can be found in `FlexLexer.h`.

Objects of the class `Scanner` perform two tasks:

- They push file information about the current file to a file stack;
- They pop the last-pushed information from the stack once EOF is detected in a file.

Several member functions are used to accomplish these tasks. As they are auxiliary to the scanner, they are private members. In practice, develop these private members only when the need for them arises. Note that, apart from the private member functions, several private data members are defined as well. Let's have a closer look at the implementation of the class `Scanner`:

- First, we have a look at the class's initial section, showing the conditional inclusion of `FlexLexer.h`, its class opening, and its private data. At the top of the class interface the private struct `FileInfo` is defined. `FileInfo` is used to store the names and pointers to open files. The struct has two constructors. One accepts a filename, the other also expecting a `bool` argument indicating that the file is already open and should not be handled by `FileInfo`. This former constructor is used only once. As the initial stream is an already open file there is no need to open it again and so `Scanner`'s constructor will use this constructor to store the name of the initial file only. `Scanner`'s public section starts off by defining the enum `Error` defining various symbolic constants for errors that may be detected:

```
#if ! defined(_SKIP_YYFLEXLEXER_)
#include <FlexLexer.h>
#endif

class Scanner: public yyFlexLexer
{
    struct FileInfo
    {
        std::string d_name;
        std::ifstream *d_in;

        FileInfo(std::string name)
        :
            d_name(name),
            d_in(new std::ifstream(name.c_str()))
        {}
        FileInfo(std::string name, bool)
        :
            d_name(name),
            d_in(0)
        {}
    };

    // inline bool operator==(FileInfo const &rhs) const
    // {
    //     return d_name == rhs.d_name;
    // };

    friend bool operator==(FileInfo const &fi, std::string const &name);

    std::stack<yy_buffer_state *>    d_state;
    std::vector<FileInfo>            d_fileInfo;
    std::string                      d_nextSource;

    static size_t const              s_maxDepth = 10;

public:
```



```
enum Error
{
    invalidInclude,
    circularInclusion,
    nestingTooDeep,
    cantRead,
};
```

- As they are objects, the class's data members are initialized automatically by Scanner's constructor. It activates the initial input (and output) file and pushes the name of the initial input file on the file stack, using the second FileInfo constructor. Here is its implementation:

```
#include "scanner.ih"

Scanner::Scanner(istream *yyin, string const &initialName)
{
    switch_streams(yyin, yyout);
    d_fileInfo.push_back(FileInfo(initialName, false));
}
```

- The scanning process proceeds as follows: once the scanner extracts a filename from an #include directive, a switch to another file is performed by pushSource. If the filename could not be extracted, the scanner throws an invalidInclude exception. The pushSource member and the matching function popSource handle file switching. Switching to another file proceeds like this:

- First, the current depth of the include-nesting is inspected. If s_maxDepth is reached, the stack is considered full, and the scanner throws a nestingTooDeep exception.
- Next, throwOnCircularInclusion is called to avoid circular inclusions when switching to new files. This function throws an exception if a filename is included twice using a simple literal name check. Here is its implementation:

```
#include "scanner.ih"

inline bool operator==(Scanner::FileInfo const &fi, string const &name)
{
    return fi.d_name == name;
}

void Scanner::throwOnCircularInclusion()
{
    vector<FileInfo>::iterator
        it = find(d_fileInfo.begin(), d_fileInfo.end(), d_nextSource);

    if (it != d_fileInfo.end())
        throw circularInclusion;
}
```

- Then the new filename is added to the FileInfo vector, at the same time creating a new ifstream object. If this fails, the scanner throws a cantRead exception.
- Finally, a new yy_buffer_state is created for the newly opened stream, and the lexical scanner is instructed to switch to that stream using yyFlexLexer's member function yy_switch_to_buffer.

Here is pushSource's implementation:

```
#include "scanner.ih"

void Scanner::pushSource(yy_buffer_state *current, size_t size)
{
    if (d_state.size() == s_maxDepth)
```



```

        throw nestingTooDeep;

        throwOnCircularInclusion();
        d_fileInfo.push_back(FileInfo(d_nextSource));

        ifstream *newStream = d_fileInfo.back().d_in;

        if (!*newStream)
            throw cantRead;

        d_state.push(current);
        yy_switch_to_buffer(yy_create_buffer(newStream, size));
    }

```

- The class `yyFlexLexer` provides a series of member functions that can be used to switch files. The file-switching capability of a `yyFlexLexer` object is founded on the struct `yy_buffer_state`, containing the state of the *scan-buffer* of the currently read file. This buffer is pushed on the `d_state` stack when an `#include` is encountered. Then `yy_buffer_state`'s contents are replaced by the buffer created for the file to be processed next. In the flex specification file the function `pushSource` is called as

```
pushSource(YY_CURRENT_BUFFER, YY_BUF_SIZE);
```

`YY_CURRENT_BUFFER` and `YY_BUF_SIZE` are macros that are *only* available in the rules section of the lexer specification file, so they must be passed as arguments to `pushSource`. It is *not* possible to use these macros in the Scanner class's member functions directly.

- Note that `yylineno` is not updated when a file switch is performed. If line numbers are to be monitored, then the current value of `yylineno` should be pushed on a stack and `yylineno` should be reset by `pushSource`. Correspondingly, `popSource` should reinstate a former value of `yylineno` by popping a previously pushed value from the stack. Scanner's current implementation maintains a stack of `yy_buffer_state` pointers. Changing that into a stack of `pair<yy_buffer_state *, size_t>` elements allows us to save (and restore) line numbers as well. This modification is left as an exercise to the reader.
- The member function `popSource` is called to pop the previously pushed buffer off the stack. This allows the scanner to continue its scanning process just beyond the just completed `#include` directive. The member `popSource` first inspects the size of the `d_state` stack. If it is empty, `false` is returned and the function terminates. If it isn't empty, then the current buffer is deleted and it is replaced by the state waiting on top of the stack. The file switch is performed by the `yyFlexLexer` members `yy_delete_buffer` and `yy_switch_to_buffer`. The `yy_delete_buffer` function does *not* close the `ifstream` and does *not* delete the memory allocated for this stream by `pushSource`. Therefore `delete` is called for the `ifstream` pointer stored at the back of `d_fileInfo` to take care of both. Following this the last `FileInfo` entry is removed from `d_fileInfo`. Finally the function returns `true`:

```

#include "scanner.ih"

bool Scanner::popSource(yy_buffer_state *current)
{
    if (d_state.empty())
        return false;

    yy_delete_buffer(current);
    yy_switch_to_buffer(d_state.top());
    d_state.pop();

    delete d_fileInfo.back().d_in;        // closes the stream as well
    d_fileInfo.pop_back();
}

```

```
    return true;
}
```

- Two service members are offered: `stackTrace` dumps the names of the currently pushed files to the standard error stream. It may be called by exception catchers. Here is its implementation:

```
#include "scanner.ih"

void Scanner::stackTrace()
{
    for (size_t idx = 0; idx < d_fileInfo.size() - 1; ++idx)
        cerr << idx << ": " << d_fileInfo[idx].d_name << " included " <<
            d_fileInfo[idx + 1].d_name << '\n';
}
```

- `lastFile` returns the name of the currently processed file. It may be implemented inline:

```
inline std::string const &Scanner::lastFile()
{
    return d_fileInfo.back().d_name;
}
```

- The lexical scanner itself is defined in `Scanner::yylex`. Therefore, `int yylex` must be declared by the class `Scanner`, as it overrides `FlexLexer`'s virtual member `yylex`.

23.8.1.3 Using a 'Scanner' object

The program using our `Scanner` is very simple. It expects a filename indicating where to start the scanning process. It first checks the number of arguments. If at least one argument was given, then an `ifstream` object is created. If this object can be created, then a `Scanner` object is constructed, receiving the address of the `ifstream` object and the name of the initial input file as its arguments. Then the `Scanner` object's `yylex` member is called. The scanner object throws `Scanner::Error` exceptions if it fails to perform its tasks properly. These exceptions are caught near `main`'s end. Here is the program's source:

```
#include "lexer.h"
using namespace std;

int main(int argc, char **argv)
try
{
    if (argc == 1)
    {
        cerr << "Filename argument required\n";
        return 1;
    }

    ifstream yyin(argv[1]);
    if (!yyin)
    {
        cerr << "Can't read " << argv[1] << '\n';
        return 1;
    }

    Scanner scanner(&yyin, argv[1]);
    try
    {
        return scanner.yylex();
    }
}
```

```

    }
    catch (Scanner::Error err)
    {
        char const *msg[] =
        {
            "Include specification",
            "Circular Include",
            "Nesting",
            "Read",
        };
        cerr << msg[err] << " error in " << scanner.lastFile() <<
            ", line " << scanner.lineno() << '\n';
        scanner.stackTrace();
        return 1;
    }
}

```

23.8.1.4 Building the program

The final program is constructed in two steps. These steps are given for a Unix system, on which `flex` and the Gnu C++ compiler `g++` have been installed:

- First, the lexical scanner's source is created using `flex`. For this the following command can be given:

```
flex lexer
```

- Next, all sources are compiled and linked. In situations where the default `yywrap()` function is used, the `libfl.a` library should be linked against the final program. Normally, that's not required, and the program can be constructed as, e.g.:

```
g++ -o lexer *.cc
```

For the purpose of debugging a lexical scanner, the matched rules and the returned tokens provide useful information. When the `%option debug` was specified, debugging code is included in the generated scanner. To obtain debugging info, this code must also be activated. Assuming the scanner object is called `scanner`, then the statement

```
scanner.set_debug(true);
```

will produce debugging info written to the standard error stream.

23.8.2 Using 'bisonc++' and 'flex'

Once an input language exceeds a certain level of complexity, a *parser* is often used to control the complexity of the language. In this case, a *parser generator* can be used to generate the code verifying the input's grammatical correctness. The lexical scanner (preferably composed into the parser) provides chunks of the input, called *tokens*. The parser then processes the series of tokens generated by the lexical scanner.

Starting point when developing programs that use both parsers and scanners is the grammar. The grammar defines a *set of tokens* that can be returned by the lexical scanner (called the *scanner* below).

Finally, auxiliary code is provided to 'fill in the blanks': the actions performed by the parser and by the scanner are not normally specified literally in the grammar rules or lexical regular expressions,

but should be implemented in *member functions*, called from the parser's rules or which are associated with the scanner's regular expressions.

In the previous section we've seen an example of a C++ class generated by `flex`. In the current section we concentrate on the parser. The parser can be generated from a grammar specification file, processed by the program `bisonc++`. The grammar specification file required by `bisonc++` is similar to the file processed by `bison` (or by `bison`'s successor (and `bisonc++`'s predecessor) `bison++`, written in the early nineties by the Frenchman *Alain Coetmeur*).

In this section a program is developed converting *infix expressions*, where binary operators are written between their operands, to *postfix expressions*, where operators are written behind their operands. Also, the unary operator `-` is converted from its prefix notation to a postfix form. The unary `+` operator is ignored as it requires no further actions. In essence our little calculator is a micro compiler, transforming numeric expressions into assembly-like instructions.

Our calculator will recognize a very basic set of operators: multiplication, addition, parentheses, and the unary minus. We'll distinguish real numbers from integers, to illustrate a subtlety in `bison`-like grammar specifications. That's all. The purpose of this section is, after all, to illustrate the construction of a C++ program that uses both a parser and a lexical scanner, rather than to construct a full-fledged calculator.

In the coming sections we'll develop the grammar specification for `bisonc++`. Then, the regular expressions for the scanner are specified. Following that, the final program is constructed.

23.8.2.1 The 'bisonc++' specification file

The grammar specification file required by `bisonc++` is comparable to the specification file required by `bison`. Differences are related to the class nature of the resulting parser. Our calculator distinguishes real numbers from integers, and supports a basic set of arithmetic operators.

`Bisonc++` should be used as follows:

- As usual, a grammar is defined. With `bisonc++` this is no different, and `bisonc++` grammar definitions are for all practical purposes identical to `bison`'s grammar definitions.
- Having specified the grammar and (usually) some declarations `bisonc++` can generate files defining the parser class and the implementation of the member function `parse`.
- All class members (except those that are required for the proper functioning of the member `parse`) must be separately implemented. Of course, they should also be declared in the parser class's header. At the very least the member `lex` must be implemented. This member is called by `parse` to obtain the next available token. However, `bisonc++` offers a facility providing a standard implementation of the function `lex`. The member function `error(char const *msg)` is given a simple default implementation that may be modified by the programmer. The member function `error` is called when `parse` detects (syntactic) errors.
- The parser can now be used in a program. A very simple example would be:

```
int main()
{
    Parser parser;
    return parser.parse();
}
```

The `bisonc++` specification file has two sections:

- The *declaration section*. In this section `bison`'s tokens, and the priority rules for the operators are declared. However, `bisonc++` also supports several new declarations. These new declarations are important and are discussed below.

- **The *rules* section.** The grammatical rules define the grammar. This section is identical to the one required by `bison`, albeit that some members that were available in `bison` and `bison++` are obsolete in `bisonc++`, while other members can be used in a wider context. For example, **ACCEPT** and **ABORT** can be called from any member called from the parser's action blocks to terminate the parsing process.

Readers familiar with `bison` will note that there is no *header section* anymore. Header sections are used by `bison` to provide for the necessary declarations allowing the compiler to compile the **C** function generated by `bison`. In **C++** declarations are part of or already used by class definitions. Therefore, a parser generator generating a **C++** class and some of its member functions does not require a header section anymore.

The declaration section The declaration section contains several sets of declarations, among which definitions of all the tokens used in the grammar and the priorities and associativities of the mathematical operators. Moreover, several new and important specifications can be used here as well. Those relevant to our current example and only available in `bisonc++` are discussed here. The reader is referred to `bisonc++`'s man-page for a full description.

- **%baseclass-header** *header*
Defines the pathname of the file to contain (or containing) the parser's base class. Defaults to the name of the parser class plus the suffix `.h`.
- **%baseclass-preinclude** *header*
Use *header* as the pathname to the file pre-included in the parser's base-class header. This declaration is useful in situations where the base class header file refers to types which might not yet be known. E.g., with `%union a std::string *` field might be used. Since the class `std::string` might not yet be known to the compiler once it processes the base class header file we need a way to inform the compiler about these classes and types. The suggested procedure is to use a pre-include header file declaring the required types. By default *header* will be surrounded by double quotes (using, e.g., `#include "header"`). When the argument is surrounded by angle brackets `#include <header>` will be included. In the latter case, quotes might be required to escape interpretation by the shell (e.g., using `-H '<header>'`).
- **%class-header** *header*
Defines the pathname of the file to contain (or containing) the parser class. Defaults to the name of the parser class plus the suffix `.h`.
- **%class-name** *parser-class-name*
Declares the class name of this parser. This declaration replaces the `%name` declaration previously used by `bison++`. It defines the name of the **C++** class that will be generated. Contrary to `bison++`'s `%name` declaration, `%class-name` may appear anywhere in the first section of the grammar specification file. It may be defined only once. If no `%class-name` is specified the default class name `Parser` will be used.
- **%debug**
Provides `parse` and its support functions with debugging code, showing the actual parsing process on the standard output stream. When included, the debugging output is active by default, but its activity may be controlled using the `setDebug(bool on-off)` member. Note that no `#ifdef DEBUG` macros are used anymore. By rerunning `bisonc++` without the `-debug` option an equivalent parser is generated not containing the debugging code.
- **%filenames** *header*
Defines the generic name of all generated files, unless overridden by specific names. By default the generated files use the class-name as the generic file name.
- **%implementation-header** *header*
Defines the pathname of the file to contain (or containing) the implementation header. Defaults to the name of the generated parser class plus the suffix `.ih`. The implementation header should contain all directives and declarations *only* used by the implementations of the parser's member functions. It is the only header file that is included by the source file containing `parse's`

implementation. It is suggested that user defined implementations of other class members use the same convention, thus concentrating all directives and declarations that are required for the compilation of other source files belonging to the parser class in one header file.

- **%parsefun-source** source

Defines the pathname of the file containing the parser member `parse`. Defaults to `parse.cc`.

- **%scanner** header

Use header as the pathname to the file pre-included in the parser's class header. This file should define a class `Scanner`, offering a member `int yylex()` producing the next token from the input stream to be analyzed by the parser generated by `bisonc++`. When this option is used the parser's member `int lex()` will be predefined as (assuming the parser class name is `Parser`):

```
inline int Parser::lex()
{
    return d_scanner.yylex();
}
```

and an object `Scanner d_scanner` will be composed into the parser. The `d_scanner` object will be constructed using its default constructor. If another constructor is required, the parser class may be provided with an appropriate (overloaded) parser constructor after having constructed the default parser class header file using `bisonc++`. By default header will be surrounded by double quotes (using, e.g., `#include "header"`). When the argument is surrounded by angle brackets `#include <header>` will be included.

- **%stype** typename

The type of the semantic value of tokens. The specification `typename` should be the name of an unstructured type (e.g., `size_t`). By default it is `int`. See `YYSTYPE` in `bison`. It should not be used if a `%union` specification is used. Within the parser class, this type may be used as `STYPE`.

- **%union** union-definition

Acts identically to the `bison` declaration. As with `bison` this generates a union for the parser's semantic type. The union type is named `STYPE`. If no `%union` is declared, a simple stack-type may be defined using the `%stype` declaration. If no `%stype` declaration is used, the default stacktype (`int`) is used.

An example of a `%union` declaration is:

```
%union
{
    int      i;
    double   d;
};
```

In pre-C++0x code a union cannot contain objects as its fields, as constructors cannot be called when a union is created. This means that a `string` cannot be a member of the union. A `string *`, however, is a possible union member. In time C++0x will offer *unrestricted unions* (cf. section 7.11) allowing class type objects to become fields in union definitions, but these unrestricted unions have not yet been implemented by compilers.

As an aside: the scanner does not have to know about such a union. It can simply pass its scanned text to the parser through its `YYText` member function. For example using a statement like

```
$$ .i = A2x(scanner.YYText());
```

matched text may be converted to a value of an appropriate type.

Tokens and non-terminals can be associated with union fields. This is strongly advised, as it prevents type mismatches, since the compiler will be able to check for type correctness. At the same time, the bison specific variabls `$$`, `$1`, `$2`, etc. may be used, rather than the full field specification (like `$$.i`).

A non-terminal or a token may be associated with a union field using the <fieldname> specification. E.g.,

```
%token <i> INT           // token association (deprecated, see below)
        <d> DOUBLE
%type  <i> intExpr       // non-terminal association
```

In the example developed here, both the tokens and the non-terminals can be associated with a field of the union. However, as noted before, the scanner does not have to know about all this. In our opinion, it is cleaner to let the scanner do just one thing: scan texts. The *parser*, knowing what the input is all about, may then convert strings like "123" to an integer value. Consequently, the association of a union field and a token is discouraged. When describing the rules of the grammar this will be illustrated further.

In the %union discussion the %token and %type specifications should be noted. They are used to specify the tokens (terminal symbols) that can be returned by the scanner, and to specify the return types of non-terminals. Apart from %token the token declarators %left, %right, and %nonassoc can be used to specify the associativity of operators. The tokens mentioned at these indicators are interpreted as tokens indicating operators, associating in the indicated direction. The precedence of operators is defined by their order: the first specification has the lowest priority. To overrule a certain precedence in a certain context %prec can be used. As all this is standard bisonc++ practice, it isn't further elaborated here. The documentation provided with bisonc++'s distribution should be consulted for further reference.

Here is the specification of the calculator's declaration section:

```
%filenames parser
%scanner ../scanner/scanner.h
%lines

%union {
    int i;
    double d;
};

%token  INT
        DOUBLE

%type   <i> intExpr
%type   <d> doubleExpr

%left   '+'
%left   '*'
%right  UnaryMinus
```

In the declaration section %type specifiers are used, associating the intExpr rule's value (see the next section) to the i-field of the semantic-value union, and associating doubleExpr's value to the d-field. At first sight this may look complex, since the expression rules must be included for each individual return type. On the other hand, if the union itself would have been used, we would still have had to specify somewhere in the returned semantic values what field to use: less rules, but more complex and error-prone code.

The grammar rules The rules and actions of the grammar are specified as usual. The grammar for our little calculator is given below. There are quite a few rules, but they illustrate various features offered by bisonc++. In particular, note that no action block requires more than a single line of code. This keeps the grammar simple, and therefore enhances its readability and understandability. Even the rule defining the parser's proper termination (the empty line in the line rule) uses a single member function called done. The implementation of that function is simple, but it is worth while noting that it

calls **Parser::ACCEPT**, showing that **ACCEPT** can be called indirectly from a production rule's action block. Here are the grammar's production rules:

```

lines:
    lines
    line
|
    line
;

line:
    intExpr
    '\n'
    {
        display($1);
    }
|
    doubleExpr
    '\n'
    {
        display($1);
    }
|
    '\n'
    {
        done();
    }
|
    error
    '\n'
    {
        reset();
    }
;

intExpr:
    intExpr '*' intExpr
    {
        $$ = exec('*', $1, $3);
    }
|
    intExpr '+' intExpr
    {
        $$ = exec('+', $1, $3);
    }
|
    '(' intExpr ')'
    {
        $$ = $2;
    }
|
    '-' intExpr          %prec UnaryMinus
    {
        $$ = neg($2);
    }
|
    INT
    {

```



```

        $$ = convert<int>();
    }
;

doubleExpr:
    doubleExpr '*' doubleExpr
    {
        $$ = exec('*', $1, $3);
    }
|
    doubleExpr '*' intExpr
    {
        $$ = exec('*', $1, d($3));
    }
|
    intExpr '*' doubleExpr
    {
        $$ = exec('*', d($1), $3);
    }
|
    doubleExpr '+' doubleExpr
    {
        $$ = exec('+', $1, $3);
    }
|
    doubleExpr '+' intExpr
    {
        $$ = exec('+', $1, d($3));
    }
|
    intExpr '+' doubleExpr
    {
        $$ = exec('+', d($1), $3);
    }
|
    '(' doubleExpr ')'
    {
        $$ = $2;
    }
|
    '-' doubleExpr          %prec UnaryMinus
    {
        $$ = neg($2);
    }
|
    DOUBLE
    {
        $$ = convert<double>();
    }
;

```

This grammar is used to implement a simple calculator in which integer and real values can be negated, added, and multiplied and in which standard priority rules can be overruled by parentheses. The grammar shows the use of typed nonterminal symbols: `doubleExpr` is linked to real (double) values, `intExpr` is linked to integer values. Precedence and type association is defined in the parser's definition section.

The Parser's header file Several functions called from the grammar are defined as template functions. BisonC++ generates multiple files, among which the file defining the parser's class. Functions called from the production rule's action blocks are usually member functions of the parser. These member functions must be declared and defined. Once bisonC++ has generated the header file defining the parser's class it will not automatically rewrite that file, allowing the programmer to add new members to the parser class once they are required. Here is the `parser.h` file as used in our little calculator:

```
#ifndef Parser_h_included
#define Parser_h_included

#include <iostream>
#include <sstream>
#include <bobcat/a2x>

#include "parserbase.h"
#include "../scanner/scanner.h"

#undef Parser
class Parser: public ParserBase
{
    std::ostringstream d_rpn;
    // $insert scannerobject
    Scanner d_scanner;

public:
    int parse();

private:
    template <typename Type>
        Type exec(char c, Type left, Type right);
    template <typename Type>
        Type neg(Type op);
    template <typename Type>
        Type convert();

    void display(int x);
    void display(double x);
    void done() const;
    void reset();
    void error(char const *msg);
    int lex();
    void print();

    static double d(int i);

    // support functions for parse():

    void executeAction(int d_ruleNr);
    void errorRecovery();
    int lookup(bool recovery);
    void nextToken();
};

inline double Parser::d(int i)
{
    return i;
}
```

```

template <typename Type>
Type Parser::exec(char c, Type left, Type right)
{
    d_rpn << " " << c << " ";
    return c == '*' ? left * right : left + right;
}

template <typename Type>
Type Parser::neg(Type op)
{
    d_rpn << " n ";
    return -op;
}

template <typename Type>
Type Parser::convert()
{
    Type ret = FBB::A2x(d_scanner.YYText());
    d_rpn << " " << ret << " ";
    return ret;
}

inline void Parser::error(char const *msg)
{
    std::cerr << msg << '\n';
}

inline int Parser::lex()
{
    return d_scanner.yylex();
}

inline void Parser::print()
{
}

#endif

```

23.8.2.2 The 'flex' specification file

The flex-specification file used by the calculator is simple: blanks are skipped, single characters are returned, and numeric values are returned as either `Parser::INT` or `Parser::DOUBLE` tokens. Here is the complete specification file:

```

%{
    #define _SKIP_YYFLEXLEXER_
    #include "scanner.ih"

    #include "../parser/parserbase.h"
}%

%option yyclass="Scanner" outfile="yylex.cc" c++ 8bit warn noyywrap
%option debug

%%

[ \t]                ;
[0-9]+                return Parser::INT;

```

```

"."[0-9]*          |
[0-9]+("."[0-9]*)? return Parser::DOUBLE;

.|\\n              return *yytext;

%%

```

23.8.2.3 Generating code

The program's code is generated in the same way as with programs using `bison` and `flex`. The files `parser.cc` and `parser.h` are generated by the command:

```
bisonc++ -V grammar
```

The option `-V` produces the file `parser.output` showing information about the internal structure of the provided grammar (among which its states). It is useful for debugging purposes and can be omitted if no debugging is required.

`Bisonc++` may detect conflicts (shift-reduce conflicts and/or reduce-reduce conflicts) in the provided grammar. These conflicts may be resolved explicitly using disambiguating rules or they are 'resolved' by default. By default, a shift-reduce conflict is resolved by shifting (i.e., the next token is consumed). By default a reduce-reduce conflict is resolved by using the first of two competing production rules. `Bisonc++`'s conflict resolution procedures are identical to `bison`'s procedures.

Once a parser class and a parsing member function has been constructed `flex` may be used to create a lexical scanner using, e.g., the command

```
flex -I lexer
```

On Unix systems a command like

```
g++ -o calc -Wall *.cc -s
```

can be used to compile and link the source of the main program and the sources produced by the scanner and parser generators.

Finally, here is a source file in which the `main` function and the parser object is defined. The parser features the lexical scanner as one of its data members:

```

#include "parser/parser.h"

using namespace std;

int main()
{
    Parser parser;

    cout << "Enter (nested) expressions containing ints, doubles, *, + and "
          "unary -\n"
          "operators. Enter an empty line to stop.\n";

    return parser.parse();
}

```

`Bisonc++` can be downloaded from <http://bisoncpp.sourceforge.net/>. It requires the `bobcat` library, which can be downloaded from <http://bobcat.sourceforge.net/>.

23.8.3 Using polymorphic semantic values with Bisonc++

Below the way Bisonc++ may use a polymorphic semantic value is described. The described method is a direct result of a suggestion initially brought forward by Dallas A. Clement in September 2007.

One may wonder why a union is still used by Bisonc++ as C++ offers inherently superior constructs to combine multiple types into one type. The C++ way to combine types into one type is by defining a polymorphic base class and a series of derived classes implementing the alternative data types. Bisonc++ supports the union approach (and the unrestricted unions with C++0x) for various (e.g., backward compatibility) reasons. **Bison** and **bison++** both support the %union directive.

An alternative to using a union is using a polymorphic base class. Such a class is developed below (the class Base). As it is a polymorphic base class it has the following characteristics:

- Its destructor is virtual (and has a default implementation);
- Objects of the derived classes may be obtained from a pure virtual ownClone member implementing a so-called *virtual constructor* (cf. the *virtual constructor* design pattern, *Gamma et al.* (1995));
- To obtain a clone of the current (derived class) object, the interface function clone must be called. It calls ownClone and forms a layer between the derived class implementations of ownClone and the user-software. Right now it only calls ownClone, but by not defining it as an inline function clone can easily be extended once that is required;
- Several convenient utility members are defined: a pure virtual insert member and an overloaded operator« to allow derived objects to be inserted into ostream objects.

Here is **Base**'s interface:

```
#ifndef INCLUDED_BASE_
#define INCLUDED_BASE_

#include <iosfwd>

class Base
{
    friend std::ostream &operator<<(std::ostream &out, Base const &obj);

public:
    virtual ~Base() = default;
    Base *clone() const;
private:
    virtual Base *ownClone() const = 0;
    virtual std::ostream &insert(std::ostream &os) const = 0;
};

inline std::ostream &operator<<(std::ostream &out, Base const &obj)
{
    return obj.insert(out);
}

#endif
```

Instead of using fields of a classical union we are now using classes that are derived from the class Base. For example:

- Objects of the class Int contain int values. Here is its interface (and implementation):

```
#ifndef INCLUDED_INT_
```

```

#define INCLUDED_INT_

#include <ostream>

#include <bobcat/a2x>

#include "../base/base.h"

class Int: public Base
{
    int d_value;

    public:
        Int(char const *text);
        Int(int v);
        int value() const;           // directly access the value
    private:
        virtual Base *ownClone() const;
        virtual std::ostream &insert(std::ostream &os) const;
};

inline Int::Int(char const *txt)
:
    d_value(FBB::A2x(txt))
{}

inline Int::Int(int v)
:
    d_value(v)
{}

inline Base *Int::ownClone() const
{
    return new Int(*this);
}

inline int Int::value() const
{
    return d_value;
}

inline std::ostream &Int::insert(std::ostream &out) const
{
    return out << d_value;
}

#endif

```

- Objects of the class `Text` contain text. These objects can be used, e.g., to store the names of identifiers recognized by a lexical scanner. Here is the interface of the class `Text`:

```

#ifndef INCLUDED_TEXT_
#define INCLUDED_TEXT_

#include <string>
#include <ostream>

#include "../base/base.h"

```

```

class Text: public Base
{
    std::string d_text;

    public:
        Text(char const *id);
        std::string const &id() const;           // directly access the name.
    private:
        virtual Base *ownClone() const;
        virtual std::ostream &insert(std::ostream &os) const;
};

inline Text::Text(char const *id)
:
    d_text(id)
{}

inline Base *Text::ownClone() const
{
    return new Text(*this);
}

inline std::string const &Text::id() const
{
    return d_text;
}

inline std::ostream &Text::insert(std::ostream &out) const
{
    return out << d_text;
}

#endif

```

The polymorphic Base can't immediately be used as the parser's semantic value type for various reasons:

- A Base class object cannot contain derived class's data members, so plain Base class objects cannot be used to store the parser's semantic values.
- It's not possible to define a Base class reference as a semantic value either as containers cannot store references.
- Finally, the semantic value should not be a pointer to a Base class object. Although a pointer would offer programmers the benefits of the polymorphic nature of the Base class, it would also require them to keep track of all memory used by Base objects, thus countering many of the benefits of using a polymorphic base class.

To solve the above problems, a *wrapper class* Semantic around a Base pointer is used. To simplify memory bookkeeping Semantic itself is defined as a class derived from `std::shared_ptr` (cf. section 18.4). This allows us to benefit from default implementations of the copy constructor, the overloaded assignment operator, and the destructor. Semantic itself offers an overloaded insertion operator allowing us to insert the object that is controlled by the Semantic object and derived from Base into an ostream. Here is Semantic's interface:

```

#ifndef INCLUDED_SEMANTIC_
#define INCLUDED_SEMANTIC_

#include <memory>

```

```

#include <ostream>

#include "../base/base.h"

class Semantic: public std::shared_ptr<Base>
{
    friend std::ostream &operator<<(std::ostream &out, Semantic const &obj);

    public:
        Semantic(Base *bp = 0);                // Semantic owns the bp
        ~Semantic() = default;

};

inline Semantic::Semantic(Base *bp)
:
    std::shared_ptr<Base>(bp)
{}

inline std::ostream &operator<<(std::ostream &out, Semantic const &obj)
{
    if (obj)
        return out << *obj;

    return out << "<UNDEFINED>";
}

#endif

```

23.8.3.1 The parser using a polymorphic semantic value type

In Bisonc++'s grammar specification %stype is of course `Semantic`. A simple grammar is defined for this illustrative example. The grammar expects input according to the following rule:

```

rule:
    IDENTIFIER '(' IDENTIFIER ')' ';'
|
    IDENTIFIER '=' INT ';'
;

```

The rule's actions simply echo the received identifiers and int values to `cout`. Here is an example of a decorated production rule, where due to `Semantic`'s overloaded insertion operator the insertion of the object controlled by `Semantic` is automatically performed:

```

IDENTIFIER '=' INT ';'
{
    cout << $1 << " " << $3 << '\n';
}

```

Bisonc++'s parser stores *all* semantic values on its semantic values stack (irrespective of the number of tokens that were defined in a particular production rule). At any time *all* semantic values associated with previously recognized tokens are available in an action block. Once the semantic value stack is reduced, the `Semantic` class's destructor takes care of the proper destruction of the objects controlled by its `shared_ptr` base class.

The scanner must of course be allowed to access the parser's data member representing the most recent semantic value. This data member is available as the parser's data member `d_val__`, whose address

or reference can be passed to the scanner when it is constructed. E.g., with a scanner expecting an `STYPE__` & the parser's constructor could simply be implemented as:

```
inline Parser::Parser()
:
    d_scanner(d_val__)
{ }
```

23.8.3.2 The scanner using a polymorphic semantic value type

The scanner for our polymorphic parser is simple and only needs to recognize numbers, identifiers and some simple characters, returned as character tokens. The scanner must also have access to the parser's `d_val__` data member. Therefore the Scanner class defines a `Semantic *d_semval` member, initialized to the parser's `Semantic d_val__` data member that is made available to the Scanner's constructor:

```
inline Scanner::Scanner(Parser::STYPE__ *semval)
:
    // or: Semantic *semval
    d_semval(semval)
{ }
```

The scanner (generated by `flex`) recognizes input patterns, returns Parser tokens (e.g., `Parser::INT`), and returns a semantic value when applicable. E.g., when recognizing a `Parser::INT` the rule is:

```
{
    d_semval->reset(new Int(yytext));
    return Parser::INT;
}
```

IDENTIFIER's semantic value is obtained analogously:

```
[a-zA-Z_][a-zA-Z0-9_]* {
    d_semval->reset(new Text(yytext));
    return Parser::IDENTIFIER;
}
```

Index

!=, 236
'0', 59
-std=c++0x, 9, 10
->, 338
->*, 338
.*, 338
..., 529
.h, 19
.ih extension, 133
.template, 577
//, 13
::, 23, 214
::template, 576
<, 236
<=, 236
= 0, 297
= default, 120
= delete, 120
==, 236
>, 236
>=, 236
>>, 201
>>: with templates, 253
[begin, end), 239
[first, beyond), 239, 243, 252, 257, 263
[first, last), 395
[left, right), 363
#define __cplusplus, 17
#error, 499
#ifdef, 18
#ifndef, 18
#include, 6, 666
#include <condition_variable>, 388
%baseclass-header, 675
%baseclass-preinclude, 675
%class-header, 675
%class-name, 675
%debug, 675
%filenames, 675
%implementation-header, 675
%left, 677
%name, 675
%nonassoc, 677
%option 8bit, 667
%option c++, 664, 667
%option debug, 667, 673
%option noyywrap, 667
%option outfile, 667
%option warn, 667
%option yyclass, 667

%option yylineno, 667
%parsefun-source, 676
%prec, 677
%right, 677
%scanner, 676
%stype, 676
%token, 677
%type, 677
%union, 675, 676
&, 35
__cplusplus, 17, 18
__gnu_cxx, 6
\u, 44
[=], 389
[&], 389
0-pointer, 138
0x30, 59

A2x, 656
abort exception, 190
abs, 272
absolute position, 314
abstract base class, 327, 634
abstract classes, 297
access, 43
access files, 87, 93
access promotion, 287
access rights, 108
accessor, 108, 110
accessor member function, 201
accumulate, 396
actions, 673
adaptor: inserter, 365
adaptor: object to iterator, 362
adaptor: required typedefs, 366
add_lvalue_reference, 596
add_rvalue_reference, 596
addExceptFd, 645
addReadFd, 645
address of objects, 154
address-of operator, 35
addWriteFd, 645
adjacent_difference, 397
adjacent_find, 398
adjustfield, 81
Aho, A.V., 241
Alexandrescu, A., 501, 571, 577, 602, 610, 611
Alexandrescu, H., 599
algorithm: header file, 395
allocate arrays, 139

- allocate memory, 215
- allocate objects, 138
- allocate primitive types, 138
- allocator class, 353
- ambiguity, 300, 301
- amd, 44
- and, 226
- and_eq, 226
- angle bracket notation, 237, 238, 353
- angle brackets, 493
- angle brackets: consecutive, 253
- anonymous, 357, 367
- anonymous function, 388
- anonymous object, 123, 223
- anonymous object: lifetime, 124
- anonymous pair, 237
- anonymous variable, 35
- anonymous variable: generic form, 237
- ANSI/ISO, 6, 8, 13, 17, 42, 49, 72, 75, 78
- app, 88, 99
- append, 64
- arg, 272
- argument_type, 591
- arithmetic function object, 355
- arithmetic operations, 355, 655
- array bounds, 239
- array bounds overflow, 197
- array-to-pointer transformation, 478
- array: 0-sized, 139
- array: dynamic, 139
- array: enlarge, 139
- array: fixed size, 139, 140
- array: local, 139
- ASCII, 85, 86, 91, 249
- ascii to anything, 656
- ascii-value, 630
- ASCII-Z, 59, 65, 86, 92, 103, 598
- ASCII-Z string, 59
- assembly language, 11
- assign, 64
- assignment, 287
- assignment: pointer to members, 337
- assignment: refused, 288
- assignment: sequential, 154
- associative array, 252, 260, 268
- asynchronous alarm, 643
- asynchronous input, 642
- at, 64
- ate, 88, 100
- atoi, 95, 656
- atol, 656
- auto, 40
- auto_ptr, 374
- auto_ptr: deprecated, 370
- automatic expansion, 239
- available member functions, 288
- avoid global variables, 20
- back, 239, 243, 247, 251
- back_inserter, 365
- backdoors, 110
- background process, 638
- bad, 76
- bad_alloc, 148, 182, 184, 218
- bad_cast, 182, 308
- bad_exception, 180, 182
- bad_typeid, 182, 311
- badbit, 76
- base class, 273, 288, 625, 634
- base class destructor, 279
- base class initializer, 277
- base class initializers: calling order, 284
- base class: converting to derived class, 306
- base class: hiding members, 281
- base class: prototype, 312
- base class: virtual, 301
- bash, 97
- BASIC, 11
- basic guarantee, 184
- basic operators of containers, 236
- basic_, 71
- basic_ios.h, 75
- beg, 86, 93, 319
- begin, 119, 239, 243, 251, 255, 263, 363
- bernoulli_distribution, 392
- bidirectional_iterator_tag, 562
- BidirectionalIterator, 365, 562
- binary, 89, 100
- binary file, 86, 91, 100, 101
- binary function object, 360
- binary input, 91
- binary operator, 655
- binary output, 81, 85
- binary predicate, 361
- binary tree, 463
- binary_function, 655
- binary_search, 399
- bind1st, 360
- bind2nd, 360
- binder, 360
- binomial_distribution<IntType = int, RealType = double>, 392
- Bison, 683
- bison, 664, 674
- bison++, 664, 674, 683
- bisonc++, 664, 674
- bisonc++: grammar file, 674
- bitand, 226
- bitfunctional, 655
- bitor, 226
- bits/stl_function.h, 655
- bitwise, 655
- bitwise and, 78, 655
- bitwise operations, 655
- Bobcat library, 270, 619, 623
- bool, 41, 256, 263
- boolalpha, 82
- bound friend, 542, 545, 560

- bridge design pattern, 312
- buffer, 314
- buffer overflow, 30
- built-in, 41
- C++0x, 118, 253, 268, 270, 474
- C++0x standard, 9
- C++: function prevalence rule, 473
- c_str, 65
- call back, 232
- call_once, 386
- calling order of base class initializers, 284
- calloc, 137
- candidate functions, 494
- capacity, 65, 239
- case-insensitive, 60
- catch, 166, 175
- catch: empty enum, 351
- ccbuild, 10
- cerr, 26, 85, 97
- chain of command, 313
- char, 71
- char *, 201
- child process, 634, 635
- cin, 26, 74, 91, 97
- circular queue, 502
- class, 13, 27, 49, 351, 471, 587
- class hierarchy, 273, 295
- class interface, 543
- class name, 309
- class scope, 336
- class template, 479, 501, 502, 655
- class template: adding functionality, 551
- class template: as base class, 589
- class template: conditional data organization, 581
- class template: declaration, 509, 540
- class template: deducing parameters, 540
- class template: default argument, 509
- class template: default arguments, 508
- class template: defining a type, 578
- class template: derivation, 550
- class template: derived from ordinary class, 555
- class template: friend function template, 499
- class template: generate types, 501
- class template: identifying subtypes, 516
- class template: instantiation, 540
- class template: member instantiation, 540
- class template: member template, 513
- class template: nested, 560
- class template: non-type parameter, 511
- class template: partial specialization, 522, 524
- class template: partially compiled, 550
- class template: pointer to, 540
- class template: reference to, 540
- class template: shadowing parameters, 514
- class template: static members, 515
- class template: subtype vs. static members, 573
- class template: transformation to a base class, 480
- class template: using friend, 542
- class template: values without objects, 579
- class template: wrapped in simpler template, 611
- class vs. typename, 471
- class-type parameters, 132
- class-type return values, 132
- class: abstract, 297
- class: concept defined, 331
- class: enforcing constraints, 585
- class: externally declared functions, 331
- class: having pointers, 380
- class: ordinary, 479
- class: policy, 585
- class: trait, 591
- classes: local, 128, 290
- classes: without data members, 298
- clear, 78, 239, 243, 251, 255, 263
- Cline, 25
- clog, 85
- clone, 683
- close, 87, 88, 94, 320
- closure, 389
- cmatch, 270
- code bloat, 589
- Coetmeur, A., 674
- collating order, 310
- collision, 268
- command language, 642
- common data fields, 227
- common pool, 138
- compare, 65
- compile-time, 16, 293, 295, 304, 469, 499
- compiler, 8, 9
- compiler firewal, 312
- compiler flag, 9
- compiler flag: -pthread, 382
- compiler option, 10
- compl, 226
- complex, 271
- complex container, 235
- complex numbers, 235, 271
- complex: header file, 271
- composition, 114, 132, 273, 283
- condition flags, 76
- condition member functions, 76
- condition state, 76
- condition variable, 382
- condition_variable, 382, 386–388
- conditional, 596
- conflict resolution, 682
- conj, 272
- consecutive closing angle brackets, 253
- const, 24, 479
- const data and containers, 236
- const function attribute, 14
- const functions, 25
- const member, 110
- const member functions, 120, 298
- const-qualification, 121
- const_cast<type>(expression), 46

- const_iterator, 363
- const_pointer_cast, 378
- constant expression, 472
- constexpr, 385
- construction: delegate to base classes, 278
- constructor, 223, 284, 353
- constructor: and exceptions, 190
- constructor: calling order, 279
- constructor: default, 109
- constructor: of derived classes, 277
- constructor: primitive type, 473
- container, 235
- container without angle brackets, 237
- container: nested, 253
- container: storing pointers, 236
- containers: basic operators, 236
- containers: data type requirements, 236
- containers: equality tests, 236
- containers: initialization, 238
- containers: ordering, 236
- container: storing const data, 236
- conversion operator, 202
- conversion operator: explicit, 206
- conversion rules, 42
- conversions, 512
- conversions: binary to text, 90
- conversions: text to binary, 95
- cooked literal, 538
- copy, 65, 400, 554
- copy construction, 120
- copy constructor, 124, 155, 250, 278
- copy elision, 162
- copy non-involved data, 241
- copy_backward, 401
- copyfmt, 79
- cos, 272
- cosh, 272
- count, 255, 260, 263, 264, 402
- count_if, 360, 402
- coupling, 13
- cout, 26, 74, 85, 97, 637
- cplusplus, 6
- create files, 87
- cref(arg), 476
- cstddef, 44
- cstdint, 44
- cstdio, 14
- cstdlib: header file, 541
- cur, 86, 93, 319
- Cygnus, 9
- Cygwin, 10

- daemon, 637, 638, 650, 652
- data, 65
- data hiding, 10, 13, 29, 108, 109, 229, 275, 315, 331
- data integrity, 331
- data member: initialization, 118
- data members, 108, 315, 585

- Data Structures and Algorithms, 241
- data.cc, 228
- database applications, 93
- deadlock, 384
- deallocate memory, 215
- Debian, 9
- dec, 81
- declaration section, 675
- declarative region, 49
- declare iostream classes, 71
- decltype, 40, 474
- decrement operator, 206
- default, 120
- default arguments, 15
- default constructor, 139, 155, 236, 277
- default implementation, 318
- default value, 240, 244, 252
- define members of namespaces, 57
- delete, 120, 137, 138, 214
- deleter, 370, 372, 375, 376
- delete[], 140, 146
- deletions, 241
- delimiter, 368
- deque, 251, 363
- deque constructors, 251
- deque: header file, 251
- derivation, 273
- derived class, 273, 288, 306
- derived class destructor, 279
- derived class vs. base class size, 289
- derived class: using declaration, 281
- design pattern, 297, 683
- design pattern: Prototype, 327
- design pattern: template method, 634
- Design Patterns, 634
- design patterns, 13, 634
- destructor, 108, 144, 296
- destructor: and exceptions, 195
- destructor: called at exit, 636
- destructor: calling order, 279
- destructor: derived class, 279
- destructor: empty, 297
- destructor: explicit call, 143, 145
- destructor: for policy classes, 589
- destructor: inline, 297
- destructor: main task, 144
- destructor: virtual, 296
- device, 74, 617
- direct base class, 276
- display field width, 80
- display floating point numbers, 80, 83
- divides, 357
- domain_error, 182
- DOS, 100
- double free, 378
- double initialization, 289
- doubly ended queue, 251
- down-casting, 306
- dup, 637

- dup2, 637, 640
- dynamic arrays, 139
- dynamic binding, 295
- dynamic cast, 306
- dynamic cast: prerequisite, 306
- dynamic growth, 241
- dynamic polymorphism, 501, 589
- dynamic_cast, 309
- dynamic_cast<>, 306
- dynamic_pointer_cast, 378
- dynamically allocated variables, 512
- E, 42
- early binding, 293, 295
- eback, 315, 621, 623, 628
- ECHO, 668
- efficiency, 268
- egptr, 315, 621, 623, 628
- ellipsis, 203, 529, 594, 599
- empty, 65, 239, 243, 248, 250, 251, 255, 263, 267
- empty deque, 252
- empty destructor, 297
- empty enum, 351
- empty function throw list, 179
- empty list, 244
- empty parameter list, 17
- empty struct, 598
- empty vector, 240
- enable_if, 596
- encapsulation, 13, 30, 110, 275, 331
- end, 86, 119, 239, 243, 251, 255, 263, 319, 363
- end of line comment, 13
- end-of-stream, 367
- endian, 86
- endl, 27, 83
- ends, 84
- enum, 21
- enum class, 38
- enum values: and arithmetic operators, 224
- enum values: evaluated compile-time, 595
- enumeration: nested, 349, 561
- environ, 13
- eof, 76
- eofbit, 76
- epptr, 619
- equal, 403
- equal_range, 255, 260, 263, 264, 404
- equal_to, 358
- equality operator, 236
- erase, 66, 239, 243, 251, 255, 260, 263, 264
- error, 674
- error code, 165
- escape sequence, 38
- exceptFd, 645
- exception, 78, 307
- exception class, 181, 182
- exception guarantees, 184
- exception handler: order, 176
- exception neutral, 186
- exception safe, 183
- exception specification list, 179
- exception: and constructors, 190
- exception: and destructors, 195
- exception: and new, 185
- exception: and new[], 218
- exception: bad_alloc, 148
- exception: replace, 190
- exception: standard, 182
- Exceptional C++, 185
- exceptions, 165
- exceptions (function), 181
- exec..., 636
- exercise, 671
- exit, 165, 171, 636, 638
- exit status, 635
- exit: avoid, 144
- exit: calling destructors, 636
- exp, 272
- expandable array, 238
- expected constructor, destructor, or type conversion, 572
- explicit, 205
- explicit instantiation declaration, 483
- explicit template type arguments, 486
- explicit type specification, 477
- explicit: conversion operator, 206
- exponential_distribution<Type = double>, 393
- exponentiation, 42
- export, 48
- expression: actual type, 306
- expression: type of, 310
- extendable array, 235
- extensible literals, 538
- extern, 9, 540
- extern C | hyperpage, 18
- extern template, 509, 510
- extracting strings, 91
- extraction operator, 26, 27, 72, 90, 91
- F, 42
- factory functions, 161
- fail, 77, 86, 93
- failbit, 76
- failure class, 181
- false, 42, 420, 429, 666
- field ‘...’ has incomplete type, 545
- field selector, 338
- field width, 221
- FIFO, 235, 247
- FILE, 71
- file descriptor, 87, 97, 625, 627
- file descriptors, 74, 617, 639
- file flags, 88
- file is rewritten, 89
- file modes, 88
- file rewriting: preventing, 88
- file: binary mode, 89
- file: copying, 95

- filebuf, 72, 74, 319
- fill, 79, 406
- fill characters, 81
- fill_n, 406
- FILO, 235, 266
- find, 66, 256, 260, 263, 264, 407
- find_end, 407
- find_first_of, 66, 409
- find_if, 410
- find_last_not_of, 67
- find_last_of, 66
- first, 237
- first in, first out, 235, 247
- first in, last out, 235, 266
- first_argument_type, 591
- Fistream, 630
- fixed, 83
- flags, 79
- flags: of ios objects, 78
- flex, 664, 665, 668, 673, 674, 682, 687
- flex yylineno, 668
- flex: %option yylineno, 668
- flex: debugging code, 667
- flex: set_debug, 667, 673
- flex: yyleng, 668
- flex: yytext, 668
- FlexLexer.h, 666, 669
- floatfield, 83
- flow-breaking methods, 165
- flush, 84, 87
- fopen, 85, 91
- for-statement, 41
- for_each, 411, 652
- for_each: vs. transform, 460
- fork, 634, 635, 638
- formal type, 471, 503
- formal types, 469
- formatted input, 91
- formatted output, 81, 85
- formatting, 75, 79
- formatting commands, 72
- formatting flags, 79, 81
- forward, 531
- forward class reference, 131
- forward declaration, 347, 348
- forward declaration: enum class, 38
- forward declarations, 71, 132
- forward iterators, 62
- forward: parameters, 533
- forward_iterator_tag, 562
- ForwardIterator, 365
- fprintf, 72
- free, 137, 142, 146
- free compiler, 9
- free function, 200
- Free Software Foundation, 9
- Friedl, J.E.F, 270
- friend, 331, 542, 543
- friend: bound, 542, 545
- friend: function declaration, 332
- friend: in class templates, 542
- friend: nested classes, 346
- friend: unbound, 548
- friend: using a template parameter, 661
- friendship among classes, 331
- front, 239, 243, 248, 252
- front_inserter, 365
- FSF, 9
- fstream, 87, 93, 99
- fstream: header file, 74, 319
- ftp://research.att.com/dist/c++std/WP/, 7
- ftp://prep.ai.mit.edu/pub/non-gnu, 664
- fully qualified name, 55, 474
- fully qualified name: nested class members, 345
- function adaptor, 360
- function adaptors, 354
- function call operator, 219, 268
- function object, 219, 268
- function object: arithmetic, 355
- function object: logical, 359
- function object: relational, 358
- function overloading, 15, 121
- function prevalence rule, 473
- function selection, 493
- function template, 469
- function template: overloading, 487
- function template: specialization vs. overloading, 493
- function templates: multiply included, 482
- function templates: specialized type parameters, 490
- function throw list, 179, 182
- function try block, 189
- function-to-pointer transformation, 478
- function: anonymous, 388
- function: free, 210
- functional: header file, 353, 475, 535
- functionality, 238
- functions as members of structs, 21
- functions having identical names, 14, 22
- functions: candidate, 494
- functions: viable, 494
- g++, 8, 9, 673
- Gamma, E., 297, 327, 634, 659, 683
- gamma_distribution<Type = double>, 393
- gbump, 315, 624
- gcount, 91
- generalized pair, 238, 537
- generate, 413
- generate_n, 414
- generator: random number, 391
- generic algorithm: categories, 396
- generic algorithms, 236, 395
- generic algorithms: required types, 591
- generic data type, 395
- generic software, 71
- generic type, 237

- geometric_distribution<IntType = int, RealType = double>, 393
- get, 92, 371, 373, 376, 377, 537
- get_deleter, 373, 377
- getline, 67, 76, 92
- global try block, 166
- global function, 231
- global namespace, 48
- global scope, 336
- global variable, 512
- global variables, 227
- global variables: avoid, 20
- Gnu, 8, 9, 149, 209, 349, 673
- good, 77
- goodbit, 76
- goto, 165
- gptr, 315, 621, 623, 628
- grammar, 617, 673
- grammar specification file, 674
- grammatical rules, 675
- Graphical User Interface Toolkit, 108
- greater, 358
- greater_equal, 358
- has_nothrow_assign, 596
- has_nothrow_copy_constructor, 596
- has_nothrow_default_constructor, 596
- has_nothrow_destructor, 596
- has_trivial_assign, 596
- has_trivial_copy_constructor, 596
- has_trivial_default_constructor, 596
- has_trivial_destructor, 596
- hash function, 268
- hash function: predefined, 268
- hash value, 268
- hashing, 268
- header file, 49, 74, 130, 133
- header section, 675
- heap, 463
- hex, 81
- hidden data member, 323
- hiding: base class members, 281
- hierarchic sort, 553
- hierarchy of code, 273
- Hopcroft J.E., 241
- <http://bisoncpp.sourceforge.net/>, 682
- <http://bobcat.sourceforge.net/>, 270, 619, 623
- <http://bobcat.sourceforge.net/>, 682
- <http://en.wikipedia.org/wiki/C++0x>, 4
- <http://gcc.gnu.org>, 10
- <http://oreilly.com/catalog/>, 382
- http://publications.gbdirect.co.uk/c_book/, 3
- <http://sourceforge.net/projects/cppannotations/>, i
- <http://sources.redhat.com>, 9
- <http://www.cplusplus.com/ref>, 8
- <http://www.csci.csusb.edu/dick/c++std>, 8
- <http://www.debian.org>, 9
- <http://www.gnu.org>, 6, 9
- <http://www.gnu.org/licenses/>, 3
- <http://www.linux.org>, 9
- <http://www.oreilly.com/catalog/lex>, 664
- <http://www.research.att.com/...>, 25
- <http://www.sgi.com/.../STL>, 236
- <http://www.trolltech.com>, 108
- <http://www.parashift.com/c++-faq-lite/>, 25
- <http://yodl.sourceforge.net>, 3
- human-readable, 81
- hyperlinks, 8
- I/O, 71
- I/O library, 71
- I/O multiplexing, 643
- icmake, 10
- identically named member functions, 284
- identifiers starting with an underscore, 48
- IFdNStreambuf, 622
- IFdSeek, 625
- IFdStreambuf, 621, 650
- ifstream, 91, 93, 104
- ifstream constructors, 94
- ignore, 92
- imag, 272
- imaginary part, 271, 272
- implementation, 107
- implementation dependent, 331
- implemented-in-terms-of, 293
- implicit conversion, 288
- in, 88, 89, 99
- in_avail, 313
- INCLUDE, 130, 133
- include guard, 18
- includes, 415
- increment operator, 206
- index operator, 197, 239, 251, 255, 260
- indirect base class, 276
- inequality operator, 236
- inheritance, 128, 273, 275
- inheritance: access to base class member, 287
- inheritance: multiple, 283
- inheritance: no derived class constructors, 278
- inheritance: private derivation, 552
- init, 637, 638
- initialization, 118, 138, 155, 238
- initialization: static data member, 228
- initializer list, 39, 118
- initializer lists, 238
- initializer_list, 119
- initializer_list<Type>, 39
- inline, 125–127, 221, 297, 354
- inline function, 127
- inline member functions, 345
- inline: disadvantage, 127
- inline: static members, 231
- inner types, 585
- inner_product, 416
- inplace_merge, 418
- input, 90, 97
- input language, 673

- input_iterator_tag, 562
- InputIterator, 364, 562
- InputIterator1, 364
- InputIterator2, 364
- insert, 67, 239, 243, 252, 256, 260, 263, 264, 366
- inserter, 365, 366
- inserter: and non-STL classes, 366
- inserter: required typedefs, 366
- inserting streambuf *, 96
- insertion operator, 26, 72, 84, 85, 200
- insertions, 241
- instantiation, 469, 471
- instantiation declaration, 483
- instantiation function, 510
- instantiation source, 510
- int32_t, 44
- integral conversions, 512
- interface, 107, 297
- interface functions, 109
- internal, 81
- internal buffer, 87
- internal header, 133
- internal header file, 636
- Internet, 8
- invalid_argument, 182
- iomanip, 79
- iomanip: header file, 74
- ios, 72, 75, 97, 349, 483, 625
- ios object: as bool value, 78
- ios: header file, 625
- ios::exceptions, 181
- ios::fail, 88, 94
- ios_base, 72, 74, 75
- ios_base.h, 75
- iosfwd, 59, 71, 74
- iostate, 181
- iostream, 19, 26, 85, 87, 91, 93
- iostream.h, 19
- iostream: header file, 74
- is-a, 293, 311, 312
- is-implemented-in-terms-of, 311
- is_base_of, 596
- is_convertible, 596
- is_lvalue_reference, 596
- is_open, 88, 94, 319
- is_pod, 596
- is_reference, 596
- is_rvalue_reference, 596
- is_signed, 596
- is_unsigned, 596
- istream, 72, 90, 91, 104
- istream constructor, 91
- istream: header file, 74
- istream: iterator, 366
- istream_iterator, 366
- istreambuf_iterator, 367, 368
- istringstream, 72, 91, 95, 630, 656
- iter_swap, 419
- iterator, 40, 239, 243, 251, 263, 343, 362, 363, 562
- iterator range, 239, 243, 252, 257, 263
- iterator: and generic algorithms, 562
- iterator: as class template, 661
- iterator: class type, 562
- iterator: common characteristics, 562
- iterator: data type, 562
- iterator: header file, 362, 562
- iterator: range, 363
- iterator: requirements, 364
- iterator: to const elements, 363
- iterator: types, 364
- iterator_tag, 562
- iterators, 236, 237, 239

- Java, 306
- Java interface, 297
- jmp_buf, 168
- Josutis, N., 571

- key, 253
- key type, 268
- key/value, 252
- keywords, 47
- kludge, 207
- Koenig lookup, 52

- L, 42
- lake, 10
- Lakos, J., 108, 133
- lambda function, 388, 413
- late binding, 293
- late bining, 295
- late-specified return type, 41, 389, 474
- left, 81
- left-hand, 236
- leftover, 438, 460
- length, 67
- length_error, 68, 182
- less, 358
- less-than operator, 236
- less_equal, 358
- letter (US paper size), 6
- letters in literal constants, 42
- Lewis, P.A.W., 392
- lex, 664, 674
- lexical scanner specification file, 666
- lexicographical_compare, 420
- libfl.a, 673
- library, 133
- lifetime: anonymous objects, 124
- LIFO, 235, 266
- linear search, 219
- linear chaining, 268
- linear search, 221
- linear_congruential, 391
- lineno, 667, 668
- linker: removing identical template instantiations, 485
- Linux, 9
- Liskov Substitution Principle, 293, 311

- Lisp, 11
- list, 235, 240
- list constructors, 242
- list container, 240
- list: circular, 241
- list: header file, 240
- list: traversal, 240
- literal constants, 42
- literal float using F, 42
- literal floating point value using E, 42
- literal long int using L, 42
- literal unsigned using U, 42
- literal wchar_t string L, 42
- local arrays, 139
- local class, 128, 290
- local context, 382, 389
- local variables, 19, 512
- lock, 384
- lock_guard, 384
- log, 272
- logic_error, 182
- logical function object, 359
- logical operations, 655
- logical operators, 359
- logical_and, 359
- logical_not, 359
- logical_or, 359
- long double, 42
- long long, 42
- long long int, 44
- longjmp, 165, 167, 168
- lower_bound, 257, 263, 422
- lsearch, 219
- lseek, 625
- LSP, 293, 311
- Ludlum, 52
- lvalue, 35, 197, 207, 365, 373
- lvalue reference, 35
- lvalue transformations, 478, 512
- lvalue-to-rvalue transformation, 478
- lvalue: distinguish from rvalue, 658

- macro, 16, 222, 223
- main, 13, 14
- make, 10
- make_heap, 464
- make_signed, 597
- make_unsigned, 597
- malloc, 137, 138, 142, 146, 149
- manipulator, 221
- manipulator: as objects, 222
- manipulators, 72, 108
- map, 235, 252
- map constructors, 253
- map: header file, 252, 260
- Marshall Cline, 25
- mathematical functions, 272
- max, 392, 423
- max-heap, 396, 464
- max_element, 424
- max_size, 67, 236
- member function, 59, 373, 377
- member function: called explicitly, 281
- member function: pure virtual implementation, 298
- member functions, 28, 243, 247, 250, 315, 585
- member functions: available, 288
- member functions: identically named, 284
- member functions: overloading, 15
- member initializer, 115
- member template, 513
- member: class as member, 343
- member: const, 110
- members: in-class, 126
- members: overriding, 296
- memcpy, 187
- memory allocation, 137
- memory buffers, 72
- memory consumption, 323
- memory leak, 138, 140, 147, 173, 176, 236, 296, 369, 380
- memory leaks, 137
- memory: header file, 142, 369, 375
- memory: initialization, 139
- merge, 243, 424
- merging, 396
- min, 392, 426
- min_element, 427
- mini scanner, 666, 667
- minus, 357
- mixing C and C++ I/O, 72
- modifier, 200
- modulus, 357
- move, 160, 373, 375
- move constructor, 159, 278
- move semantics, 36, 158, 374
- move-aware, 37, 159, 211
- MS-WINDOWS, 100
- MS-Windows, 9, 89
- mt19937, 392
- Multi, 610
- multi threading, 382
- multi threading: -pthread, 382
- multimap, 260
- multimap: no operator[], 260
- multiple inheritance, 283
- multiple inheritance: vtable, 324
- multiplexing, 643
- multiplies, 357
- multiset, 264
- multiset::iterator, 264
- mutable, 129
- mutex, 291, 382, 384
- mutex: header file, 384

- name conflicts, 23
- name lookup, 19
- name mangling, 15
- name: fully qualified, 474

- namespace, [23](#), [133](#)
- namespace alias, [56](#)
- namespace declarations, [50](#)
- namespace: anonymous, [50](#)
- namespace: closed, [50](#)
- namespace: import all names, [51](#)
- namespaces, [49](#)
- negate, [357](#)
- negator function, [361](#)
- negators, [361](#)
- nested blocks, [20](#)
- nested class, [343](#)
- nested class: declaration, [345](#)
- nested class: member access, [347](#)
- nested class: static members, [345](#)
- nested container, [253](#)
- nested derivation, [276](#)
- nested enumerations, [349](#)
- nested functions, [128](#)
- nested inheritance, [300](#)
- nested trait class, [592](#)
- nesting depth, [665](#)
- new, [137](#), [138](#), [212](#)
- new Type[0], [139](#)
- new-style casts, [44](#)
- new: and exceptions, [185](#)
- new: placement, [142](#), [213](#)
- new[], [139](#), [140](#), [212](#)
- new[]: and exceptions, [218](#)
- new[]: and non-default constructors, [289](#)
- next_permutation, [429](#)
- Nichols, B, [382](#)
- nm, [540](#)
- no arguments depending on a template parameter, [573](#)
- noAlarm, [645](#)
- noboolalpha, [82](#)
- non-constant member functions, [298](#)
- non-local return, [165](#)
- non-mutating operation, [162](#)
- norm, [272](#)
- normal_distribution<Type = double>, [393](#)
- noshowbase, [82](#)
- noshowpoint, [83](#)
- noshowpos, [82](#)
- noskipws, [84](#)
- not, [226](#)
- not1, [361](#)
- not2, [361](#)
- not_eq, [226](#)
- not_equal_to, [358](#)
- notation, [239](#)
- nothrow guarantee, [187](#)
- notify_all, [387](#)
- notify_one, [387](#)
- nounitbuf, [84](#)
- nouppercase, [82](#)
- npos, [60](#)
- nReady, [644](#)
- nth_element, [430](#)
- NULL, [16](#), [17](#), [137](#)
- null-bytes, [86](#)
- nullptr, [17](#), [48](#)
- NullType, [598](#)
- numeric: header file, [395](#)
- Numerical Recipes in C, [436](#)
- object, [21](#)
- object hierarchy, [273](#)
- object oriented approach, [12](#)
- object: address, [154](#)
- object: allocation, [138](#)
- object: anonymous, [123](#)
- object: assign, [151](#)
- object: parameter, [156](#)
- object: static/global, [109](#)
- obsolete binding, [19](#)
- oct, [82](#)
- off_type, [86](#), [93](#)
- ofstream, [85](#), [87](#), [104](#)
- ofstream constructors, [87](#)
- once_flag, [386](#)
- one definition rule, [107](#), [482](#)
- open, [87](#), [94](#), [319](#), [619](#)
- openmode, [88](#), [319](#)
- operator, [153](#)
- operator &, [31](#), [35](#)
- operator and, [226](#)
- operator and_eq, [226](#)
- operator bitand, [226](#)
- operator bitor, [226](#)
- operator bool, [373](#), [377](#)
- operator compl, [226](#)
- operator delete, [142](#), [214](#)
- operator delete[], [216](#)
- operator keywords, [48](#)
- operator new, [141](#), [182](#), [212](#)
- operator new(sizeInBytes), [139](#)
- operator new[], [215](#)
- operator not, [226](#)
- operator not_eq, [226](#)
- operator or, [226](#)
- operator or_eq, [226](#)
- operator overloading, [152](#), [197](#)
- operator overloading: within classes only, [226](#)
- operator xor, [226](#)
- operator xor_eq, [226](#)
- operator!=, [220](#), [358](#)
- operator(), [219](#), [221](#), [268](#), [436](#)
- operator*, [272](#), [357](#), [364](#), [373](#), [377](#)
- operator*=, [272](#)
- operator+, [208](#), [272](#), [356](#), [357](#), [396](#)
- operator++, [206](#), [364](#)
- operator+=, [272](#)
- operator-, [272](#), [357](#)
- operator-, [206](#)
- operator=, [272](#)
- operator->, [373](#), [377](#)

- operator/, 272, 357
- operator/=: 272
- operator: free, 210
- operator<, 253, 268, 358, 424, 425, 429, 431, 432, 435, 449–453, 455, 462, 464, 465
- operator<<, 272
- operator<=: 358
- operator=: 373, 377
- operator==, 268, 358, 364, 447, 448, 460, 461
- operator>, 358
- operator>=: 358
- operator>>, 91, 201, 272
- operator%, 357
- operator&, 655
- operator&&, 359
- operator~, 655
- operator||, 359
- operators: of containers, 236
- operators: textual alternatives, 226
- operator[], 197, 202, 585, 658
- options, 667
- or, 226
- or_eq, 226
- ordered pair, 272
- ordinary class, 469, 479
- ordinary function, 469
- ostream, 72, 74, 75, 84, 85, 104, 221, 223, 298
- ostream *yyout, 668
- ostream constructor, 85
- ostream coupling, 97
- ostream: define using 0-pointer, 85, 91
- ostream: header file, 74
- ostream: iterator, 368
- ostream_iterator, 368
- ostreambuf_iterator, 368
- ostreamstream, 72, 85, 89
- out, 89, 99
- out of memory, 149
- out_of_range, 182
- output, 97
- output formatting, 72, 74
- output_iterator_tag, 562
- OutputIterator, 365, 562
- overflow, 314, 317, 617, 619
- overflow_error, 182
- overloadable operators, 225
- overloaded assignment, 236
- overloading: by const attribute, 15
- overloading: function template, 487
- overriding members, 296
- overview of generic algorithms, 236
- p, 42
- padding, 79
- pair, 237, 254
- pair container, 235, 237
- pair<map::iterator, bool>, 256
- pair<set::iterator, bool>, 263
- pair<type1, type2>, 238
- parameter list, 14
- parameter pack, 529
- parameter pack: rvalue reference, 531
- parameter packs not expanded, 534
- parameter packs not expanded with ‘...’, 534
- parameter: ellipsis, 594
- parent process, 634, 635
- ParentSlurp, 641
- parse(), 664
- parse-tree, 617
- parser, 617, 664, 673
- parser generator, 664, 673
- partial class template specialization, 519
- partial specialization, 522
- partial_sort, 431
- partial_sort_copy, 432
- partial_sum, 433
- partition, 434
- Pascal, 128
- Pattern, 270
- pbackfail, 315
- pbase, 318, 619
- pbump, 318, 620
- pdf, i
- peculiar syntax, 221
- peek, 92
- penalty, 295
- perfect forwarding, 36, 482, 531
- perfect forwarding: inheritance, 533
- perfect forwarding: to data members, 538
- permuting, 396
- pimpl, 312
- pipe, 617, 639
- placement new, 142, 213, 216, 586
- plain old data, 163, 596
- plus, 355, 357
- pod, 163
- point of instantiation, 484, 498, 542
- pointer in disguise, 288
- pointer juggling, 590
- pointer protection, 41
- pointer to a function, 222
- pointer to an object, 288
- pointer to function, 232
- pointer to member field selector, 338
- pointer to members, 335, 594
- pointer to members: assignment, 337
- pointer to members: defining, 336
- pointer to members: size of, 341
- pointer to members: virtual members, 338
- pointer to objects, 515
- pointer: to a data member, 336
- pointer: to class template, 540
- pointer: to function, 219
- pointer: to policy base class, 589
- pointer: wild, 370, 380
- pointers to deleted memory, 150
- pointers to objects, 215
- pointers: as iterators, 364

- poisson_distribution<IntType = int, RealType = double>, 29, 229, 284
- 393
- polar, 272
- policy, 585, 587
- policy class: defining structure, 590
- polymorphism, 293, 320
- polymorphism: bypassing, 575
- polymorphism: dynamic, 501
- polymorphism: how, 322
- polymorphism: static, 501
- polymorphous wrapper, 391
- pop, 248, 250, 267
- pop_back, 240, 244, 252
- pop_front, 244, 252
- pop_heap, 464
- POSIX, 44
- postponing decisions, 165
- pow, 272
- power specification using p, 42
- pptr, 318, 619
- precision, 79
- precompiled header, 482
- predefined function object, 655
- predicate, 219
- predicate function, 361
- preprocessor, 222, 223
- preprocessor directive, 17, 666
- preprocessor directive: error vs. static_assert, 499
- Press, W.H., 436
- prev_permutation, 435
- primitive types, 42
- printf, 28, 86, 528
- printf(), 14
- priority queue data structure, 248
- priority rules, 248
- priority_queue, 248, 250
- private, 29, 560, 669
- private backdoor, 200
- private derivation, 284
- private derivation: too restrictive, 286
- private inheritance, 311
- private members, 543
- problem analysis, 273
- procbuf, 6
- procedural approach, 12
- process ID, 634
- process id, 634
- profiler, 127, 242
- Prolog, 11
- promotion, 205
- promotions, 512
- protected, 29, 621, 668
- protected derivation: too restrictive, 286
- protocol, 297
- Prototype design pattern, 327
- prototyping, 9
- Proxy Design Pattern, 659
- Proxy: stream insertion and extraction, 659
- Pthreads Programming, 382
- public, 29, 229, 284
- pubseekoff, 314, 319
- pubseekpos, 314
- pubsetbuf, 314
- pubsync, 314
- pure virtual functions, 297
- pure virtual member: implementation, 298
- push, 248, 250, 267
- push_back, 240, 244, 252, 365
- push_front, 244, 252, 365
- push_heap, 465
- put, 86
- putback, 92, 627
- qsort, 541
- qsort(), 232
- Qt, 108
- qualification conversions, 512
- qualification transformation, 479
- queue, 235, 247
- queue data structure, 247
- queue: header file, 247, 248
- radix, 79
- rand, 391
- random, 241
- random access, 365
- random number generator, 436
- random: header file, 392
- random_access_iterator_tag, 562
- random_shuffle, 436
- RandomAccessIterator, 365, 562, 564
- RandomIterator, 661
- range, 41
- range of values, 239
- range_error, 183
- raw literal, 538
- raw memory, 139, 141
- raw string literal, 38
- rbegin, 240, 244, 252, 257, 263, 363, 568
- rdbuf, 75, 97, 637
- rdstate, 78
- read, 93
- read first, test later, 96
- readFd, 644
- reading and writing, 72
- readsome, 93
- real, 272
- real part, 271, 272
- realloc, 149
- recompilation, 276
- recursive_mutex, 384
- recursive_timed_mutex, 384
- redirection, 97, 637
- reduce-reduce, 682
- ref(arg), 476
- reference, 221, 288
- reference operator, 31
- reference parameter, 116

- reference wrapper, 476
- reference: to class template, 540
- references, 31
- regcomp, 270
- regex, 270
- regex: header file, 270
- regex_replace, 270
- regex_search, 270
- regexexec, 270
- regular expression, 665, 668
- regular expressions, 270
- reinterpret_cast, 289, 577
- reinterpret_cast<type>(expression), 46
- reinterpret_to_smaller_cast, 577
- relational function object, 358
- relational operations, 655
- relationship between code and data, 273
- relative address, 337
- release, 373
- remove, 244, 438
- remove_copy, 438
- remove_copy_if, 439
- remove_if, 440
- remove_reference, 596
- rend, 240, 245, 252, 257, 263, 363, 568
- renew, 139, 140
- replace, 67, 441
- replace_copy, 442
- replace_copy_if, 443
- replace_if, 443
- repositioning, 86, 93
- reserve, 68, 240
- reserved identifiers, 48
- reset, 374, 377
- resetiosflags, 80
- resize, 68, 240, 244, 252
- resource: stealing, 159
- responsibility of the programmer, 239, 243, 247, 251, 267, 374
- restrictions, 11
- result_of, 535
- result_type, 591
- return, 165
- return by argument, 33
- return type: late-specified, 389
- return value, 14, 221
- return value optimization, 162
- reusable software, 297, 313
- reverse, 245, 444
- reverse iterator, 567
- Reverse Polish Notation, 266
- reverse_copy, 444
- reverse_iterator, 240, 244, 252, 257, 263, 567
- reverse_iterator: initialized by iterator, 568
- reversed_iterator, 362
- rfind, 68
- right, 81
- right-hand, 236, 237
- rmExceptFd, 645
- rmReadFd, 645
- rmWriteFd, 645
- rotate, 445
- rotate_copy, 446
- RPN, 266
- rule of thumb, 14, 19, 25, 47, 55, 116, 127, 129, 134, 140, 185, 187, 203, 206, 215, 241, 275, 276, 297, 337, 381, 472, 490, 498, 509, 525
- run-time, 293, 306, 499
- run-time error, 179
- run-time support system, 149
- run-time vs. compile-time, 578
- runtime_error, 183
- rvalue, 35, 197, 207, 364, 373
- rvalue reference, 35, 159
- rvalue: distinguish from lvalue, 658
- sbumpc, 313, 623
- scalar numeric types, 268
- scalar type, 271
- scan-buffer, 671
- scanf, 91
- scanner, 617, 664, 673
- scanner generator, 664
- scientific, 83
- scientific notation, 83
- scope resolution operator, 23, 50, 214, 281, 284, 301
- scope: class, 336
- scope: global, 336
- search, 447
- search_n, 448
- second, 237
- second_argument_type, 591
- seek beyond file boundaries, 86, 93
- seek_dir, 349
- seek_off, 625
- seekdir, 86, 93, 314
- seekg, 93
- seekoff, 319, 625
- seekp, 86
- seekpos, 319, 625, 626
- segmentation fault, 371
- select, 642, 643
- Selector, 644
- semaphore, 387
- Sergio Bacchi, 5
- set, 262
- set: header file, 262, 264
- set_debug, 667
- set_difference, 449
- set_intersection, 450
- set_new_handler, 149
- set_symmetric_difference, 451
- set_union, 452
- setAlarm, 645
- setbase, 82
- setbuf, 318

setf, 80
setfill, 79
setg, 315, 621, 623, 625
setiosflags, 80
setjmp, 165, 167, 168
setp, 318, 619
setprecision, 80
setstate, 78
setup.exe, 9
setw, 80
SFINAE, 498
sgetc, 313
sgetn, 314, 624
shadow member, 286
shared_ptr, 45, 375, 563
shared_ptr: 0-pointer, 376
shared_ptr: default, 375
shared_ptr: defining, 375
shared_ptr: initialization, 376
shared_ptr: operators, 377
shared_ptr: used type, 376
shift-reduce, 682
showbase, 82
showmanyc, 317
showpoint, 83
showpos, 82
shuffling, 396
signal, 637
sin, 272
single inheritance, 283
sinh, 272
size, 69, 119, 240, 245, 248, 250, 252, 258, 264, 267
size specification, 228
size: of pointers to members, 341
size_t, 44, 212
size_type, 60
sizeof, 8, 134, 137, 142, 529, 595
sizeof derived vs base classes, 289
SKIP_FLEXLEXER_, 667
skipping leading blanks, 27
skipws, 84, 368
slicing, 287
snnextc, 314
socket, 617
sockets, 74
sort, 245, 358, 453
sort criteria: hierarchic sorting, 553
sort: multiple hierarchal criteria, 456
sort_heap, 465
sorted collection of value, 264
sorted collection of values, 262
sorting, 396
special containers, 235
splice, 245
split buffer, 317
sprintf, 85
sputback, 314
sputc, 314
sputn, 314
sqrt, 272
sscanf, 91
sstream, 89, 95
sstream: header file, 74
stable_partition, 454
stable_sort, 455, 553
stack, 235, 266
stack constructors, 267
stack data structure, 266
stack operations, 221
stack: header file, 266
standard exceptions, 182
standard layout, 163
standard namespace, 23
standard namespace: and STL, 353
Standard Template Library, 353
standard-layout, 163
stat, 43, 117
state flags, 181
state of I/O streams, 72, 74
static, 11, 50, 227
static binding, 293, 295
static data members: initialization, 228
static data: const, 230
static inline member functions, 231
static member functions, 230, 231
static members, 227, 515
static object, 109
static polymorphism, 501, 589
static type checking, 306
static type identification, 306
static variable: initialization, 385
static: data members, 227
static: members, 340
static_assert, 498
static_cast, 484
static_cast<type>(expression), 45
static_pointer_cast, 378
std, 71
std namespace: off limits, 456
std::streambuf, 620
stderr, 26
STDERR_FILENO, 640
stdexcept, 68
stdexcept: header file, 182
stdin, 26
STDIN_FILENO, 639
stdio.h, 14, 18
stdout, 26
STDOUT_FILENO, 620, 640
STL, 353
STL: required types, 655
storing data, 241
str, 89, 95
str..., 137
strcasecmp, 60, 354
strdup, 137, 149, 150
stream, 319
stream state flags, 78

- stream: as bool value, 78
- stream: processing, 95
- stream: read and write, 99
- streambuf, 72, 75, 96, 313, 367, 368, 617, 621, 622, 625, 626
- streambuf: header file, 74
- streams: associating, 103
- streams: reading to memory, 95
- streams: writing to memory, 89
- streamsize, 313
- string, 59
- string constructors, 62
- string extraction, 91
- string: as union member, 676
- string: declaring, 59
- string: iterator types, 62
- string::iterator, 343
- string::size_type, 60
- strlen, 538
- strong guarantee, 185
- Stroustrup, 25
- struct, 21
- struct: empty, 598
- Structured Computer Organization, 387
- substitution failure, 498
- substr, 69
- subtract_with_carry, 391
- sungetc, 314
- Sutter, H., 185, 501
- swap, 69, 157, 187, 240, 246, 252, 258, 264, 374, 377, 457
- swap area, 149
- swap_ranges, 458
- swapping, 396
- Swiss army knife, 283
- symbol area, 667
- symbolic constants, 27
- sync, 319, 618, 619
- syntactic elements, 165
- system, 634, 637
- Tanenbaum, A.S., 387
- TCP/IP stack, 313
- tellg, 93
- tellp, 86
- template, 71, 353, 470, 502
- template declaration, 483
- template explicit specialization, 490
- template explicit type specification: omitting, 493
- template header, 471
- template header: for member templates, 513
- template instantiation declaration, 493
- template mechanism, 469, 470
- template members: without template type parameters, 574
- template meta programming, 482, 571
- Template Method, 297
- template method design pattern, 634
- template non-type parameter, 472
- template pack: and template template parameters, 610
- template parameter deduction, 477
- template parameter list, 470, 472, 502
- template parameter: default value, 512
- template parameters: identical types, 481
- template programming, 577
- template template parameter, 571, 587
- template template parameter: and template packs, 610
- template type deduction, 480
- template type parameter, 471
- template type: initialization, 473
- template using declaration, 539
- template: and the < token, 576
- template: class, 502
- template: embedded in typedefs, 518
- template: embedding integral values, 578
- template: explicit specialization, 492
- template: id-declaration mismatch, 492
- template: identifying subtypes, 516
- template: IfElse, 581
- template: parameter type transformation, 477
- template: point of instantiation, 484, 498
- template: preventing instantiation, 509
- template: select type given bool, 581
- template: specialization, 519
- template: specified within template, 576
- template: statements depending on type parameters, 498
- template: subtypes inside templates, 573
- template: variadic, 528
- template: when instantiated, 509
- templates vs. using, 474
- templates: iteration by recursion, 583
- templates: overloading type parameter list, 487
- terminate, 321
- text files, 100
- textMsg, 174
- this, 154, 213, 227, 231, 232
- thread, 382
- thread: header file, 382
- throw, 166, 171
- throw list, 179, 182
- throw: empty, 174
- throw: pointer, 173
- tie, 75, 97
- timed_mutex, 384
- timeval, 643
- token, 266, 673
- top, 250, 266, 267
- trait class, 591
- trait class: class detection, 594
- trait class: nested, 592
- transform, 357, 359, 459
- transform: vs. for_each, 460
- transformation to a base class, 480
- trivial copy constructor, 156, 163
- trivial default constructor, 120, 163, 596

trivial destructor, 147, 163
 trivial member, 163
 trivial overloaded assignment operator, 163
 true, 42, 88, 94, 236, 361, 420, 429, 666
 trunc, 89, 100
 try, 175
 tuple, 537
 tuple: header file, 537
 tuple_element, 537
 tuple_size, 537
 Type, 237
 type checking, 14
 type conversions, 494
 type identification: run-time, 306
 type of the pointer, 288
 type safe, 27, 91, 137, 138
 type safety, 72
 type specification: explicit, 477
 type-safe, 27
 type: primitive, 42
 type: without values, 351
 type_traits: header file, 595
 typedef, 21, 71, 238, 253
 typedefs: nested, 561
 typeid, 306, 309
 typeid: argument, 310
 typeid: header file, 309
 typename, 571
 typename ... Params, 528
 typename &&, 35
 typename vs. class, 587
 typename: and template subtypes, 516
 typename: disambiguating code, 516
 types: required by STL, 655

 U, 42
 uflow, 313, 317
 uint32_t, 44
 Ullman, J.D., 241
 unary function object, 360
 unary not, 655
 unary operator, 655
 unary predicate, 402
 unary_function, 655
 unbound friend, 542, 548
 undefined reference to vtable, 326
 underflow, 317, 621
 underflow_error, 183
 unget, 93, 626
 Unicode, 43
 uniform initialization, 118
 uniform_int<Type = int>, 393
 uniform_real<Type = real>, 393
 unimplemented: mangling dotstar_expr, 475
 union, 21, 676
 unique, 246, 377, 460
 unique_copy, 461
 unique_lock, 384
 unique_ptr, 369, 563

unique_ptr: 0-pointer, 370
 unique_ptr: assignment, 371
 unique_ptr: default, 370
 unique_ptr: defining, 370
 unique_ptr: initialization, 371
 unique_ptr: move constructor, 371
 unique_ptr: operators, 373
 unique_ptr: reaching members, 372
 unique_ptr: used type, 372
 unistd.h: header file, 618, 621, 622, 625, 639
 unitbuf, 84
 Unix, 97, 100, 637, 638, 673, 682
 unordered_map, 268
 unordered_map: header file, 268
 unordered_multimap, 268
 unordered_multiset, 268
 unordered_set, 268
 unordered_set: header file, 268
 unpack operator, 529, 533
 unrestricted union, 135
 unsetf, 80
 unsigned int, 44
 upper_bound, 258, 264, 462
 uppercase, 82
 US-letter, 6
 use_count, 377
 user defined literals, 538
 using, 133, 539
 using declaration, 51
 using directive, 51
 using namespace std, 23
 using vs. templates, 474
 using: in derived classes, 281
 using: restrictions, 55
 using: template declaration, 539
 UTF-16, 43
 UTF-32, 43
 UTF-8, 43
 utility, 160
 utility: header file, 237, 531

 valid state, 60
 value, 253
 value type, 268
 value_type, 253, 262
 Vandevoorde, D., 571
 variadic functions, 528
 variadic template: number of arguments, 529
 variadic templates, 528
 vector, 235, 238, 363
 vector constructors, 238
 vector: header file, 238
 vector: member functions, 239
 vform, 6
 viable functions, 494
 vice versa, 481
 virtual, 295, 665
 virtual base class, 301
 virtual constructor, 327, 683

- virtual derivation, [302](#)
- virtual destructor, [296](#), [298](#)
- virtual member function, [295](#)
- virtual: vs static, [227](#)
- visibility: nested classes, [343](#)
- void, [17](#)
- void *, [176](#), [212](#), [214](#), [215](#)
- volatile, [479](#)
- vpointer, [323](#)
- vprintf, [86](#)
- vscanf, [91](#)
- vtable, [323](#), [589](#)
- vtable: and multiple inheritance, [324](#)
- vtable: undefined reference, [326](#)

- wait, [644](#)
- waitpid, [635](#)
- wchar_t, [42](#), [43](#), [71](#)
- what, [181](#), [182](#)
- white space, [27](#), [84](#)
- width, [80](#)
- wild pointer, [150](#), [173](#)
- wrapper, [148](#), [456](#), [630](#)
- wrapper class, [74](#), [207](#), [285](#)
- wrapper functions, [232](#)
- write, [86](#)
- write beyond end of file, [86](#)
- writeFd, [644](#)
- ws, [84](#)

- X-windows, [44](#)
- X2a, [658](#)
- xor, [226](#)
- xor_eq, [226](#)
- XQueryPointer, [44](#)
- xsgetn, [314](#), [317](#), [622–624](#)
- xspn, [314](#), [318](#)

- yacc, [664](#)
- Yodl, [3](#)
- YY_BUF_SIZE, [671](#)
- yy_buffer_state, [670](#), [671](#)
- YY_CURRENT_BUFFER, [671](#)
- yy_delete_buffer, [671](#)
- yy_switch_to_buffer, [670](#)
- yyFlexLexer, [665](#), [668](#)
- yyin, [668](#)
- YYLeng, [668](#)
- yylex, [665](#), [666](#)
- yylineno, [671](#)
- yyout, [668](#)
- YYText, [668](#), [676](#)

- zombie, [637](#), [648](#)